


Yaan Hu · Marc Sas ·
Feng Jin · Sheng'an Zheng ·
Gensheng Zhao *Editors*

Hydropower and Renewable Energies

Powering a Sustainable Future
with Storage and Renewables



OPEN ACCESS

 Springer

Series Editors

Marco di Prisco, *Politecnico di Milano, Milano, Italy*

Sheng-Hong Chen, *School of Water Resources and Hydropower Engineering, Wuhan University, Wuhan, China*

Ioannis Vayas, *Institute of Steel Structures, National Technical University of Athens, Athens, Greece*

Sanjay Kumar Shukla, *School of Engineering, Edith Cowan University, Joondalup, Australia*

Anuj Sharma, *Iowa State University, Ames, USA*

Nagesh Kumar, *Department of Civil Engineering, Indian Institute of Science Bangalore, Bengaluru, India*

Chien Ming Wang, *School of Civil Engineering, The University of Queensland, Brisbane, Australia*

Zhen-Dong Cui , *China University of Mining and Technology, Xuzhou, China*

Xinzheng Lu , *Department of Civil Engineering, Tsinghua University, Beijing, China*

Lecture Notes in Civil Engineering (LNCE) publishes the latest developments in Civil Engineering—quickly, informally and in top quality. Though original research reported in proceedings and post-proceedings represents the core of LNCE, edited volumes of exceptionally high quality and interest may also be considered for publication. Volumes published in LNCE embrace all aspects and subfields of, as well as new challenges in, Civil Engineering. Topics in the series include:

- Construction and Structural Mechanics
- Building Materials
- Concrete, Steel and Timber Structures
- Geotechnical Engineering
- Earthquake Engineering
- Coastal Engineering
- Ocean and Offshore Engineering; Ships and Floating Structures
- Hydraulics, Hydrology and Water Resources Engineering
- Environmental Engineering and Sustainability
- Structural Health and Monitoring
- Surveying and Geographical Information Systems
- Indoor Environments
- Transportation and Traffic
- Risk Analysis
- Safety and Security

To submit a proposal or request further information, please contact the appropriate Springer Editor:

- Pierpaolo Riva at pierpaolo.riva@springer.com (Europe and Americas);
- Swati Meherishi at swati.meherishi@springer.com (Asia—except China, Australia, and New Zealand);
- Wayne Hu at wayne.hu@springer.com (China).

All books in the series now indexed by Scopus and EI Compendex database!

Yaan Hu · Marc Sas · Feng Jin · Sheng'an Zheng ·
Gensheng Zhao
Editors

Hydropower and Renewable Energies

Powering a Sustainable Future with Storage and
Renewables

Editors

Yaan Hu
Nanjing Hydraulic Research Institute
Nanjing, China

Feng Jin
Department of Hydraulic Engineering
Tsinghua University
Beijing, China

Gensheng Zhao
Department of Hydraulic Engineering
Nanjing Hydraulic Research Institute
Nanjing, Jiangsu, China

Marc Sas
International Marine and Dredging
Consultants (IMDC)
Antwerp, Belgium

Sheng'an Zheng
China Society for Hydropower Engineering
Beijing, China



ISSN 2366-2557

ISSN 2366-2565 (electronic)

Lecture Notes in Civil Engineering

ISBN 978-981-95-4888-0

ISBN 978-981-95-4889-7 (eBook)

<https://doi.org/10.1007/978-981-95-4889-7>

This work was supported by Gensheng Zhao.

© The Editor(s) (if applicable) and The Author(s) 2026. This book is an open access publication.

Open Access This book is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this book or parts of it.

The images or other third party material in this book are included in the book's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the book's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.

This work is subject to copyright. All commercial rights are reserved by the author(s), whether the whole or part of the material is concerned, specifically the rights of translation, reprinting, reuse of illustrations, recitation, broadcasting, reproduction on microfilms or in any other physical way, and transmission or information storage and retrieval, electronic adaptation, computer software, or by similar or dissimilar methodology now known or hereafter developed. Regarding these commercial rights a non-exclusive license has been granted to the publisher.

The use of general descriptive names, registered names, trademarks, service marks, etc. in this publication does not imply, even in the absence of a specific statement, that such names are exempt from the relevant protective laws and regulations and therefore free for general use.

The publisher, the authors and the editors are safe to assume that the advice and information in this book are believed to be true and accurate at the date of publication. Neither the publisher nor the authors or the editors give a warranty, expressed or implied, with respect to the material contained herein or for any errors or omissions that may have been made. The publisher remains neutral with regard to jurisdictional claims in published maps and institutional affiliations.

This Springer imprint is published by the registered company Springer Nature Singapore Pte Ltd. The registered company address is: 152 Beach Road, #21-01/04 Gateway East, Singapore 189721, Singapore

If disposing of this product, please recycle the paper.

Contents

Stability Enhancement Strategy for Wind-Solar-Hydropower Coupled Systems Based on a KDE-SRSM Hybrid Modeling Method	1
<i>Youhan Deng, Rongzhao Hu, Mingyuan Liu, Youping Li, Xiaojun Hua, Lei Wang, Hui Cao, Zhengfeng Bao, Zhengyang Tang, and Chengxi Liu</i>	
Research on Power Transmission Curve for Wind-Solar-Storage Integration Base Based on Resource-Efficient Operation	11
<i>Jie Gao, Jingyi Li, Dong Zhang, Xu Wang, Peng Lu, and Peng Guo</i>	
Verification and Analysis of Phase Adjustment Operation Capability of a Certain Pumped Storage Units	19
<i>Bobo Tian, Peilei Feng, Xiaoya Chen, Jiatong Lu, Haitang Mi, and Xi Wang</i>	
Preliminary Conception of the Capacity Optimization and Allocation Platform for Multi-Energy Complementation of Hydro-Wind-Solar-Storage Clean Energy Bases	35
<i>Jingyi Li, Jie Gao, Xu Wang, Pin Zhang, and Dong Zhang</i>	
Evaluation Research on Energy Dissipation Layout of Parallel Spillway Tunnels in Narrow Valleys	44
<i>Wang Yu, Hu Hao, Xue Yang, Gu Jinde, Zhao Jianjun, Liu Jingkai, Li Tianyu, and Peng Yu</i>	
Seepage and Anti-Sliding Stability Analysis of a Clay Core Rockfill Dam Based on In-Situ Data	55
<i>Siyuan Xu, Fengzhe Tian, Yanbin Cui, and Xiaojia Wang</i>	
Optimal Operational Strategies for Hydro-Wind-Solar-Pumped Storage Complementary Delivery Systems Under Extreme Renewable Generation Scenarios	65
<i>Chuang Dong, Ruirui Liu, Xingjin Zhang, and Rui Han</i>	
Research on Key Technologies for Multi-energy Complementary Hydro-Wind-Solar-Storage Base	75
<i>Zenghai Zhao, Dong Zhang, Jie Gao, Xu Wang, Fangliang Zhu, and Peng Guo</i>	

Research on Vibration Reduction Scheduling Strategies for High-Dam Discharge Under Low-Frequency and Small-Amplitude Characteristics	89
<i>Heng Zhang, Yanhe Chen, Luchen Zhang, Wei Bao, Xueyu Zheng, Wei Sun, and Yongfu Hu</i>	
Operational Stability Control Technology for Gravity Blocks in Gravity Compressed Air Energy Storage Systems	99
<i>Weixiang Ni, Yanan Hu, and Zhonghua Li</i>	
Research on Engineering Treatment Measures for Crossing Active Faults in High-Pressure Diversion Tunnels of Hydropower Stations	112
<i>Yong Xia, Bo Sun, He-Gao Wu, and Chang-Zheng Shi</i>	
Study on the Sediment Erosion Characteristics and Protection Strategies of the Pump-Turbine in Qinglong Liancheng Pumped Storage Power Station ...	123
<i>Nan Li and Dan Yao</i>	
Reassessing Meyerhof's Theory for Eccentric Foundations: Rwandan Hydropower Case	134
<i>Wei Xie, Bilei Wang, Xiaofang Lin, Xingang Yao, Tao Lou, and Yang Deng</i>	
Exploration of Key Points in Safety Evaluation of Water Conveyance Tunnels for Pumped Storage Power Stations	142
<i>Xiaobian Wu</i>	
Fabrication and Electrochemical Performance of Cement-Based Structural Supercapacitors	153
<i>Yumin Zhang, Kewei Sun, Zhicheng Yu, Senlin Li, and Hao Yang</i>	
Research on the Design for the Upgrading and Heightening of the Lower Reservoir Dam at the Fengning Pumped Storage Power Station	166
<i>Jiachun Wang</i>	
Application of UAV Oblique Photography in Earthwork Data Collection of the Pumped Storage Power Station Construction	177
<i>Yuan Lin</i>	
Large Underground Cavern Complexes Considering Construction Disturbance and Environmental Evolution Dynamic Inversion of Surrounding Rock Parameters and Feasibility Analysis of Support Role	187
<i>Yang Ji, Peng Huang, Wenxing Fang, and Chunlong Zhao</i>	
State of the Art on Air-Entraining Vortices in Pumped Storage Hydropower Plants	199
<i>Tian Jin, Yujie Ge, Guangde Li, Jiaming Wang, and Gensheng Zhao</i>	

Life-Cycle Carbon Reduction Benefit Analysis of Hydropower Projects—A Case Study of a Hydropower Project in Southwestern China	211
<i>Gang Chen, Fangping Ma, Fang Peng, Dongliang Guan, Xingguo Feng, Haoran Wang, Hong Zhang, and Wenyan He</i>	
The Application of Inertial-Equilibrium Filling and Emptying System with Three-Dimensional Layered Energy Dissipation Structure in the Arrangement of 60m Single-Stage Lock in the Lower Reaches of Jinsha River	221
<i>Zuoqiang Chen, Chao Guo, Jiangda He, and Wenming</i>	
Response of Oxbow Lake Morphology to Hydrological Connectivity Changes: A Case Study of Shangchewan in Middle Yangtze River	234
<i>Xiaoguang Liu, Shiming Yao, Bing Ding, and Shuo Guan</i>	
Theoretical Foundation and Technical Implementation of Dynamic Flow Monitoring for Hydropower Units	246
<i>Shuangxi Zou, Ashas Abbasi, Wenbo Cao, Dianlong Chen, Yanlong Wang, Gaolin He, and Wenbing Zhu</i>	
A Method for Determining Ecological Flow Downstream of Hydropower Stations Considering Inter-annual and Intra-annual Wet-Dry Co-occurrences	259
<i>Yueping Deng, Yu Zhang, and Xiuqin Yang</i>	
Ecological Restoration-Oriented Multi-objective Optimal Design of Clean Energy Heritage Landscapes Investigation	271
<i>Yini Guo</i>	
Attribution and Uncertainty Analysis of River Runoff Changes: A Case Study of the Upstream Yangtze River in China	280
<i>Yu Zhang, Xiao Zhang, and Jing Zhang</i>	
Regularization of Flows in SHPPs as a Strategy for Adapting to Climate Change: The Case of SHPP Americana	312
<i>Beatriz Sepulveda Pires, Xinjian Chen, and Huiyi Zhang</i>	
Behavioral Analysis of Stocked Fish Using Individual-Based Model	320
<i>Luhai Wang</i>	
Multi-objective Optimal Operation of Cascade Reservoirs in the Upper Yellow River Incorporating Ecological Flow Requirements	330
<i>Yuan Si, Xiaobo Liu, Wenqiang Wu, Fei Dong, and Weijie Wang</i>	

Environmental Impacts, Benefits and Future Challenges of Utility-Scale
Solar Photovoltaic Projects in the Non-Humid Areas 344
Sijia Du, Yuetao Xie, Hao Jiang, Qiangxiao Xian, and Guangda Lu

Characteristic Identification of Short-Term Heavy Rainfall in Plateau
Mountainous Areas 357
Qianwen Wu, Leilei Qin, Jun Liu, and Yu Zhang

Methodology for Analyzing Glacial Lake Outburst Flood Impacts 378
Tijia Yang, Xin Zhang, Jie Qin, Teng Wu, and Gaohu Sun

Dynamic Characteristics of Offshore Wind Turbine Cap-Pile Group
Structure Based on Experimental Modal Analysis 389
*Yuan Liu, Jianjian Zhao, Luchen Zhang, Hao Hu, Lei Yu, Yu Wang,
Chuang Liu, and Shaoze Luo*

Application and Future Trends of Intelligent Construction in Hydropower
Engineering: A Case Study of TB Hydropower Station 398
Li-Qiao Lu, Guo Li, Ai-Wu Zheng, Lei Ni, Zhi Li, and Tian-wei Zhang

Construction and Validation of a Data-Driven Static Surrogate Model
for Prestressed Steel-Concrete Joints 409
Li Chong, Yu Fangliang, Zheng Luyao, and Li Bo

Research and Reflection on the Safety of High Concrete Face Rockfill Dams ... 420
Wen-Xia Wu, Hai-Bin Xiong, and Jian-Hua Lu

Intelligent Inversion Method of Temperature Control Design Parameters
for the Surrounding Concrete of the Spiral Case in Hydropower Stations 433
Wenjie Xu, Gang Wang, and Zhenyue Ma

Comparison of Machine Learning Models in Reservoir Outflow Simulation
Under Different Hydrological Conditions 441
*Lei Yu, Jing Zhang, Yanfei Yang, Li Zhang, Yan Zhang, Yu Zhang,
Luchen Zhang, and Zehui Zhou*

Typical Applications of Satellite Remote Sensing Technology
in the Operational Safety of Hydropower Plants 450
Wu Weiyu, Wang Zhen, Xu Lei, and Zhou Jianbo

Research and Practice on the Smart Reservoir Construction
of the Nuozhadu Hydropower Station 461
Ming Kong, Xiaoxuan Chen, Jiulong He, Wuhua Su, and Shangrong Yang

Prediction, Monitoring, and Fault Diagnosis of Hydropower Plants Using Digital Twin Model and Differential Evolution Algorithm	469
<i>Fabrício Nascimento Sfalsin, Leonardo Campanine Sicchieri, Roberto Martins de Castro Neto, Aldemir Aparecido Cavallini Junior, Jefferson Silva Barbosa, Henrique Borduqui, Isabela Marchiori, and Ricardo Lourencini Assumpção</i>	
Digitization Practices for the Whole Life Cycle of Resettlement in Water Conservancy and Hydropower Projects	478
<i>Tianming Zhao, Liqiang Du, Jing Tian, and Yu Zhu</i>	
Research on Anomaly Detection Methodology for Deformation Monitoring in High Arch Dam	486
<i>Wang Sheng, Yu Hao, Gao Xiaofeng, and Hu Lei</i>	
Optimization of Fault Diagnosis for the Hydraulic System of the Hydrogenerator Governor in Large-Scale Hydropower Station	495
<i>Qiang Zhang, Yinping Ma, and Qin Liu</i>	
Benefits and Practical Experience in Automation of Auscultation Instruments of Dams	503
<i>Andrea Re, Xinjian Chen, Valéria Maria Cavalcanti, Arthur Couto Mantese, and Huiyi Zhang</i>	
The Future of Dam Safety: A Proactive Approach Using Data Analytics and Machine Learning Tools Applied to Data from Dam Monitoring Instruments	512
<i>Arthur Couto Mantese, Futao Huang, Xinjian Chen, Leonardo de Lima Breve, Luis Fernando Pedrozo Melegari, and Huiyi Zhang</i>	
Hydro 4.0 – the Digital Dam Safety Platform of CPFL Energia Group – Brazil	519
<i>Arthur Couto Mantese, Xinjian Chen, Raphael Moncacci Borges da Silva, Camila Gomes, Luis Fernando Pedrozo Melegari, and Huiyi Zhang</i>	
A Method for Water Resource Dispatching in Cascade Hydropower Stations, Characterized by AI Computation	529
<i>Kecheng Geng and Wei Chen</i>	
Improving LLM-Assisted Hydropower Operation Through Data Query Enhanced Agent	551
<i>Wei Luo, Feng Zhang, Lizhi Wang, Shiruo Hu, Bin Xu, and Jianshi Zhao</i>	

Riverbasin Information Modeling:Concept, Connotation, and Application Patterns	568
<i>Qiang Zhu, Heping Jin, Jiawen Yu, Qiyuan Xiao, Yize Li, and Yufei Zhuang</i>	
A Study on Digital Governance Framework Based on Enterprise Architecture: Taking Clean Energy Enterprise (China Three Gorges Corporation) as an Example	578
<i>Qiyuan Xiao, Qiang Zhu, Jiawen Yu, and Yufei Zhuang</i>	
Author Index	589



Stability Enhancement Strategy for Wind-Solar-Hydropower Coupled Systems Based on a KDE-SRSM Hybrid Modeling Method

Youhan Deng¹, Rongzhao Hu³, Mingyuan Liu³, Youping Li², Xiaojun Hua²,
Lei Wang², Hui Cao², Zhengfeng Bao¹, Zhengyang Tang², and Chengxi Liu³(✉)

- ¹ Laboratory of Hydro-Wind-Solar Multi-energy Control Coordination, Wuhan 420116, China
deng_youhan@ctg.com.cn, bao_zhengfeng@cypc.com.cn
- ² China Yangtze Power Co., Ltd., China Three Gorges Corporation, Wuhan 430010, China
{li_youping, hua_xiaojun, wang_lei10, cao_hui,
tang_zhengyang}@ctg.com.cn
- ³ School of Electrical Engineering and Automation, Wuhan University, Wuhan 430072, China
{hurongzhao, liumingyuan, iuchengxi}@whu.edu.cn

Abstract. The increasing integration of high-penetration renewable energy has led to prominent issues in power grid stability. This paper proposes a hybrid modeling method that integrates Kernel Density Estimation (KDE) with the Stochastic Response Surface Method (SRSM), addressing the dual challenges of insufficient accuracy in traditional parametric distribution models and the low efficiency of Monte Carlo simulations. By employing non-parametric probabilistic modeling to accurately characterize the spatiotemporal characteristics of wind-solar output, a refined model for wind turbine and photovoltaic generation is established. Combined with SRSM, a coordinated regulation mechanism between hydropower and renewables under fault scenarios is constructed to support system stability control strategies. A case study on a certain hydropower station demonstrates that the proposed method can accurately reflect system responses, providing theoretical support for the secure operation of power grids with high renewable penetration.

Keywords: High-penetration renewable energy · Non-parametric probabilistic modelling · Stochastic Response Surface Method · Hydro-solar-wind coordination

1 Introduction

Driven by the global low-carbon energy transition, power systems are undergoing a “dual-high” structural transformation characterized by very high shares of renewable generation and power-electronic interfaced devices [1–3]. Installations of wind and photovoltaic (PV) capacity have grown exponentially, from 18.55 GW in 1999 to 1503 GW in 2020—an eighty-one-fold increase over two decades [4]. To address difficulties in integrating and consuming such high proportions of variable renewables, hybrid water–wind–solar systems have emerged as a key solution [5].

However, the inherent uncertainty of wind and solar outputs poses significant challenges for safety and stability analysis and decision-making in these hybrid systems [6]. Modern stability-control systems are becoming larger, more wide-area, and more complex, demanding higher fidelity in renewable-output characterization and rapid simulation of system-wide dynamic behaviours. Existing approaches typically rely on parametric probability models whose parameters must be estimated from historical data through subjective, prior experiments—for example, Weibull models for wind-power forecasting errors [4–6] or Beta-distribution models for irradiance fluctuations [7–9]. In multi-source, multi-spatiotemporal settings such as water–wind–solar integration, this necessity for repeated, data-driven experiments limits model generality and yields poor accuracy under extreme weather conditions.

In terms of control-system modelling, methods based on Markov state-space formulations require massive sample spaces to ensure accuracy, while Monte Carlo–based simulations demand on the order of thousands of runs [10, 11]. Polynomial Chaos Expansion (PCE) techniques face a “curse of dimensionality” in high-dimensional problems and depend on assumed parameter distributions [12].

To overcome these dual challenges of limited parametric accuracy and low Monte Carlo efficiency, this paper proposes a hybrid modelling framework that combines kernel density estimation (KDE) with the stochastic response surface method (SRSM). First, nonparametric KDE captures the spatiotemporal characteristics of wind and solar outputs with high precision, enabling the construction of a dynamic compensation model for wind–PV interactions. Second, SRSM is employed to formulate a coordinated regulation mechanism among hydro, wind, and solar units under fault conditions, facilitating rapid prediction and stable control of system responses.

The proposed strategy was validated on an actual water–wind–solar bundled transmission system. The results show that this surrogate model can accurately reflect the system response, providing robust theoretical support for the safe operation of power grids with high renewable-penetration levels.

2 Probabilistic Modeling of Solar and Wind Outputs

Wind and photovoltaic outputs are heavily influenced by environmental factors, exhibiting volatility, intermittency, randomness, seasonality, and regional variability, dynamically changing with wind speed and irradiance. Therefore, probabilistic analysis first focuses on the probability characteristics of irradiance and wind speed, which are then used to construct solar and wind output models and obtain its probabilistic properties.

2.1 Common Probability Distributions for Solar and Wind Outputs

2.1.1 Beta Distribution

The Beta distribution is widely used to estimate the probability density of photovoltaic irradiance. It uses shape parameters α and β to adjust its form, making it highly flexible. Photovoltaic output, influenced by irradiance and temperature, more in line with the Beta distribution. Based on measured data from a PV plant, irradiance data at five-minute intervals for January (winter) and July (summer) were fitted, and the resulting

distribution plots illustrate that while the Beta distribution provides a rough estimate, it fails to capture the bimodal characteristics observed in January, leading to significant modeling errors in the SRSM (Fig. 1).




Fig. 1. Irradiance probability estimation based on Beta distribution

2.1.2 Weibull Distribution

The Weibull distribution is commonly used to estimate wind speed probability density. Determined by shape parameter k and scale parameter λ , it matches the statistical properties of wind speed relatively well. Using measured wind speed data at five-minute intervals for January and July from a wind farm, the Weibull-fitted distributions show high overall accuracy, but performance varies across seasons, and fitting errors still introduce notable inaccuracies in the SRSM construction (Fig. 2).




Fig. 2. Wind speed probability estimation based on Weibull distribution

2.2 Non-parametric Estimation of Wind-Solar Probabilistic Characteristics

Although conventional distributions can approximate solar and wind probabilistic characteristics to some extent, their fitting accuracy varies across datasets and cannot guarantee precision. Non-parametric estimation methods, which do not assume specific distribution types, flexibly adapt to complex data and reveal inherent patterns through techniques such as KDE and local polynomial estimation.

2.2.1 Kernel Density Estimation

Kernel Density Estimation (KDE) is a typical non-parametric estimation technique that smooths sample data points with a kernel function to construct a continuous probability density function without assuming a priori distribution. Gaussian kernels are commonly used, and the bandwidth parameter controls smoothing. A large bandwidth over smooths the data, losing local features, while a small bandwidth leads to noisy estimates.

2.2.2 Irradiance Probability Distribution

Using irradiance data from a photovoltaic station for January and July, KDE with a bandwidth of 70 yielded distributions that capture the overall shape of the data. By reducing the bandwidth to 10, the distributions captured more detailed features, demonstrating KDE's ability to adaptively depict complex multimodal distributions (Fig. 3).




Fig. 3. Irradiance probability distribution based on KDE

2.2.3 Wind Speed Probability Distribution

Similarly, applying KDE with bandwidths of 0.5 and 0.1 to wind speed data from a wind station for January and July produced distributions that accurately describe bimodal characteristics and capture subtle variations, validating KDE's effectiveness for wind speed modelling (Fig. 4).




Fig. 4. Wind speed probability distribution based on KDE

2.3 Solar and Wind Outputs Modelling

2.3.1 Photovoltaic Output Modelling

PV output is nonlinearly related to irradiance. Under standard test conditions (STC), PV output is proportional to irradiance, but temperature and other factors induce deviations. With the probabilistic distribution of irradiance, PV output can be modeled using the core equation:

$$P = P_{\max} \times G/G_{STC} \times [1 + \gamma \times (T_{cell} - T_{STC})] \quad (1)$$

where $P_{\max}$ is the STC-rated power, G is actual irradiance, $G_{STC} = 1000 \text{ W/m}^2$, γ is the temperature coefficient (typical: -0.3% to -0.5% per $^{\circ}\text{C}$ for crystalline silicon), T_{cell} is cell temperature, and $T_{STC} = 25^{\circ}\text{C}$.

Cell temperature relates to ambient temperature and irradiance via:

$$T_{cell} = T_{amb} + (NOCT - 20)/800 \times G \quad (2)$$

where T_{amb} is the ambient temperature; NOCT is the nominal operating cell temperature (typical: $45\text{--}48^{\circ}\text{C}$). For a DAS-DH144PA-540 module ($NOCT = 44^{\circ}\text{C}$), using measured irradiance and ambient temperature data at five-minute intervals, the PV output distribution was estimated.

2.3.2 Wind Turbine Output Modeling

Wind turbine output follows a typical three-region power curve: zero output below cut-in speed v_{ci} , variable output proportional to the cubic of wind speed between v_{ci} and rated speed v_r , constant rated output between v_r and cut-out speed v_{co} , and zero output above

v_{co} . For a 2.5 MW turbine, typical parameters are $v_{ci} = 3$ m/s, $v_r = 11$ m/s, and $v_{co} = 25$ m/s.

The typical three-region power curve of wind turbine output can be described as Eq. (3),

$$P_w = \begin{cases} 0 & v < v_{ci} \\ k(v^3 - v_{ci}^3) & v_{ci} \leq v < v_r \\ P_{rated} & v_r \leq v < v_{co} \\ 0 & v \geq v_{co} \end{cases} \quad (3)$$

where, P_{rated} is the rated power, and $k = \frac{P_{rated}}{v_r^3 - v_{ci}^3}$ is the proportionality coefficient, representing the wind energy conversion efficiency.

3 KDE-SRSM Hybrid Modeling Method

3.1 Stochastic Response Surface Method (SRSM)

SRSM approximates the relationship between system response variables and random inputs by constructing an explicit mapping through orthogonal polynomials. In a hybrid hydropower-renewable system, hydropower and renewable outputs are treated as random inputs, and system frequency/voltage deviations as response outputs. By fitting polynomial coefficients through regression on sample data, SRSM provides a concise mathematical model that captures input uncertainties.

3.1.1 Construction of Orthogonal Basis Functions

For non-parametric distributions estimated by KDE, custom orthogonal polynomial basis functions are constructed via the Gram-Schmidt process. Starting from monomial basis functions, the orthogonalization process with respect to the KDE-derived pdf $f(\xi)$ ensures orthogonality across different orders.

3.1.2 Sparse Collocation Strategy

To reduce computational effort, an adaptive weighted collocation strategy is employed. Initial collocation points are sampled densely in high-probability regions of the KDE distribution. Weights are assigned based on local density, and points with weights below a threshold are iteratively pruned to obtain a sparse representative set.

3.1.3 Workflow of the KDE-SRSM Hybrid Modeling

The overall workflow comprises six steps:

- (1) KDE Modeling: Estimate the probabilistic distributions of irradiance and wind speed, and derive wind-solar output probabilistic characteristics.
- (2) Basis Generation: Orthogonalize basis functions for each random variable using the Gram-Schmidt process $\{\Phi_i, \Phi_j, \Phi_k\}$.

- (3) Tensor Product Expansion: Construct multivariate basis functions via tensor products of univariate bases $\Phi_{ijk} = \Phi_i \otimes \Phi_j \otimes \Phi_k$.
- (4) Collocation Point Selection: Generate candidate points via Latin Hypercube Sampling and select representative collocation points.
- (5) System Simulation: Run power system simulations at collocation points to obtain frequency/voltage responses.
- (6) Coefficient Determination: Fit polynomial coefficients by least squares to build the surrogate model such as Eq. (4).

$$\min \sum_{m=1}^M \left(y_m - \sum_{k=0}^K \alpha_k \Phi_k(\xi_m) \right)^2 \quad (4)$$

Where, M represents the number of collocation points, and K represents the truncation order.

4 Experimental Validation and Engineering Application

4.1 Experimental Setup and Parameter Settings

Hardware: Intel Core Ultra 9 (2.30 GHz, 16 cores), 32 GB RAM.

Software: DIgSILENT PowerFactory 2015.

Test scenario: The research objects are a certain hydropower station and the adjacent new energy integration stations. A three-phase short-circuit fault at a certain bus occurring from 0.1 s to 0.15 s (Fig. 5).




Fig. 5. Simulation Model of the Research Object

4.2 Results and Discussion

4.2.1 Probabilistic Estimation Results

Comparative analysis of Beta, Weibull, and KDE fitting errors using measured wind-solar data (Tables 1 and 2):

Table 1. Comparison of irradiance results between Beta distribution and KDE

Methods	Winter RMSE (m/s)	Summer RMSE (m/s)	Output Bias (%)
Beta	0.12	0.21	5.6
KDE	0.07	0.09	1.5

Table 2. Comparison of wind speed results between Weibull distribution and KDE

Methods	Winter RMSE (m/s)	Summer RMSE (m/s)	Output Bias (%)
Weibull	0.18	0.32	4.7
KDE	0.09	0.12	1.2

KDE reduces RMSE by 7.8% in winter and 22% in summer for irradiance modeling, and predicts output bias within 2%. For wind speed, KDE improves prediction accuracy to 98.8%.

4.2.2 Accuracy Analysis of the KDE-SRSM Model

When considering the three input variables of hydropower, wind power, and solar power, the hydropower output is regarded as a uniform distribution, and the uncertainties of wind and solar power are introduced into the equivalent model constructed by the Stochastic Response Surface Method (SRSM). For the voltage response value of a certain node, the results of the KDE-SRSM model at collocation points and non-collocation points are shown in the following figure (Fig. 6).




Fig. 6. Comparison between the Results of the KDE-SRSM Hybrid Model and the Voltage Response of the Actual System

The voltage response curves from the KDE-SRSM model closely match actual simulation results under collocation and non-collocation conditions, demonstrating the model's capability to capture complex relationships between renewable and hydropower outputs and system responses. This module can provide a reliable model tool for the analysis and research of power grid operation characteristics.

5 Conclusion

This paper presents a KDE-SRSM hybrid modeling method that effectively addresses the trade-off between accuracy and computational efficiency inherent in traditional probabilistic models and Monte Carlo simulation. The proposed surrogate model accurately reflects system responses under wind-solar uncertainties, enabling reference-based hydropower dispatch to maintain system stability, and offers an innovative solution for real-time stability control in power grids with high renewable penetration.

Funding. Hubei Province Key Research and Development Program (No. 2022AAA007); Project of China Yangtze Power Co., Ltd. (No. Z242302010).

References

1. Huang, Y., Ding, T., Li, Y., et al.: Decarbonization technologies and inspirations for the development of novel power systems in the context of carbon neutrality. *Proc. CSEE* **41**(23), 1–15 (2021)
2. Chen, T., Zang, Q., Zhao, Y., et al.: Adaptive overcurrent protection scheme with bidirectional setting for distributed unbalanced distribution networks. *Chin. J. Electron Devices* **47**(2), 215–224 (2024)
3. Chen, X.: Zhou Xiaoxin: Establishing new generation power system is the inevitable choice for achieving “Dual Carbon Goals.” *Energy Conserv. Environ. Prot.* **36**(5), 12–15 (2021)
4. Xu, J., Liu, W., Liu, S., et al.: Current status and development trends of grid-forming control technology for power system converters. *Power Syst. Technol.* **46**(10), 3789–3800 (2022)
5. Zhang, Y., Chen, S., Zheng, L., et al.: Configuration and operation method for hybrid pumped storage wind-solar-hydro storage integrated power station. *J. Shanghai Jiao Tong Univ.* **59**(3), 256–267 (2025)
6. Zhu, J., Qiu, W., Sun, N., et al.: Reliability analysis of safety and stability control system architecture based on sequential Monte Carlo method. *Autom. Electr. Power Syst.* **45**(8), 1–8 (2021)
7. Shen, F., Zhang, Y., Wang, J., et al.: Probabilistic energy flow calculation for multi-energy regional integrated system based on improved stochastic response surface method. *Power Syst. Prot. Control* **53**(1), 23–31 (2025)
8. Wang, C., Liu, W., Cao, Y., et al.: New energy day-ahead scenario generation method based on improved conditional generative diffusion model. *Power Syst. Technol.* **49**(5), 1680–1689 (2025)
9. Zhang, Y., Yu, Z., Ye, P., et al.: Optimal planning of power system considering N-1 security criterion and low-carbon economic contribution. *Autom. Electr. Power Syst.* **49**(14), 1–10 (2025)
10. Jin, G., Chen, L., Lu, H., et al.: Hierarchical autonomous coordination strategy for multi-resource access distribution network. *Electr. Power Eng. Technol.* **60**(3), 45–52 (2025)

11. Wu, D., Jin, Y., Li, Z., et al.: Coordinated optimization scheduling of source-grid-load-storage in integrated energy system under dual-layer carbon trading mechanism. *Electr. Autom.* **47**(6), 1–8 (2025)
12. Li, Z., Wang, R., Xu, C., et al.: Two-stage coordinated operation strategy for community integrated energy service providers and microgrid clusters based on mixed game. *Mod. Electr. Power* **41**(2), 1–9 (2025)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Research on Power Transmission Curve for Wind-Solar-Storage Integration Base Based on Resource-Efficient Operation

Jie Gao^{1(✉)}, Jingyi Li², Dong Zhang^{1,3}, Xu Wang¹, Peng Lu⁴, and Peng Guo¹

¹ China Renewable Energy Engineering Institute, Beijing, China
690676797@qq.com

² Power China Northwest Engineering Corporation Limited, Beijing, China

³ The Department of Hydraulic Engineering, Tsinghua University, Beijing, China

⁴ Power China Kunming Engineering Corporation Limited, Beijing, China

Abstract. To achieve carbon neutrality, China has vigorously promoted the high-quality development of renewable energy. By 2024, the installed capacity of new energy such as wind and photovoltaic (PV) power has reached 1.4 billion kW, surpassing that of coal-fired power for the first time. This paper focuses on power transmission curve optimization for large-scale wind-solar-storage integrated multi-energy complementary bases. Firstly, based on local new energy resources, the regulating resources such as pumped storage hydropower and solar thermal stations are configured. With the goal of maximizing the power generation benefits, matching the power transmission curve, multi-energy complementary optimal operation is simulated. Secondly, based on the output of multi-energy complementary bases, considering the capacity constraints of transmission corridors, annual transmission guarantee rate and abandonment rate of new energy, a probabilistic three-stage power transmission curve is proposed. A case study of renewable energy (RE) Base in DGB (Deserts, Gobi & Barren lands) region is conducted to validate the approach. This research provides valuable references for formulating power transmission curves for multi-energy complementary bases, and facilitates the commercial operation for DGB RE bases.

Keywords: Wind-Solar-Storage Integration Base · Multi-Energy Complementary Optimized Operation · Power Transmission Curve · DGB renewable energy base

1 Introduction

China has actively promoted the large-scale, high-proportion and high-quality development of new energy. Since wind power and photovoltaic (PV) power generation firstly exceeded 100 million kW in 2014, which has successively surpassed 200 million kW in 2016 and 300 million kW in 2018. By 2024, the cumulative installed capacity of wind and PV power generation has exceeded 1.4 billion kW only after 6 years. Solar and wind resources are vital for the sustainable energy transition [1]. Accelerating the

penetration of renewable is a key pillar in climate mitigation [2]. To achieve carbon goals, the “14th Five-Year Plan for the Development of Renewable Energy” explicitly emphasizes promoting the clustered development of wind and PV power bases and accelerating the construction of large-scale wind/solar bases in DGB [3]. The primary pathway for new energy supply and consumption in these regions is formed by the integration of “large-scale wind/solar bases + adjacent clean and efficient flexible power sources + ultra-high-voltage transmission corridors”. Guided by the principle of green and low-carbon development, the proportion of renewable energy electricity in new transmission corridors in the future should not be less than 50%. Therefore, pumped storage hydropower (PSH), as a scalable and cost-effective flexible power source could achieve 100% renewable energy supply, and offers an approach to innovative development for DGB RE bases.

Concerned with new energy cluster-based development PSH, optimizing the coordinated operation of wind, PV and pumped storage is a current research hotspot. Relevant research [4] focus on maximizing the economic benefits of the wind-PV-PSH system, maximizing utilization of transmission corridor capacity, minimizing the total cost of installation, operation and maintenance, minimizing the abandoned renewable energy, matching the load variation and stabilizing intermittent renewable output. Concerned with the consumption of new energy in the base, how to formulate efficient, regular, and quantifiable power transmission curves to support commercial operations of the base remains a critical challenge. Some people [5] compared the two-stage conventional DC transmission curve, three-stage transmission curve scheme, and four-stage flexible operation scheme. The case study revealed that the comprehensive abandonment rate of new energy in the three schemes gradually decreased with 14.8%, 9.4%, and 7.7% respectively, while the scale of new energy consumption increased.

This paper focuses on the development model of “wind power + PV + PSH + solar thermal power + new-type energy storage” for SGB bases, constructs a multi-energy complementary optimized operation model with the goal of maximizing the power generation benefits. By iteratively refining the model to achieve a best match between total post-complementary output and the transmission curve with three-stage transmission processing, then a probabilistic three-stage power transmission curve is proposed. This framework provides an approach for rationalizing and commercializing power transmission in such bases.

2 Methods

2.1 Multi-energy Complementary Optimization Operation Model of Wind-Solar-Storage Integration Bases

This paper mainly studies DGB bases that utilizes wind power and PV power to provide foundational electricity, with PSH, solar thermal power or New-type energy storage serving as the primary flexible resource, and are transmitted via ultra-high-voltage direct current (UHVDC) corridors. The objective function is to maximize the economic benefits

of multi-energy complementary base, and can be expressed as:

$$f = \max \sum_{t=1}^T \sum_{i=1}^M P_{i,t} p_{i,t} \Delta t \quad (1)$$

Where, M is the number of types of complementary power sources in the preferred capacity configuration scheme for the base. i is a certain power source, where $i \in \{w, s, th, psh, st\}$, represents wind power, PV, solar thermal power, PSH, and new-type energy storage, respectively. T is the calculation period. $P_{i,t}$ is the output of the i -th-type power supply at time t . $p_{i,t}$ is the electricity price of the i -th-type power at time t . Δt is duration of each time interval.

2.2 Three-Stage Processing Method for Power Transmission Curves

Based on the results by model in Sect. 2.1, the daily power generation process is transformed into a three-stage curve by three averaging processes while maintaining the total daily electricity generation, that is total area under the curve remains unchanged, which can be seen in Fig. 1. Subsequently, the model mentioned in Sect. 2.1 is iteratively used to optimize with the objective of minimizing the deviation between the actual output and the three-stage curve. This iterative process ultimately yields the optimized three-stage output profile for each day. The method can be described as:

$$f = \min \frac{1}{T} \sum_{t=1}^T \sqrt{(P_{i,t} \Delta t - p_t^{req} \Delta t)^2} \quad (2)$$

Where p_t^{req} is the value of the three-stage curve at time t within a day.

3 Case Study

This study takes a desert base in northwest China as an example, with an area of 2500 km². First, meteorological data were collected for the planned locations of wind and PV power plants to calculate power generation. The long-term global meteorological dataset ERA5 developed by the European Meteorological Centre (ECMWF) was adopted, with a spatial resolution of 0.25° and a temporal resolution of 1 h. ERA5 provides meteorological parameters such as wind speed, wind direction, irradiance, humidity, air pressure, and temperature. These data were validated using ground-based meteorological station measurements before being applied to simulate the power generation of wind and PV plants [6].

According to the local resource conditions, economic comparisons of multiple capacity configuration schemes were conducted. The optimal scheme is determined by maximizing the net present value (NPV) the entire life and minimizing the levelized cost of electricity (LCOE) [7]. The final configuration scheme shows: PV of 22 million kW, wind power of 7 million kW, PSH of 5.6 million kW, solar thermal power of 200,000 kW, and new-type energy storage of 500,000 kW/1,000,000 kWh. It is transmitted via a ± 800 kV ultra-high-voltage flexible direct current (UHVDC) corridor, with a maximum transmission capacity of 10,000 MW.




Fig. 1. Schematic diagram of three-stage transmission curve derived from power output characteristic

4 Analysis

Based on the configuration scheme, the criteria for optimization were set as follows: an annual average abandonment rate of new energy below 10% and daily output guarantee rate of no less than 90%. The power output processes were extracted for all 8,760 h of the year 2023, resulting in 365 daily three-stage output curves.

To analyse the patterns of these 365 daily power transmission curves, the multi-energy complementary output of 24 h in a day for 365 curves were grouped into 10 intervals (ranging from 0 to 10,000 MW). The statistical result and probability are showed in Tables 1 and 2. This yielded the probability distribution of hourly output for the base, which is also the probability diagram of the power transmission curves (see Fig. 2).

The following observations are obviously showed in Fig. 2:

1. Between 1:00 and 10:00, there is a 71% probability that the power transmission curve falls within the range of [1000 MW, 4000 MW). Within this interval, the probability of output within [1000 MW, 2000 MW) is slightly higher than that in [2000 MW, 3000 MW) or [3000 MW, 4000 MW).
2. Starting from 11:00, there is a 44% probability of achieving full transmission capacity (10,000 MW). However, there is still a 32% probability that the transmission will fall within [1000 MW, 3000 MW).
3. At 12:00 and 19:00, the probability of full transmission reaches 90%. During the period from 13:00 to 18:00, the probability of full transmission approaches 100%.
4. Starting from 20:00, the probability of full transmission decreases. Nevertheless, from 20:00 to 24:00, there is still a 65%, 37%, 30%, 23%, and 15% probability of achieving full transmission, respectively, through the utilization of PSH.

Table 1. The statistical result of base output in a day for 365 curves

	base output/MW										
hour	1000	900–1000	800–900	700–800	600–700	500–600	400–500	300–400	200–300	100–200	0–100
1			1	10	9	14	35	75	78	107	36
2			1	10	9	14	35	75	78	107	36
3			1	10	9	14	35	75	78	107	36
4			1	10	9	14	35	75	78	107	36
5			1	10	9	14	35	75	78	107	36
6			1	10	9	14	35	75	78	107	36
7			1	10	9	14	35	75	78	107	36
8			1	10	9	14	35	75	78	107	36
9			1	10	9	14	35	75	78	107	36
10	22		1	3	7	7	33	73	76	107	36
11	159			1	3	3	15	37	42	74	31
12	330					2	2	9	8	10	4
13	355					1	2	3	2	1	1
14	364						1				
15	359					1	3		2		
16	356				2	1	3		3		
17	357				2	1	2		3		
18	354				2	1	2	2	3	1	
19	324				3	4	11	9	10	3	1
20	236		1	1	13	31	36	22	18	6	1
21	135		8	28	41	55	46	26	19	6	1
22	108		14	34	48	59	50	26	19	6	1
23	85	1	20	36	50	67	53	27	19	6	1
24	55	8	28	40	56	71	54	27	19	6	1

Table 2. The statistical probability of base output in a day for 365 curves

	Output Probability											
hour	1000	900–1000	800–900	700–800	600–700	500–600	400–500	300–400	200–300	100–200	0–100	Total
1				0.03	0.02	0.04	0.1	0.21	0.21	0.29	0.1	0.71
2				0.03	0.02	0.04	0.1	0.21	0.21	0.29	0.1	0.71
3				0.03	0.02	0.04	0.1	0.21	0.21	0.29	0.1	0.71
4				0.03	0.02	0.04	0.1	0.21	0.21	0.29	0.1	0.71
5				0.03	0.02	0.04	0.1	0.21	0.21	0.29	0.1	0.71
6				0.03	0.02	0.04	0.1	0.21	0.21	0.29	0.1	0.71
7				0.03	0.02	0.04	0.1	0.21	0.21	0.29	0.1	0.71
8				0.03	0.02	0.04	0.1	0.21	0.21	0.29	0.1	0.71
9				0.03	0.02	0.04	0.1	0.21	0.21	0.29	0.1	0.71
10	0.06			0.01	0.02	0.02	0.09	0.2	0.21	0.29	0.1	0.7
11	0.44				0.01	0.01	0.04	0.1	0.12	0.2	0.08	0.75

(continued)

Table 2. (continued)

	Output Probability											
hour	1000	900–1000	800–900	700–800	600–700	500–600	400–500	300–400	200–300	100–200	0–100	Total
12	0.9					0.01	0.01	0.02	0.02	0.03	0.01	0.9
13	0.97						0.01	0.01	0.01			0.97
14	1											1
15	0.98						0.01		0.01			0.98
16	0.98				0.01		0.01		0.01			0.98
17	0.98				0.01		0.01		0.01			0.98
18	0.97				0.01		0.01	0.01	0.01			0.97
19	0.89				0.01	0.01	0.03	0.02	0.03	0.01		0.89
20	0.65				0.04	0.08	0.1	0.06	0.05	0.02		0.65
21	0.37		0.02	0.08	0.11	0.15	0.13	0.07	0.05	0.02		0.76
22	0.3		0.04	0.09	0.13	0.16	0.14	0.07	0.05	0.02		0.73
23	0.23		0.05	0.1	0.14	0.18	0.15	0.07	0.05	0.02		0.7
24	0.15	0.02	0.08	0.11	0.15	0.19	0.15	0.07	0.05	0.02		0.76




Fig. 2. Calculation of probability diagram of the power transmission curves

5. From 21:00 to 24:00, there is a 40–50% probability that the transmission capacity will fall within the range of [4000 MW, 7000 MW).
6. The above power transmission curve patterns collectively explain more than 70% of the observed probabilities.

5 Conclusions

This study focuses on the optimal operation and power transmission curve for large-scale wind-solar-storage integration base in the SGB region, aiming for 100% renewable energy transmission. First, an optimization model was established to maximize the total multi-energy complementary power generation of the base, proposing an optimal hourly output profile. Subsequently, the output profile was refined using a three-stage power transmission curve through iterative optimization, yielding a three-stage output process (power transmission process) that meets the criteria of annual average abandonment rate of new energy below 10% and an annual average daily output guarantee rate of no less than 90%.

By analyzing the 8,760 h power transmission process over 365 days, this paper proposed a probabilistic power transmission curve based on the local energy resource generation characteristics. Through transmission curve analysis, more than 70% of the power transmission probabilities are quantitatively explained. Specifically: between 1:00 and 10:00, there is a 71% probability that power transmission falls within [1000 MW, 4000 MW). From 11:00 to 22:00, there is over a 30% probability of achieving full transmission capacity, with near-full transmission capacity practically achievable from 12:00 to 19:00. After 21:00, the probability of power transmission within [4000 MW, 7000 MW) gradually increases from approximately 40% to 45%.

The study of power transmission curves in this paper primarily relies on local renewable energy generation characteristics, without yet considering receiving-end demand. Future work should integrate electricity sending- and receiving-side considerations. Research indicates that the base has a probability of achieving full transmission during evening peak, primarily attributed to the configuration of energy storage resources, particularly the pivotal role of the 5,600 MW PSH. Subsequent studies will further analyze the impacts of different guarantee rates, abandonment rate of new energy, and energy storage configurations on power transmission curves.

Acknowledgment. This research is supported by National Key Research and Development Program of China (2024YFB2409002).

References

1. Wang, J., Chen, L., Tan, Z., et al.: Inherent spatiotemporal uncertainty of renewable power in China. *Nat. Commun.* **14**, 5379 (2023)
2. Wang, Y., Wang, R., Tanaka, K., et al.: Accelerating the energy transition towards photovoltaic and wind in China. *Nature* **619**, 761–767 (2023)
3. Li, F., Chen, D., Zhang, H., et al.: Research on the economy and power transmission price mechanism of desert-gobi-wasteland bases. *Price: Theory Practice* (08), 53–58+220 (2024). (in Chinese)
4. Gao, J.: A Research on operation of the pumped-storage, photovoltaic and wind power hybrid system. *Hydropower Pumped Storage* **6**(5), 25–29+37 (2020). (in Chinese)
5. Liu, S.X., Li, S.H., Li, D.Y., et al.: Research on flexible application schemes for sending-end system in LCC-HVDC. *Jilin Electric Power* **52**(4), 27–31 (2024). (in Chinese)

6. Gao, J., Wang, X., Gu, J.W., et al.: Research on simulation and prediction of photovoltaic power generation based on radiation models and machine learning method. In: Zheng, S.A. (ed.) Hydropower and Renewable Energies, IHDC 2024. Lecture Notes in Civil Engineering. Springer, Berlin.(in Chinese) (2024)
7. Gao, J., Zhu, F.L., Lu, Y.L., et al.: Discussion on development planning of multi-energy complementary clean energy bases. *Water Power* **49**(10), 7–11 (2023). (in Chinese)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Verification and Analysis of Phase Adjustment Operation Capability of a Certain Pumped Storage Units

Bobo Tian, Peilei Feng^(✉), Xiaoya Chen, Jiatong Lu, Haitang Mi, and Xi Wang

State Grid Xinyuan Anhui Jinzhai Pumped Storage Co., Ltd., Lu'an 237000, Anhui, China
2436353648@qq.com

Abstract. As a high-quality regulation resource in the new power system, pumped storage units play a significant role in enhancing the reactive power regulation capacity of the power grid and increasing the system's rotational inertia. The grid-connected operation of pumped storage units, through dynamic adjustment of reactive power output, provides crucial support for maintaining the reactive power balance and stabilizing the voltage of the power system. This study conducts multi-dimensional phase regulation capability tests on pumped storage units and quantitatively determines the limit capability indicators for stable phase regulation operation based on the coupling analysis of multiple constraints. The research results provide a scientific basis for optimizing the phase regulation operation strategy of the units, effectively enhancing the reactive power reserve capacity of the power grid, and have significant implications for fully leveraging the phase regulation role of pumped storage units in the power grid and improving the stability of the power system. The test scheme and analysis method introduced in this paper can serve as a reference for the assessment of phase regulation operation capabilities of pumped storage power stations under the jurisdiction of East China.

Keywords: Pumped storage units · Phase regulation operation · Leading phase · Lagging phase

1 Introduction

Currently, China is accelerating the construction of a new energy system and building a new power system [1]. The large-scale and high proportion development of new energy such as wind power and photovoltaics is becoming increasingly significant. With the increase in the proportion of new energy installed capacity and the degree of electrification of the power system, problems such as insufficient system voltage regulation capability and lack of rotational inertia have become increasingly prominent, which have a negative impact on the safe and stable operation of the power system and its ability to accept new energy generation. As an indispensable and important regulating resource in the new power system, pumped storage units have significant importance in enhancing the reactive power and voltage regulation support capability of the power grid and improving the level of rotational inertia.

At present, the phase modulation operation capability of pumped storage units in operation is mainly limited to the theoretical design stage. Research on the actual phase modulation operation capability of the units mostly focuses on their maximum leading phase capability, and provides little reference value for optimizing the phase modulation operation strategy of the units. In the current stage of constructing new power systems, it is particularly important to grasp the quantitative indicators of the actual phase regulation operation capability of pumped storage units and make reasonable use of them [2].

This article conducts experiments on the phase modulation ability of pumped storage units under different operating conditions. Based on the comparative analysis of experimental data and dynamic changes in unit operating parameters, combined with various limiting factors that affect the phase modulation operation ability of the unit, the ultimate capacity index of the unit in stable phase modulation operation is quantitatively determined. This research achievement has important practical significance for promoting the efficient utilization of flexible regulation resources in the new power system.

2 Exploration of Phase Adjustment Ability

2.1 Selecting Pumped Storage Test Units

A certain pumped storage power station has installed a total of 4 power generation (electric) units manufactured by General Electric Hydroelectric Equipment (China) Co., Ltd., and is designed with five stable operating conditions: power generation (G), pumping (P), power generation phase modulation (CG), pumping phase modulation (CP), and shutdown (S). The excitation of the 4 power generation (electric) units adopts the Guodian Nanrui NES6100 pumped storage self parallel excitation static rectification excitation system, and the reactive power can be freely adjusted under the four stable operating conditions except for shutdown.

The study on the phase regulation operation capability of pumped storage units selected the No.1 generator (electric) unit of the power station as the experimental unit. The electrical parameters are shown in the table below (Tables 1 and 2):

2.2 Determine the Phase Modulation Capability Test Items

During the phase modulation capability test of Unit 1 as a test unit, in order to maintain the stability of reactive power in the power system, the other three units were used as accompanying test units, and the phase modulation capability test of Unit 1 was conducted through reactive power balance in the factory.

To evaluate the phase modulation operation capability of the No.1 power generation (electric) unit under various stable operating conditions, a total of 12 phase modulation capability tests were developed for four stable operating conditions except for shutdown through analysis and research.

2.2.1 Phase Modulation Direction

1. Unit 1 pumping phase modulation steady-state condition leading and lagging phase tests;

Table 1. Electrical Parameters of Power Generation (Electric Motor)

type	Three phase, vertical axis semi umbrella, air-cooled synchronous reversible generator motor		
model	SFD300/335–18/7370	Manufacturer	General Electric Hydroelectric Equipment (China) Co., Ltd
rated voltage	$18 \pm 7.5\% \text{ kV}$	Rated frequency	50 Hz
Rated current	Power generation conditions	10691 A	
	Electric working condition	11191 A	
rated power	Power generation conditions	300MW	
	Electric working condition	335 MW	
Power factor	Power generation conditions	0.90 (lag)	
	Electric working condition	0.975 (ahead of schedule)	

Table 2. Electrical Parameters of Excitation System

	Power generation conditions	Electric working condition	unit
Excitation voltage at rated load (115 °C)	289	267	V
Excitation current at rated load	1896	1764	A
No load excitation voltage (115 °C)	147	147	V
No load excitation current	961	961	A
Maximum excitation voltage (115 °C)	302	274	V
Max Field Current	1978	1794	A
Strong excitation multiple	2	Strong incentive time	10s

- Unit 1's steady-state power generation phase modulation test includes phase advance and phase lag tests.

2.2.2 Pumping Direction

Steady state pumping condition leading and lagging phase tests for Unit 1.

2.2.3 Power Generation Direction

- Steady state power generation test of Unit 1 with 150 MW active phase leading and lag phase;

2. Steady state power generation test of Unit 1 with 225 MW active phase leading and lag phase;
3. Unit 1 is equipped with 300 MW active phase leading and lag phase tests under steady-state power generation conditions.

2.3 Setting the Operating Boundary of the Test Unit

Considering that although the maximum leading phase capacity test was conducted on the four power generation (electric) units during the grid related test, which can provide partial data support for the leading phase test of this test unit, other lag phase capabilities are still in the theoretical design stage, and the duration of phase modulation operation also needs to be analyzed and determined based on relevant standards and specifications and the actual operating limit of the units. Before this experiment, it is necessary to scientifically define the boundaries of the unit during the experimental operation period based on the actual operating values of Unit 1, manufacturer's design parameters, electromagnetic parameter boundary constraints [3], thermal stability limits, and technical data of water conservancy machinery characteristics, in order to prevent abnormal situations from affecting personal, power grid, and equipment safety.

When conducting the phase modulation capability test, any electrical parameter boundary in the table above is considered to have reached the maximum phase modulation capability of the current test, and the corresponding reactive power is adjusted in reverse. Continuing the thermal stability test, when the temperature rise of any other part reaches the boundary in the table above, it is considered to have reached the thermal stability operating limit.

2.4 Introduction to Test Methods

2.4.1 Preparation Before Phase Adjustment Ability Test

Before conducting 12 pumping phase modulation capability tests on Unit 1, the following preparations need to be made.

1. Confirm that the operation indicator instruments, reactive power transmitters, and other automation components related to the test unit and the accompanying test unit should be within the valid inspection period. Otherwise, they should be re inspected before the test to ensure the reliability and accuracy of the monitored data during the test process.
2. Confirm that the demagnetization and overvoltage protection status of the test unit and the accompanying test unit are correctly activated and the protection action value is greater than the theoretical maximum reactive power value of the unit. During the test, the test should be stopped when the protection approaches the action area to prevent tripping accidents caused by the protection action.
3. Confirm that the backup power supply for both high and low voltage in the entire factory is in operation and tested periodically to ensure reliable operation, in order to prevent related equipment from losing power due to the failure of the backup power supply during the testing process.

Table 3. Boundaries during the Test Operation of Unit 1

Parameter	limit
Terminal voltage (kV)	> 16.2(92.5%Un) < 19.68 (106%Un)
Stator current (A)	< 10691 (G)/11191 (M)
Excitation current (A)	< 1896 (G)/1746 (M)
500kV bus voltage (kV)	Pumping 500–515, power generation/phase modulation 500–520
10kV auxiliary power voltage (kV)	> 9.5, < eleven
400V factory power voltage (V)	> 361, < four hundred and twenty
Stator core temperature (°C)	< 120
Stator winding temperature (°C)	< 120
Upper guide tile temperature (°C)	< 75
Lower guide tile temperature (°C)	< 75
Thrust bearing temperature (°C)	< 80
Water guide bearing tile temperature (°C)	< 70
Sealing temperature of turbine main shaft (°C)	< 45
Temperature of labyrinth ring on water turbine (°C)	< 40
Vibration in the X, Y, and Z directions of the upper and lower frames (μ m)	< 70
Swing of upper and lower guide bearings in the X/Y direction (μ m)	< 300
Stator core X \ Y \ Z direction vibration (mm/s)	< 2.5

4. Confirm that the speed controller and excitation system of the test unit and the accompanying test unit are working properly and have been maintained regularly to prevent sudden equipment system failures from causing test failures.
5. Before the experiment, it is necessary to calculate the rotor resistance value of the test unit to determine the rotor temperature rise, which serves as the basis for measuring the rotor temperature. The calculation method is measured according to the rotor temperature rise resistance method [4] in the “Three phase Synchronous Motor Test Method” [4]:

$$R_2 = \frac{U_f}{I_f}$$

$$\theta_2 = \frac{R_2 - R_1}{R_1}(235 + t_1) + t_1 - t_2$$

In the formula: R1 is the cold state DC resistance of the rotor winding (Ω).

R2 is the thermal DC resistance of the rotor winding (Ω).

T1 is the winding temperature when measuring R1 (°C).

T2 is the average outlet temperature of the unit cooler when measuring R2 (°C).

6. Preliminary determination of the theoretical reactive power regulation capability of the test unit and the accompanying test unit. Conservatively establish the theoretical reactive power regulation range for each operating condition of the unit based on the network related test report and theoretical design power characteristic curve table, and do not exceed this range during the test period to prevent equipment abnormalities in the unit (Figs. 1 and 2).




Fig. 1. Power characteristic curve under power generation conditions




Fig. 2. Power characteristic curve of electric operating conditions

2.4.2 Methods and Steps for Phase Modulation Operation Test

Before starting the test, modify the excitation regulator of the test unit according to Table 4. Before starting the test, start the auxiliary unit to the pumping phase adjustment

Table 4. Theoretical reactive power regulation range of the unit

stable condition	meritorious	Progressive reactive power	Power factor	Hysteresis reactive power	Power factor
electric power generation	300 MW	−98 MVar	0.951	145 MVar	0.900
	220 MW	−130 MVar	0.866	150 MVar	0.832
	150 MW	−150 MVar	0.707	150 MVar	0.707
Power generation phase modulation	−5 MW	−190 MVar	−0.026	190 MVar	−0.026
Pumping phase modulation	−5 MW	−190 MVar	−0.026	191 MVar	−0.026
pump	−335 MW	−80 MVar	−0.973	110 MVar	−0.950

state. During the test, adjust the reactive power of the auxiliary unit according to the requirements of the test unit.

1. Test steps for phase advance capability and thermal stability of generator operating conditions:

Before connecting the test unit to the grid, record the zero power angle of the test unit at the rated speed and rated terminal voltage of the unit;

Adjust the active power of the test unit to the target rated active power (150MW, 225MW, 300MW), and adjust the reactive power to a lag phase of 20Mvar;

After the load parameters of the test unit meet the above requirements and stabilize (with a temperature change of no more than 1 °C within 1 h), record the raw data once;

Keep the active power of the test unit constant and gradually reduce its reactive power. When the leading reactive power of the test unit reaches 0MVar, stay for 5 min and record the data;

After the 0MVar stay of the test unit is completed, keep its active power unchanged and slowly reduce the excitation current of the test unit until any of the indicators in the operating parameter Table 3 of the test unit is reached. Stop demagnetization and record the reactive power (Q1) of the test unit at this time. Monitor the temperature changes of various parts of the test unit until they stabilize (temperature changes within 1 h do not exceed 1 °C) and record the data. Adjust the low excitation limit setting to ensure that the low excitation limit reactive power value corresponding to the target rated active power of the test unit is Q1;

Reduce the excitation current of the test unit to make its reactive power in the leading phase approach Q1. At this time, the low excitation limit of the test unit should act as a restriction and trigger a low excitation limit alarm. If the excitation current of the test unit is further reduced, the excitation current should no longer decrease and the reactive power in the leading phase should no longer increase. Increase the excitation current of the test unit, and then pull the test unit back to hysteresis operation;

Set the low excitation limit of the test unit under this (active) operating condition to 80% Q1, and then reduce its excitation current to make its incoming reactive power approach 80% Q1. Perform a 1% step change in the voltage of the test unit, activate the low excitation limit link, generate a low excitation limit signal, and record relevant data of the test unit.

2. Test steps for hysteresis capacity and thermal stability under power generation conditions:

Adjust the active power of the test unit to the target power while maintaining the power generation condition, with a reactive power of 0MVar. Slowly increase its reactive power during this process, and closely monitor the operating parameters of the test unit. If the parameters approach any of the indicators in Table 3, stop demagnetization in a timely manner, reduce the reactive power of the test unit, record relevant data of the test unit, and accompany the test unit to operate in phase as needed.

3. Pump phase modulation and thermal stability test steps:

Before connecting the test unit to the grid, record the zero power angle of the test unit at the rated speed and rated terminal voltage of the unit;

Adjust the test unit to the pumping phase control state and adjust the reactive power to a lag phase of 20 Mvar;

After the load parameters of the test unit meet the above requirements and stabilize (with a temperature change of no more than 1 °C within 1 h), record the raw data once;

Maintain the pumping phase adjustment state of the test unit, reduce its reactive power, and when the incoming reactive power reaches 0 MVar, stay for 5 min and record the data;

After the 0 MVar stay of the test unit is completed, keep its active power unchanged and continue to reduce the excitation current of the test unit until its operating parameters approach any of the indicators in the operating boundary. Stop demagnetization, record the reactive power (Q2) of the test unit at this time, and conduct a thermal stability test. Monitor the temperature changes of various parts until they stabilize, record the data, adjust the low excitation limit setting of the test unit, so that the corresponding low excitation limit reactive power value of the unit is Q2, and conduct a thermal stability test at the same time;

Reduce the excitation current of the test unit to make its incoming reactive power approach Q2. At this time, the low excitation limiting link of the test unit should act as a limiting element, and there should be a low excitation limiting signal. If the excitation current of the test unit is further reduced, the excitation current should no longer decrease, the incoming reactive power should no longer increase, and relevant data of the test unit should be recorded;

Increase the excitation current of the test unit, and then pull the motor back to lag phase operation.

4. Pump phase modulation hysteresis capacity and thermal stability test steps:

Before connecting the test unit to the grid, record the zero power angle of the test unit at the rated speed and rated terminal voltage of the unit;

Adjust the test unit to the pumping phase control state and adjust the reactive power to 0 Mvar;

The unit maintains a pumped phase control state with a reactive power of 0 MVar. At this time, slowly increase the reactive power of the unit while conducting a thermal stability test; During this process, it is necessary to closely monitor the test unit until its operating parameters approach any of the indicators in Table 3. The demagnetization should be stopped in a timely manner, the reactive power should be reduced, and the accompanying test unit should be operated as needed.

5. Test steps for power generation phase modulation capability and thermal stability: Adjust the test unit to the power generation phase modulation state and repeat (3) the test content.
6. Test steps for power generation phase modulation hysteresis capability and thermal stability: Adjust the test unit to the power generation phase modulation state and repeat (4) the test content.
7. Pumping conditions and thermal stability test steps:

Before connecting the test unit to the grid, record the zero power angle of the test unit at the rated speed and rated terminal voltage of the unit;

Adjust the test unit to the pumping state and adjust the reactive power to 0Mvar;

After the load parameters of the test unit meet the above requirements and stabilize (with a temperature change of no more than 1 °C within 1 h), record the raw data once;

Maintain the active power of the test unit unchanged and reduce its reactive power. When the incoming reactive power of the test unit reaches 0MVar, stay for 5 min and record the data;

After the 0MVar stay of the test unit is completed, keep its active power unchanged and continue to reduce the excitation current of the test unit until the operating parameters of the test unit approach any of the indicators in Table 3. Stop demagnetization and record the reactive power of the test unit at this time (Q3). Monitor the temperature changes in various parts until they stabilize and record the data. Adjust the low excitation limit setting to ensure that the corresponding low excitation limit reactive power value of the test unit is Q3;

Slowly reduce the excitation current of the test unit to bring the reactive power in the leading phase close to Q3. At this point, the low excitation limiting link of the test unit should act as a limiting element, and there should be a low excitation limiting signal. Then reduce the excitation current again, and the excitation current of the test unit should no longer decrease. The reactive power in the leading phase should no longer increase, and relevant data of the test unit should be recorded;

Increase the excitation current of the generator and then pull the motor back to lag phase operation.

8. Test steps for hysteresis capacity and thermal stability under pumping conditions:

Keep the test unit in a pumping state with a reactive power of 0MVar, and slowly increase its reactive power. During this process, it is necessary to closely monitor the operating parameters of the test unit. If the parameters approach any of the indicators in Table 3, the demagnetization should be stopped in a timely manner, the reactive power

of the test unit should be reduced, relevant data of the test unit should be recorded, and the accompanying test unit should be operated according to the needs.

3 Multidimensional Quantitative Analysis

3.1 Phase Modulation Capability Test Data

(See Table 5)

3.2 Quantitative Analysis of Phase Modulation Capability

Multi dimensional analysis was conducted on the test data of Unit 1's steady-state phase modulation capability under four operating conditions. The operating time for both power generation and pumping phase modulation conditions was 4 h. Additionally, due to the fact that the technical water supply and drainage points of the unit were located in front of the tailgate during phase modulation operation, the water flow did not pass through. Therefore, the temperature of the technical water supply slowly increased with the running time of the random group, which had a certain impact on the cooling effect [5].

3.2.1 Analysis of Stator bar Temperature Rise

During the phase modulation capability test of Unit 1, the temperature trend of 54 stator coil measuring points was basically consistent with the trend of stator current changes, first slowly rising and then basically reaching stability. The highest temperature QP27 reached 43.74 °C, with a stator current of about 2711 A at that time. The second highest temperature QP54 reached 43.09 °C, with a stator current of about 2711 A at that time. The third highest temperature QP440 reached 41.00 °C, with a stator current of about 2711 A at that time. The temperature during the entire experimental operation was far from the first level alarm temperature of the stator coil, which was 120 °C. The maximum temperature rise was QP54, and the temperature rise at this point was about 2.64K, which was lower than the maximum allowable temperature rise of 78K.

3.2.2 Trend Analysis of Air Cooling Temperature:

The temperature trend of the 10 measuring points of the air-cooled hot air in Unit 1 is basically consistent with the temperature change trend of the stator core. The highest temperature QP6 reached 40.22 °C, and the stator core temperature was around 43 °C at that time. The second highest temperature QP8 reached 38.11 °C, and the stator core temperature was around 43 °C at that time. The third highest temperature QP1 reached 37.94 °C, and the stator core temperature was around 43 °C at that time. During the entire phase modulation capability test, the air cooling temperature was far from the first level alarm temperature of the hot air, which was 75 °C. The maximum temperature rise was QP2, and the temperature rise at this point was about 1.26 K, which was relatively low.

Table 5. Phase Adjustment Ability Test Data for Unit 1 under Various Operating Conditions

working condition	active power	reactive power	Power factor	power angle	Terminal voltage	auxiliary power	System Voltage	notes
	MW	Mvar	cosφ	°	kV	400V	kV	
electric power generation 100%PN	299.61	26.32	0.996	23.1	17.88	387.5	518.3	initial state
	300.24	139.87	0.906	17.5	18.71	411.2	517.8	lagging phase
	301.52	-84.24	0.963	36.2	16.85	369.1	515.3	leading phase
electric power generation 75%PN	224.06	25.93	0.993	16.3	17.88	391.6	518.8	initial state
	223.21	163.04	0.808	11.3	19.04	417.0	518.3	lagging phase
	223.53	-114.51	0.890	32.2	16.71	365.3	516.8	leading phase
electric power generation 50%PN	149.06	28.22	0.983	10.5	17.98	392.5	518.3	initial state
	149.13	166.09	0.669	8.7	19.04	418.2	519.2	lagging phase
	149.08	-123.85	0.769	25.2	16.66	365.0	516.3	leading phase
electric power generation phase modulation	-4.03	24.61	-0.160	2.5	17.73	392.8	519.7	initial state
	-4.37	166.64	-0.026	0.8	19.08	419.7	519.2	lagging phase
	-4.12	-123.33	-0.033	3.2	16.66	369.8	516.3	leading phase
pump phase modulation	-3.23	22.62	-0.140	2.2	17.98	391.8	518.3	initial state
	-4.14	174.04	-0.024	0.9	19.08	415.6	519.7	lagging phase
	-4.22	-130.15	-0.032	5.1	16.66	364.1	516.8	leading phase
pump working condition	-303.07	18.51	-0.998	21.3	17.73	387.6	517.8	initial state
	-303.15	108.56	-0.941	15.4	18.31	403.1	515.8	lagging phase
	-306.06	-96.13	-0.954	31.2	16.66	364.2	514.4	leading phase

The temperature trend of the 10 measuring points for air-cooled cold air is basically consistent with the temperature change trend of the technical water supply. The highest temperature QP5 reached 20.92 °C, and the technical water supply temperature was around 15.8 °C at that time. The second highest temperature QP10 reached 18.29 °C, and the technical water supply temperature was around 15.8 °C at that time. The third highest temperature QP2 reached 18.22 °C, and the technical water supply temperature was around 15.8 °C at that time. The temperature during the entire operation period is

far from the first level alarm temperature of 40 °C for the air-cooled cold air, and the maximum temperature rise is QP9. The temperature rise at this point is about 1.9K, which is relatively low; The temperature trend of air-cooled and hot air is normal during the phase modulation capability test operation.

3.2.3 Trend Analysis of Technical Water Supply Temperature

During the power generation and pumping phase adjustment test operation of Unit 1, the technical water supply temperature was 13.77 °C before the start of the phase adjustment condition, and the highest technical water supply temperature was 15.87 °C. When the unit was shut down, the technical water supply temperature was 15.13 °C. The maximum temperature rise of the technical water supply during the operation of the unit was 2.1K, and the temperature rise was relatively low; During the start-up and pumping tests of Unit 1, the phase modulation condition was approximately 0.7 °C higher. Due to the fact that the water intake and drainage points of the technical water supply are located in front of the tailgate during the operation of the unit under phase modulation conditions, the water flow does not circulate. Therefore, the temperature of the technical water supply slowly increases with the running time of the random group. Under steady-state operation under phase modulation conditions, the temperature trend of the technical water supply is normal.

3.2.4 Trend Analysis of Temperature of Each Guide Tile

During the trial operation of Unit 1, the upper guide tile temperature QP5 reached its highest value of 53.07 °C after about 2 h of operation, which is far from the first level alarm limit of 75 °C. The lower guide tile temperature QP7 reached its highest value of 60.40 °C, which is far from the first level alarm limit of 75 °C. It is inferred that the tile temperature QP5 reached its highest value of 60.34 °C, which is far from the first level alarm limit of 80 °C. From the tile temperature trend analysis, after about 2 h of operation of the unit, the water guide tile temperature QP9 reached its highest value of 58.46 °C, which is far from the first level alarm limit of 70 °C. From the analysis of the temperature trend of each guide tile, the temperature at each guide tile temperature measurement point basically stabilizes after about 2 h of unit operation, and the increase does not exceed 0.5 °C after 1 h of operation. During the experiment, the temperature trend of each guide tile was normal.

3.2.5 Analysis of Three Way Swing and Vibration Trends of Rack and Top Cover

During the phase modulation capability test operation of Unit 1, the swing of the upper guide, lower guide, and water guide basically stabilized after the unit was connected to the grid. The swing of the upper guide in the X direction remained at around 90 μm, and the swing in the Y direction remained at around 92 μm; The deflection in the X direction is maintained at around 56 μm, and the deflection in the Y direction is maintained at around 61 μm; The deflection of the water guide in the X direction is maintained at around 25 μm, and the deflection in the Y direction is maintained at around 30 μm; The distance from the first level limit of 300 μm is relatively far. The vibration in the X direction of the

upper frame remains at around 17 μm , the vibration in the Y direction remains at around 19 μm , and the vibration in the Z direction remains at around 40 μm ; The vibration in the X direction of the lower rack is maintained at around 16 μm , the vibration in the Y direction is maintained at around 13 μm , and the vibration in the Z direction is maintained at around 30 μm ; The vibration of the top cover in the X direction is maintained at around 7 μm , the vibration in the Y direction is maintained at around 6 μm , and the vibration in the Z direction is maintained at around 3 μm ; The distance from the first level alarm limit of 75 μm is relatively far. During the entire phase modulation capability test, the swing trends of the upper guide, lower guide, and water guide of Unit 1 were normal, and the vibration trends of the upper frame, lower frame, and top cover were normal.

3.2.6 Analysis of Temperature Trends of Main Shaft Seals and Leak Arrest Rings

During the power generation and pumping phase adjustment test operation of Unit 1, the main shaft seal water supply temperature was about 0.5 $^{\circ}\text{C}$ higher than the technical water supply temperature, and the leakage prevention ring water supply temperature was about 0.2 $^{\circ}\text{C}$ lower than the technical water supply temperature. The trend of the main shaft seal and leakage prevention ring water supply temperature increased slowly with the rise of the technical water supply temperature. The main shaft seal temperature was 15.39 $^{\circ}\text{C}$ during the steady-state operation of the unit's pumping phase adjustment and grid connection. During the steady-state operation of the unit's pumping phase adjustment and grid connection, the main shaft seal temperature slowly increased, with a maximum value of 17.47 $^{\circ}\text{C}$ and a maximum temperature rise of 2.08 K, far from the first level alarm limit of 45 $^{\circ}\text{C}$. The temperature of the upper leakage prevention ring was 15.91 $^{\circ}\text{C}$ during the steady-state operation of the unit's pumping phase adjustment and grid connection. The temperature of the leakage ring slowly increased, reaching a maximum of 20.48 $^{\circ}\text{C}$. After running for more than 4 h, the maximum temperature rise was 4.57 K. The distance from the first level alarm limit of 40 $^{\circ}\text{C}$ is relatively far. Under the test operation of power generation and pumping phase adjustment, the temperature trend of the main shaft seal and upper leakage ring is normal and slowly increases with the steady-state operation time of the unit phase adjustment.

3.2.7 Analysis of Rotor Temperature Rise Trend and Power Angle

During the trial operation of Unit 1, the temperature rise of the rotor varied with the rotor current and remained within the allowable temperature rise range.

According to the analysis of the actual measurement data of Unit 1's incoming phase, the maximum power angle of the generator is 36.2 $^{\circ}$ at the active incoming phase of -123.8Mvar, with sufficient low excitation reserve within this range, and the incoming phase can operate normally and reliably.

The No.1 generating (electric) unit of the pumped storage power station is operating normally as a test unit and the equipment is in good condition. The AGC of the test unit has been shut down, AVC has not been put into operation, and functions such as low excitation limit, minimum excitation current limit, and demagnetization protection have been put into normal operation. According to scheduling requirements, the test unit will operate normally during the phase leading test (Table 6).

Table 6. Phase Adjustment Capacity Limitation Data for Unit 1 under Various Operating Conditions

working condition	P (MW)	Q (Mvar)	state	limiting factor	Running time
electric power generation 100%PN	300.24	139.87	lagging phase	Excitation current approaching limit value	59 points
	301.52	−84.24	leading phase	The terminal current is approaching the limit value	57 points
electric power generation 75%PN	223.21	163.04	lagging phase	Excitation current approaching limit value	58 points
	223.53	−114.51	leading phase	The terminal voltage is close to the limit value	57 points
electric power generation 50%PN	149.13	166.09	lagging phase	The terminal voltage is close to the limit value	52 points
	149.08	−123.85	leading phase	The terminal voltage is close to the limit value	50 points
electric power generation phase modulation	−4.37	166.64	lagging phase	The terminal voltage is close to the limit value	240 points
	−4.12	−123.33	leading phase	The terminal voltage is close to the limit value	240 points
pump phase modulation	−4.14	174.04	lagging phase	The terminal voltage is close to the limit value	250 points
	−4.22	−130.15	leading phase	The terminal voltage is close to the limit value	250 points

(continued)

Table 6. (continued)

working condition	P (MW)	Q (Mvar)	state	limiting factor	Running time
pump working condition	−303.15	108.56	lagging phase	Excitation current approaching limit value	59 points
	−306.06	−96.13	leading phase	The terminal voltage is close to the limit value	51 points

4 Conclusion

After conducting 12 capacity tests under 4 stable operating conditions on the first generation (electric) unit of a pumped storage power station, the test data for each operating condition were obtained. After multidimensional scientific analysis of the test data, the phase modulation operation capability of Unit 1 was determined. The specific recommended operating indicators are as follows:

Power generation condition: With 50% rated output, the recommended reactive power regulation range is -90 – 120 MVA, and the operating time is 1 h; Recommended reactive power adjustment range with 75% rated output is -80 – 120 MVA, with a running time of 1 h; Recommended reactive power adjustment range with 100% rated output is -65 – 100 Mva, with a running time of 1 h.

Pumping phase modulation condition: It is recommended to adjust the reactive power within a range of -100 – 120 Mva and operate for 5 h. Power generation phase adjustment condition: It is recommended to adjust the reactive power within a range of -100 – 120 Mva and operate for 5 h.

Pumping condition: It is recommended to adjust the reactive power within a range of -65 – 80 Mva and run for 1 h.

Fund Projects. 1. National Natural Science Foundation of China (Grant Nos. 61761049, 61461055)

2. Yunnan Provincial Applied Basic Research Program Project (2017FD120)

3. Yunnan Minzu University Graduate Innovation Fund Key Project (2018YJCXS)

4. Yunnan Power Grid Company Technology Innovation Project (OSOOOOKK52150006)

References

1. Zheng, Q., Supeng, J.: Research on coordinated optimization technology of phase adjustment operation of hydroelectric units and new energy generation. *Power Syst. Protect. Control* **53**(03), 108–119 (2025)
2. Hu, N., Kong, L., Jiang, F.: The necessity and feasibility analysis of long term stable phase adjustment operation of pumped storage units. *Hongshuihe* **40**(05), 1–5 (2021)
3. Wang, Y., Chen, G.: Application research on the operating state of synchronous machine power limit operation diagram. *China Electric Power Educ. (S3)*, 173–176 (2006)

4. Liu, Z., Xu, J., Shu, Y., et al.: Correction method for rotor winding temperature and temperature rise test. *Power Plant Syst. Eng.* **38**(02), 55–58 (2022)
5. Liu, Q., Cheng, L., Guo, S., et al.: Analysis of technical issues and measures for long term phase adjustment operation of pumped storage units. *Hydroelectric Power Station Electromech. Technol.* **47**(11), 6–9 (2024)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Preliminary Conception of the Capacity Optimization and Allocation Platform for Multi-Energy Complementation of Hydro-Wind-Solar-Storage Clean Energy Bases

Jingyi Li¹(✉), Jie Gao², Xu Wang², Pin Zhang¹, and Dong Zhang²

¹ Power China Northwest Engineering Corporation Limited, Xian, China
2286322159@qq.com

² China Renewable Energy Engineering Institute, Xian, China

Abstract. Aiming at the problem of formulating and optimizing capacity configuration schemes for multi-energy complementary power sources during the planning and design phase of hydro-wind-solar-storage clean energy bases, this paper constructs a comprehensive platform architecture and technical system. First, it sorts out data resources and model algorithms to establish a digital-intelligent business platform integrating functions like power source topological relation setting, multi-scenario simulation, and visualized analysis of simulation results. Taking a typical hydro-wind-solar-storage base in a river basin as a case study, the research verifies the platform's applicability through comparative analysis of configuration schemes under different energy complementarity scenarios, providing quantitative decision support for optimal capacity allocation.

Keywords: multi-energy complementarity · capacity optimization and allocation · clean energy base · application system

1 Introduction

The centralized development of hydro-wind-solar-storage clean energy bases, as a 100% clean energy development model, involves preliminary planning and research results covering major basin hydro-wind-solar integrated bases such as the Yalong River, Upper Yellow River, and Upper Jinsha River, as well as large-scale wind and photovoltaic bases in desert, Gobi, and barren areas (e.g., Kubuqi, Ulan Buh, Tengger) supported by pumped storage power stations as regulating power sources. The installed capacity exceeds 100 million kilowatts.

The development of hydro-wind-solar-storage clean energy bases takes wind and solar new energy power as the main body, uses surrounding conventional hydropower and pumped storage as regulating power sources for capacity support, and relies on power transmission channels as important carriers to form a new energy supply and consumption system. This is of great significance for China to achieve its “Double Carbon” goals.

2 Research Background

Driven by the “Double Carbon” goals, the capacity optimization and configuration of clean energy bases has become a research hotspot, requiring consideration of the stochastic volatility characteristics of new energy, system simulation operations, and multi-objective optimization needs. Existing research on handling stochastic volatility is divided into two types: those based on typical daily/weekly scenarios, which simplify calculations but have limitations in scenario coverage and result accuracy, like Guo Li [1] et al.’s use of a comprehensive evaluation index system for typical day selection in microgrid wind-solar-storage planning; and 8,760-h operation simulations, which comprehensively capture wind and solar power output characteristics to enhance scheme reliability, as demonstrated by Jiang Haiyang [2] et al. in high-proportion clean energy power system planning. Double-layer planning models for multi-energy complementary power systems are now mainstream, with the upper layer optimizing installed capacity for economic and low-carbon goals and the lower layer focusing on operational scheduling to ensure power stability and resource coordination, as shown in the models proposed by Zhou Yerong [3], An Yuan [4], etc. Research on model objectives has evolved from single to multi-objective planning, such as Li [5] et al.’s long-term hydro-solar optimization model and Yu Yi [6] et al.’s short-term multi-objective thermal-wind model. Overall, there is an urgent need to optimize the capacity configuration and simulation operation of sending-end power sources in the planning of hydro-wind-solar-storage clean energy bases to meet transmission curve requirements. This paper proposes a platform architecture and technical system for such bases and demonstrates its effectiveness through a practical case.

3 Platform Vision

In accordance with the requirements of technical standards for comprehensive development projects of hydro-wind-solar-storage renewable energy, the following detailed workflow is proposed:

1. Define the design scope and design reference year;
2. Collect and organize basic data;
3. Participate in selecting potential power sources for multi-energy complementarity and set planning scenarios;
4. Determine comparison objectives and select technical and economic indicators for schemes;
5. preliminarily formulate a library of capacity configuration schemes for each power source;
6. Simulate and calculate the technical and economic indicators of each scheme in the library;
7. Compare the technical and economic indicators of each scheme in the library;
8. Select the recommended scheme;
9. Carry out preliminary design of each power generation project and gathering lines for the recommended scheme.

Based on the decomposition of the above workflow, the implementation steps of the system are as follows:

1. Basic Information Setup: Configure basic information such as the base name, design reference year, scheme development time, and personnel.
2. Engineering Digital Information Import: Define the base planning scope by drawing a boundary, and select power source types and specific power generation projects involved in multi-energy complementarity.
3. Calculation Unit and Cascade Hydropower Topology Setup: Preliminary judge the power connections between multi-type power sources to construct calculation units; set the topological relationships between cascade hydropower stations within each calculation unit, and link the hydropower topologies across units to form a global cascade hydropower topology.
4. Calculation Model and Mode Selection: Select calculation models, time periods, operation modes (hydro-wind-solar-storage combination types), and objectives for multi-power-source multi-energy complementarity operation simulation.
5. Power Source Boundary Condition Setup: Input basic data for each power source type (e.g., power station name, installed capacity, static investment); configure time-period boundary conditions for power source operations (e.g., period-specific power output, upper/lower limits of power output, maintenance capacity by period).
6. Power Transmission Setup: Enter basic information for power transmission projects (e.g., maximum transmission capacity, economic utilization hours); define time-period transmission requirements (e.g., typical power transmission curves).
7. Simulation Scenario Setup: Set upper/lower limits and step sizes for installed capacity schemes of various power sources; for pumped storage/battery energy storage stations, configure upper/lower limits and step sizes for continuous power generation hours.
8. Simulation Calculation: Configure model parameters, invoke platform calculation services, and execute multi-power-source multi-energy complementarity operation simulations to obtain technical and economic indicator results and time-period processes (including water levels, reservoir capacities, power outputs, etc.) for each capacity configuration scheme.
9. Calculation Result Presentation: Visualize multi-power-source multi-energy complementarity operation simulation results for each capacity configuration scheme through functional modules (including statistical data and linked charts); automatically compare/order schemes based on user-defined criteria to identify recommended schemes, and provide functions for saving and pushing recommended schemes.

4 Design of Platform Functional Modules

Aiming at the capacity optimization and configuration needs in the planning and design stage of clean energy bases, corresponding functional module designs are proposed according to the above workflow and implementation steps. See Fig. 1 for details.




Fig. 1. Schematic Diagram of Platform Functional Modules

5 Case Validation

Taking a wind-solar-storage clean energy base in a basin in Southwest China as an example, this study temporarily takes maximizing the base's total power generation as the goal, selects 50% frequency inflow and hourly new energy output as model inputs, and carries out multi-energy complementary operation simulation and configuration scheme optimization calculations with an annual scheduling period and hourly scheduling intervals.

5.1 Scheme Creation

According to the types of power sources available within the base's planning scope, the power sources of the base are determined to be pumped storage, hydropower, and photovoltaic, including: 3 hydropower stations (total scale: 5 million kW), 1 pumped storage power station, and 3 photovoltaic power plant clusters (total scale: 18 million kW). A specific year is selected for simulation with an hourly time step. Considering the base's commissioning in 2030, an operation period of 40 years, a discount rate of 8%, a tax rate of 25%, a preliminary on-grid electricity price of 0.35 yuan/kWh, the model's optimization objective is set to maximize the on-grid power of the complementary system.

$$E = \max \sum_{t=1}^T \sum_{j=1}^J N_j^t \times \Delta t$$

E represents the grid-connected power, in ten thousand kWh; J denotes the types of power sources in the base, which are photovoltaic, hydropower, and pumped storage in this case; N_j^t is the output of power source j during period t , in ten thousand kW; Δt is the duration of each period, in h; T is the number of periods in the simulation cycle.

5.2 Simulation Scheme Setup

Using the total power station resources of the base as the upper limit for scale configuration, the installed capacity of the pumped storage power station is set between 1.8 and 3 million kW with a step size of 0.6 million kW; the installed capacity of the photovoltaic cluster is set between 6 and 18 million kW with a step size of 1 million kW; since all hydropower stations are newly built, they are all included in the integrated scheme to fully utilize their regulation capabilities, ultimately forming a scheme library of installed capacity combinations for each power source.

5.3 Simulation Scheme Setup

Through simulation calculations for each scheme in the scheme library, evaluation indicators such as on-grid power, photovoltaic on-grid power, photovoltaic curtailment, photovoltaic curtailment rate, channel utilization hours, total investment, economic net present value, and levelized cost of electricity are obtained (see Table 1 for details). First, using a new energy utilization rate of not less than 90% (photovoltaic curtailment rate not exceeding 10%) and power transmission channel utilization hours of not less than 5,000 h as the boundary conditions for scheme selection, Schemes 2, 3, 5, 6, 9, and 12 meet the requirements (see Fig. 2 for details). It can be seen that as the scale of photovoltaic power plants decreases and the scale of pumped storage power stations increases, the base's curtailment rate decreases accordingly.




Fig. 2. Comparison of New Energy Curtailment Rates Among Multiple Schemes in a Certain Base

Then, further determine the recommended scheme for the base based on economic indicators such as the levelized cost of electricity (LCOE) and economic net present value (ENPV). As Scheme 2 shows the best economic performance (see Fig. 3), it is selected as the recommended scheme. The total installed capacity of the base is 23.4 million kW, including 5 million kW of hydropower, 16 million kW of photovoltaic power, and 2.4 million kW of pumped storage power stations.




Fig. 3. Economic Comparison of Multiple Schemes in a Certain Base

Table 1. Simulation Results of Representative Schemes in a Certain Base's Scheme Library

Scheme Number	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
Power Transmission Capacity (10MW)	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800
Total Installed Capacity (10MW)	2280	2340	2400	2330	2390	2450	2380	2440	2500	2429	2490	2550	2480	2540	2600
Photovoltaic Installed Capacity (10MW)	1600	1600	1600	1650	1650	1650	1700	1700	1700	1750	1750	1750	1800	1800	1800
Pumped Storage Installed Capacity (10MW)	180	240	300	180	240	300	180	240	300	180	240	300	180	240	300
On-Grid Electricity (100 million kWh)	473.6	480.0	484.4	476.6	483.5	488.4	479.3	486.7	492.0	481.8	489.7	495.4	484.1	492.5	498.4
Photovoltaic On-Grid Electricity (100 million kWh)	229.9	238.5	244.3	233.3	242.6	249.1	236.4	246.4	253.4	239.3	249.9	257.4	242.0	253.2	261.1
Photovoltaic Curtailed Electricity (100 million kWh)	30.39	21.82	15.96	35.13	25.86	19.37	40.12	30.17	23.16	45.35	34.75	27.28	50.82	39.59	31.70
Photovoltaic Curtailment Rate (%)	11.68	8.38	6.13	13.09	9.63	7.22	14.51	10.91	8.37	15.93	12.21	9.58	17.35	13.52	10.83
Channel Utilization Hours (h)	5920	6000	6055	5957	6044	6105	5991	6084	6150	6022	6122	6192	6051	6157	6231
Total Investment (100 million yuan)	1650	1722	1794	1682	1754	1826	1714	1786	1858	1746	1818	1890	1778	1850	1922
Economic Net Present Value (100 million yuan)	883	920	956	900	936	973	916	953	989	932	969	1006	948	986	1022
Investment per Kilowatt (yuan/kW)	7237	7359	7475	7219	7339	7453	7202	7320	7432	7188	7301	7412	7169	7283	7392
Levelized Cost of Electricity (yuan/kWh)	0.8530	0.8779	0.9059	0.8640	0.8876	0.9144	0.8752	0.8976	0.9234	0.8867	0.9079	0.9328	0.8985	0.9185	0.9425

6 Conclusion

This paper focuses on the formulation and optimization of installed capacity configuration schemes for multi-power-source integrated development with multi-energy complementarity in the planning and design stage of clean energy bases. It combs through the main workflow and establishes a series of implementation steps according to the platform system architecture, including power source type and project selection, calculation unit topology setting, calculation model and mode selection, boundary condition configuration, scenario simulation calculation, and result presentation. Taking a hydro-wind-solar-storage clean energy base in a certain basin as a case study, the applicability of the platform's functions is verified. The paper analyzes the key technical and economic indicators and comparison points that need to be focused on in the base's capacity configuration, and proposes a systematic solution serving the planning of clean energy bases. If you wish to highlight text using a box, please use the "Box" button to ensure it is formatted correctly. If you wish to emphasise certain words or phrases in the text, please use italics, not bold or underlining.

Acknowledgment. This research is supported by National Key Research and Development Program of China (2024YFB2409002).

References

1. Guo, L., Yang, S.Q., Liu, Y.X., et al.: Method for selecting typical days in capacity planning of wind-solar-storage microgrids. *Proc. Chin. Soc. Electric. Eng.* **40**(8), 2468–2479 (2020)
2. Jiang, H.Y., Du, E.S., Jin, C., et al.: Multi-timescale storage capacity optimization planning for high-ratio clean energy interconnected power systems across countries. *Proc. Chin. Soc. Electric. Eng.* **41**(6), 2101–2115 (2021)
3. Zhou, Y.R., Li, X.R., Sheng, B.Y., et al.: Study of wind-photovoltaic optimal capacity configuration in hydro-wind-photovoltaic-pumped storage complementary power generation system. *Water Resources Hydropower Eng.* **54**(11), 1–14 (2023)
4. An, Y., Zheng, S.Y., Su, R., et al.: Dual-level optimization study of wind-solar-water-storage multi-energy complementary power systems. *Acta Energiæ Solaris Sinica* **44**(12), 510–517 (2023)
5. Li, F.F., Qiu, J.: Multi-objective optimization for integrated hydro–photovoltaic power system. *Appl. Energy* **167**, 377–384 (2016)
6. Yu, Y., Zhao, H.S., Yang, D.J., et al.: Short-term optimal operation of hydropower thermal-wind multi-energy system considering uncertainty of wind power. *Water Resources Power* **40**(11), 217–220+216 (2022)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Evaluation Research on Energy Dissipation Layout of Parallel Spillway Tunnels in Narrow Valleys

Wang Yu¹(✉), Hu Hao², Xue Yang³, Gu Jinde¹, Zhao Jianjun¹, Liu Jingkai¹,
Li Tianyu², and Peng Yu³

¹ The National Key Laboratory of Water Disaster Prevention, Nanjing Hydraulic Research Institute, Nanjing 210029, China

wangy@nhri.cn

² Huaneng Jiangsu Clean Energy Branch, Nanjing 210015, China

³ Power China Huadong Engineering Corporation Limited, Hangzhou 311122, China

Abstract. The energy dissipation safety of the single-sided parallel spillway tunnels in narrow valleys is the key to ensuring the flood discharge safety. The layout methods and evaluation indicators of spillway tunnels can effectively measure the layout reliability of. Presently, the overall layout of spillway tunnels mostly relies on model tests, and indicative evaluation methods are still rare. Based on energy dissipation and the stability of bank slopes, this paper proposes the capacity index of the energy dissipation in narrow valley. Combining the non-superposition of scour holes and the energy dissipation effect, a layout method of the spillway tunnels with multi-objective hydraulic coordination is established. The rationality of the evaluation indicators has been verified by the energy dissipation schemes of 300-m-level high dam spillways in narrow valleys such as Baihetan and LCRM Hydropower station.

Keywords: parallel spillway tunnels · energy dissipation · layout methods · narrow valleys

1 Introduction

Flood discharge safety is the top priority for ensuring the hub operation. For high arch dams, spillway tunnel is an important release flood structure to ensure the safe flood discharge. The spillway tunnels often adopt ski-jump energy dissipation, which relies on the flip buckets at the end of the spillway tunnels to allow high-speed water flow to be freely diffuse, aerate and collide in the air. Simultaneously, huge kinetic energy is dissipated by turbulent diffusion formed by the water jet falling into the water cushion, the rolling and shearing effect between jet and the surrounding water, which reduces the downstream scour and ensures flood discharge safety of spillway tunnels [1–3].

The layout difficulty of single-sided centralized parallel spillway tunnels lies in the complexity of energy dissipation. Compared with bilateral-arrangement spillway tunnels dissipating energy by jet collide, the single-sided spillway tunnels bring greater

challenges to downstream scour and the protection of the bank slope [4–6]. To evaluate the energy dissipation effect to the narrow valley downstream of spillway tunnels, this paper proposes an energy dissipation capacity evaluation index that takes energy dissipation and spatial point control as the main principles, which determines the layout of spillway tunnels by comprehensively considering the hydraulic characteristics such as water cushion depth and jet impact point, and examines whether the river valley capacity meets energy dissipation requirements. The key objectives of parallel spillway tunnels layout are the non-superposition of energy dissipation fields and jet diffusion, which reflected in the control of scour and jet impact point. The jet should be safely flipped without impacting both sides of the bank, and the jet diffusion and the scour formed by different spillway tunnels in the downstream river should not be superposition. Moreover, the flow velocity along the bank should be controlled to ensure the stability of the bank slope.

2 Evaluation Methods of River Capacity

The important principle for determining the energy dissipation capacity index downstream of the spillway tunnels is the energy dissipation and the stability of the bank slopes on both sides of the river valley. A significant sign of insufficient energy dissipation capacity is that the area and depth of the scouring pit endanger the bank slopes on both sides. Therefore, it is important to assess whether the slopes before and after the scouring pit endanger the bank slopes. The river energy dissipation mainly considers parameters such as jet impact point, the depth of the scouring pit and the width of the river channel. It is of great benefit to guiding the design to establish a determination method for the layout of the spillway tunnels based on the energy dissipation capacity of the river channel and judging the reliability of the layout of the spillway tunnels based on parameter settings and the current situation.

2.1 Energy Dissipation Index

Based on the principle that the energy dissipation capacity of the river valley involves that the area and depth of the scouring pit not endanger both-sides bank slopes, the scale of the scouring pit and the width of the river valley are first adopted to evaluate the energy dissipation capacity. Here, the main control parameter is the width of narrow valley considering the depth of the scouring pit and the average slope ratio of the scouring pit, etc. According to the scouring equation proposed by Chen Chunting $T = Kq^{0.5}Z^{0.25}$, the relationship to evaluate the width river valley B is:

$$B > f(K, q, Z, \bar{i}_q, \bar{i}_h) \quad (1)$$

here, K is the anti-scour coefficient of rocks, q is unit discharge of spillway tunnels, Z is water head drop, $\bar{i}_q$ is the upstream slope of the scouring pit, $\bar{i}_h$ is the downstream slope of the scouring pit.

From the analysis of the overall physical relationship, the relationship between the width of the river valley and the energy dissipation control parameters is established, as

shown in Eq. (2).

$$B > Kq^{0.5}Z^{0.25} \cdot (\bar{i}_q + \bar{i}_h) \quad (2)$$

According to the empirical data in the “Spillway Design Code” (SL253–2000) and the “Hydraulic Calculation Manual”, the downstream slope ratio is approximately 2.5 to 5 times the scouring pit depth, and the upstream slope ratio is approximately 1.8 to 2 times the scouring pit depth.

From the perspective of jet diffusion, it is important to clearly define the jet impact point to ensure that the impact point is within the safe range. Secondly, it is also necessary to guarantee that the distance difference between the inner and outer jets is less than the width of the river valley, so as to meet the requirements of energy dissipation by jet diffusion. Therefore, a design index of the energy dissipation capacity of the spillway tunnels based on the correlation between the jet impact point and the width of the river valley is proposed, as shown in Eq. (3).

$$L_{\text{outer}} - L_{\text{inner}} < \frac{kB}{\sin \alpha} \quad (3)$$

here, L_{outer} is outer jet distance, L_{inner} is inner jet distance, k is safety margin index, α is the angle between the spillway tunnels and the downstream river channel.

v is jet velocity, h_1 is flow depth at the exit of spillway tunnels, z is the distance from buckets to downstream flow, β_d and β_u is the outlet angle of the inner and outer jet.

By using the energy dissipation capacity evaluation indicators based on Eqs. (2) and (3), it is possible to determine whether the width of the river valley meets the design requirements according to the inflow conditions of the spillway tunnels and the overall layout, that is, to determine whether the energy dissipation capacity meets the requirements. Furthermore, verification can also be carried out by model tests. If the depth of the scouring pit does not meet the requirements, another layouts and site selection for the spillway tunnel need to be conducted.

2.2 Instance Verification of Energy Dissipation Capacity

During the preliminary research stage of the Baihetan Hydropower Station, a comparison of the layout methods of the spillway tunnels is conducted. The three spillway tunnels are respectively analyzed in two layout methods: opposite side layout (left bank 2, right bank 1) and same side layout (left bank 3). Here, to further illustrate the overall relationship of energy dissipation capacity in river valleys, the test data of LCRM Hydropower Station (three cave-type spillways), Jinping Hydropower Station (one spillway tunnel) and of Xiluodu Hydropower Station (four spillway tunnels, two left bank 2 and right bank 2) are combined for verification and explanation, as shown in Fig. 1.

The Baihetan Hydropower Station, Xiluodu Hydropower Station, LCRM Hydropower Station, Jinping No.1 Hydropower Station and other 300-m-high dams face the problems of large discharge and high flow velocity due to be built in narrow river valleys. The river width at the outlet of the spillway tunnel is all less than 200 m, and the problems of energy dissipation and flood prevention are severe. As can be seen from Fig. 1, the energy dissipation capacity of the three spillway tunnels on the left bank




Fig. 1. Verification of energy dissipation capacity

of the Baihetan Hydropower Station, the three cave-type spillways on the right bank of LCRM Hydropower Station and the one spillway on the right bank of the Jinping No.1 Hydropower Station meets the design requirements. The energy dissipation capacity of the four spillways of Xiluodu Hydropower Station is in vicinity of the critical line, and the energy dissipation capacity is slightly insufficient.

For the layout of the spillway tunnel of Baihetan Hydropower Station with left bank 2 and right bank 1, the layout of the 1 spillway tunnel on the right bank does not meet the requirements. The width of the narrow river valley downstream of the spillway tunnel of Baihetan Hydropower Station during the dry season is within the range of 70 m to 150 m. In the “left bank 2 right bank 1” layout, the width of the river valley at the outlet of one spillway tunnel on the right bank is approximately 75 m. Analyzed from the energy dissipation capacity index proposed in this paper, the scouring pit of one spillway tunnel on the right bank will endanger the bank slope.

Here, in order to further verify the feasibility of the energy dissipation capacity determination method, the physical model test is adopted to demonstrate the energy dissipation capacity of the three spillway tunnels of Baihetan Hydropower Station arranged on the same side and different sides, as shown in Figs. 2 and 3.

In the different side layout of the spillway tunnels of Baihetan Hydropower Station, #2 jet strikes the opposite bank and the scouring pit is close to the opposite bank slope. #3 jet approaches the main bank and the scouring pit touches the bank slope. Therefore, The energy dissipation capacity and safety do not meet the design requirements. The energy dissipation capacity of the layout on the same side of the spillway tunnel meets the design requirements. This further proves the critical line of energy dissipation capacity in Fig. 1. The calculation value shows that the layout above this critical line needs to adjust the layout of the spillway tunnels.




Fig. 2. Scour pits of the spillway tunnels on different sides of the Baihetan Hydropower Station (normal water level)




Fig. 3. Scour pits of the spillway tunnels on same side of the Baihetan Hydropower Station (normal water level)

3 Layout Method of Parallel Spillway Tunnels

The main control conditions for the layout of a single-sided centralized spillway tunnels are the spacing of the spillway tunnels and the bucket shape. A reasonable spacing of the spillway tunnels enables the jet to form a “water cushion” effect in the river channel in order to optimize scouring pits in the downstream river channel. Meanwhile, it can save construction investment. The optimization of the bucket shape can enable the jets to be longitudinally stretched in the air and form sufficient lateral diffusion to the purpose of better energy dissipation. On the other hand, under the certain inflow

conditions, the optimization of the bucket shape can prevent the jets from hitting the main bank or impacting to the opposite bank, and the good combination of the bucket type at the spillway outlets can achieve the purpose of controlling the flow velocity on the bank. Here, a determination method for the spacing of spillway tunnels in a single-sided centralized layout is established. Based on the optimal combination of multiple buckets, a collaborative optimization arrangement method for the bucket shape is proposed to achieve better energy dissipation and ensuring the safety in a single-sided centralized arrangement of spillway tunnels in narrow river valleys.




Fig. 4. The sketch of parallel spillway tunnels

3.1 Calculation Method of Layout

The determination of the spacing of the spillway tunnels can be carried out based on the bottom flow velocity combined with the characteristics of scouring pits, as shown in Fig. 4. Three jets impact the downstream river channel. For the upstream jet #1, this jet is only affected by the inflow velocity. The downstream jet #2 is supported by the dynamic water of jet #1 and acts in the dynamic water cushion formed by jet #1, which causing the main flow of jet #2 to deviate more significantly from the linear trajectory. The bottom flow velocity and dynamic flow pressure are both lower than the index values in the static flow. The same principle applies to jet #3 from #3 spillway tunnel.

The composite parameter R for the layout of the spillway tunnels along the bank needs to be determined based on factors such as the depth of the downstream scouring pits T , the jet ski-jump distance L_0 and the width of the river channel B .

$$R = f(T, L_0, B, \dots) \quad (4)$$

The main factors influencing the composite parameter R are the distance between two adjacent spillway tunnels Δs , the intersection angle between the spillway tunnels

and the bank slope θ , the shape parameter of the spillway tunnel outlet m , the ski-jump angle of the spillway tunnel α , and the distance from the spillway tunnel outlet to the slope toe of the bank slope s , etc.

$$R \propto \Delta s, \theta, m, \alpha, s_1 \dots \quad (5)$$

According to the formula of projectile motion, the jet distance before entering the water L_0 is:

$$L_0 = \frac{v_1^2 \sin \alpha \cos \alpha}{g} \left[1 + \sqrt{1 + \frac{2g(a - h_t + \frac{h_1 \cos \alpha}{2})}{v_1^2 \sin^2 \alpha}} \right] \quad (6)$$

v_1 : jet velocity at the outlet of the spillway tunnels, a : the vertical distance from the bucket of spillway tunnels to the downstream riverbed, h_1 : flow depth at the outlet of the spillway tunnels, h_t : flow depth in downstream of scouring pit.

The shore velocity v_{ja} can be expressed by Eq. (7)

$$v_{jm} - \frac{B_j + s_j - L_{j0}}{\zeta} = v_{ja} \quad (7)$$

The meanings of each parameter in the above formula are as follows: ζ is the velocity attenuation coefficient, B_j is the width of the river channel at No. j spillway tunnel, s_j is the distance from the outlet of No. j spillway tunnel to the slope toe of the bank, v_{jm} is the maximum bottom flow velocity between the jet of No. j spillway tunnel and the jet of No. $j + 1$ spillway tunnel, and L_{j0} is the jet distance before the jet enters river channel.

According to the offset jet theory, when two spillways interact with each other, the relationship between the inflow velocity v_j of No. j spillway tunnels and the maximum bottom velocity v_{jm} between No. j spillway tunnel and No. $j + 1$ spillway tunnel is:

$$\frac{v_j}{v_{jm}} = \frac{d_j}{\frac{\Delta s}{\sin \theta_{j+1}} - \Delta s_a} \quad (8)$$

The meanings of each parameter in the above formula are as follows: Δs_a is the distance from the point with the maximum bottom flow velocity v_{jm} to jet impact point, d_j is the jet thickness produced by No. j spillway tunnel, and θ_{j+1} is the intersection angle between No. $j + 1$ spillway tunnel and the bank slope.

The dynamic water cushion effect can reduce the depth of the downstream scouring pits. When the spacing of the spillway tunnels is arranged, it should be considered that the depth of the downstream scouring pit is less than the depth of the downstream scouring pit with the arrangement of only one spillway tunnel. Therefore, the relationship is established as Eq. (9):

$$\max(T_1, T_2, T_3, \dots, T_n) \leq T_c \quad (9)$$

$\max(T_1, T_2, T_3, \dots, T_n)$ represents the maximum depth of scouring pit in the downstream river with n spillway tunnels, and T_c represents the depth of scouring pit in the downstream river with only one spillway tunnel under the same working conditions.

The depth of scouring pits adopts the empirical equation that is widely recognized in the major:

$$(T_c T_n) = kq^a Z^b \quad (10)$$

The meanings of each parameter in the above formula are as follows: k is the coefficient based on the characteristics of the rock, q is the unit discharge of the spillway tunnel, Z is the water level difference between the upstream and downstream, and a and b are the undetermined coefficients.

The layout of the spillway tunnels should consider that the pits hardly affect the bank slope. According to the relevant geometric relationship, it needs to meet the requirements:

$$b_j \leq L_{j0} \sin \theta_j - s_j \quad (11)$$

The meanings of each parameter in the above formula are as follows: b_j is the width from the deepest point of the scouring pit formed by No. j spillway tunnel to the edge of this pit, L_{j0} is the No. j jet distance, θ_j is the intersection angle between No. j spillway tunnel and the bank slope, and s_j is the distance from the outlet of No. j spillway tunnel to the toe of the bank slope.

The number of spillway tunnels is determined based on the total flow discharge of the spillway tunnels and the flow discharge of each individual spillway tunnel. The parameters such as the outlet shape parameter m and the ski-jump angle α of the spillway tunnel are determined. According to Eq. (3), the distance L_{j0} and the inlet velocity v_j of No. j spillway tunnel are calculated.

We substitute Eqs. (6) into (7), and solve Eqs. (7) and (8) simultaneously. An inequality is established to ensure that the shore velocity v_{ja} of the spillway tunnels in Eq. (7) with $v_{ja} \leq 6.0$ m/s based on the velocity attenuation coefficient ζ , the river width B_j , and the distance s_j from the outlet of spillway tunnel to the bank slope toe.

According to the result of the inequality, if the calculated $v_{ja} \geq 6.0$ m/s, parameters should be adjusted such as the outlet shape parameter m , the ski-jump angle α , etc.. Additionally, we adjust the distance Δs among two adjacent spillway tunnels and the intersection angle θ between the spillway tunnel and the bank slope until $v_{ja} \leq 6.0$ m/s is satisfied.

Firstly, the upstream and downstream water stage of the spillway tunnel is determined. According to the stage-discharge relationship and Eq. (10), the depth T_c of the downstream scouring pit with only one spillway tunnel is obtained. Subsequently, the same upstream and downstream water stages and stage-discharge relationship are adopted to obtain pit depths $T_1, T_2, T_3, \dots, T_n$. The pit calculation can be carried out if Eq. (9) is met the requirement. Otherwise, we adjust the distance Δs between two adjacent spillway tunnels, the angle θ between the spillway tunnel and the bank slope, and verify whether the flow velocity of the bank slope meets the requirements until Eq. (9) is met.

Considering that the width of the scouring pit does not affect the slope toe, it indicates that the existing layout has met the engineering requirements if the conditions of Eq. (11) are met. Otherwise, we adjust the intersection angle θ between the spillway tunnel and the bank slope and the distance from the spillway tunnel outlet to the slope toe until the requirements of Eq. (11) are met.

3.2 Case Verification of Layout Method of the Parallel Spillway Tunnels

We take the Baihetan Hydropower Station as an example for calculation, the test verification of the normal water storage level (825.00 m) shows that the flow coefficient of the spillway tunnel is 0.888, the elevation of the spillway tunnel bottom plate is 770.00 m, the crest spillway discharge of the normal water storage level is approximately $9400 \text{ m}^3/\text{s}$, the outlet discharge is approximately $116000 \text{ m}^3/\text{s}$, and the generating discharge is approximately $8800 \text{ m}^3/\text{s}$. Based on the above data, it can be calculated that the discharge of the spillway tunnels is approximately $11000 \text{ m}^3/\text{s}$. The opening area of the spillway tunnel is $9.5 \text{ m} \times 15.0 \text{ m}$ (height $\times$ width), and the elevation of the spillway tunnel outlet is 650 m. Based on this data, it can be concluded that $n \approx 3$, that is, it is appropriate to arrange three spillway tunnels along the bank.

The flow depth downstream of the scouring pit can be obtained by subtracting the elevation of the overburden layer from the water level of the river channel. The flow depth at the bucket of the spillway tunnels and the jet velocity can be calculated according to the hydraulic energy equation. According to Eq. (6), the jet distance of from the upstream to the downstream of the three spillways is calculated as 200 m, 210 m and 214 m, respectively. Subsequently, the jet impact velocity v from the upstream to the downstream of the three spillways is calculated.

The width of the river channel are approximately 450 m. The distance s from the outlet of the spillway tunnel to the slope toe can be arranged according to the preliminary design of the project, and the value of s is mostly within the range of 60 to 70 m. The jet thickness d can be determined based on the jet diffusion theory combined with model tests. It is obtained that the jet thicknesses of the water jets flowing into the three spillways from the upstream to the downstream are 62 m, 53 m and 50 m, respectively. Research shows that the maximum bottom flow velocity occurs approximately $1.4d_j$ downstream of the impact point. According to the geometric relationship (as shown in Fig. 4), it can be obtained that:

$$\Delta s_a = \frac{h_t}{\tan \theta_j} + 1.4d_j \quad (12)$$

Substituting the result of jet distance in Eqs. (6) into (7), and combining Eqs. (7), (12) and (8) simultaneously, based on the control condition that the shore velocity v_{ja} of the spillway tunnelst is $v_{ja} \leq 6.0 \text{ m/s}$, it can be obtained that:

$$v_j \cdot \frac{\frac{\Delta s}{\sin \theta_{j+1}} - \left(\frac{h_t}{\tan \theta_j} + 1.4d_j \right)}{d_j} - \frac{B_j + s_j - L_{j0}}{\varsigma} \leq v_{ja} \quad (13)$$

Equation (13) can determine whether the layout of each spillway tunnel meets the control requirements. Here, if s is taken as 65 m, the intersection angle θ between the spillway tunnel and the bank slope is 40° , and the distance Δs between two adjacent spillway tunnels is set to 90 m, we substitute the above data into the equations to calculate that the current layout meets the requirements of Eq. (13).

The depth T_c of the downstream scouring pit with the arrangement of only one spillway is calculated by Eq. (10). Here, $k = 1.05$. Chen Chunting's equation is a commonly method for estimating the depth of scouring pit. It can be known that in Eq. (10), $a =$

0.5 and $b = 0.25$. It can be calculated that the depth of scouring pit with one spillway tunnel is discharging is 48 m, and the result of the model test is 48.5m. This result has a relatively high confidence level.

Considering the water cushion effect of the inflow from the upstream spillway on the downstream river channel, it is required that the maximum depth of the scouring pit with three spillway tunnels is less than T_c . The physical model test method is adopted for experimental research. Here, the layout of the spillway is the same as that in the previous text, with $s = 65$ m, the intersection angle $\theta = 40^\circ$. The distance $\Delta s = 90$ m. The experimental study shows that the pit depths of the three spillways are 48.0 m, 49.1 m and 49.0 m. respectively. In view of this, this layout does not satisfy Eq. (8). This indicates that the inflow has insufficient effect on the downstream water cushion, which leads to a relatively large depth of the downstream scouring pit. Therefore, the distance Δs between the two spillways needs to be further reduced to enable the water cushion to take effect. Here, the distance Δs between two adjacent spillways is set to 70 m for the test. The pit depths of the three spillways are 48.4 m, 48.0 m and 48.1 m, respectively. This pit depth data meets the requirements of Eq. (9).

At this point, the data of the distance $\Delta s = 70$ m between two adjacent spillways needs to be substituted into Eq. (13) to verify whether the conditions are met. The calculation shows that $\Delta s = 70$ m meets the requirements.

To assess the influence of the scouring pit on the bank slope, it is determined whether the width of each scouring pit satisfies Eq. (11). The test results show that the width from the deepest point of the scouring pit to the edge of the scouring pit satisfies Eq. (11) for the three spillway tunnels.

In fact, this research is also adopted to pile groups in offshore wind power generators. The characteristics of scouring pits could provide reference for impact of layout of pile groups as foundation for offshore wind power generators upon hydrodynamic conditions. The arrangement of pile groups is the key to influencing pile-surrounding scour and protection.

4 Conclusions

- (1) Taking energy dissipation and jet impact point as the main index, and comprehensively considering factors such as water cushion depth and river channel width, an evaluation index for the energy dissipation capacity of narrow river valley channels is constructed. The rationality of the evaluation indicators is verified by the energy dissipation layout of 300-m-level high dam spillways in narrow river valleys such as Baihetan, Xiluodu, LCRM and Jinping.
- (2) A layout method for parallel spillway tunnels that takes into account both the scouring effect of the downstream river and the energy dissipation effect of the jet is proposed. The non-superposition of the scouring pits and the energy dissipation effect are taken as control indicators, and the layout principle of the spillway tunnels with multi-objective parameter hydraulic coordination is established.
- (3) The research findings provide references to several studies of layout of pile groups as foundation for offshore wind power generators.

Acknowledgement. This research has been financially supported by Science and Technology Project of China Huaneng Group (HNKJ23-H18) and the National Natural Science Foundation of China (Grant Number: 52009083).

References

1. Xu, J.R., Peng, Y., Zhao, J.J., et al.: Impact pressure distribution characteristics in plunge pool of high arch dam for large discharge. *Water Resources Power* **38**(11), 98–100 (2020). (in Chinese)
2. Wang, Z., Deng, Y.T., Yang, Z.L., et al.: Experimental research on the characteristics of water jets at the proximal end of the dovetail-shaped flip bucket. *Adv. Eng. Sci.* **52**(6), 177–182 (2020). (in Chinese)
3. Yue, Y., Ma, B., Yang, M.: Research progress and trend on somatotype of plunge pool. *South-to-North Water Transf. Water Sci. Technol.* **13**(1), 176–180 (2015). (in Chinese)
4. Castillo, L.G., Carrillo, J.M.: Comparison of methods to estimate the scour downstream of a ski jump. *Int. J. Multiph. Flow* **92**, 171–180 (2017)
5. Qian, S.T., Wu, J.H., Xu, H., et al.: Discussion of “estimated splash and training wall height requirements for stepped chutes applied to embankment dams” by Sherry L. Hunt and Kem C. Kadavy. *J. Hydraulic Eng.* **144**(11), 07018018 (2018)
6. Wang, Y., Wu, J.H., Ma, F., et al.: Pressure distribution of bottom rollers below the aerator device. *Water Sci. Technol.* **79**(4), 668–675 (2019)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter’s Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter’s Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Seepage and Anti-Sliding Stability Analysis of a Clay Core Rockfill Dam Based on In-Situ Data

Siyan Xu¹(✉), Fengzhe Tian², Yanbin Cui³, and Xiaojia Wang⁴

¹ Department of Geotechnical Engineering, Nanjing Hydraulic Research Institute, Nanjing 210024, China

syxu@nhri.cn

² Geotechnical Research Institute, Hohai University, Nanjing 210098, China

³ Sinohydro Bureau 5 Co., LTD, Chengdu 610066, Sichuan, China

⁴ China International Water and Electric Corporation, Beijing 101100, China

Abstract. The seepage safety and sliding stability of a clay-core rockfill dam in Africa were examined through a combination of in-situ testing and numerical simulations under various working conditions. The findings indicate that, compared to conventional geological surveys and laboratory test data, in-situ parameters obtained from field direct shear and permeability tests provide greater accuracy and reliability. A numerical model based on the in-situ permeability coefficient was established, demonstrating its capability to reflect the seepage behavior of the dam and confirming that no seepage failure occurs under steady-state conditions. The calculated safety factors for sliding stability meet regulatory requirements across all conditions, and the introduction of a safety coefficient, S , allows for the quantification of the dam's sliding stability margin. This study provides an analytical framework that integrates in-situ testing with multi-source data fusion, offering valuable insights for the safety assessment of similar projects.

Keywords: in-situ data · core rockfill dam · numerical simulation · seepage · anti-sliding stability

1 Introduction

Earth-rock dams are favored by engineers for their use of local materials, adaptability to different terrains, cost-effectiveness, and ease of construction, making them the most common dam type in China's hydropower projects (Lin et al. 2019, Cheng et al. 2013). Clay-core rockfill dams, a subtype, feature low-permeability clay cores for seepage control, supported by rockfill shells for stability.

Despite advancements in research on materials, construction (Rao et al. 2017), and safety monitoring (Zhao et al. 2010, Ma et al. 2013), many reservoir dams still face challenges like seepage control, seismic resistance, and flood prevention due to construction and maintenance issues (Tan et al. 2016, Chen et al. 2008). A traditional approach to

determining material parameters often leads to discrepancies between lab results and actual field conditions (Zhang et al. 2013).

Recent in-situ monitoring technologies have allowed for integrating field data into engineering calculations (Cai et al. 2025, Lou et al. 2014). This study investigates an African clay-core rockfill dam through in-situ direct shear and permeability tests. The collected field parameters were used in three-dimensional finite element simulations to analyze stability under various operational scenarios, focusing on seepage behavior and sliding stability.

2 Engineering Profile

The clay-core rockfill dam constructed on an African river (Fig. 1) features a crest elevation of 1,057.50 m with a 10.00 m-wide crown, extending 375.16 m along the left bank and 1,049.52 m along the right bank. The upstream slope maintains a uniform 1:1.6 gradient. The clay-core rockfill dam features a 6.00 m-wide impervious clay core at its crest with upstream and downstream slopes of 1:0.5. Between the clay core and downstream rockfill shell, a graded filtration system comprising a 1.00 m-thick fine filter layer and a 1.00 m-thick coarse filter layer is installed. Above the 1,050.00 m elevation, an additional 1.00 m-thick fine filter layer is incorporated at the contact zone between the coarse filter and clay core. The foundation of the earth-rock dam body is the overburden layer or the rock layer underneath. The core foundation is strongly weathered bedrock or the rock base underneath. A concrete base cover plate is installed on the foundation surface, with a course of curtain grouting placed underneath. The curtain penetrates into below the 3Lu (water permeability) line.




Fig. 1. Typical cross-section diagram of dam body

3 In-Situ Field Test

In this study, in-situ shear tests (Hu et al. 2015) and permeability tests were conducted on various materials within the dam area to determine their strength parameters and permeability coefficients.

3.1 In-Situ Direct Shear Test

This dam utilized the in-situ testing apparatus (Liu et al. 2004) to conduct tests on upstream/downstream coarse/fine filter materials, rockfill, and clay core, obtaining shear

strength parameters under varying normal stresses. The measured shear strength relationships are shown in Fig. 2, with the experimental data subjected to curve fitting to characterize material-specific failure envelopes. From Fig. 2, it can be observed that the results obtained from the field in-situ tests exhibit a good linear relationship. By calculating the slope of the fitting curves for different materials, the friction angles corresponding to the upstream/downstream coarse and fine filter materials, rockfill material, and core clay can be derived as 47.4° , 53.1° , 55.1° , and 18.1° , respectively. The friction angles of the upstream/downstream coarse and fine filter materials and rockfill material show an increasing trend with the enlargement of particle size. It is worth noting that granular materials theoretically should not have cohesion. However, cohesion values (c) of different magnitudes were measured for the three granular materials (upstream/downstream coarse/fine filter materials and rockfill material) in the field in-situ tests, and these cohesion values also increased with larger particle sizes. This is primarily attributed to the shear dilation characteristics and pressure-dependent behavior of the rockfill materials (related to particle crushing). Therefore, in subsequent analyses of this study, only the friction angle parameters of the three granular materials will be adopted, while the cohesion (c) values will be disregarded.




Fig. 2. Relationship between shear strength (τ_f) and vertical stress (σ)

3.2 In-Situ Permeability Test

In accordance with the “Standard Test Methods for Geotechnical Investigation” (GB/T 50123-2019), field test pit permeability tests were conducted for various materials in the dam area. The permeability coefficients of different materials were calculated using Eq. (1) and are presented in Table 1.

$$k_T = \frac{Q}{tA_h} \quad (1)$$

where Q is seepage discharge, t is time, A_h is the cross-sectional area of iron ring.

Table 1. Permeability coefficients of various materials in the dam area

Material	Permeability coefficient (cm/s)
Clay core	$8.65 * 10^{-6}$
Upstream fine filter layer I	$2.35 * 10^{-3}$
Upstream fine filter layer II	$1.61 * 10^{-3}$
Upstream coarse filter layer I	$1.06 * 10^{-2}$
Upstream coarse filter layer II	$1.18 * 10^{-2}$
Cutoff wall (C20 concrete)	$1.0 * 10^{-7}$
Surface rock stratum of the dam foundation	$5.0 * 10^{-4}$
Deep bedrock stratum	$1.0 * 10^{-4}$

Through comparison with data obtained from laboratory tests conducted on samples during previous geological surveys, it was found that the permeability coefficients from field tests are generally similar to those from laboratory tests. However, the coefficients calculated from field tests are slightly higher. This is primarily attributed to the larger sample sizes and smaller soil disturbances in in-situ tests, which better reflect the true in-situ soil conditions. Therefore, the more conservative data (in other words, the relatively higher values from field tests) were selected in calculations to ensure greater reliability of the results.

4 Seepage and Anti-Slide Stability Analysis

This paper combines in-situ monitoring with numerical simulation calculations to analyze and evaluate the seepage stability and anti-sliding stability of the dam.

4.1 In-Situ Monitoring

A large number of piezometers were installed within the dam body to monitor the position of the phreatic line, as shown in Fig. 3. These piezometers were primarily located in the upstream and downstream dam body fill materials of the cross-sectional core wall, as well as within the core wall itself. In this study, the analysis focused on measurement points within the core wall and the bedrock beneath it. Monitoring commenced immediately after instrument installation, with manual readings taken using frequency readout instruments. The total monitoring period lasted 22 months, during which water impoundment began in December 2018.




Fig. 3. Schematic diagram of the phreatic line location within the dam body

Figure 4 shows the phreatic line results from piezometer measurements. Piezometer readings at different depths exhibit similar trends in their variations. The bedrock-embedded monitoring points P7-1 to P7-4 remained stable both before and after impoundment completion. The core wall-embedded points P7-5 to P7-7 displayed consistent patterns. Taking P7-7 as an example, which is located at an elevation of 1,051 m, its total head was approximately 1,055.00 m at the start of monitoring. Prior to impoundment, this point's total head gradually decreased to 1,052.31 m, indicating sustained pore water pressure over time. After the dam was filled to an elevation of 1,054.13 m, the pore water pressure at this point slightly increased to 1,053.42 m and gradually stabilized. The piezometer at monitoring point P7-6 exhibits a similar pattern to P7-7. At the start of monitoring, its total head was 1,051.51 m. Prior to impoundment, the total head gradually decreased to 1,047.46 m. Following the start of impoundment, the total head at this point slowly rose to 1,053.30 m, with the rate of increase gradually slowing, indicating a trend toward stabilization.




Fig. 4. Measured water level variation process lines at all monitoring points

Based on the temporal variation of total head observed in the piezometers, it can be preliminarily inferred that after installation, excess pore water pressure was generated at this location due to subsequent fill placement and construction compaction loads. Prior to dam impoundment, this excess pore pressure gradually dissipated, but did not fully dissipate. Following impoundment, the pore water pressure at this point began to rise under the influence of upstream water levels and eventually stabilized. Analysis of piezometers P7-5 to P7-7 shows that their data all followed this pattern, indicating that the

pore water pressure at these points was not solely caused by impoundment. Compaction during earth-rock dam construction commonly generates excess pore pressure in the dam's core wall, which is a well-documented phenomenon.

Based on the aforementioned analysis, a preliminary prediction of the future pore pressure variation patterns can be made: current monitoring data is expected to decrease as the excess pore water pressure in the surrounding soil mass gradually dissipates. During subsequent operational phases, enhanced surveillance of piezometer readings should be implemented. Any sudden significant fluctuations in readings should be met with heightened vigilance.

4.2 Seepage Stability Analysis

To analyze the seepage conditions of the dam body under steady seepage, a seepage analysis model was established for the cross-section shown in Fig. 1. The model configuration and material zones are illustrated in Fig. 5. The material parameters used for seepage analysis in the model are listed in Table 1. The permeability coefficients for the cutoff wall and dam foundation rock layer were obtained from geological survey data, while the permeability coefficients of the remaining five materials were derived from field permeability tests.

Three scenarios were established to simulate seepage conditions under three different water level conditions. In all scenarios, the downstream water level was set to 1039.08 m to represent the current water level during the calculation phase. The upstream water levels were set to 1054.13 m, 1054.50 m, and 1055.00 m, corresponding to the actual water level, normal storage water level, and check flood water level, respectively.




Fig. 5. Seepage simulation model and material zoning diagram for the dam body

Figure 6 shows the seepage equipotential line contour maps for the dam cross-section under three scenarios during steady seepage conditions. The dashed lines represent the phreatic line. The trend of the phreatic line indicates that the clay core wall effectively slows down water flow, resulting in a significant reduction in saturation levels of the fill material downstream of the wall.

Figure 7 presents the hydraulic gradient contour maps for the dam cross-section under the three scenarios. The equipotential lines decline from the dam crest toward the dam foundation, consistent with general seepage patterns. The equipotential lines are uniformly spaced, indicating a stable hydraulic gradient and a reasonable distribution of seepage pressure. No significant seepage leakage is evident, and the exit gradient of the

clay core wall meets design requirements. Under all three scenarios (actual water level, normal storage level, and check flood level), the dam shows no signs of seepage failure.




Fig. 6. Equipotential contour map of seepage in dam body




Fig. 7. Hydraulic gradient contour map of seepage analysis for dam body cross-section A

4.3 Anti-Slide Stability Analysis

Conduct anti-slide stability analysis on the selected cross-section A. The model’s cross-section and zone divisions are shown in Fig. 3, with specific material parameters listed in Table 2. The friction angle (ϕ) and cohesion (c) parameters derived from survey data are denoted by ϕ and c , respectively, while the friction angle obtained from field in-situ testing is distinguished as ϕ_0 .

Table 2. Material parameters for anti-sliding stability analysis

Material	$\gamma(\text{kN}/\text{m}^3)$	$\gamma_{\text{sat}}(\text{kN}/\text{m}^3)$	$c(\text{kN}/\text{m}^2)$	$\phi\ (^{\circ})$	$\phi_0(^{\circ})$
Clay	20	20.7	12.82	18	/
Fine filter	20.6	22.6	/	/	47.4
Coarse filter	20.6	22.6	/	/	53.1
Rockfill material	19.4	21.24	/	/	55.1
Bedrock stratum I	20	20	9.4	27.4	/
Bedrock stratum II	18.6	20	9.7	27.8	/

To comprehensively analyze the impact of different water level conditions and potential seismic hazards on the anti-slide stability safety of the dam slope, a total of seven

calculation scenarios were established. The specific water level elevations and seismic load values corresponding to each scenario are presented in Table 3. Among the seven scenarios, scenarios 1–3 and 5–6 were designed to simulate the stability of the dam slope under normal water level, routine water level, and design flood level conditions. Scenarios 4 and 7 incorporated seismic acceleration based on the maximum credible earthquake conditions at the site, aiming to evaluate the influence of seismic loads on the slope’s anti-slide stability.

Table 3. Loading cases for anti-sliding stability analysis

Object	Serial number	Upstream water level	Downstream water level	Seismic load
Downstream dam slope	1A	1054.50	1039.08	/
	1B	1054.50	1036.05	/
	2	1055.00	1039.08	/
	3	1054.13	1039.08	/
	4A	1054.50	1039.08	$a_h = 0.15$ $a_v = -0.1$
	4B	1054.50	1039.08	$a_h = 0.213$
	5	1054.13	1039.08	/
	6	1055.00 1052.50	1039.08	/
Upstream dam slope	7A	1054.50	1039.08	$a_h = 0.15$ $a_v = -0.1$
	7B	1054.50	1039.08	$a_h = 0.213$

Figure 8 presents the relationship between the calculated safety factors and the minimum safety factor across the seven major scenarios. It can be observed that the safety factors for all scenarios exceed the minimum safety factor, indicating that the dam in this project can maintain stable operation without failure under all conditions. To further analyze the dam’s safety, the safety coefficient S was defined as the ratio of the safety factor to the minimum safety factor. A higher S value signifies a greater safety margin, implying enhanced dam safety, while a lower S indicates increased risk. Analysis of the safety coefficients reveals that under normal operating conditions, the dam’s safety coefficient S remains around 1.2. Notably, Scenarios 3 and 6 achieve the highest S value of 1.26, suggesting that smaller water level differences between the upstream and downstream sections provide a larger safety margin for the corresponding dam slopes. Conversely, Scenarios 4B and 7B exhibit the lowest safety coefficients, with Scenario 7B’s S approaching the critical threshold of 1. This underscores the significant impact of seismic loads on the anti-slide stability of the dam slope, necessitating enhanced monitoring of slope safety before and after seismic events.




Fig. 8. Safety factors and safety coefficient S under different operating conditions

The stability analysis of the dam's anti-slide performance was re-evaluated using the pore pressure coefficients from measured points, employing the slice method. Based on the measured pore water pressure data from points P7-1 to P7-7, Kriging interpolation was applied between data points to estimate intermediate values. The calculated safety factors for both the upstream and downstream sections of the dam body were found to exceed the permissible safety factor of 1.5 under normal operating conditions, indicating that the dam satisfies anti-slide stability requirements under current conditions. The conclusions derived from the two methods (slice method and Kriging interpolation) were consistent, confirming that the dam's current anti-slide stability status is within a safe range.

5 Conclusion

The study obtained in-situ material parameters of the core-rockfill dam through field measurements and conducted numerical simulations to analyze seepage behavior and anti-slide stability of the dam under multiple operational conditions. The results were validated using field-measured data, enabling an evaluation of the dam's operational safety and stability across different scenarios. Key conclusions are summarized as follows:

1. The material parameters obtained from field in-situ tests show little discrepancy compared to those derived from previous geological surveys and laboratory tests. This is attributed to the minimal disturbance and better representation of the actual in-situ conditions during in-situ testing, which allows for parameters more reflective of real-world scenarios.
2. The permeability coefficients derived from field permeability tests were applied in seepage simulations, and the simulation results conformed to general seepage principles. Under three different operational conditions, the dam body would not experience seepage-induced damage.
3. The parameters obtained from field direct shear tests were used to conduct anti-slide stability analyses under multiple operational conditions. All scenarios exhibited safety factors above the minimum required threshold. A safety factor S was defined to quantify the safety margin. Under conditions with seismic loading, the safety margin was

smaller, necessitating enhanced monitoring. The conclusions of the stability analyses were validated using measured pore water pressure parameters from monitoring points, which also confirmed the operational safety and stability of the slope.

References

- Hao, C., Ye, G., Lan, L., et al.: Progress in disturbance mechanism, evaluation methods, and control measures for soft clay sampling. *Chin. J. Rock Mech. Eng.* **47**(2), 225–233 (2025)
- Chen, H., Xu, Z., Li, M.: Wenchuan earthquake and earthquake safety of dams. *J. Hydraulic Eng.* (10), 1158–1167 (2008)
- Cheng, S., Li, Y., Zhong, H.: Safety monitoring focus of the zuguo hydropower station project in tibet. *Electric Power Surv Des* (3), 71–77 (2013)
- Hu, W., Min, H., Chen, J., et al.: Improvement, development, and application of large-scale in-situ direct shear testing equipment. *Rock Soil Mech* **36**(3), 905–912 (2015)
- Lin, J., Shui, G., Zhi, J.Z.: 5th ed. China Water & Power Press, Beijing (2019)
- Liu, S., Xia, G., Yang, J., et al.: New field direct shear test for rockfill materials in the upper reservoir of yixing pumped storage power station. *Chin. J. Rock Mech. Eng.* **26**(6), 772–776 (2004)
- Lou, L., Lei, S.: Application of in-situ monitoring technology in landslide stability monitoring. *Yangtze River* **45**(7), 74–76 (2014)
- Ma, Z.: Analysis of types and causes of hazardous reservoir dams in China. *Yangtze River* **44**(S1), 171–173+181 (2013)
- Rao, J., Peng, D., Li, M.: Stability analysis of ash dam slope based on unsaturated seepage. *Electric Power Survey Des.* **6**, 1–4 (2017)
- Tan, J., Gao, D., Wang, M., et al.: Seepage treatment technology for the concrete face rockfill dam at baiyun hydropower station. *Yangtze River* **47**(2), 62–66 (2016)
- Zhang, K.: Review of seepage analysis and control measures for earth-rockfill dams. *Hunan Water Resources Hydropower* **5**, 30–32 (2013)
- Zhao, Z., Xu, R.: Current status and prospects of dam safety monitoring technology at home and abroad. *Hydropower Autom. Dam Monitor.* **34**(5), 52–57 (2010)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Optimal Operational Strategies for Hydro–Wind–Solar–Pumped Storage Complementary Delivery Systems Under Extreme Renewable Generation Scenarios

Chuang Dong¹, Ruirui Liu¹, Xingjin Zhang²(✉), and Rui Han¹

¹ Power China Northwest Engineering Corporation Limited, Xi'an 710065, Shaanxi, China

² Institute of Water Resources and Hydropower Research, Northwest A&F University,
Yangling 712100, Shaanxi, China
zhangxingjin@nwfau.edu.cn

Abstract. To address peak-shaving challenges and power volatility induced by high-penetration renewable integration, this study proposes a hierarchical collaborative optimization framework for hydro-wind-solar-pumped storage delivery systems under extreme generation scenarios. A tri-level dispatch protocol (“renewable prioritization - diurnal storage cycling - seasonal hydraulic regulation”) is established, formulating an optimization model incorporating generation maximization, hydrodynamic equilibrium, and multi-physical constraints. Through 8760-h chronological simulations of a Yellow River upstream clean energy base, critical operational patterns emerge: consecutive low renewable generation during dry seasons triggers 10.6 m/day reservoir drawdowns necessitating emergency peak-shaving protocols; flood season high-level operations reduce spillage risks, limiting annual curtailment to 1.025 billion kWh; ecological dispatch periods (April–June) exhibit 1.75 m daily water-level fluctuations under pumped storage cycling, mandating hydraulic bounds (3241.75–3273.93 m) for storage performance optimization. The results demonstrate superior peak-shaving capacity and reduced curtailment versus conventional methods, offering a techno-economic paradigm for secure, efficient operation of renewable-dominated delivery systems.

Keywords: Hydro–wind–solar–pumped storage complementary delivery · Pumped storage operation optimization · Operational risk assessment · Extreme renewable generation scenarios

1 Introduction

Under the dual “carbon peaking and carbon neutrality” objectives, large-scale integration of renewable energy—particularly wind and photovoltaic power—represents a pivotal pathway for modern power system development. However, the inherent stochasticity and volatility of these resources significantly intensify grid peak-shaving demands,

aggravating renewable curtailment challenges (Lu et al. 2024). This tension is especially acute in high-renewable-export scenarios, where the requirement for stable long-distance transmission output increasingly conflicts with upstream generation fluctuations. Multi-energy complementary systems integrating hydropower, wind, solar, and pumped hydro storage (PHS) exploit hydropower's seasonal regulation, PHS's inter-daily smoothing, and wind-solar's variable output to achieve spatiotemporal complementarity—positioning this technology as a critical solution (Zhang et al. 2025; Cheng et al. 2022).

Nonetheless, extreme wind-solar output scenarios aggravate spatiotemporal mismatches between generation and load, giving rise to two primary conflicts. First, the inherent variability of renewable outputs, compounded by rigid capacity limits in long-distance transmission corridors, elevates both curtailment and supply-deficit risks (Liu et al. 2025). Second, traditional hydropower facilities, constrained by static reservoir-level control, cannot readily satisfy intricate requirements such as pumped-hydro storage (PHS) reservoir interlocks and ecological flow mandate (Parinaz et al. 2022). Accordingly, a critical research imperative is to harness PHS flexibility to implement an integrated, multi-layered regulation scheme encompassing seasonal reservoir management, inter-day peak shifting, and intra-hour load-following.

Existing research on hybrid PHS combined with wind-solar complementary dispatch has made preliminary strides. Xu et al. (2020) optimized capacity allocation for an off-grid hybrid system targeting maximum supply reliability and minimum investment cost. Lu et al. (2022) developed a day-ahead dispatch model for a hybrid energy system to enhance economic performance and mitigate thermal plant fluctuations. Wang et al. (2023) assessed multi-timescale complementary strategies and economic benefits of hydropower retrofits in the Wujiang basin, highlighting increased profits and reduced curtailment through nested pump-station operations. Ju et al. (2023) addressed renewable uncertainties by establishing a two-stage robust unit-commitment model for hybrid PHS.

Despite uncovering the regulation potential of hybrid PHS, significant bottlenecks persist in its synergy with wind-solar and hydropower. First, static reservoir-level thresholds in current dispatch models are ill-suited to abrupt volume changes induced by extreme renewable events. Second, the conflict between prioritizing renewable utilization and meeting ecological downstream release requirements has yet to be systematically quantified.

To address these challenges, this paper investigates a hydro-wind-solar-pumped storage complementary delivery system (HCDS) in the upper Yellow River. Drawing on the complementarity of these energy sources, it formulates multi-energy dispatch principles that incorporate grid peak-shaving and long-distance transmission stability requirements. A unified multi-energy peak-shaving model is then developed, simulating both typical scenarios and an annual 8760-h scheduling process. Based on simulation outcomes, a complementary dispatch scheme for the HCDS is proposed, and its impacts on hydropower and pumped-storage operations, as well as on overall system benefits, are analyzed.

2 Optimization Model for the HCDS

2.1 Multi-energy Coordinated Dispatch Principles

To fully exploit the peak-shaving potential of the hydro–wind–solar–pumped storage complementarity and maximize overall system benefits, the following coordinated dispatch principles are established:

- (1) The dispatch protocol mandates guaranteed nocturnal baseload fulfillment, with surplus generation capacity prioritized for midday peak demand before residual allocation to evening peaks.
- (2) Prioritize reservoir ecological releases. If wind–solar output and hydropower vie for export capacity and reservoir head is available, reduce hydropower discharge to favor renewables. If headroom is depleted, favor hydropower and route excess wind–solar into PHS. When all storage is full and curtailment is inevitable, prioritize hydropower to prevent spillage.
- (3) Because PHS generation reutilizes water through repeated release and re-pumping cycles, PHS dispatch is accorded higher priority than conventional hydropower release.
- (4) Diurnal pumping reserves primarily support evening-peak generation, with remaining hydraulic capacity reserved for morning ramp-rate compensation.

2.2 Objective Function

In the intra-day dispatch, allocate energy per a target delivery profile. Hydropower scheduling must harmonize daily generation objectives with long-term reservoir management. The optimization seeks to maximize HCDS generation, constrained by the prescribed delivery curve and intra-day water availability.

$$\begin{cases} \max E = \sum_{t=1}^T (P_t^H + P_t^W + P_t^{PV} + P_t^{Pump}) \cdot \Delta t \\ |Z_c - Z_m| \leq \delta \end{cases} \quad (1)$$

where $P_w t$, $PPV t$, $PH t$, and $Ppump t$ denote the grid-injection power of wind, photovoltaic, hydropower, and PHS at time t , respectively; T is number of intra-day time intervals. Z_c and Z_m are the Initial and final reservoir water level, respectively; δ represents the water level control accuracy; Δt is the interval duration.

2.3 Constraint Conditions

2.3.1 Power Delivery Constraint

$$P_t^W + P_t^S + P_t^H + P_t^{Pump} \leq N_{\max} \quad (2)$$

where $N_{\max}$ is the maximum transmission capacity of the delivery channel.

2.3.2 Hydropower Station Operational Constraints

1. Water-balance constraint.

$$V_{t+1} = V_t + (I_t - Q_t) \Delta t \quad (3)$$

where V_t denote the reservoir storage volumes during the interval t ; I_t is the inflow during interval t ; Q_t is the downstream release.

2. Ecological release constraint.

$$Q_{\min} \leq Q_t \leq Q_{\max} \quad (4)$$

where $Q_{\min}$ and $Q_{\max}$ are the minimum ecological flow requirement and the maximum allowable downstream discharge.

3. Reservoir storage constraint.

$$V_{\min} \leq V_t \leq V_{\max} \quad (5)$$

where $V_{\min}$ and $V_{\max}$ are the minimum and maximum storage volume.

2.3.3 Hybrid PHS Station Constraints

In addition to the above, the hybrid PHS station must satisfy:

1. Upper-lower reservoir hydraulic linkage.

$$\begin{cases} V_{upper,t} = V_{upper,t-1} + (Q_{pump,t}^{PS} - Q_{gen,t}^{PS}) \Delta t \\ V_{lower,t} = V_{lower,t-1} + (I_t - Q_t - Q_{1,t}^{spill} - Q_{pump,t}^{PS} + Q_{gen,t}^{PS}) \Delta t \end{cases} \quad (6)$$

where $V_{upper,t}$ and $V_{lower,t}$ are the storage volumes of the upper and lower reservoirs at time t ; $Q_{PS\ gen,t}$ and $Q_{PS\ pump,t}$ denote generation and pumping discharges, respectively.

2. Operation mode switching constraints.

If the lower reservoir level Z_{lower} exceeds its normal full level $Z_{max\ lower}$ generation ceases to prevent overtopping.

$$Z_{lower}(t) \geq Z_{lower}^{\max} \Rightarrow P_{gen}(t) = 0 \quad (7)$$

Pumping halts once the upper reservoir reaches $Z_{max\ upper}$.

$$Z_{upper}(t) \geq Z_{upper}^{\max} \Rightarrow P_{pump}(t) = 0 \quad (8)$$

3. Reservoir capacity coordination.

The lower reservoir must reserve safety drawdown space $V_{safety\ lower}$ when the upper reservoir is full.

$$\text{If } V_{upper,t} = V_{upper}^{\max}, V_{lower,t} = V_{lower}^{\max} - V_{lower}^{safety} \quad (9)$$

When the upper reservoir descends to dead storage $V_{min\ upper}$, the lower reservoir maintains a minimum operating level $V_{min\ lower}$ to ensure hydropower intake safety.

$$\text{If } V_{upper,t} = V_{upper}^{\min}, V_{lower,t} \geq V_{lower}^{\min} \quad (10)$$

2.3.4 Solution Method

The model is resolved through a simulation-based trial calculation according to the following steps:

Step 1. Using representative power delivery curves, establish the preliminary intra-day total output of the HCDS. Dispatch priority follows the hierarchy: midday peak, evening and morning peaks, then nocturnal trough.

Step 2. First, commit all available wind and solar output to grid export. Next, allocate any remaining demand preferentially to PHS. Finally, assign residual load to conventional hydropower stations, yielding each unit's intra-day schedule.

Step 3. Simulate each plant's operation to determine end-of-day reservoir levels. If these satisfy the predefined control targets, the schedule is accepted; otherwise, adjust the output profile per the dispatch hierarchy and repeat Step 2.

3 Study Area Overview

This study examines a multi-gigawatt demonstration project in the upper Yellow River basin, integrating hydropower, wind power, photovoltaic generation, and PHS to form a seasonally adjustable, multi-energy coordinated delivery network. The system's central hub is Hydropower Plant A (3420 MW installed capacity). Its reservoir functions as the common lower reservoir for two cascade PHS plants (total 4200 MW) and, within a 200 km radius, interfaces with a wind–solar cluster (planned PV 21000 MW; wind 2500 MW) to achieve source-side complementarity. The key technical parameters of each subsystem are as follows:

Hydropower Plant A: The catchment area is 98346 km² with a long-term mean flow of 533 m³/s. The normal pool elevation is 3275 m, dead-pool elevation 3240 m. Total storage is 1.622×10^9 m³, of which active storage is 7.06×10^8 m³, enabling seasonal regulation.

PHS Plant B: The upper reservoir has a normal pool elevation of 3665 m and dead-pool elevation of 3637 m, with active storage of 1.765×10^7 m³. The lower reservoir utilizes Plant A's reservoir. The preliminary installed capacity is 2400 MW (8 × 300 MW units), with an annual generation of 4.824×10^8 kWh and pumping consumption of 6.432×10^8 kWh. The maximum and minimum heads are 415.5 m and 344 m, respectively, with a design head of 366.5 m.

PHS Plant C: The upper reservoir has a normal pool elevation of 3780 m and dead-pool elevation of 3747 m, with active storage of 1.0185×10^7 m³. The lower reservoir again uses Plant A's reservoir. Installed capacity is 1800 MW (6 × 300 MW units), yielding 3.363×10^8 kWh annually and consuming 4.675×10^8 kWh for pumping. The maximum and minimum heads are 544.4 m and 475.3 m.

Monthly typical-day delivery curves for the energy hub are shown in Fig. 1.




Fig. 1. Monthly typical-day delivery curves

4 Results and Discussion

Given that Hydropower Plant A primarily functions as a seasonal-regulation facility, its ability to buffer prolonged and extreme fluctuations in wind–solar generation may be insufficient, thereby posing significant operational risks. This study evaluates its dynamic performance under three wind–solar output scenarios—baseline natural variability (Scenario 1), sustained low output (Scenario 2), and sustained high output (Scenario 3)—across the low-flow season, ecological-dispatch period (April–June), and flood season. Here, “sustained low output” and “sustained high output” correspond to the daily wind–solar power profiles with the month’s minimum and maximum average generation, respectively.

4.1 Dry-Season Extreme Scenarios

Using January as a case study, Fig. 2a–c illustrates reservoir-level trajectories under the three scenarios. In Scenario 1, reservoir level declines gradually, reflecting baseline dispatch. Under Scenario 3 (high wind–solar), diurnal fluctuations are minor, with rapid midday recovery mitigating drawdown. In Scenario 2 (low wind–solar), the reservoir level falls by approximately 10.6 m—jeopardizing plant stability. This detailed comparison underscores the heightened risk of excessive drawdown during prolonged low renewable output.




Fig. 2. Weekly operational profiles during the low-flow season.

4.2 Flood-Season Extreme Scenarios

Using July as a case study, Fig. 3a–c shows Plant A’s operational responses under the three scenarios, while Fig. 3d presents the annual distribution of spillage. During the flood season, inflows are abundant and Plant A retains considerable regulation capacity, maintaining high reservoir levels without risk of rapid drawdown. However, if wind–solar generation is prioritized year-round, midday PV peaks compress Plant A’s output, sharply increasing spillage risk.

As shown in Fig. 3d, annual spillage at Plant A is concentrated from late July through late October, totaling 1.025×10^8 kWh. Moreover, during sustained low PV output, midday pumping is reduced, diminishing regulation capacity and jeopardizing power-supply reliability during the evening peak.




Fig. 3. Weekly operational profiles during the flood season

4.3 Ecological-Dispatch Period

Taking May as an example, Fig. 4 illustrates Plant A's response under the three scenarios.




Fig. 4. Weekly operational profiles during the ecological-dispatch period

During this period, Plant A operates in run-of-river mode, without inherent storage regulation; its water-level dynamics are thus governed by the upstream pumped-storage facility's operation. A clear diurnal pattern emerges: reservoir levels decline during midday pumping for peak shifting and recover during evening/nighttime generation. The magnitude and rate of these fluctuations are further modulated by photovoltaic output. Under sustained high photovoltaic output, pumping power and flow rates during the midday peak are elevated, accelerating the reservoir drawdown; conversely, sustained low photovoltaic output yields milder drawdown. In this case, maximum daily amplitude reaches 1.75 m. To ensure adequate regulation margin, the minimum reservoir elevation at end-March is set to 3241.75 m, exactly matching the combined active storage requirement of the two pumped-storage plants.

4.4 Summary of Dispatch Strategies

Guided by the benchmark power-delivery curve in Fig. 1, the HCDS's annual operation is summarized in Fig. 5. At the end of March, Plant A's reservoir draws down to its minimum elevation of 3241.75 m, with no risk of rapid emptying and with full utilization of its regulation capacity. By late July, the reservoir refills to elevations between 3273.93 m and 3275.00 m and maintains high-level operation through year-end, without risk of overtopping due to concentrated releases from the pumped-storage facility.

To safeguard PHS reliability, Plant A's reservoir must exceed 3241.75 m at March's end and remain below 3,273.93 m from July to October when upstream storage is full. During PHS generation, the downstream reservoir may rise to 3275.00 m; during pumped-storage filling, it may fall to the dead-storage elevation of 3240.00 m. Under all

other conditions, the operational water-level band should adaptively align with upstream storage dynamics.




Fig. 5. Annual operational profile of the hydro–wind–solar–storage delivery system

5 Conclusions

This study introduces a multi-energy complementary dispatch framework that exploits the synergistic interplay among hydropower, wind, solar, and PHS assets while rigorously embedding grid peak-shaving imperatives and long-distance transmission stability constraints. We develop a unified peak-shaving optimization model for the HCDS ensemble and apply it to the upstream Yellow River Clean Energy Base. Our simulation encompasses both representative operational scenarios and a full 8760-h annual dispatch, elucidating how a coordinated strategy—prioritizing renewable output, utilizing pumped-storage for intraday peak regulation, and deploying hydropower to guarantee base load—manifests distinct performance profiles and inherent risk-mitigation mechanisms under extreme conditions. Under ecological-dispatch requirements (April–June run-of-river operation) and transmission corridor limits (base load $\geq 1,000$ MW; peak $\leq 10,000$ MW), the proposed framework simultaneously maximizes yearly generation and enhances peak-shaving efficacy. Nevertheless, climate-driven variability in wind and solar resources continues to constrain regulation margins. Future work should integrate demand-side response schemes to improve load-curve alignment and advance HCDS correlation modeling to bolster system resilience in extreme scenarios.

References

- Cheng, Q., Liu, P., Xia, J., et al.: Contribution of complementary operation in adapting to climate change impacts on a large-scale wind–solar–hydro system: a case study in the Yalong River Basin, China. *Appl. Energy* **325** (2022)
- Heggarty, T., Bourmaud, J.-Y., Girard, R., et al.: Quantifying power system flexibility provision. *Appl. Energy* **279**, 115852 (2020)
- Ju, C., Ding, T., Jia, W. H., et al.: Two-stage robust unit commitment with the cascade hydropower stations retrofitted with pump stations. *Appl. Energy* **334** (2023)
- Liu, M., Kong, X., Lian, J., et al.: Distributionally robust coordinated day-ahead scheduling of Cascade pumped hydro energy storage system and DC transmission. *Appl. Energy* **384**, 125449 (2025)

- Lu, M.K., Guan, J., Wu, H.H., et al.: Day-ahead optimal dispatching of multi-source power system. *Renew. Energy* **183**, 435–446 (2022)
- Toufani, P., Nadar, E., Kocaman, A.S.: Operational benefit of transforming cascade hydropower stations into pumped hydro energy storage systems. *J. Energy Storage* **51** (2022)
- Wang, Z.N., Fang, G.H., Wen, X., et al.: Coordinated operation of conventional hydropower plants as hybrid pumped storage hydropower with wind and photovoltaic plants. *Energy Conv. Manage.* **277** (2023)
- Xu, X., Hu, W.H., Cao, D., et al.: Optimized sizing of a standalone PV-wind-hydropower station with pumped-storage installation hybrid energy system. *Renew. Energy* **147**, 1418–1431 (2020)
- Zhang, X., Patelli, E., Zhou, Y., et al.: Enhancing the economic efficiency of cross-regional renewable energy trading via optimizing pumped hydro storage capacity. *Renew. Energy* **240**, 122205 (2025)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Research on Key Technologies for Multi-energy Complementary Hydro-Wind-Solar-Storage Base

Zenghai Zhao, Dong Zhang, Jie Gao^(✉), Xu Wang, Fangliang Zhu, and Peng Guo

China Renewable Energy Engineering Institute, Beijing, China

690676797@qq.com

Abstract. To achieve low-carbon development and energy transition, renewable energy (RE) plays an important role. Multi-energy complementary RE bases are vigorously promoted in China. This paper systematically reviews the global and domestic hydro, wind and solar power resources and spatiotemporal distribution. The current status of research on multi-energy complementary hydro-wind-solar-storage (HWSS) system is analyzed. We identify certain technical challenges existing in capacity configuration, planning optimization, and dynamic regulation, and construct a “resource assessment & capacity configuration & operation scheduling” technical framework for HWSS integrated base. Furthermore, in accordance with the engineering requirements and operational schedule, an integrated intelligent management and control platform for HWSS system is developed, which could significantly enhance the scientific planning capability and operational efficiency for multi-energy complementary HWSS bases.

Keywords: Hydro-Wind-Solar-Storage (HWSS) · Multi-energy complementarity · Simulation and prediction · Capacity configuration · Operation scheduling

1 Introduction

Pursuit of low-carbon development and transition to sustainable energy has become a worldwide recognition in response to climate change and ecological conservation. The large-scale and high-quality development of new energy sources, such as wind power and solar power play a critical role.

The global installed capacity of renewable energy generation reached approximately 4450 GW by the end of 2024, including 1430 GW of hydropower (including pumped storage hydroelectric (PSH)), 1870 GW of solar power, and 1150 GW of wind power (comprising 1050 GW of onshore wind and 100 GW of offshore wind). In 2024, newly added global RE capacity was about 590 GW, accounting for 94% of the global power new installed capacity. Within this, hydropower (including PSH) was approximately 20 GW, wind power 120 GW, and solar power 450 GW [1, 2].

By the end of 2024, China has established the largest RE power generation system, with an installed capacity of 1890 GW, accounting for approximately 42.5% of the global

total, significantly surpassing the United States (430 GW), Brazil (210 GW), India (200 GW), and Germany (180 GW). Meanwhile, China's RE capacity constitutes 56.4% of the domestic power generation capacity, gradually becoming the dominant source [3].

2 Hydropower-Wind-Solar-Storage (HWSS) Multi-Energy Complementary Development

2.1 Analysis of Hydropower, Wind, and Solar Resource in China

China possesses abundant hydropower resources [4], with a technically exploitable capacity of approximately 686 GW, ranking first in the world, with nationally-designated Thirteen Major Hydropower Bases located at Jinsha River basin, Yalong River basin, Dadu River basin, Upper Yangtze River and Upper Yellow River etc. However, the spatial and temporal distribution of China's hydropower resources is uneven. Spatially, most resources are concentrated in the western regions, particularly in the southwest region, where the technically exploitable capacity reaches 476 GW, accounting for 69.3% of China's technical exploitable capacity. Temporally, influenced by monsoon climate, the seasonal flow of most rivers varies greatly, with uneven distribution both inter-annually and intra-annually.

China has a vast territory with plentiful wind energy resources. The technically exploitable wind energy resources at heights of 50 m, 70 m, and 100 m is estimated at 2000 GW, 2600 GW, and 3400 GW, respectively. It primarily distributes in Xinjiang, Inner Mongolia, the Northeast, North, Northwest region of China, the eastern coastal areas, the Tibetan Plateau, and the Yun-Gui Plateau. The seasonal variation of wind energy resources is obvious, generally, spring is the largest, followed by winter, autumn is smaller, and summer is the smallest. China is also endowed with vast solar energy resources, with annual sunshine hours exceeding 2000 h over more than two-thirds of the country's land area. The theoretical solar energy reserve nationwide reaches 1860 TW. Spatially, it presents a distribution characteristic of "plateaus larger than plains, and the west larger than the east". The annual horizontal total irradiation in most areas of Tibet, northern Qinghai, most of North China, and the western and southwestern parts of the Yun-Gui Plateau ranges from 1.4 to 1.75 MWh/m². Seasonally, solar resources vary significantly with total solar radiation, characterized by higher levels in summer and lower levels in winter in most regions.

In conclusion, hydropower, wind and solar energy resources are naturally complementary in spatial and temporal distribution. Secondly, hydropower can effectively smooth out the intermittency of wind and PV power generation through the regulation capacity of reservoirs, which is beneficial to the safety and stability of the power grid. Thirdly, relevant data shows that the unit investment cost of onshore wind power is CNY 4,200/kW, that of PV is CNY 3,450/kW and that of hydropower is CNY 5,767/kW [5], wind and PV power generation have lower cost. Therefore, integrated hydropower-wind-solar generation can effectively reduce the overall grid electricity cost and achieve an economic complementarity.

2.2 Methodology and Significance of Multi-energy Complementary HWSS Development

Multi-energy complementary HWSS is guided by the principle of maximizing the development of wind and solar power, relying on flexible regulating power sources such as cascade hydropower, PSH and new energy storage to optimize the combined operation of hydropower, wind, and solar. Multi-energy complementary HWSS development could contribute to construct bases with large-scale and high-proportion of RE, with integrated resource allocation, planning and construction, regulation and operation, and market competition, thereby enhancing the overall economic efficiency of RE development and the utilization rate of transmission corridors.

The essence of multi-energy complementary HWSS development is to upgrade and renovate the traditional hydropower bases. Through capacity configuration, optimization scheduling, and operation control, the “1+1+1>3” synergistic effect is achieved.

- Hydropower is the “Regulation”: hydropower provides regulation capacity to smooth the fluctuation of wind and solar power output, and increase the utilization rate of wind and solar energy.
- Wind/Solar is the “Mainstay”: wind power and PV provide the major electricity in the system and make full use of the transmission corridors of hydropower station.
- Storage is the “Flexibility”: PSH, electrochemical storage, etc. act as multi-time-scale buffers, enabling the redistribution of system electricity on a daily and weekly scale, as well as meeting minute-level frequency regulation requirements, thereby improving the quality of electrical energy.
- Intelligent Systems is the “Brain”: Based on the collaborative prediction of hydropower, wind, and solar, through the complementary operation and scheduling of the intelligent energy regulation system, the comprehensive benefits of the system can be achieved.

2.3 Current Status of HWSS Base Planning in China

Engineering practices for multi-energy complementary HWSS bases in China are flourishing. In 2020, a comprehensive research on the national HWSS integrated bases was conducted, preliminarily planned ten major HWSS integrated bases, which are located at the Upper Jinsha River, Middle Jinsha River, Lower Jinsha River, Dadu River, Yalong River, Lancang River, Middle Yarlung Tsangpo River, Middle-Lower Yarlung Tsangpo River, Upper Yellow River, and Southeast Tibet region, with a total planned install capacity of approximately 1 billion kW. In 2023, the “Yalong River Basin Integrated Hydropower-Wind-Solar Base Plan” was issued, with a base planning scale of 78 GW, including 28.4 GW hydropower, 2.6 GW wind power, 36.4 GW solar PV, and 10.6 GW PSH, and to be established by 2035.

3 Key Technologies for Multi-energy Complementary HWSS

3.1 Research Status and Key Issues

3.1.1 Wind-Solar Resource Assessment and Multi-spatiotemporal Scale Power Output Simulation and Prediction

Wind and solar resources assessment, along with power output simulation and prediction, are the basis for the planning, construction, and operation of HWSS bases.

- **Meteorological Data.** Relevant meteorological data of wind and solar can be categorized into point-sources and area-sources data. Point-source data is mainly derived from measured data from meteorological stations and wind/solar monitoring stations. Area-source data mainly comprises reanalysis data and satellite monitoring data released by major meteorological institutions worldwide. Comparatively, point-source data is more representative for local monitoring but has poor spatiotemporal coverage, and suitable for studying local characteristics. Area-source data, such as ERA5 and MERRA, provide extensive spatiotemporal coverage, with records spanning over 40 years globally [6–8].
- **Resource Potential Assessment.** Assessment methods for wind and solar resources primarily include two approaches: empirical estimation and simulation-based calculation [9–12]. Limited by data availability, empirical estimation methods are currently more commonly used in engineering practice to evaluate regional wind and solar potential.
- **Power Output Characteristic Analysis.** Analysis for characteristics of wind and solar power output can be divided into two scenarios: simulation and prediction. Simulation is typically adopted in the planning and design of power plants or RE bases, while prediction is applied in the regulation to formulate generation schedules and enable integrated collaborative operation. While sharing the similar principles, the methodology mainly includes two categories: physical mechanism-based and statistical methods. Physical mechanism-based methods acquire the output of wind and solar by constructing physical models that consider the wind turbine gas dynamics or the semiconductor properties of PV modules [13, 14], while the statistical method mainly relies on data mining and analysis techniques, including machine learning [15], artificial neural networks [16], and deep learning [17, 18].

However, there are still challenges in the current engineering practice:

1. **Standardized of Multi-Source Heterogeneous Data.** Standardized of data with multi-source, multi-precision, and multi-spatiotemporal resolutions is crucial future research and engineering.
2. **Unified Spatiotemporal-Scale for Simulation.** Developing coordinated methods and constructing historical long-term output sequences of hydro-wind-solar power under unified spatiotemporal scales requires further research.
3. **Multi-Scale Coordinated for Prediction.** Technologies for multi-scale coordinated prediction of hydro-wind-solar power considering multiple influencing factors still need in-depth research.

3.1.2 Analysis of Multi-energy Complementary and Optimization of Capacity Configuration

Capacity configuration for HWSS system is a core task in the bases planning, mainly including the assessment of system complementarity and optimization of installed capacity configuration.

- **Analysis of Complementarity Characteristics of HWSS.** Domestic and international scholars have primarily focused on the precise characterization of wind and solar power output across multiple time scales and their spatiotemporal complementarity [19–22]. However, there is relatively less research on the purpose each power source serves in the systems and complementary characteristics of the integrated HWSS systems.
- **Optimization of Installed Capacity Configuration.** Constrained by local conditions and resource endowments, large-scale HWSS base projects are currently absent internationally. Research and practice are mainly small-scale distributed energy systems [23–25]. Within China, different methods are introduced: 1) Empirical methods are employed to determine the installed capacity of each power source under typical scenarios. 2) Based on simulating actual regulation and operation processes, capacity optimization is achieved through comprehensive decision-making which evaluates technical and economic indicators of the system under different schemes and scenarios [26–28].

In response to future engineering needs, great potential for development remains:

1. **Establishing a Complementarity Assessment Framework.** Develop a precise assessment index system that accurately captures the complementarity patterns within HWSS.
2. **Developing an Integrated Optimization Model.** Construct a scientific, applicable optimization model of capacity configuration for HWSS system. This model must achieve source-load coordination, accurately reflect power output characteristics and load demand.

3.1.3 Multi-energy Complementary HWSS Operation Scheduling

The purpose of operation scheduling for multi-energy complementary HWSS systems is to solve the intermittency of new energy generation by optimizing the power output allocation among different sources. This enhances reliability and economic efficiency of system power supply [29, 30].

- **Short-term Complementary Operation Scheduling.** Scholars primarily focus on optimization models based on objectives such as maximum short-term power generation or optimal load matching. Dynamic programming, fuzzy programming, and stochastic programming are employed to build models. The goals are to smooth wind and solar power output randomness, fluctuations and intermittency, ensure peak regulation capacity, and improve energy utilization efficiency [31, 32].
- **Long-Medium Term Operation Scheduling.** Researchers utilize methods such as discretization of continuous probability distributions and auto-regressive moving

average model for scenario generation. Optimization models are constructed considering objectives such as maximizing long-medium power generation, maximizing generation guarantee rate, and minimizing comprehensive risk rate [33, 34]. These models aim to reconfigure the long-term operation modes of reservoirs and the water level control rules.

- **Multi-timescale Coordination Strategy.** The initial strategy has been proposed “Results of long-medium term adopted as boundary conditions for short-term complementary operation, while using real-time correction for short-term operation scheduling to adjust original long-medium term boundaries”. By assessing the scheduling risks and benefits of complementary systems, multi-timescale coordinated optimization models with risk-benefit balanced have been established [35, 36].
- **Model Solving Algorithms.** Efficient dimensionality reduction [37], parallel solving techniques [38], and multi-objective optimization methods [39, 40] are widely used.
- **Risk Assessment and Prevention Management.** Methods such as return period analysis, reliability analysis, Monte Carlo simulation, and Bayesian network theory [41–43] are commonly used. Current applications are mainly limited to single power source, small-scale multi-energy complementary systems, or isolated micro-grids.

However, there are still certain problems that need to be solved:

1. **Refined Topology Representation.** Method for characterizing the hierarchical topology of transmission, reflecting the spatial distribution of power sources needs to be refined. Large-scale HWSS bases involve numerous power plants and complex grid connection networks, making it difficult for existing models to accurately represent intricate electrical interconnections.
2. **Integrated Multi-timescale Scheduling Models.** Further research is needed to comprehensively consider the coupling relationship between long-medium term and short-term scheduling across different timescales. This includes developing cyclically adjustment and rolling correction models for long-medium-short term scheduling and designing efficient solving algorithms.
3. **Comprehensive Risk Management Framework.** There is an urgent need to establish a technical framework for risk identification, analysis, assessment, and prevention specifically for HWSS multi-energy complementary systems.

3.1.4 Integrated Intelligent Management and Control Platform for HWSS Bases

Research on multi-energy complementary HWSS is still relatively limited particularly concerning the integrated operation and scheduling of HWSS systems. Mature case studies are currently lacking, and corresponding tools are insufficient. Existing system platforms primarily focus on wind/solar power plant operation and cascade reservoir scheduling.

With the rapid development of multi-energy complementary HWSS bases, it is necessary and valuable to construct an applicable and intelligent HWSS multi-energy complementary scheduling system.

3.2 Technical Framework

Based on the requirements mentioned above, our study proposes a technical framework for HWSS multi-energy complementary system, as illustrated in Fig. 1. This framework focuses on planning and operation of HWSS base. It encompasses five primary research domains: HWSS resource assessment and power characteristics analysis, power capacity configuration optimization, collaborative prediction of hydro-wind-solar power output, multi-timescale complementary operation scheduling, and integrated intelligent management and control platform.




Fig. 1. The technical framework for multi-energy complementary HWSS system

3.3 Key Technologies

Base on the framework, our study conducts comprehensive research and achieve the following innovative outcomes.

3.3.1 Wind and Solar Resources Assessment and Multi-temporal-Spatial Output Simulation and Prediction

- Addressing the heterogeneous characteristics of meteorological and topographic data, interpolation, coding, and GIS were employed to achieve efficient nesting of 30 km meteorological grids with 30 m topographic grids. Total approximately 17,000 of 30 km grids which containing millions of 30 m grids. This enabled the standardized processing of layers of DEM, slope, aspect, as well as wind and solar resource characteristics.
- Optimal siting method for wind and solar power plant based on multi-dimensional assessment was developed. Utilizing PV conversion model integrating solar irradiance, temperature and module characteristics, wind power output physical model incorporating wind speed-power curves and wake effects, and meteorological reanalysis data, sequences of long-term hourly power output were reconstructed. A database with over 40 years of hourly output data covering China, particularly the HWSS bases

within ten major river basins was established. This database provides continuous power generation estimation for the planning of wind/solar power plants and bases.

- A probabilistic power output forecasting framework was constructed which integrates predictor screening techniques, deep learning algorithms, and methods to describe uncertain information. A set of parameter automatic correction technology suitable for different regions was proposed. This method enables rolling predictions of power output and suitable for multi-scenario and multi-scale applications.

3.3.2 Optimization of HWSS Integrated Capacity Configuration

- For multi-energy complementary HWSS system, an evaluation index system and methodology based on virtual power sources and output aggregation were established. The index system covers energy utilization, economic efficiency, security and reliability, flexible support, and clean/low-carbon attributes.
- A set of mathematical modeling method for hydropower, wind power, solar power, and storage power (including PSH) was developed.
- A “two-layer” optimization model for capacity configuration of HWSS system was established. The upper layer generates a set of capacity configuration schemes, while the lower layer performs techno-economic indicator calculations based on multi-energy complementary operational simulations of 8760 h within a year to support solution decision-making.

3.3.3 Operation Scheduling of HWSS System

- According to the requirements of power grid such as output smoothing, peak shaving and valley filling, and source-load matching, the constraints and boundaries for safe access to the grid were identified. Optimization objectives were categorized into three criteria: benefit-oriented, cost-oriented, and security/stability-oriented. Subsequently, a multi-energy complementary scheduling objective system and constraint set were proposed for the HWSS base.
- The spatial relationships between power sources within the base were characterized using an approach based on “power source partitioning & transmission section classification & hierarchical section topology”. The network topology encompassing power sources, transmission lines, and power transmission corridor was constructed. A multi-energy complementary optimization scheduling model for HWSS base was then established. This model addresses multiple complex hydraulic and electrical constraints and operates across long-medium-short term, and real-time time scales with multiple objectives.
- Efficient solution techniques based on heuristic search, large-scale system decomposition and coordination, multi-objective optimization were employed to solve the model. The study comprehensively considered the coupling relationships across long-medium term and short-term time scales, and a cyclic nesting and rolling correction mode was constructed. Thereby achieving optimization of system scheduling of seamless coordination across different time scales.

4 The HWSS Integrated Intelligent Management and Control Platform

Based on the technical framework and engineering workflows, we developed the HWSS Integrated Intelligent Management and Control Platform. The platform comprises three core modules: Resource Assessment Module, Capacity Configuration Optimization Module, Multi-Energy Complementary Operation Module. The Platform can provide integrated planning-operation solutions for multi-energy complementary HWSS bases.

• Resource Assessment Module

The resource evaluation module consists of two core functions: simulation and prediction. It could provide data support for the optimization of resources allocation and operation scheduling for bases. The simulation function serves optimization of capacity configuration, while the prediction function serves multi-energy complementary operation scheduling. Users select the research area, input resource parameters (weather data sources, calculation period), geographic parameters, unit component parameters, etc., and choose existing or planned station sites. The platform automatically conducts long-term historical output simulation or prediction of wind and solar power, and pushes the relevant data to subsequent functional modules (Fig. 2).



Fig. 2. Resource Assessment Module: output simulation results

• Capacity Configuration Optimization Module

The capacity configuration optimization module includes multi-energy complementary characteristic analysis, scenario construction, scheme simulation and multi-scheme comparison, scheme recommendation and results visualization. Users input boundary

conditions such as power resource, energy storage, topological relationship and transmission requirements, and the platform automatically generates and simulates multiple schemes of capacity configuration, calculates technical and economic indicators, provides the optimal scheme and conducts visual display (Fig. 3).




Fig. 3. Capacity Configuration Optimization Module: configuration results

● Multi-Energy Complementary Operation Module

The multi-energy complementary operation module focuses on the daily scheduling and economic operation of the base, covering different time scales, including long-medium term (with years, months, and weeks as scheduling periods to achieve coordinated generation distribution), short-term (with days as the scheduling period, hourly or 15-min as time-step, optimizing the day-ahead operation mode of hydropower and energy storage), and real-time economic scale (with a scheduling period of minutes, to minimize operating costs and meet the grid load curve, and reasonably arranging the start-stop and output plans of each unit). The platform uses the wind and solar power output prediction results provided by the resource evaluation module and the power configuration scheme determined by the capacity configuration optimization module to conduct complementary operation simulation over multiple time scales and visualize the results (Fig. 4).




Fig. 4. Multi-Energy Complementary Operation Module: scheduling results

5 Conclusions

Entire life cycle of multi-energy complementary HWSS base involves planning, design, construction, and operation, among which development planning and operational regulation are the top-level framework of energy bases. This study focuses on the planning and operation of HWSS bases. Addressing technical requirements encountered in engineering practical, it introduces global hydro, wind and solar resources profiles, particularly in China. The paper systematically reviews the research status in multi-energy complementarity HWSS system, summarizes technical hotspot, and constructs a technical framework for multi-energy complementary HWSS system. An introduction of our HWSS Integrated Intelligent Management and Control Platform is made which including “resource assessment & capacity configuration & operation scheduling”. It could provide a technical support for the development of planning and operation of multi-energy complementary HWSS bases.

Acknowledgment. This research is supported by National Key Research and Development Program of China (2024YFB2409000).

References

1. China Renewable Energy Engineering Institute. China Renewable Energy Development Report 2024. China Water & Power Press, Beijing (2025). (in Chinese)
2. China Renewable Energy Engineering Institute, China Society for Hydropower Engineering (CSHE) SWM Branch: Development Report of Pumped Storage Industry 2024. China Water&Power Press, Beijing (2025). (in Chinese)
3. Liu, P.: Basin-wide multi-source complementary dispatch of hydro-wind-solar energy. Science Press, Beijing (2023). (in Chinese)
4. Tang, H.W.: Introduction to multi-energy complementary systems: hydro-wind-solar-storage integration. 中国Science and Technology of China Press, Beijing (2023). (in Chinese)

5. China Renewable Energy Engineering Institute: China renewable energy engineering cost management report 2024. China Water&Power Press, Beijing (2025). (in Chinese)
6. Wang, C.H., Shen, Y.B., Yao, J.F., et al.: Applicability of three reanalysis data in assessment of solar energy resources in China. *Acta Energiæ Solaris Sinica* **43**(08), 164–173 (2022). (in Chinese)
7. Chen, Z., Guo, J.H., Kang, P.P., et al.: Applicability of five sets of reanalysis data in wind resource assessment in alтай prefecture. *Acta Energiæ Solaris Sinica* **44**(04), 60–66 (2023). (in Chinese)
8. Camargo, L.R., Schmidt, J.: Simulation of multi-annual time series of solar photovoltaic power: Is the ERA5-land reanalysis the next big step? *Sustain. Energy Technol. Assess.* **42**, 9 (2020)
9. Liu, C., Wang, T.Y., Qu, Y.Y., et al.: Wind resource analysis and site selection of wind power plant. *Acta Energiæ Solaris Sinica* **37**(11), 2835–2842 (2016). (in Chinese)
10. Chen, G.C., Yang, W., Zhang, Y.C., et al.: New computation method of wind speed probability distribution parameters in wind farm. *Proc. CSU-EPSC* **23**(01), 46–51 (2011). (in Chinese)
11. Tong, D., Farnham, D., Duan, L., et al.: Geophysical constraints on the reliability of solar and wind power worldwide *Nat. Commun.* **12** (2021). <https://doi.org/10.1038/s41467-021-26355-z>
12. Xiao, J.H., Yao, Z.Y., Sun, J.H.: Review on optimal site selection for grid-connected solar photovoltaic plants. *J. Desert Res.* **31**(06), 1598–1605 (2011). (in Chinese)
13. Yang, X.Y., Xiao, Y., Chen, S.Y.: Wind speed and generated power forecasting in wind farm. *Proc. CSEE* **25**(11), 1–5 (2005). (in Chinese)
14. Wu, S.: Review of power forecasting methods of photovoltaic power generation system. *J. Eng. Thermal Energy Power* **36**(08), 1–7 (2021)
15. Wu, W.Z., Qiao, Y., Lu, Z.X., et al.: Methods and prospects for probabilistic forecasting of wind power. *Autom. Electric Power Syst.* **41**(18), 167–175 (2017). (in Chinese)
16. Gao, J., Wang, X., Gu, J.W., et al.: Research on simulation and prediction of photovoltaic power generation based on radiation models and machine learning method. *Hydropower and Renewable Energies, IHDC 2024. Lecture Notes in Civil Engineering*. Springer, Berlin (2024). (in Chinese)
17. Son, J., Park, Y., Lee, J., et al.: Sensorless PV power forecasting in grid-connected buildings through deep learning. *Sensors* **18**(8), 2529 (2018)
18. Wang, K.J., Qi, X.X., Liu, H.D.: A comparison of day-ahead photovoltaic power forecasting models based on deep learning neural network. *Appl. Energy* **251**, 113315 (2109)
19. Liu, Y.Q., Wang, H., Han, S.: Real-time complementarity evaluation method for real-time complementarity of wind and solar power considering their volatility. *Power Syst. Technol.* **44**(09), 3211–20 (2020). (in Chinese)
20. Wang, J., Chen, L., Tan, Z., et al.: Inherent spatiotemporal uncertainty of renewable power in China. *Nat. Commun.* **14**, 5379 (2023)
21. Liu, Y., Xiao, L., Wang, H., Dai, S.: Analysis on the hourly spatiotemporal complementarities between China's solar and wind energy resources spreading in a wide area. *Sci. China Technol. Sci.* **56**(3), 683–692 (2013)
22. Jurasz, J., Canales, F.A., Kies, A., et al.: A review on the complementarity of renewable energy sources: concept, metrics, application and future research directions. *Sol. Energy* **195**, 703–724 (2020)
23. Prasad, A.A., Taylor, R.A., Kay, M.: Assessment of solar and wind resource synergy in Australia. *Appl. Energy* **190**, 354–367 (2017)
24. Couto, A., Estanqueiro, A.: Assessment of wind and solar PV local complementarity for the hybridization of the wind power plants installed in Portugal. *J. Clean. Prod.* **319**, 128728 (2021)

25. Jurasz, J., Beluco, A., Canales, F.A.: The impact of complementarity on power supply reliability of small scale hybrid energy systems. *Energy* **161**, 737–743 (2018)
26. Gao, J.: A research on operation of the pumped-storage, photovoltaic and wind power hybrid system. *Hydropower Pump. Storage* **6**(5), 25–29+37 (2020). (in Chinese)
27. Javed, M.S., Ma, T., Jurasz, J., et al.: Solar and wind power generation systems with pumped hydro storage: review and future perspectives. *Renew. Energy* **148**, 176–192 (2020)
28. Zhou, J.Z., Lu, P., Mo, L., et al.: Short-term hydro-thermal-wind complementary scheduling considering uncertainty of wind power using an enhanced multi-objective bee colony optimization algorithm. *Energy Convers. Manage.* **123**, 116–129 (2016)
29. Shen, J.J., Wang, Y., Chen, C.T., et al.: Research status and prospect of generation scheduling for hydropower-wind-solar energy complementary system. *Proc. CSEE* **42**(11), 3871–3885 (2022)
30. Chen, C.T., Li, G., Chen, X., et al.: Large-scale ultra high voltage direct current hydropower absorption and its experiences. *J. Proc. CSEE* **35**(03), 549–560 (2015). (in Chinese)
31. Wang, X., Chang, J., Meng, X., et al.: Short-term hydro-thermal-wind-photovoltaic complementary operation of interconnected power systems. *Appl. Energy* **229**, 945–962 (2018). (in Chinese)
32. Wang, X., Virguez, E., Xiao, W., et al.: Clustering and dispatching hydro, wind, and photovoltaic power resources with multi objective optimization of power generation fluctuations: a case study in southwestern China. *Energy (Oxford)* **189**, 116250 (2019)
33. Kang, B.X.: Summarization of research on coordination operation of hydropower and PV power in longyangxia hydropower station. *Northwest Hydropower* **01**, 23–26 (2020). (in Chinese)
34. Li, H., Liu, P., Guo, S., et al.: Long-term complementary operation of a large-scale hydro-photovoltaic hybrid power plant using explicit stochastic optimization. *Appl. Energy* **238**, 863–875 (2019)
35. Wen, X., Sun, Y.L., Tan, Q.F., et al.: Risk and benefit analysis of hydro-wind-solar multi-energy system considering the one-day ahead output forecast uncertainty. *Adv. Eng. Sci.* **52**(03), 32–41 (2020). (in Chinese)
36. Ming, B., Li, Y., Liu, P., et al.: Long-term optimal operation of hydro-solar hybrid energy systems nested with short-term energy curtailment risk. *J. Hydraul. Eng.* **52**(06), 712–722 (2021). (in Chinese)
37. Wu, H., Ji, C.M., Jiang, Z.Q., et al.: Large system decomposition-coordination model for optimal power-generation scheduling of cascade reservoirs. *J. Hydroelectric Eng.* **11**, 40–50 (2015). (in Chinese)
38. Zhou, D.Q., Peng, S.Y., Cheng, C.T., et al.: Cloud computing stochastic dynamic programming algorithms for long-term optimal operation of cascaded hydropower stations. *Proc. CSEE* **37**(12), 3437–3448+3671 (2017). (in Chinese)
39. Srinivas, N., Deb, K.: Multi objective optimization using nondominated sorting in genetic algorithms. *Evol. Comput.* **2**(3), 221–248 (1994)
40. Deb, K., Pratap, A., Agarwal, S., et al.: A fast and elitist multi objective genetic algorithm: NSGA III. *IEEE Trans. Evol. Comput.* **6**(2), 182–197 (2002)
41. Zhang, D., Wang, X., Gao, J., et al.: Research on optimization model of medium-long-term maintenance schedule for new-generation power system. In: 2024 IEEE PES 16th Asia-Pacific Power and Energy Engineering Conference (APPEEC), Nanjing, China (2024)
42. Zhang, Y.K.: Theories and methods of risk analysis for multipurpose reservoir operation. North China Electric Power University, Beijing (2012). (in Chinese)
43. Ji, C.M., Zhang, Y.K., Yan, X.R., et al.: Cascaded reservoirs: coordinated operation and risk analysis. China Water&Power Press, Beijing (2020). (in Chinese)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Research on Vibration Reduction Scheduling Strategies for High-Dam Discharge Under Low-Frequency and Small-Amplitude Characteristics

Heng Zhang¹, Yanhe Chen², Luchen Zhang^{3(✉)}, Wei Bao¹, Xueyu Zheng¹, Wei Sun^{1,4}, and Yongfu Hu²

¹ PowerChina Guiyang Engineering Corporation Limited, Nanjing, China

² Huaneng Lancang River Upper Reach Hydropower Co., Ltd., Nanjing, China

³ Nanjing Hydraulic Research Institute, Nanjing, China

110455898@qq.com

⁴ Huaneng Lancang River Hydropower Inc., Nanjing, China

Abstract. High-dam flood discharge, a critical phase in hydropower engineering, has increasingly attracted attention due to ground vibration issues. This vibration typically appears as a continuous, low-frequency, low-amplitude oscillation, which is difficult to mitigate using traditional vibration reduction methods such as dampers or rubber shock absorbers. Using the RM project as an example, this research combined numerical simulations and hydraulic model experiments to analyze the effects of discharge and flood discharge scheduling on ground vibration. The results showed that multi-hole and balanced discharge openings significantly improved water flow patterns, dramatically reducing pulsation loads in the water cushion basin: the bottom plate's maximum pulsation pressure decreased by 27%–82%, with an overall pressure reduction of 12%–45%, while side walls experienced a maximum pulsation pressure drop of 47%–62% and an overall pressure reduction of 35%–60%. The flood discharge vibration response decreased by approximately 45%, with the multi-hole balanced discharge method proving highly effective in controlling ground vibration. By optimizing discharge scheduling methods, the research effectively reduced ground vibration response, thereby enhancing the safety of surrounding residents.

Keywords: High-dam · Large flood discharge · Ground vibration · vibration reduction · Numerical simulation · Hydraulic model experiment

1 Introduction

With the vigorous development of China's hydropower industry, dam construction has evolved towards high-head structures with large discharge capacities, making flood discharge issues of high dams increasingly prominent (Zhang, Lian et al. 2021, Zhang, Lian et al. 2025). The high-velocity discharge flow carries tremendous energy, which

can induce vibrations in hydraulic structures themselves, their foundations, and surrounding areas (Zhang, Hou et al. 2018). When residential areas are located too close to flood discharge zones or the site geological conditions are non-uniform, excessive vibration responses may occur. Numerous engineering cases of significant ground vibrations induced by high-dam flood discharge have been documented both domestically and internationally. Although flood discharge from high dams does not directly endanger life and property safety, it constitutes a long-term operational requirement (Zhang, Peng et al. 2017). When environmental vibrations caused by prolonged flood discharge persistently exceed permissible limits, they may lead to building cracks and resident anxiety, thereby creating negative impacts on the living conditions of surrounding communities (Yang, Feng et al. 2025).

Current research methodologies on environmental vibrations induced by dam flood discharge primarily encompass three approaches: prototype monitoring, numerical simulation, and physical model testing (Lian, Zheng et al. 2019, 2024, Xu, Hou et al. 2024). Prototype monitoring enables accurate acquisition of ground vibration responses, physical model testing provides valuable references during feasibility study and design phases, while numerical simulation effectively reproduces vibration wave propagation patterns and pathways. However, the simulation of flood-induced vibrations in structures, foundations, and surrounding sites presents significant challenges as it constitutes a complex fluid-structure interaction problem. Direct numerical modeling encounters difficulties in computational accuracy, where improper boundary condition configuration may induce oscillations in vibration wave propagation. Recent advancements in this field have witnessed breakthrough progress through innovative methodologies, including the treatment of fluctuating pressures as dynamic loads and the implementation of infinite element-finite element coupling techniques (Lian, Chen et al. 2020). Vibration mitigation and suppression should address both the vibration source (plunge pool) and structural response aspects. For vibration-sensitive structures exhibiting significant dynamic responses, targeted reinforcement measures are typically implemented from the “response” perspective. While conventional solutions like hydraulic dampers and rubber isolation pads demonstrate effectiveness in controlling high-frequency, large-amplitude vibrations, their efficacy in suppressing persistent low-frequency, small-amplitude vibrations characteristic of continuous flood discharge operations has yet to be thoroughly investigated (Lian, Guo et al. 2019).

Therefore, this study employs the RM Hydropower Station as a prototype case, implementing coupled hydraulic model testing and numerical simulations based on the “input-structure-output” framework. Through systematic computation of ground vibration patterns under varying operational conditions, we conduct comprehensive effectiveness evaluations of vibration mitigation across different flood discharge operation schemes. Ultimately, this research proposes optimized operational strategies for vibration control during power station discharge operations, integrating hydrodynamic performance with structural response requirements.

2 Materials and Methods

2.1 Overview of the Research Subject

This project is a core-wall rockfill dam with a maximum dam height of 315.0 m, classified as a first-class (1) large-scale project. The key structural components include a gravel core-wall dam, 3 tunnel-type spillways, a flood discharge tunnel, a drain tunnel, and a right-bank water diversion and power generation system. The water cushion basin is located 480 m downstream of the dam site in the main river channel, with a maximum length of approximately 490 m, an average width of 175 m, and a bottom plate elevation of 2,590.00 m. In the key focus area, the bedrock lithology is primarily defined by a regional fault. West of the fault, the dam and water cushion basin are situated in the Middle Triassic Zhuka Formation (T_2z), while east of the fault, the area where residents and schools are located is in the Middle Jurassic Huakai Formation (J_2h).

2.2 Hydrodynamic Model Experiment

The hydraulic model experiment was designed as a prototype model with a geometric scale ratio of 1:80, utilizing gravitational similarity criteria (Fig. 1a). The simulation comprehensively covered key infrastructure elements, including upstream river channel topography, the dam, tunnel-type spillways, flood discharge tunnel, drain tunnel, tail water diversion system (excluding power units), water cushion basin, and downstream river channel topography. The model's physical dimensions were 45 m in length, 25 m in width, 5 m in height, with a water supply flow rate of 250 L/s.

2.3 Finite Element Model

The overall grid model is shown in Fig. 1, with a total of 1,395,000 nodes and 1,347,000 elements. Eight-node hexahedral elements were used for spatial discretization, with grid sizes ranging approximately from 20 to 40 m (Fig. 1b). Due to limitations in large-scale modelling precision, the influence of the cover layer was not considered. The mountain terrain was approximately simulated, and the Zhu Ka fault was simplified into 3 segments along its strike, while maintaining its dip angle and thickness.




Fig. 1. Overall model: (a) hydraulic physical model, and (b) finite element model with mesh

2.4 Load Input Method

By measuring the pulsation pressure at the bottom and side walls of the water cushion basin through hydraulic model experiments, and then applying the measured pulsation pressure to the model to calculate its response, this creates a classic “input - structure - output” vibration system. At the water cushion basin bottom plate, 17 measurement points were arranged, with 4 measurement points on each side wall (left and right banks), total 25 measurement points (Fig. 2).




Fig. 2. Measurement point layout for plunge pool

2.5 Working Condition Design

Considering three flood frequencies, the operation conditions for the discharge system are set as shown in Table 1. For the discharge volumes of working conditions 1–3, multi-opening and uniform discharge methods were adopted, with the optimized working conditions listed in Table 2.

Table 1. Operating conditions for flood discharge system

Conditions	Flood frequencies	Operation conditions of the spillway tunnel			Operation conditions of the flood discharging tunnel	Upstream water-level (m)	Total discharge (m ³ /s)
		1#	2#	3#			
1	P = 1%	1/8	1	1	0	2895.00	6723

(continued)

Table 1. (continued)

Conditions	Flood frequencies	Operation conditions of the spillway tunnel			Operation conditions of the flood discharging tunnel	Upstream water-level (m)	Total discharge (m ³ /s)
		1#	2#	3#			
2	P = 5%	0	1/2	1	0	2895.00	5067
3	P = 20%	0	1/8	1	0	2895.00	3657

Note: The operation condition 0 indicates “off”, 1 indicates “on”, and other values represent the gate opening degree

Table 2. Optimized scheduling conditions

Conditions	Upstream water-level (m)	Spillway tunnel discharge (m ³ /s)			flood discharging tunnel discharge (m ³ /s)
		1#	2#	3#	
18	2895.00	1680	1680	1680	1680
19		1267	1267	1267	1267
20		914	914	914	914

3 Results and Discussion

3.1 Vibration Regularity Analysis

3.1.1 Random Distribution Characteristics

Hydrodynamic pressure experiment research was conducted under fixed (reservoir) water level and fixed (gate) opening conditions, with the water discharge structure experiencing a steady flow process. Figure 3a shows a typical time-domain waveform, and Fig. 3b is its probability distribution diagram. From the figures, it can be observed that the pulsating pressure in the water cushion basin is essentially a stationary random process, approximately following a normal distribution.




Fig. 3. Time-domain characteristics and probability density distribution of fluctuating pressures in the plunge pool

3.1.2 Random Distribution Characteristics

The maximum root mean square (RMS) values of pulsation pressure for each working condition are shown in Table 3. The maximum RMS values of pulsation pressure for the three working conditions are 3.49, 3.65, and 4.02×9.8 kPa, respectively. This indicates that the pulsation pressure of the water cushion bottom plate increases with the decrease of total discharge and downstream water level. The pulsation pressure of the right bank side wall is relatively small, with a maximum value of 1.53×9.8 kPa, primarily caused by backflow and wave fluctuations.

Table 3. Statistical RMS values of fluctuating pressure in the plunge pool under various conditions (unit: $\times 9.8$ kPa)

Working conditions number	Bottom plate	The left bank side wall	The right bank side wall
1	3.49	3.15	1.53
2	3.65	3.05	0.91
3	4.02	3.31	0.76

3.1.3 Frequency Domain Energy Distribution Characteristics

Figure 4 show the self-power spectral density curves of pulsation pressure at measurement points. In the non-impact zone and energy dissipation zone, the dominant frequency of water cushion side wall pulsation pressure is less than 1 Hz, with a narrow frequency band (Fig. 4a). The primary energy of pulsation pressure is concentrated within a 10 Hz range. In contrast, the impact zone and side wall energy dissipation zone exhibit more intense water-air mixing, resulting in a higher dominant frequency of pulsation pressure (between 2–5 Hz) compared to the non-impact and energy dissipation zones (Fig. 4b).

The frequency band is also wider, with the primary energy of pulsation pressure concentrated within a 20 Hz range. Overall, the excitation generated by hydrodynamic pulsation pressure can be characterized as a low-frequency excitation load.




Fig. 4. Self-power spectral density curves of pulsation pressure at measurement points: (a) non-impact zone, and (b) impact zone

3.2 Analysis of the Damping Effect of Scheduling

3.2.1 Random Distribution Characteristics

The pulsation pressure distribution on the bottom plate and side walls of the water cushion chamber under working conditions 18 and 20 is illustrated in Figs. 5 and 6, with the maximum root mean square values of pulsation pressure for each optimized working condition summarized in Table 4; comparative analysis reveals that when adopting multi-opening and uniform discharge methods at the same discharge volume, compared to working conditions 1–3, both the overall and maximum pulsation significantly decreased, with the bottom plate’s maximum pulsation pressure reducing by 27%–82% and overall pulsation pressure dropping by 12%–45%, while the side walls experienced a maximum pulsation pressure reduction of 47%–62% and an overall pulsation pressure decrease of 35%–60%.




Fig. 5. Fluctuating pressure distribution on plunge pool bottom plate (Working conditions 18/20)




Fig. 6. Fluctuating pressure distribution on plunge pool side wall (Working conditions 18/20)

Table 4. Maximum RMS values of plunge pool fluctuations pressure under optimized conditions ($\times 9.8\text{kPa}$)

Working conditions number	Bottom plate	The left bank side wall	The right bank side wall
18	2.35	1.68	1.05
19	2.22	1.47	0.69
20	1.45	1.25	0.65

3.2.2 Vibration Response of the Focused Region

The maximum vibration response values of the focused region are listed in Table 5. Under the same discharge volume, by comparing working conditions 1 and 18, working conditions 2 and 19, and working conditions 3 and 20, after adopting multi-opening and uniform discharge methods, the pulsation pressure of the water cushion chamber significantly decreased. As a result, the overall discharge ground vibration response reduced by approximately 45%, demonstrating the significant effect of operational scheduling methods in controlling discharge ground vibration.

Table 5. Peak vibration response statistics for optimized cases

Focused region	Working conditions	Acceleration (cm/s^2)		Velocity (mm/s)		Displacement (mm)	
		Amplitude	RMS value	Amplitude	RMS value	Amplitude	RMS value
Residential and school areas	18	0.196	0.051	0.141	0.039	0.020	0.007
	19	0.176	0.045	0.101	0.025	0.017	0.005
	20	0.120	0.034	0.081	0.020	0.008	0.002
Dam site	18	0.846	0.253	0.292	0.089	−0.042	0.021
	19	0.566	0.145	0.196	0.054	0.031	0.011

(continued)

Table 5. (continued)

Focused region	Working conditions	Acceleration (cm/s^2)		Velocity (mm/s)		Displacement (mm)	
		Amplitude	RMS value	Amplitude	RMS value	Amplitude	RMS value
	20	−0.431	0.116	0.099	0.031	−0.014	0.005
Substation and relocation housing	18	−0.280	0.075	−0.226	0.061	−0.036	0.013
	19	−0.236	0.063	−0.145	0.043	0.023	0.007
	20	−0.194	0.050	−0.085	0.023	0.007	0.003
Debris flow deposition zone	18	−0.468	0.143	−0.243	0.069	−0.038	0.017
	19	0.408	0.099	−0.163	0.045	0.025	0.008
	20	−0.311	0.069	0.092	0.031	−0.013	0.004

4 Conclusions

This study focuses on the RM Hydropower Station, employing a coupled hydraulic model testing and numerical simulation approach based on the “input-structure-output” framework to analyze site vibration patterns under various operational conditions and evaluate vibration mitigation effects of different flood discharge strategies. The results reveal that the implementation of a multi-gate simultaneous opening with uniform discharge strategy significantly improves flow regimes and reduces dynamic loads in the plunge pool. Specifically, the maximum fluctuating pressure on the floor slab decreased by 27%–82% (with an overall reduction of 12%–45%), while the sidewalls exhibited a 47%–62% reduction in peak fluctuating pressure (overall reduction: 35%–60%). The total flood discharge-induced vibration response decreased by approximately 45%, demonstrating the strategy’s effectiveness. Furthermore, the optimized operation strategy successfully suppresses persistent low-frequency, small-amplitude vibrations (0.5–5 Hz range, $<0.1 \text{ mm/s}^2$), reducing cumulative vibration exposure duration by 60%–75% during continuous discharge operations. Field validations confirm compliance with ISO 4866 safety thresholds within a 1.5 km radius, ensuring long-term residential safety and structural integrity.

Acknowledgments. This research was mainly financed by Xizang Autonomous Region Lancang River Clean Energy Safe, Green and Intelligent Construction Technology Innovation Center; Fine Research on the Safety of Flood Discharge and Energy Dissipation of High Rockfill Dams at High Altitudes; The Science and Technology Planning Project of Xizang Autonomous Region (XZ202501ZY0109); Zhukeke Contract [2024] No. 2-39.

References

- Lian, J.J., Chen, L., Liang, C., Liu, F.: Presentation and verification of an optimal operating scheme aiming at reducing the ground vibration induced by high dam flood discharge. *Int. J. Environ. Res. Public Health* **17**(1), 377 (2020)
- Lian, J.J., Guo, X.Y., Ma, C., Xu, K.: Optimal reservoir flood control operation using a hedging model and considering the near-field vibrations induced by flood release. *Water Resour. Manage* **33**(8), 2645–2663 (2019)
- Lian, J.J., et al.: An evaluation and reduction approach for the ground vibration induced by high dam flood discharge. *Water* **16**(11), 1559 (2024)
- Lian, J.J., Zheng, Y., Liang, C., Ma, B.: Analysis for the vibration mechanism of the spillway guide wall considering the associated-forced coupled vibration. *Appl. Sci.-Basel* **9**(12), 2572 (2019)
- Xu, L.H., Hou, C.Y., Zhang, H.Y., Liu, G.Q.: Test and analysis of flood discharge vibration characteristics of beams on surface orifice gate piers of xiluodu dam. *Proceedings of the 2024 3rd International Conference on Structural Seismic Resistance, Monitoring And Detection, SSRMD 2024*, vol. 27, pp. 70–84 (2024)
- Yang, Z.T., Feng, S.Z., Fu, K.X., Wang, J.W.: Optimal flood discharge scheduling to alleviate vibration under gate operational rules. *J. Flood Risk Manage.* **18**(1), e70015 (2025)
- Zhang, J.M., Peng, Y., Xu, W.L.: Hydraulic prediction of near-field vibrations induced by releasing flood. *J. Hydraul. Eng.* **143**(9), 05017002 (2017)
- Zhang, J.W., Hou, G., Cao, K.L., Ma, B.: Operation conditions monitoring of flood discharge structure based on variance dedication rate and permutation entropy. *Nonlinear Dyn.* **93**(4), 2517–2531 (2018)
- Zhang, W.J., Lian, J.J., Liu, F., Zhao, X., Liang, C.: Mathematical prediction model for ground vibrations of nearby territories induced by high dam flood discharge. *J. Low Freqen. Noise Vibrat. Active Control* (2025)
- Zhang, Y., Lian, J.J., Li, S.H., Zhao, Y.B., Zhang, G.X., Liu, Y.: Predicting dam flood discharge induced ground vibration with modified frequency response function. *Water* **13**(2), 144 (2021)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Operational Stability Control Technology for Gravity Blocks in Gravity Compressed Air Energy Storage Systems

Weixiang Ni, Yanan Hu^(✉), and Zhonghua Li

The National Key Laboratory of Water Disaster Prevention and Hydraulic Engineering, Nanjing
Hydraulic Research Institute, Nanjing 210029, China
yahu@nhri.cn

Abstract. To address the attitude instability of kiloton-scale gravity blocks under high-pressure gas, this study reveals the influence mechanism of guide rail parallelism errors on guiding forces through physical modeling. Utilizing a 1:10 scaled model (total block mass: 6,102.2 kg; stroke: 2.131 m), we quantitatively characterize rail parallelism distribution features (maximum fluctuation range: -2 to 1.71 mm), identifying a “narrow-center, wide-ends” gradient distribution pattern between front rail surfaces. Results demonstrate that coupling between parallelism gradient errors and block tilt induces extreme guide force deviations (64.04 t at design spring stiffness). We propose a collaborative spring stiffness-preload optimization method, determining an optimal spring stiffness of 0.45×10^7 N/m and a four-layer preload configuration (0/0/10/10 t). This solution reduces guide force deviation extrema by $>56\%$ while maintaining continuous wheel-rail contact throughout operation. The proposed strategy eliminates instability risks arising from coupled seal membrane buckling and rail errors, providing critical technical foundations for engineering applications.

Keywords: Gravity compressed air energy storage · Rail parallelism · Guiding force control · Layered preload design · Operational stability

1 Introduction

Under the “Dual Carbon” strategic background, large-scale energy storage technology has become a crucial support for China’s energy transition. As an original mechanical energy storage technology in China, Gravity Compressed Air Energy Storage (GCAES) integrates the advantages of compressed air energy storage and gravitational potential energy storage. It enables constant-pressure system operation while significantly enhancing energy storage density and reducing air reservoir volume requirements [1], playing a vital role in supporting new power system construction and ensuring national energy security. However, for a typical 1 MW system, the gravity block weighs 6,102.2 t with a slenderness ratio exceeding 2.1. Its low flexural stiffness sealing membrane is prone to buckling wrinkles under high-pressure gas (Fig. 1b), inducing gravity block inclination. The rail parallelism gradient distribution dynamically couples with tilting motion,

amplifying abnormal guidance force fluctuations and triggering localized derailment failure (Table 3), severely constraining engineering applications.

Existing stability research on heavy vertical motion systems primarily focuses on two domains: (1) Shiplift stability: Chen et al. [2] established an overturning moment model identifying guide rail error as the primary instability cause; Liao et al. [3] proposed lateral guidance systems to suppress tilting; Cheng et al. and Zhang et al. [4, 5] demonstrated that rail installation accuracy must be controlled within ± 0.5 mm to prevent cascading failures; Hu et al. [6] validated via full-scale trials that rail deviations amplify impact forces to 2.5 times design values. (2) Elevator guide vibration control: Wang et al. [7] deciphered the mechanism by which rail deviations induce horizontal car vibrations; Song et al. [8] revealed that a straightness error of 0.1 mm/m increases elevator vibration acceleration by 35–45%; Recent fault diagnosis [9] further confirmed parallelism error as the key catalyst for nonlinear vibrations.

While these studies prove that insufficient rail flatness amplifies guidance force fluctuations, three critical limitations persist: (1) Object limitation: Studies are confined to hydraulic-load shiplifts or constant-load elevators, neglecting the gravity block - sealing membrane - pressure chamber system; (2) Mechanism gap: Failure to address the coupled effect between rail parallelism gradient distribution (non-uniform straightness) and block inclination; (3) Design deficiency: Conventional uniform preload designs cannot adapt to gradient errors, failing to mitigate instability risks for blocks with slenderness ratios > 2 (e.g., 2.1 in this system).

To bridge these gaps, this study employs a 1:10 scaled physical model (block mass: 6,102.2 kg; stroke: 2.131 m), achieving three breakthroughs: (1) Mechanism elucidation: First quantification of how parallelism gradient distribution (measured as “narrower centrally, wider terminally”) couples with block inclination to amplify guidance force extremes; (2) Methodological innovation: Proposal of a “guide spring stiffness-layered preload co-optimization” method, reducing peak guidance force deviation by $> 56\%$ and eliminating derailment risk; (3) Engineering solution: Development of a “four-layer guide configuration with stiffness optimization” scheme, resolving instability from sealing membrane buckling and rail error coupling for megawatt-scale GCAES applications.

2 System Principle and Experimental Method

The GCAES system comprises a gas storage chamber, gravity-compensated blocks (a pressure-bearing cylinder + seven-tier gravity blocks), and a guide system (Fig. 1a). During energy storage, electrical energy drives compressors to generate high-pressure gas, which pushes the gravity blocks upwards, converting the gas’s internal energy into gravitational potential energy. During energy release, the descending gravity blocks drive a turbine to generate electricity, converting potential energy back into electrical energy [10]. While operation at constant system pressure enhances efficiency, the high-pressure gas readily induces buckling in the sealing membranes. Consequently, guide mechanisms are essential to constrain the block posture.




Fig. 1. Schematic of the GCAES system and sealing membrane buckling/wrinkling

The mechanical equilibrium equation for the vertical motion of the gravity blocks is established as follows:

$$pA - Mg - f_1 - f_2 = M \frac{d^2H}{dt^2} \quad (1)$$

Where, p is the gas chamber pressure within the storage chamber, MPa; A_1 is the shaft cross-sectional area, m^2 ; M is the total mass of the gravity blocks, kg; f_1 is the friction force, N; f_2 is the reaction force exerted by the sealing membrane, N; H is the stroke (travel distance) of the gravity blocks, m.

Based on the gravitational similarity criterion (geometric scaling factor $\lambda = 10$), a 1:10 experimental model was established (Fig. 2).




Fig. 2. Experimental model and guidance system

Key prototype parameters: gas chamber pressure is 2.5 MPa ($\lambda_p = 10$); gravity block ascent/descent time is 60 min each; initial spring stiffness design is 1.25×10^7 N/m; design load limit for guide rails is 50 t.

The model comprises: 2 m × 2 m steel structure with dual acrylic shafts (inner diameter 0.6 m); total mass 6102.2 kg, divided into 7 tiers (single tier dimensions: 1 m × 1 m × 0.3 m); four guide rails (total length 4.5 m), each tier is equipped with four X-direction (front/rear) and four Y-direction (lateral) guides.

Attitude Monitoring: A six-component force/torque sensor (inclination accuracy: 0.001°) was installed at the center of the top-tier gravity block. Gravity Block Stroke Monitoring: Four cable-extension displacement transducers were employed. Guiding Force Monitoring: Spoke-type load cells (rated capacity: 500 kgf) were integrated into the guide wheels. Parallelism Measurement: Laser displacement sensors (measuring range: ± 15 mm, accuracy: 50 μm) were utilized (Fig. 3).




Fig. 3. Instrumented measurement points on the experimental model

3 Experimental Results and Analysis

Figure 4 reveals significant spatial heterogeneity in rail parallelism.




Fig. 4. Distribution of guide rail parallelism errors

Specifically, a positive relative ranging measurement indicates narrowing of the rail spacing, while a negative value denotes widening. The front faces of the rails exhibit a

“narrow in the middle, wide at both ends” gradient distribution (Fig. 4a), with a maximum error (peak-to-peak variation) of 3.71 mm (ranging from -2 mm to $+1.71$ mm). In contrast, the side-face parallelism errors were below 0.14 mm (Fig. 4b), which is negligible.

3.1 Coupling Mechanism of Parallelism and Guiding Force

Experimental investigations were conducted for the double-layer guide configuration at tiers 2 and 7 of the gravity blocks, employing five different guide spring stiffness values (ranging from 0.022×10^7 to 2.95×10^7 N/m). The design preloads were 25 t for tier 2 and 12.5 t for tier 7 (Table 1).

Table 1. N Fundamental experimental parameters under different guide spring stiffness values

Case	Design Preload (t)		Spring Stiffness ($\times 10^7$ N/m)
	Tier 2	Tier 7	
CG1	25	12.5	0.022
CG2			0.13
CG3			0.45
CG4			1.25
CG5			2.95

It is crucial to note that buckling and wrinkling of the sealing membrane under air pressure caused force imbalance within the system under the initial preload settings. To address this, a dynamic equilibrium compensation method was implemented: After each complete as-cent/descent cycle of the gravity blocks, the preload was maintained constant. Subsequent test conditions were only initiated after the blocks had returned to the locked position and the measured guiding forces matched those from the previous experiment. This method effectively compensated for the nonlinear deformation induced by membrane buckling, ensuring system force equilibrium. However, it resulted in an actual guiding preload deviation of ± 3.2 t from the de-sign value.

3.1.1 Variation Law of Guiding Force Under Parallelism Influence

Taking the initial design spring stiffness of 1.25×10^7 N/m as an example (Fig. 5), the influence mechanism of rail parallelism on guiding force variation is revealed.




Fig. 5. Variation of guiding force deviation under rail parallelism influence

Experimental data indicate:

- (1) The operation process of the gravity blocks can be divided into six typical state nodes: Start of energy storage (S0) → Block ascent (S1) → Pressure holding (S2) → Block descent (S3) → Gas chamber depressurization (S4) → End of energy release (S5).
- (2) Initial energy storage phase (S0): Pressurization of the gas storage chamber causes buckling and wrinkling of the sealing membrane. The pressure-bearing cylinder ascends with tilt (X/Y-direction inclination angles reaching $-0.011^\circ/0.0055^\circ$), triggering initial guiding force fluctuations. The guiding force deviation (real-time guiding force minus guiding preload) conforms to the classical overturning theory:

$$\Delta F_{n-i} = \frac{kH\Delta\theta}{9800d_0} \quad (2)$$

Where, ΔF_{n-i} is the guiding force deviation at the i -th guide device of tier n , t; k is the spring stiffness, N/m; H is the height of the gravity blocks' center of mass, m; $\Delta\theta$ is the inclination angle, $^\circ$; d_0 is the nominal rail spacing, m. For instance, the X-direction guiding force deviation at Tier 7 ranged from -5.24 t to 5.25 t, deviating by $<5\%$ from the theoretical value (5.52 t). Furthermore, guides 7-1~7-2 were under compression, while guides 7-3~7-4 were under tension. The guiding force variation during this stage aligns with the theoretical posture of the gravity blocks.

- (3) Full ascent/descent phase (S1 → S3): The measured Y-direction guiding forces were consistent with theoretical predictions. However, the X-direction guiding forces exhibited significant spatial differentiation. Based on the mechanical mechanism of the GCAES system, the guiding force variation comprises three components: the classical overturning theory term + the parallelism-induced additional term + the gas force term. Specifically:

Tier 2 (Lower Region):

$$\frac{\partial d_{rail}}{\partial z} < 0 \Rightarrow \Delta F_+ \propto \frac{MgH}{d_0} \sin \theta + k\zeta |\Delta d_{rail}| + \beta C_{gas} \Delta PA \left(\frac{d_0}{d_{\downarrow}} \right)^3 \quad (3)$$

Where, $\partial d_{rail} / \partial z$ is the spatial gradient of parallelism, mm/m; ΔF_+ is the guiding constraint enhancement quantity, t; ζ is the comprehensive amplification factor; Δd_{rail} is

the variation in rail spacing, m ; β is the height attenuation factor; C_{gas} is the gas coupling coefficient; ΔP is the gas pressure fluctuation, MPa, range: 0~0.25; A is the effective area of the pressure-bearing cylinder, m^2 ; $d_{\downarrow}$ is the real-time rail spacing (narrowing), mm.

Equation (3) indicates that increasing parallelism at Tier 2 (spacing narrowing, $\partial d_{rail} / \partial z < 0$) $\rightarrow$ increases spring compression $\rightarrow$ guides the force deviation towards positive values (maximum value: 64.04 t).

Tier 7 (Upper Region):

$$\frac{\partial d_{rail}}{\partial z} > 0 \Rightarrow \Delta F_{-} \propto k(\delta_{pre} - \Delta d_{rail}) - \frac{C_{gas} \Delta P A}{1 + \gamma(d_0 - d_{\uparrow})^2} \quad (4)$$

Where, ΔF_{+} is the guiding constraint weakening quantity, t; δ_{pre} is the spring pre-compression, m; $d_{\uparrow}$ is the real-time rail spacing (widening), mm; γ is the geometric nonlinearity coefficient, m^{-2} .

Equation (4) indicates that decreasing parallelism at Tier 7 (spacing widening, $\partial d_{rail} / \partial z > 0$) $\rightarrow$ weakens contact constraint, risking guide wheel disengagement $\rightarrow$ guides the force deviation towards negative values (minimum value: -15.61 t).

3.1.2 Guiding Force Variation Excluding Rail Parallelism Influence

The coupling of rail parallelism errors and gravity block tilt leads to significant extremes in guiding force deviation. To isolate the influence mechanism of parallelism errors, comparative experiments were conducted using five spring stiffness values (ranging from 0.022 to 2.95×10^7 N/m), enabling a theoretical analysis of guiding force variation dominated by gravitational overturning.




Fig. 6. Relationship between partial laser distance measurements and gravity block stroke

The results indicate that the guide spring stiffness is inversely proportional to the relative measured distance (Fig. 6). The relative distance variation curves essentially coincide for spring stiffness values of 1.25×10^7 N/m and 2.95×10^7 N/m. Therefore, when $k = 2.95 \times 10^7$ N/m, the relative measured distance d'_{n-i-pz} between the guide and the rail can be approximately considered to reflect only the single rail surface unevenness. The variation in guiding force generated by the tilt of the gravity blocks is defined as the


tilt-induced guiding force deviation, expressed as:

$$F_{n-i}' = \frac{k(d_{n-i} - d_{n-i-pz'})}{9800000} \quad (5)$$


The theoretical analysis of the tilt-induced guiding force deviation is presented in Table 2 and Fig. 7.

Table 2. Theoretical tilt-induced guiding force deviation under different spring stiffness values

Spring Stiffness ($\times 10^7$ N/m)	Occurrence Position	X-direction Guidance Force Deviation due to Inclination (t)			
		Guide 2-1	Guide 2-2	Guide 2-3	Guide 2-4
0.022	Block at 21.31 m	0.26	0.09	−0.18	−0.12
0.13		0.29	0.19	−0.21	−0.22
0.45		0.55	0.29	−0.26	−0.28
1.25		0.64	0.38	−0.92	−2.17
2.95		—	—	—	—



(a) Deviation at X-direction Guide 2-1



(b) Deviation under $k = 0.022 \times 10^7$ N/m

Fig. 7. Comparison of measured guiding force and theoretical tilt-induced guiding force deviation

The results demonstrate that, after eliminating the influence of rail parallelism, X-direction guides 2-1 and 2-2 were subjected to compression, while X-direction guides 2-3 and 2-4 were subjected to tension. The variation in tilt-induced guiding force deviation aligns with the predictions of the overturning theory, exhibiting a symmetric distribution between the compression and tension zones.

Quantification of Parallelism Error Contribution:

$$\eta_{error} = \frac{|\Delta F_{n-i} - F_{n-i}'|}{\Delta F_{n-i}} \times 100\% > 63\% \quad (6)$$

Compared to the theoretical guiding force deviation caused by the coupling of rail parallelism errors and gravity block tilt, the tilt-induced guiding force deviation is significantly smaller. The contribution of parallelism errors accounts for over 63% of the total guiding force fluctuation.

3.2 Guide Parameter Optimization


Research reveals that the “narrow in the middle, wide at both ends” gradient error distribution of the guide rails (Fig. 4) is the primary cause of uneven spatial distribution of guiding forces. During the ascent phase of the gravity blocks, decreasing parallelism in lower regions significantly amplifies guiding forces through geometric amplification effects. Conversely, increasing parallelism in upper regions weakens contact constraints and, when coupled with high-pressure gas effects, may trigger guide wheel disengagement. This mechanism exposes the limitations of traditional uniform preload designs, necessitating spatially differentiated compensation strategies. Furthermore, guiding force deviation can be characterized as the product of spring stiffness and spring compression. This indicates that selecting appropriate spring stiffness can effectively reduce the amplitude of guiding force deviation. Based on these insights, this study proposes a “stiffness-layered preload collaborative optimization” method.

3.2.1 Spring Stiffness Optimization


Building on the experimental conditions in Sect. 3.2, the guiding force characteristics under different guide spring stiffness values were comparatively analyzed. Using rail load capacity and gravity block tilt angle as key evaluation metrics, optimal spring stiffness parameters were determined. In the table, “Partial loss” indicates localized contact failure.

Table 3. Influence of spring stiffness on guide performance

Spring Stiffness ($\times 10^7$ N/m)	Max. X-tilt ($^{\circ}$)	Max. Y-tilt ($^{\circ}$)	Peak positive deviation at Tier 2 (t)	Peak negative deviation at Tier 7 (t)	Rail contact state
0.022	−0.0769	0.0604	3.62	−2.61	Maintained
0.13E7	−0.044	0.0549	5.80	−3.72	Maintained
0.45	−0.0275	0.0329	25.23	−8.20	Maintained
1.25	−0.022	0.0274	64.04	−15.61	Partial loss
2.95	−0.022	0.0164	143.46	−16.76	Partial loss



(a) Tier 2 X-direction guides (2-1~2-4)



(b) Tier 7 X-direction guides (7-1~7-4)

Fig. 8. Comparison of maximum guiding force deviations under guide spring stiffness values

Experimental results demonstrate:

- (1) Effect of spring stiffness on tilt angle and guiding force: Increasing spring stiffness effectively suppresses tilt angle in gravity blocks (Table 3) but significantly amplifies guiding force deviation (Fig. 8). Taking X-direction guide 2–1 as an example, the maximum guiding force deviation increases drastically with higher stiffness, confirming that guiding force deviation equals the product of spring stiffness and compression.
- (2) Contact state and stiffness optimization: Under lower stiffness values (0.022×10^7 N/m, 0.13×10^7 N/m, 0.45×10^7 N/m), reduced growth of guiding force deviation enables guide wheels to maintain continuous rail contact. The maximum rail loads were 27.72 t, 32.00 t, and 47.23 t, respectively – all below the 50 t design load standard. Considering rail load capacity, tilt control effectiveness, and spring stiffness parameters comprehensively, 0.45×10^7 N/m was determined as the optimal spring stiffness.

3.2.2 Layered Preload Design

To reduce rail loads, a layered preload strategy was proposed based on the gradient distribution of parallelism (Fig. 4): When gravity blocks are locked on the platform, (1) Lower regions (Tiers 2/3): 0 t preload (contact without pre-tension to eliminate over-constraint); (2) Middle/Upper regions (Tiers 4/7): 10 t preload (compensating for decreasing parallelism).

Through investigating the influence patterns of guide layers and preload values on guiding forces (Table 4), a dynamic preload adjustment method was established based on rail parallelism gradients.

Table 4. Experimental parameters for guide preload combinations


Case	Spring Stiffness ($\times 10^7$ N/m)	Design Preload per Tier (t)			
		Tier 2	Tier 3	Tier 4	Tier 7
CG4	1.25	25	–	–	12.5
CG6	1.25	25	25	25	12.5
CG7	1.25	0	0	10	10
CG8	0.45	0	0	10	10

Note: The dynamic equilibrium compensation method was applied, causing deviations between actual and designed preload values

Comparative optimization effects of preload combinations are shown in Table 5 and Fig. 9.

Table 5. Comparison of preload combination optimization effects

Case	Max. X-tilt (°)	Max. Y-tilt (°)	Peak Positive Deviation (t)	Reduction (%)	Peak Negative Deviation (t)	Reduction (%)
CG4	-0.022	0.027	64.04	—	-15.61	—
CG6	-0.013	0.006	24.07	62.41	-14.2	9.03
CG7	-0.017	0.027	17.45	72.75	-12.70	18.64
CG8	-0.022	0.044	5.96	90.69	-6.87	56



(a) Tier 2 X-direction guides (2-1~2-4)

(b) Tier 7 X-direction guides (7-1~7-4)

Fig. 9. Comparison of guiding force deviations before and after preload optimization

Experimental results demonstrate:

- (1) Effect of guide layers (CG4 vs. CG6): Increasing guide layers effectively suppresses gravity block tilt (X-tilt: $-0.022^\circ \rightarrow -0.013^\circ$; Y-tilt: $0.027^\circ \rightarrow 0.006^\circ$) and reduces guiding force deviation amplitude, achieving a 62.41% decrease in peak positive deviation. However, under four-layer configuration (CG6), the peak positive deviation at Tier 2 remains 24.07 t (design preload: 25 t), bringing rail load close to the 50 t design limit.
- (2) Layered preload effect (CG6 vs. CG7): Layered preload (CG7) increases tilt (X-tilt: $-0.013^\circ \rightarrow -0.017^\circ$; Y-tilt: $0.006^\circ \rightarrow 0.027^\circ$) but reduces deviations: peak positive deviation decreases from 24.07 t to 17.45 t (-27.5%), while peak negative deviation rises from -14.20 t to -12.70 t ($+10.56\%$ mitigation).
- (3) Layered preload optimization mechanism: For increasing parallelism (spacing narrowing), reduced preload minimizes positive deviations; For decreasing parallelism (spacing widening), adjusted preload maintains contact (validated by CG8 in Table 5).
- (4) Finalized "stiffness-layered preload collaborative optimization": Low stiffness + layered preload (CG8) significantly reduces deviations. Considering safety and load capacity, the optimal solution is: Spring stiffness 0.45×10^7 N/m + four-layer preload (0/0/10/10 t), this configuration reduces extreme deviation values by $>56\%$ while maintaining continuous wheel-rail contact throughout operation.

4 Conclusions

Through a 1:10 scaled physical model experiment, this study systematically investigated the influence mechanism of rail parallelism on guiding forces in GCAES systems, and proposed a collaborative optimization method integrating “spring stiffness-layered preload” based on spatial heterogeneity of parallelism. Key conclusions are:

- (1) Gradient parallelism error is a fundamental trigger for gravity block instability. A “narrow center-wide ends” gradient parallelism error (range: 3.71 mm) exists between the front faces of inner rails. This spatial heterogeneity amplifies overturning moments through geometric constraints, causing drastic pressure increases in lower guides and negative tension trends in upper guides, inducing guide wheel disengagement risks. Under the initial design (spring stiffness: 1.25×10^7 N/m, guides at Tiers 2/7), the peak positive deviation reached 64.04 t, exceeding the design preload by 156%.
- (2) A collaborative stiffness-preload compensation strategy was developed: Optimized spring stiffness (0.45×10^7 N/m) balances posture control (tilt angle $< 0.03^\circ$) and rail load capacity (≤ 50 t design limit); Layered preload eliminates over-constraint when parallelism increases (spacing narrows) and maintains contact when parallelism decreases (spacing widens).
- (3) It is recommended to implement a four-layer guides at Tiers 2/3/4/7, with spring stiffness of 0.45×10^7 N/m and preload 0/0/10/10 t (CG8). This configuration ensures that the Peak rail load < 31 t, while maintaining continuous contact between the guide wheels and the guide rails throughout the entire system operation. This provides the design benchmark for safe and stable operation of the world’s first megawatt-scale GCAES project.

Acknowledgments. This study was jointly funded by the National Natural Science Foundation of China (grant no.: 52309099), and Jiangsu Provincial Joint Consortium for Core Technology R&D and Industrialization of Gravity Compressed Air Energy Storage (grant no.: (2024) LHT 2024009-04 and Rq125001).

References

1. He, D., Luo, N., Shen, Y.: Performance analysis and multi-objective optimization of a compressed air piston hydraulic gravity energy storage (CAPHGES) system. *J. Energy Storage* **2**, 116872 (2025)
2. Chen, J.Z., Ma, G.Y.: Stability analysis of the chamber for fully balanced vertical ship lifts. *Hydro-Sci. Eng.* **4**, 301–308 (1996). (in Chinese)
3. Liao, Z.B., Cao, Y.N., Cui, Z., et al.: Design of anti-overturning guidance system for hydraulic ship lift. *Port Waterway Eng.* **7**, 43–48 (2017). (in Chinese)
4. Cheng, X.H., Shi, D.W., Li, H.X., et al.: Stability analysis of high-head fully balanced hoist vertical ship lift system. *Chin. Mech. Eng. Soc.* **30**(8), 41–47 (2019). (in Chinese)
5. Zhang, Y., Shi, D.W., Xiao, T., et al.: Longitudinal stability characteristics of fully balanced hoist vertical ship lift under hydraulic dynamic leveling. *Mech. Electric. Eng. Magaz.* **37**(7), 758–763 (2020). (in Chinese)

6. Chen, Y.Y., Hu, Y.A., Li, Z.H., Fu, L.Z.D.: Comprehensive study on hydraulic characteristics during vessel exit process in Longtan second-stage ship lift. *Port Waterway Eng.* **11**, 18–25 (2020). (in Chinese)
7. Wang, Y., Zhang, P., Liu, Q.: Transient response feedback control for horizontal vibration of high-speed elevator car with prescribed performance. In: *Proceedings of the Institution of Mechanical Engineers, Part C: Journal of Mechanical Engineering Science* (2024)
8. Song, D., Zhang, P., Wang, Y., et al.: Horizontal dynamic modeling and vibration characteristic analysis for nonlinear coupling systems of high-speed elevators and guide rails. *J. Mech. Sci. Technol.* **37**(6), 123–135 (2023)
9. Wu, Y., Song, J., Wu, X., et al.: Fault diagnosis of linear guide rails based on SSTG combined with CA-DenseNet. *J. Dyn. Monitor. Diagnost.* **3**(1), 1–10 (2024)
10. Berrada, A., Loudiyi, K., Zorkani, I.: Toward an improvement of gravity energy storage using compressed air. *Appl. Energy* **201**, 56–67 (2017)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Research on Engineering Treatment Measures for Crossing Active Faults in High-Pressure Diversion Tunnels of Hydropower Stations

Yong Xia^{1,2,3}, Bo Sun^{1,2,3}, He-Gao Wu^{4(✉)}, and Chang-Zheng Shi⁴

¹ PowerChina Chengdu Engineering Corporation Limited, Chengdu, China
1990046@chidi.com.cn

² Technological Innovation Center of Hydropower, Wind, Solar and Energy Storage of Tibet
Autonomous Region, Tibet, China

³ Large-Scale Underground Engineering Affiliation of National Hydropower Technology
Research and Development Center, Chengdu, China

⁴ State Key Laboratory of Water Resources Engineering and Management, Wuhan University,
Wuhan 430072, Hubei, China
hgwu@whu.edu.cn

Abstract. The problem of crossing active faults is inevitable during the construction of water diversion power stations or long-distance water conveyance projects, therefore it is critical for the engineering sector to adopt particular lining structure in hydraulic tunnels to traverse active faults. Based on the actual situation of a certain hydro project, the feasibility and rationality of the multi-layer flexible composite lining structure are discussed by the finite element numerical analysis. In addition, the influences of fault displacement, fault width, fault strike and section length on the stress and deformation of the lining structure are analyzed. The calculation results show that: With the increase in the fault displacement, both the deformation and stress of the steel lining present an increasing trend. However, due to the setting of the expansion joint, the stress of the steel lining is marginally affected by the fault displacement. The smaller the angle between the pipeline and the fault strike, the greater influence on the stress and deformation of the steel lining structure. When the pipeline is orthogonal to the fault, the stress condition of the steel liner is optimal. While the stress condition of the steel liner becomes worse, as each expansion joint bears more fault displacement due to larger length of the steel pipe section or the fewer number of expansion joints. The research results of this paper can provide a reference for the structural design of high-pressure water conveyance tunnels when dealing with the creep deformation of faults.

Keywords: Water diversion power station · High-pressure tunnel · Fault displacement · Steel lining · Bellows expansion joint · Stress deformation · Numerical simulation

1 Introduction

At present, several countermeasures have been adopted for tunnels to traverse active faults, such as “flexible joint between lining section”, “isolate energy dissipation design with a composite lining”, “over-excavation of cross-section” and “exposed penstock crossing fault within the tunnel”. In recent years, the fault failure mechanism and anti-fault measures regarding water conveyance tunnels crossing active faults have been extensively investigated by scholars at home and abroad, such as Russo et al. [1], Shahidi et al. [2], Zhou et al. [3, 4], in which the Bolu Tunnel in Turkey, the Koohrang-III water conveyance tunnel in Iran and the Xianglushan Tunnel in Yunnan were studied, respectively. Furthermore, numerical simulation or small-scale physical model test were adopted to conduct in-depth study on the failure pattern and mechanism of tunnels acrossing active faults under the influence of fault displacement. Cui et al. [5] conducted model tests about adding steel fiber, basalt fiber and polypropylene fiber to the concrete lining, and compared the fault-resistance performance of the three types of fiber reinforced concrete from the perspectives of principal stress, longitudinal strain and structural safety factor. Caulfield et al. [6], Jiang et al. [7] discussed the over-excavation design, and the authors believed that expanding the cross-sectional size was a necessary measure to guarantee the operational requirements of the water conveyance pipeline after the occurrence of tunnel cracking even if there was a sudden sliding-slip movement. Ren et al. [8] discussed the engineering layout of the water diversion tunnel in Saizhu Hydropower Station, which adopted “exposed penstock inside the tunnel” to cross active fault. This engineering layout meets the needs of fault deformation and displacement and is still well-operating to this day.

It is common for a tunnel to employ reinforced concrete linings as the permanent supporting structure. However, in sections crossing faults, due to poor conditions of surrounding rock, reinforced concrete linings are prone to cracking, leading to leakage. As a result, for tunnels with high internal pressure, steel plate linings are usually adopted, since steel plate lining has high strength and reliable sealing performance, which can guarantee the operational safety of tunnels with high internal pressure under normal operation conditions. However, as the shear and compressive strength of conventional steel plate linings are relatively poor, when active faults cross through steel pipes buried in rock and soil masses, a “S”-shaped bending deformation of the steel pipe will be induced. Especially under the compressive effect of reverse faults, it is easy to cause buckling failure of the steel plate lining under pressure. As a consequence, the steel plate lining still needs to be improved when used in high internal pressure tunnels crossing active faults, such as setting up bellows expansion joints [9, 10].

In order to deal with the drawbacks of the current anti-fault measures for tunnels crossing faults, in the context of a water diversion tunnel with high internal pressure in a hydropower station, a multi-layer flexible composite lining suitable for high internal pressure diversion tunnels to cross active faults is proposed in this study. This structure is comprised of a concrete outer protective layer, a soft cushion layer, a steel lining, and a directly-buried bellow expansion joint [11]. The hydraulic tunnel of the hydropower station investigated in this paper is 16.81 km long, and the maximum internal water pressure when the tunnel crosses the Zela Cuo-Zongpo Fault reaches 438.71 m of equivalent water head. To validate the effectiveness of the proposed multi-layer flexible composite

lining structure, finite element models of different tunnel lining structures are established, and the stress of the steel lining and concrete as well as the deformation of the bellow expansion joint are thus calculated. This study can provide a reference for the structural design of high-pressure water conveyance tunnels when dealing with the creep and sliding deformation of faults.

2 Background of the Studied Engineering Project

2.1 Fault Zone and Geological Conditions

The research object is a first-level mixed-development hydropower station in the Xiaqu River Basin. The hydroelectric complex includes the rock-fill dam with concrete asphalt core wall, flood discharge and sand flushing tunnel on the left bank, overflow tunnel on the right bank, the main power station for power generation, and the ecological water release system, etc.

The water diversion tunnel crosses the Zela Cuo-Zongpo Fault (near $14 + 300$ m). The surface geophysical profile reveals that the Zela Cuo-Zongpo Fault is approximately 50 to 100 m wide and is set a strike-slip rate of about 2 to 3 mm per year in this study.

According to the “Monographic study on Seismic Safety Evaluation of Hydropower Station Engineering Sites”, the maximum possible sudden horizontal dislocation of the Zela Cuo-Zongpo Fault in the next 100 years is 1.8–2.3 m, which is taken as 2.0 ± 0.3 m, and the vertical dislocation is taken as two-thirds of the horizontal displacement in this study.

The main engineering rock mass mechanical parameters of this fault zone are as follows: The deformation modulus of the fault zone is 0.5–2 GPa, the Poisson’s ratio is 0.30, the shear friction coefficient is 0.40–0.50, and the cohesive force is 0.10–0.20 MPa. The deformation modulus of the complete surrounding rock on both sides of the fault zone is 6–8 GPa, the Poisson’s ratio is 0.25–0.27, the shear friction coefficient is 0.80–1.10, and the cohesive force is 0.70–1.0 MPa.

2.2 Layout of Steel Pipe Through Active Fault Zones

After a preliminary analysis, the proposed design scheme for the diversion tunnel crossing active fault zone is shown in Fig. 1.

The design scheme is as follows: The diameter of the diversion tunnel crossing the active fault zone is reduced from 7 m to 5 m, and a circular cross-section is adopted. It is assumed that the steel lining bears all the internal water pressure (designed as an exposed penstock), with a wall thickness of 52 mm (07Mn-MoVR steel). Each section is 5 m long, and the sections are connected by steel expansion joints (1.5 m long). The outer side of the steel liner is covered with an elastic cushion layer with thickness of 60 cm. The outside of the elastic cushion layer is a 1.5-meter-thick reinforced concrete lining. To bear the internal water pressure and the dead load of the steel lining, a reinforced concrete lining with an inverted arch of 120° , a length of 3 m and a thickness of 0.5 m is used in the middle of each section of the steel lining. Moreover, this part is cast together with the outermost thickened concrete lining.




Fig. 1. Design scheme of the diversion tunnel crossing the active fault zone.

2.3 Mechanical Parameters

According to “Design code for steel penstocks of hydroelectric stations” NB/T 35056-2015, steel of 600 MPa grade is adopted for the steel lining, with an elastic modulus of 2.06×10^5 MPa and a Poisson’s ratio of 0.30. The calculated allowable value of the overall membrane stress of the steel is 276 MPa, and the allowable value of the local membrane stress is 345 MPa. The concrete adopts C20, with an axial compressive strength of 9.6 MPa, an axial tensile strength of 1.1 MPa, an elastic modulus of 2.55×10^4 MPa, a specific gravity of 24 kN/m^3 , a Poisson’s ratio of 0.167, and a linear expansion coefficient of $1.00 \times 10^{-5}/^\circ\text{C}$.

3 Numerical Model Set-Up and Boundary Conditions

3.1 Numerical Model

A three-dimensional finite element model was established based on the layout of underground pipe as shown in Fig. 1. The length along the axis is 151.5 m, and the widths on both the left and right sides and the upper and lower heights are all taken as six times the diameter of the steel pipe, that is, 30 m. X-axis of the model being perpendicular to the pipe axis, pointing to the left (downstream) is defined as the positive direction, the positive direction of Y-axis is vertically upward, and the positive direction of the Z-axis is downstream side along the pipe axis according to the right-hand screw rule. The three-dimensional finite element schematic diagram of the model is presented in Fig. 2.

Regarding boundary conditions, it is assumed that normal constraints are applied to both sides, bottom and end faces of the model, and the top surface is a free surface.

The steel pipe was simulated using the four-node S4 shell element, and the concrete, cushion layer, fault zone and surrounding rock were simulated by the eight-node C3D8 solid isoparametric element. All materials were calculated via the linear elastic constitutive model. Surface-surface contact pairs were set between the steel pipe and the cushion layer as well as the concrete. The friction coefficient between the steel pipe and the cushion layer was taken as 0.25, and the friction coefficient between the steel pipe and the concrete was set 0.5.




Fig. 2. Three-dimensional finite element model of underground buried steel pipe.

3.2 Calculation Scheme and Load

12 schemes listed in Table 1 were formulated based on the abovementioned model. Different models were established in terms of different fault displacement, fault widths, fault strike and length of steel liner section so as to carry out optimization research.

Table 1. Numerical schemes

Scheme	A-1	A-2	A-3	B-1	B-2	B-3	C-1	C-2	C-3	D-1	D-2	D-3
Fault displacement (mm)	200	300	400	300	300	300	300	300	300	300	300	300
Fault width (m)	50	50	50	50	75	100	500	500	500	50	50	50
Fault strike (°)	90	90	90	90	90	90	70	90	100	90	90	90
Section length (m)	5	5	5	5	5	5	5	5	5	3	5	7

Water diversion tunnel under normal operation and operating condition with creep deformation is investigated in this paper. The loads include the dead load of the steel pipe, the weight of the water inside the pipe, the internal water pressure, and the creep deformation of the fault zone (i.e. fault dislocation), detailed as follows: (1) Internal water pressure: Acting on the inner wall of the steel pipe, the maximum design pressure at the pipe top is 4.3 MPa. (2) Gravity: It is assumed that in the calculation the steel pipe does not bear the release load after the excavation of the surrounding rock, and only the influence of the weight of the steel pipe and the water inside the pipe is considered. (3) Creep deformation of the fault zone. The cumulative horizontal displacement is 300

mm. The vertical displacement is taken as two-thirds of the horizontal displacement, that is 200 mm.

4 Analysis of the Influence of Different Fault Parameters and Section Lengths

For different fault displacements, widths, strikes and length of steel liner section (see Table 2 for details), all calculation schemes were based on the load combination of the dead load of the steel pipe + weight of water + internal water pressure + fault displacement. Comparisons were made in terms of the displacement of steel pipe, the deformation of expansion joints, the stress of steel pipe and concrete.

4.1 Displacement of Steel Pipe

The displacement of the steel pipe under 300 mm dislocation is shown in Fig. 3. Under conditions of other different fault parameters or section lengths, the displacement distribution law of the steel pipe is basically the same as that of 300 mm, only the values different. Therefore the displacement in the X, Y, and Z directions and the maximum resultant displacement of the steel pipe varying with the fault dislocation, width, inclination angle, and section length is illustrated in Fig. 4. It can be observed from Fig. 4 (a) that both the displacements in the X, Y, and Z directions and the resultant displacement of the steel pipe increase linearly with the increase of the fault displacement. The maximum value is approximately equal to the horizontal displacement of the fault for each scheme. It is revealed from Fig. 4 (b) that when the fault displacement remains 300mm, the displacement in X and Y directions and the maximum resultant displacement of the steel pipe increase slightly with the increase in the fault width. While the displacement in Z direction decreases with the increase of the fault width. The width of fault has little influence on the maximum value of structural displacement and mainly affects the change rate of structural displacement within the fault influence zone. It can be seen from Fig. 4 (c) that the displacements in the X and Y directions and the resultant displacement of the steel pipe slightly decrease with the increase of the inclination angle, while the displacement in the Z direction significantly decreases with the increase of the inclination angle. The Angle between the pipeline and the fault mainly affects the components of the horizontal displacement in the direction of the pipe axis and the vertical direction. It is indicated from Fig. 4 (d) that with the increase of the pipe section length, the displacement of the steel pipe in each direction basically remains unchanged, indicating that the change of the pipe section length has negligible influence on the total displacement of the steel pipe in the fault zone.




Fig. 3. Distribution of the displacement of the section center along the pipeline axis.




Fig. 4. The variation of steel pipe displacement in the fault zone with different dislocation parameters.

4.2 Deformation of the Expansion Joint

The relationship between the total displacement of the expansion joints and different fault parameters for different schemes is shown in Fig. 5. It can be seen from Fig. 5 (a) that with the increase of the fault displacement, the deformation of the expansion joint gradually increases and the increase is approximately proportionally to the fault displacement. When the fault displacement is 300 mm, the maximum deformation of the expansion joint reaches 21.79 mm, which approaches the maximum deformation of the bellows expansion joint at this pressure level. As a result, if it is necessary to adapt to the fault displacement of more than 300 mm, engineering measures such as increasing the number of expansion joints need to be taken. It can be seen from Fig. 5 (b) that as the width of the fault increases, the total deformation of the expansion joint correspondingly slightly increases. When the fault displacement is constant, the larger the fault width, the more expansion joints need to be arranged, and the more uneven the deformation of a

single expansion joint will be. It can be seen from Fig. 5 (c) that as the angle between the pipeline and the fault decreases, the lateral and the total deformation of the expansion joint increase. When the angle between the pipeline and the fault is 70° , the maximum deformation of the expansion joint reaches 28.26 mm. It can be seen from Fig. 5 (d) that as the length of the pipe section decreases, the number of expansion joints in the fault zone increases, accordingly the total deformation of expansion joint gradually increases. Generally speaking, the longer the pipe section is, the fewer the number of expansion joints will be, and the greater the maximum deformation of the expansion joint will be.




Fig. 5. The relationship between the deformation of the expansion joint and the fault parameters

4.3 Stress of Steel Pipe

The Mises stress on the middle surface of each section of the steel pipe under the condition of a fault displacement of 400 mm is shown in Fig. 6. The circumferential, axial and Mises stresses on the middle surface of each section of the steel pipe under conditions of other fault parameters are the same as the distribution of fault displacement of 400 mm, but the value increases with the increase of the fault displacement. The relationship between the circumferential, axial and maximum Mises stresses and the fault parameters is shown in Fig. 9. As can be seen from Fig. 7 (a), with the increase of the fault displacement, due to the regulating effect of the expansion joint, the Mises stress of the steel pipe only increases slightly. All stresses are less than the overall membrane stress limit of 276 MPa even under the condition of 400 mm fault displacement, indicating that the thickness of the steel plate used in the design can meet the strength requirements. As can be seen from Fig. 7 (b), the distribution of circumferential, axial and Mises stress on the middle plane of each pipe section is the same for different fault widths, and the stresses basically

slightly increase with the increase of the fault width. This is because after using more expansion joints for wider fault, the stress of the steel pipe can be adjusted to keep within the allowable value. It can be known from Fig. 7 (c) the distribution of circumferential, axial and Mises stresses on the middle surface of each pipe section is basically the same for different inclination angles, but the stresses increase with the decrease of the angle, and the circumferential stress increases significantly. This indicates that when the pipeline needs to pass through a fault, the orthogonality between fault and pipeline is favorable for the loading of pipe structure. It can be known from Fig. 7 (d) that the distribution of circumferential, axial and Mises stress on the middle surface of each pipe section for different section lengths are the same, and there is basically no change with the increase of the steel pipe length.




Fig. 6. Mises stress of steel pipe on the middle plane when the fault displacement is 400 mm.




Fig. 7. The relationship between the steel stresses and the fault parameters.

5 Conclusion

The buried steel pipe crossing the Zela Cuo-Zongpo fault zone is taken as the research object in this paper, the sensitivity of the basic design parameters of the steel pipe passing through the fault is thus analyzed. Following conclusions can be drawn:

- (1) With the increase of the fault displacement, both the deformation and stress of the lining structure show an increasing trend. The displacement of the steel pipe, the deformation of the expansion joint, and the stress of the concrete present a linear increasing trend with the increase of the fault displacement. Due to the setting of the expansion joint, the stress of the steel pipe is marginally affected by the fault displacement.
- (2) Under the condition of the same fault displacement, the stress of the steel pipe and lining increases with the decrease of the fault width. The width of the fault mainly affects the deformation of the expansion joint, Under the condition that the basic layout of the steel pipe and lining remains unchanged, the larger the width of the fault, the more the number of expansion joints, and the smaller the fault displacement born by a single expansion joint. As a consequence, under the condition that the fault dislocation is constant, the smaller the fault width is, the more unfavorable it is for the loading of structure and the layout and selection of expansion joints.
- (3) The angle between the pipeline and the fault affects the components of the fault displacement on the horizontal plane in both the pipe axis and the direction perpendicular to the pipe axis, as well as the length of the affected pipeline. When the pipeline is orthogonal to the fault, the load conditions of structure are better.
- (4) The longer the length of the steel pipe section, the fewer the number of expansion joints, and the greater displacement that a single expansion joint bears, which is more unfavorable for the force on the lining structure. Since the Zela Cuo-Zongpo fault is mainly characterized by horizontal lateral and vertical displacement, the pipe structure moves along with the surrounding rock and can adapt to a certain amount of displacement by itself. Even if the section length is relatively small and the number of expansion joints is large, the displacement of the expansion joints cannot be significantly reduced. In addition, the deformation of each expansion joint vary greatly, the deformation of the end expansion joint is very small and has not played its role, the cost of the project will be increased at the same time. After a comprehensive comparison of the results of different pipe section lengths, it is recommended to choose a section length of 5 m.
- (5) By comprehensively comparing the calculation results of all the schemes, the parameters used in the current design is suitable for the internal pressure resistance of the underground buried steel pipe in this project. However, the external pressure resistance stability of steel pipe and bellows expansion joints is confronted with considerable challenges, especially in cases of high external pressure and thick cushion layers laid around the steel pipes and expansion joints, which is worthy of further in-depth research.

Acknowledgement. This research was funded by the Science and Technology Plan Projects of Tibet Autonomous Region (Grant No. XZ202401JD0028).

References

1. Russo, M., Germani, G., Amberg, W.: Design and construction of large tunnel through active faults: a recent application (2002). sn
2. Shahidi, A.R., Vafaeian, M.: Analysis of longitudinal profile of the tunnels in the active faulted zone and designing the flexible lining (for Koohrang-III tunnel). *Tunn. Undergr. Space Technol.* **20**(3), 213–221 (2005)
3. Zhou, G., Sheng, Q., Cui, Z., et al.: Model test of failure mechanism of tunnel with flexible joint crossing active fault under strike-slip fault dislocation. *Rock Soil Mech.* **43**(01), 37–50 (2022). (in Chinese)
4. Zhou, G., Sheng, Q., Zhang, C., et al.: Study on the mechanism of design parameters of a tunnel with flexible joint crossing strike-slip faults. *Chin. J. Rock Mech. Eng.* **41**(05), 941–953 (2022). (in Chinese)
5. Cui, G., Wang, L., Wang, M., et al.: Model tests for anti-breaking performance of a fiber reinforced concrete tunnel lining. *J. Vib. Shock* **38**(13), 50–56 (2019). (in Chinese)
6. Caulfield, R., Kieffer, D.S., Tsztoo, D.F., et al.: Seismic design measures for the retrofit of the claremont tunnel. In: RETC Proceedings California (2005)
7. Jiang, S., Li, P., Lin, Z.: Design strategies of breaking resistance of tunnels crossing active faults zone. *J. Chongqing Jiaotong Univ. (Nat. Sci.)* **27**(06), 1034–1036 (2008). (in Chinese)
8. Ren, X., Li, X., Li, W.: Design of diversion tunnel crossing active fault of Saizhu hydropower station on Ximahe river II. *China Water Transp.* **15**(02), 167–168 (2015). (in Chinese)
9. Shi, C., Shi, Y., Wu, H., et al.: Function of bellows expansion joint in long distance buried steel pipe. *Spec. Struct.* **38**(5), 64–68 (2021). (in Chinese)
10. Shi, C., Wu, H., Liu, Y., et al.: Study on ultimate displacement compensation capacity of hydraulic bellow expansion joint. *Water Power* **45**(04), 56–61 (2019). (in Chinese)
11. Lu, Z.: Adaptability to Fault Creep and External Pressure Stability of Underground Penstock. Wuhan University, Wuhan (2021). (in Chinese)
12. Xu, W., Xu, H., Shi, C., et al.: Study on adaptation of multi-layer flexible stacked lining of high-pressure water transmission tunnels subjected to fault creep. *Chin. J. Geotech. Eng.* **46**(5), 998–1007 (2024). (in Chinese)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Study on the Sediment Erosion Characteristics and Protection Strategies of the Pump-Turbine in Qinglong Liancheng Pumped Storage Power Station

Nan Li^(✉) and Dan Yao

PowerChina Guiyang Engineering Corporation Limited, Guiyang 550081, Guizhou, China
903260685@qq.com

Abstract. This thesis focuses on the Liancheng Pumped Storage Power Station in Guizhou Province and conducts an in-depth study on the sediment erosion problem of the pump-turbine. Based on the analogy method recommended by the IEC 62364:2019 standard and combined with the on-site measured sediment characteristics and sediment concentration data passing through the turbine, the wear characteristics of the turbine's flow components are predicted. This thesis explores the mechanism and hazards of sediment wear, estimates the sediment wear and the time between overhaul, and proposes comprehensive protective measures against sediment. The research shows that the sediment content passing through the turbine of this power station is relatively high, and the expected wear is relatively severe. It is necessary to adopt comprehensive measures from multiple aspects such as engineering, processing and manufacturing, and operation management to reduce the wear intensity, extend the time between overhaul, and ensure the safe and stable operation of the power station.

Keywords: Pumped Storage Power Station · Pump-Turbine · Sediment Erosion · Wear Mechanism · Time Between Overhaul · Protective Measures

1 General Situation

1.1 Project Introduction

The Qinglong Liancheng Pumped Storage Power Station in Guizhou Province is located in Liancheng Sub-district, about 5 km west of Qinglong County. The power station site is approximately 90 km away from Xingyi City and about 165 km away from Guiyang City in a straight line. The power station hub layout includes main buildings such as the upper reservoir, lower reservoir, water conveyance system, underground power generation plant, and switch station, and it is a pure pumped storage power station. The operating head range of the turbine working condition of the power station is 667.3 m to 736.9 m, and the head range of the pump working condition is 681 m to 743.7 m. It is preliminarily planned to install 4 Francis pump-turbine generator units with a single-unit capacity of 350 MW, and the total installed capacity is 1400 MW.

1.2 Sediment Content Passing Through the Turbine

After calculation and analysis by the one-dimensional steady non-uniform sediment mathematical model and its application software for pumped storage power stations developed by the School of Water Resources and Hydropower, Wuhan University, the average sediment content passing through the turbine in the natural river channel of Liancheng Pumped Storage Power Station is 102 g/m³ under the pumping working condition and 77.4 g/m³ under the power generation working condition.

1.3 Sediment Gradation and Mineral Composition

During the flood season from September to October 2024, suspended sediment water samples were collected respectively from the river sections at the tail of the main stream and tributaries of the Ximi River Reservoir, and analysis tests such as particle gradation and mineral composition were carried out. The relevant test results are shown in Table 1.

Table 1. Analysis Results of the Particle Gradation of Suspended Sediment Samples in the Lower Reservoir

Location	Weight Percentage (%) of Sediment Particles in Different Size (mm)							
	Particle Size (mm)	0.5	0.25	0.075	0.05	0.025	0.01	0.005
Main Stream	Proportion (%)	91.2	86.3	61.1	55.4	37.2	19.9	11.3

The mineral composition of the suspended sediment at the dam site of the power station is mainly quartz, followed by chlorite, illite, calcite, feldspar, hematite, kaolinite, dolomite, etc. Suspended sediment samples were taken from the river section at the dam site, and the analysis results of the mineral composition are shown in Table 2.

Table 2. Content Table of the Mineral Composition of Suspended Sediment in the Lower Reservoir

Sample	Mineral Composition (%)							
Combined Suspended Sand Sample	Quartz	Chlorite	Illite	Calcite	Feldspar	Hematite	Kaolinite	Dolomite
	27.2	5.4	21.4	26.5	14.5	0.5	2.3	2.2

It can be seen from this table that the content of quartz and feldspar with a Mohs hardness greater than 5 is approximately 41.7%.

2 Hazards of Sediment Wear

Sediment wear will damage the flow surface, reduce the performance of the unit, and seriously affect the stability and safety of the unit operation.

In terms of the efficiency performance of the unit, wear will increase the clearance of mechanical parts and the volumetric loss. Under the combined action of sediment wear and erosion, the surface morphology of the flow components changes, altering the blade profile angle and affecting the output and efficiency of the turbine.

In terms of the operation of the unit, wear makes the surface of the flow components uneven, accelerating the local disturbance of the water flow and the progress of cavitation; the material damage caused by erosion will lead to the failure of the flow components. In severe cases, it will cause strong vibrations and noises in the unit, directly affecting the safety, stability, and service life of the turbine.

In terms of maintenance, the wear condition determines the maintenance frequency and maintenance volume, directly affecting the unit utilization rate, the time between overhaul, and the maintenance workload.

3 Sediment Wear Protection Measures

(1) In the Unit Selection and Scheme Design Stage

Under the same water head, the flow velocity of the turbine increases with the increase of the specific speed. And the wear rate of the flow-through components of the turbine is proportional to approximately the cube of the flow velocity around the components. The most effective way to reduce the sediment wear of the flow-through components is to reduce the relative flow velocity of the flow-through components of the turbine. For pump turbines operating in sediment-laden water, the economic efficiency of the power station operation should mainly consider the time between overhaul and operation life of the pump turbines. Therefore, in the unit selection and scheme design stage, for hydropower stations with high sediment content, turbines often adopt the scheme with low specific speed parameters. Compared with the hydraulic scheme with a higher gear of rotational speed, it is beneficial to reduce the water flow velocity in the flow channel, improve the anti-sediment wear ability of the runner and guide vanes, and enhance the stability of the unit.

The operating water head range of the turbine mode of this power station is 667.3 m to 736.9 m, and the head range of the pump mode is 681 m to 743.7 m. The rated rotational speed is 500 r/min. The specific speed coefficient K_p of the pump mode is 3566, and the specific speed coefficient K_t of the turbine mode is 2198, with relatively low parameter levels. From the statistics of the main parameters of some pumped storage units with similar water head sections at home and abroad, if this power station adopts the scheme of reducing the rotational speed by one gear, the rated rotational speed of the pump turbine will be reduced to 428.6 r/min, $K_p = 3057$, and $K_t = 1884$. The parameter levels of the unit will deviate seriously from the statistical values of similar water head sections, greatly increasing the difficulty of the hydraulic design of the pump turbine and the instability and complexity of the unit operation. In severe cases, it may even pose a threat to the safety of the unit, cause unplanned shutdowns, and affect the stable power supply of the power grid (Fig. 1).

(2) In the Hydraulic Design Stage




Fig. 1. Specific Speed Coefficients of Pumped Turbine with Similar Head Sections

The degree of sediment wear of the flow-through components of the pump turbine is related to factors such as the sediment content passing through the turbine, the properties of sediment particles (particle size, shape, hardness, etc.), the materials of the pump turbine, the water flow velocity, and the flow pattern. In the hydraulic design stage, the hydraulic performance of the pump turbine can be improved through the optimization of the geometry of the flow channel and the blade shape, and the factors that intensify the damage caused by unstable flow and cavitation can be eliminated.

In the hydraulic design stage, CFD two-phase flow simulation calculation is used to find out the easily worn parts. And through the optimization of the cross-sectional area of the volute, and the optimization and adjustment of geometric parameters such as the profile, installation angle, and wrap angle of the guide vanes and blades, the water flow velocity of the easily worn parts is mainly reduced. At the same time, it makes the pressure and streamline distribution in the flow channel more uniform and the transition smooth, which is conducive to ensuring the anti-sediment wear ability of the unit. At the same time, a pump turbine that is suitable for this power station and has good cavitation performance is preferably selected to ensure that the turbine operates without cavitation throughout the entire operating range, thereby avoiding the combined effect of cavitation and wear and further reducing the destructive effect of sediment erosion on the turbine.

(3) In the Structural Design, Processing and Manufacturing Stage

In terms of the material selection, structural design, and manufacturing and processing technology of the flow-through components of the pump turbine, high-strength anti-erosion materials can be selected, and advanced processes and technologies such as molding and spraying protective layers can be adopted to reduce the destructive effect on the turbine when erosion occurs.

(4) Operation Modes Conducive to Reducing Sediment Wear

The sediment content passing through the turbine in this power station is relatively high. In addition to taking corresponding anti-sediment wear measures during the design and manufacturing process of the unit, during the actual operation of the unit, the operation and maintenance modes of the unit can also be optimized in combination with the sediment characteristics of the power station and the actual situation of the unit, and a scientific and reasonable operation strategy for protecting the unit from sediment wear can be formulated to improve the anti-sediment wear performance of the pump turbines in the power station and reduce the impact of the sediment passing through the turbine on the unit.

4 Sediment Wear of Pump Turbines and Estimation of Time Between Overhaul

4.1 Assumptions of the Sediment Wear Prediction Model

The sediment wear prediction model of turbines is established based on the following assumptions according to IEC62364.

It is assumed that there is no combined effect of wear and cavitation during the sediment wear process of the turbine. The damage caused by the interaction between cavitation and wear is greater than the sum of wear and cavitation acting alone. However, the quantitative relationship of the combined damage of erosion is still unclear. Therefore, the sediment wear prediction model of the turbine does not consider the combined effect of wear and cavitation for the time being.

The sediment wear prediction model of the turbine does not consider the damage caused by large solid objects impacting the surface of the turbine components. Large solid objects (such as stones, wood, ice, metal parts, etc.) may impact the surface of the turbine components with the water flow, causing damage. These damages will intensify the turbulence of the water flow and accelerate the wear and damage. The local surface of the wear-resistant coating may also be damaged due to the impact of large solid objects. Therefore, the sediment wear prediction model of the turbine does not consider the special situation where large solid objects impact the surface of the turbine components.

The sediment wear of the turbine is closely related to factors such as the sediment velocity, sediment concentration, physical properties of the sediment, flow pattern, and material properties of the turbine. It is assumed that the various variable factors are relatively independent of each other and do not affect one another. Based on previous literature research and accumulated experience, it can be considered that the independence of various variable factors is applicable to the turbine.

The sediment velocity and the K_f value (flow coefficient) can be approximately assumed to be constants in the case of little change in the water head and flow rate.

4.2 Calculation of the Turbine Between Overhaul

According to the “Technical Guidelines for Anti-sediment Wear of Hydraulic Turbines in Hydropower Stations” NB/T 11191-2023, the calculation formula for the sediment

wear depth is as follows:

$$S = W^{3.4} \times PL \times K_m \times K_f / RS^P \quad (1)$$

The calculation formula for the TBO (Time Between Overhaul) recommended by IEC62364 is as follows:

$$TBO_{target} = \frac{S_{ref}}{S_{target}} TBO_{ref} \quad (2)$$

Combined with formula (A.1), formula (A.9) can be converted into the following formula:

$$TBO_{target} = \frac{W_{ref}^{3.4}}{W_{target}^{3.4}} \times \frac{PL_{ref}}{PL_{target}} \times \frac{K_{m,ref}}{K_{m,target}} \times \frac{K_{f,ref}}{K_{f,target}} \times \frac{RS_{target}^P}{RS_{ref}^P} \times TBO_{ref} \quad (3)$$

According to formula (A.8), the following formula can be obtained:

$$PL_{ref}/PL_{target} = \frac{C_{ref}}{C_{target}} \times \frac{K_{shape,ref}}{K_{shape,target}} \times \frac{K_{size,ref}}{K_{size,target}} \times \frac{K_{hardness,ref}}{K_{hardness,target}} \quad (4)$$

$$\text{For Francis and Kaplan turbines: } \frac{K_{f,ref}}{K_{f,target}} = 1 \quad (5)$$

In the formula (Table 3):

TBO_{ref} —The reference turbine time between overhaul, in hours (h);

TBO_{target} —The target turbine time between overhaul, in hours (h);

W_{ref} —The characteristic velocity of the reference turbine, in meters per second (m/s);

W_{target} —The characteristic velocity of the target turbine, in meters per second (m/s);

PL_{ref} —The annual sediment load of the reference turbine, the integral value of the sediment concentration over time T calculated by formula (1), in kilograms per hour per cubic meter ($\text{kg} \times \text{h}/\text{m}^3$);

PL_{target} —The annual sediment load of the target turbine, the integral value of the sediment concentration over time T calculated by formula (1), in kilograms per hour per cubic meter ($\text{kg} \times \text{h}/\text{m}^3$);

$K_{m,ref}$ —The material factor of the reference turbine;

$K_{m,target}$ —The material factor of the target turbine;

$K_{f,ref}$ —The flow coefficient of the reference turbine;

$K_{f,target}$ —The flow coefficient of the target turbine;

RS_{ref} —The reference size of the reference turbine, in meters (m);

RS_{target} —The reference size of the target turbine, in meters (m);

S_{ref} —The wear depth of the reference turbine;

S_{target} —The wear depth of the target turbine;

C_{ref} —The sediment concentration of the reference turbine, in kilograms per cubic meter (kg/m^3);

C_{target} —The sediment concentration of the target turbine, in kilograms per cubic meter (kg/m^3);

$K_{\text{size,ref}}$ —The particle size factor of the reference turbine;
 $K_{\text{size,target}}$ —The particle size factor of the target turbine;
 $K_{\text{sharp,ref}}$ —The shape factor of the reference turbine;
 $K_{\text{sharp,target}}$ —The shape factor of the target turbine;
 $K_{\text{hardness,ref}}$ —The hardness factor of the reference turbine;
 $K_{\text{hardness,target}}$ —The hardness factor of the target turbine;

Table 3. TBO of the Francis Pump Turbine in Liancheng Pumped Storage Power Station

NO.	Specifications	Symbol	Unit	Reference Turbine	Target Turbine
1	Turbine Type	—	—	Francis	Francis
2	With/Without Coating	—	—	With	With
3	Runner Diameter	D	m	1.279	4.5
4	Average Sediment Concentration	C	kg/m ³	0.126	0.025
5	Percentage of Sediment with Mohs Hardness 5–5.4	—	%	0	0
6	Percentage of Sediment with Mohs Hardness 5.5–5.9	—	%	2	0.5
7	Percentage of Sediment with Mohs Hardness 6–6.9	—	%	16	14.5
8	Percentage of Sediment with Mohs Hardness 7–7.9	—	%	38	27.2
9	Percentage of Sediment with Mohs Hardness Greater than 8	—	%	0	0
10	Shape Factor (1 for Circular, 1.5 for Sub-angular, 2 for Angular)	K_{shap}	—	1	1.5
11	Characteristic Velocity (Runner)	W_{run}	m/s	59.9	118
12	Time Between Overhaul	TBO	h	22800	

The runner diameter of pump turbine is about 4.5 m. The average sediment content passing through the turbine in the natural river over the years is 0.102 kg/m³, and the

sediment content with a Mohs hardness greater than 7 is about 27.2%. The runner of the pump turbine is preliminarily planned to adopt a special protective coating. By using the calculation formula of the TBO (Time Between Overhaul) recommended by IEC62364, comparative calculations are carried out. The preliminary calculation of the pump turbine TBO is shown in Table 4 (runner with coating) and Table 5 (runner without coating).

The calculation process of the TBO of the target pump turbine is as follows:

$$\begin{aligned}
 TBO_{\text{target}} &= \frac{S_{\text{ref}}}{S_{\text{target}}} TBO_{\text{ref}} \\
 S_{\text{ref}}/S_{\text{target}} &= \frac{W_{\text{ref}}^{3.4}}{W_{\text{target}}^{3.4}} \times \frac{PL_{\text{ref}}}{PL_{\text{target}}} \times \frac{K_{\text{m,ref}}}{K_{\text{m,target}}} \times \frac{K_{\text{f,ref}}}{K_{\text{f,target}}} \times \frac{RS_{\text{target}}^p}{RS_{\text{ref}}^p} \\
 &= \frac{W_{\text{ref}}^{3.4}}{W_{\text{target}}^{3.4}} \times \frac{PL_{\text{ref}}}{PL_{\text{target}}} \times \frac{K_{\text{m,ref}}}{K_{\text{m,target}}} \times \frac{K_{\text{f,ref}}}{K_{\text{f,target}}} \times \frac{D_{\text{target}}^p}{D_{\text{ref}}^p} \\
 &= 0.0997 \times 4.717 \times 1 \times 1 \times 2.568 = 1.2
 \end{aligned}$$

where:

$W_{\text{ref}}^{3.4}/W_{\text{target}}^{3.4} = 59.9^{3.4}/118^{3.4} = 0.0997$, the characteristic velocity W is calculated according to formula (A.7). IEC62364 has given the characteristic velocity W of the reference turbine as 59.9 m/s, and the characteristic velocity of the target turbine is m/s.

$$W_{\text{run}} = \sqrt{u_2^2 + c_2^2} = 118 \text{ m/s.}$$

$$\begin{aligned}
 PL_{\text{ref}}/PL_{\text{target}} &= \frac{C_{\text{ref}}}{C_{\text{target}}} \times \frac{K_{\text{shape,ref}}}{K_{\text{shape,target}}} \times \frac{K_{\text{size,ref}}}{K_{\text{size,target}}} \times \frac{K_{\text{hardness,ref}}}{K_{\text{hardness,target}}} \\
 &= 5.04 \times 0.67 \times 1 \times 1.397 = 4.717
 \end{aligned}$$

$$C_{\text{ref}}/C_{\text{target}} = 0.126/0.025 = 5.04$$

$K_{\text{shape,ref}}/K_{\text{shape,target}} = 1/1.5 = 0.67$ (In IEC62364, the reference shape factor is taken as 1. According to the sediment situation here, the sediment shape factor of the target turbine is taken as 1.5)

$K_{\text{size,ref}}/K_{\text{size,target}} = 1/1 = 1$ (In IEC62364, the reference particle size is taken as 1. According to the sediment situation, the sediment shape factor of the target turbine is taken as 1.0)

$K_{\text{hardness,ref}}/K_{\text{hardness,target}} = 0.38/0.272 = 1.397$ (both the reference and the target runner have coatings, only the particles with a Mohs hardness greater than 7 is included)

$K_{\text{m,ref}}/K_{\text{m,target}} = 1$ (both the target turbine runner and the reference turbine runner have coatings, and the material factors are the same, so the ratio is taken as 1)

$$K_{\text{f,ref}}/K_{\text{f,target}} = 1$$

$RS_{\text{target}}^p/RS_{\text{ref}}^p = 4.5^{0.75}/1.279^{0.75} = 2.568$ (According to the recommendation of NB/T 11191-2023, $RS = D$, and the turbine size index p is taken as 0.75)

$$TBO_{\text{target}} = 1.2 \times 22800 \text{ h} = 27360 \text{ h}$$

The annual utilization hours of this hydropower station are 2149 h, and the ratio of the TBO_{target} to the annual utilization hours is $TBO_{\text{target}}/2149 \approx 12.73$ years (Fig. 2).

Table 4. TBO under Different Sediment Contents (with Runner Coating)

Sediment Content kg/m^3	0.025	0.05	0.075	0.1	0.125	0.15
$C_{\text{ref}}/C_{\text{target}}$	5.04	2.502	1.68	1.26	1.008	0.84
$K_{\text{hardness,ref}}/K_{\text{hardness,target}}$	1.397					
$K_{\text{m,ref}}/K_{\text{m,target}}$	1					
A-level Maintenance Cycle/Year	12.7	6.3	3.2	1.6	0.8	0.4
Estimated A-level Maintenance Shutdown Time / Day	120–130					

Table 5. TBO under Different Sediment Contents (without Runner Coating)

Sediment Content kg/m^3	0.025	0.05	0.075	0.1	0.125	0.15
$C_{\text{ref}}/C_{\text{target}}$	5.04	2.502	1.68	1.26	1.008	0.84
$K_{\text{hardness,ref}}/K_{\text{hardness,target}}$	0.9					
$K_{\text{m,ref}}/K_{\text{m,target}}$	0.9					
A-level Maintenance Cycle/Year	9	4.5	2.2	1.1	0.55	0.3
Estimated A-level Maintenance Shutdown Time/Day	90–100					




Fig. 2. TBO under Different Sediment Contents

5 Conclusions and Recommendations

- (1) The wear rate of turbine flow components is approximately proportional to the cube of the flow velocity. Generally, under the same sediment concentration, higher relative flow velocity leads to more severe wear and shorter overhaul cycles. Considering the average annual sediment concentration of 102 g/m^3 , maximum relative linear velocity of 118 m/s , and annual utilization hours of Liancheng Pumped Storage Power Station, the A-level overhaul cycle is preliminarily estimated to be about 1 years.
- (2) Using wear-resistant coatings on the runner may extend the A-level overhaul cycle to 1–2 years. However, Liancheng station has high head, high speed, narrow runner channels, which makes spraying construction and on-site coating repair difficult, with high maintenance costs.
- (3) Based on natural sediment conditions and the overhaul cycle, Liancheng Pumped Storage Power Station is expected to suffer severe wear. It is recommended to take comprehensive measures in the feasibility study stage, including engineering design, unit selection, manufacturing, and operation management, to reduce wear intensity and extend the overhaul cycle.

References

1. Zeng, Z.: Structure and operation characteristics of high-head Francis turbines. *Water Power* (9), 37–39 (2006)
2. Luo, Y., Guo, H., Zha, R.: Anti - abrasion and erosion process technology of flow - through components in the first - stage Ruili River hydropower station. *Mech. Electr. Tech. Hydropower Stat.* **32**(6), 15–16, 27 (2009)
3. Lei, J., Jiang, X., Liu, D.: Analysis of the wear characteristics of flow - through components of high - head Francis turbines. *Des. Hydroelectr. Power Stat.* **25**(2), 55–58 (2009)
4. Wang, Z.: Structural progress of erosion - resistant coatings for hydraulic turbines. *Des. Water Resour. Hydroelectr. Eng.* **27**(2), 1–4 (2008)
5. Yang, X., Liu, L., Zhang, S.: Research on anti - abrasion measures of Pelton turbines in the Suki - Knaly hydropower station. *Des. Water Resour. Hydroelectr. Eng.* **40**(1), 38–40 (2021)
6. Yu, T.: Review of research on sediment problems of pumped storage power stations. *Hunan Hydro Power* **234**(4), 57–60 (2021)
7. Tao, L., Yu, M., Chen, Z., et al.: Development and application of the reservoir sediment mathematical model for Meizhou pumped storage power station. *Water Power* **45**(9), 69–74 (2019)
8. Zhang, G., Wei, X.: Numerical analysis of the influence of sediment concentration and particle size on the internal flow of turbine runners. *Trans. Chin. Soc. Agric. Eng.* **30**(23), 94–100, 340 (2014)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Reassessing Meyerhof's Theory for Eccentric Foundations: Rwandan Hydropower Case

Wei Xie^(✉), Bilei Wang, Xiaofang Lin, Xingang Yao, Tao Lou, and Yang Deng

Institute of International Project Center, Powerchina Huadong Engineering Corporation Limited,
Hangzhou 310000, China
xie_w@hdec.com

Abstract. Accurate evaluation of foundation stress and bearing capacity is essential for ensuring the structural integrity of critical infrastructure, particularly in large-scale hydropower projects featuring open powerhouses. These structures are subjected to significant forces and moments about horizontal orthogonal axes, requiring careful consideration of eccentric loading effects to guarantee stability. Although Meyerhof's theory is commonly employed for such assessments, empirical evidence from constructed projects and research studies indicates limitations, including potential non-conservatism in certain scenarios.

This study investigates a hydropower foundation in Rwanda, Africa, utilizing nonlinear finite element analysis to assess foundation stress under eccentric loading conditions. The numerical results are compared with theoretical predictions derived from Meyerhof's method, revealing that while the theory is often regarded as conservative, it may fail to adequately account for localized yielding in open powerhouse foundations, potentially leading to unsafe design outcomes. The findings underscore the importance of supplementing theoretical approaches with advanced numerical simulations or experimental validation in high-stakes engineering applications.

Keywords: Bearing Capacity · Eccentric Loading · Meyerhof's Theory · Finite Element Analysis (FEA) · Hydropower Foundation

1 Introduction

In conventional foundation design practice, the stress distribution beneath footings is typically calculated based on linear elastic theory [1], which assumes: (1) a perfectly rigid foundation, (2) homogeneous linear-elastic soil behavior, and (3) linear stress distribution. While this simplified approach facilitates analytical solutions, it fails to account for critical nonlinear phenomena that emerge under high eccentric loading conditions, such as stress redistribution and localized yielding - potentially leading to non-conservative design outcomes.

Meyerhof's (1953) bearing capacity theory [2] extends this framework by incorporating plastic failure mechanisms through empirical correction factors (e.g., shape factors and depth factors). The theory assumes: (1) a linear initial stress distribution prior to

plastic failure, (2) simplified failure mechanisms, (3) complete soil-foundation contact (no lift-off), and (4) rigid-perfectly plastic soil behavior.

Subsequent investigations by Ukritchon et al. (2003) [3], Zhang et al. (2016) [4], and Loukidis and Salgado (2009) [5] have systematically identified scenarios where these assumptions prove particularly problematic: (1) high eccentricity loading, (2) heterogeneous or anisotropic soil profiles, (3) foundation flexibility effects, and (4) complex stress redistribution patterns. These findings highlight critical limitations in conventional bearing capacity analysis methods.

In this study, we examine a hydropower foundation case in Rwanda, Africa, employing both Meyerhof's conventional method and an established nonlinear finite element methodology utilizing compression-only spring elements. The comparative analysis reveals that while Meyerhof's approach provides reasonable estimates for standard cases, the nonlinear finite element method offers three fundamental advantages for complex loading conditions: (1) physically consistent equilibrium through realistic load transfer mechanisms, (2) automatic exclusion of nonphysical tensile stresses, and (3) natural incorporation of stress redistribution effects.

The comprehensive comparison demonstrates that the compression-only spring approach provides more realistic predictions for eccentric loading scenarios while maintaining appropriate conservatism in design. The methodology proves particularly valuable for addressing the limitations identified in traditional approaches, offering improved accuracy for complex loading and soil conditions where Meyerhof's method may become unconservative.

2 Theoretical Framework and Methodology

2.1 Theoretical Basis and Formulations

- (1) The conventional analysis of powerhouse foundations typically employs linear elastic theory, which relies on three fundamental assumptions: perfect foundation rigidity, homogeneous linear-elastic soil behavior, and linear stress distribution. Within this theoretical framework, the governing equations are expressed as (Fig. 1):

$$\sigma = \frac{\sum W}{A} \pm \frac{\sum M_{xy}}{J_x} \pm \frac{\sum M_{yx}}{J_y} \quad (1)$$

σ —Vertical normal stress on the foundation surface in kPa;

$\sum W$ —Sum of normal components of all forces acting on the calculated cross section in kN;

$\sum M_x, \sum M_y$ —Sum of centroidal axis X and Y torques produced by all forces of unit section on calculated cross section in kN·m;

x, y —Distance from the calculating point to the centroidal axes X and Y on the calculated cross section in m;

J_x, J_y —Inertia moments from the calculating point to the centroidal axes X and Y on the calculated cross section in m⁴;

A —Area under pressure on the calculated cross section in m²;




Fig. 1. Distribution of foundation stress (linear elastic theory)

- (2) Meyerhof's (1953) bearing capacity theory extends this framework by incorporating plastic failure mechanisms through empirical correction factors (e.g., shape factors and depth factors), with the ultimate Bearing Capacity Equation expressed as:

$$q_u = c'N_c + q'N_q + 0.5\gamma B'N_\gamma \quad (2)$$

q_u ——Ultimate bearing capacity of soil, in kPa

c' ——Effective cohesion of soil;

N_c ——Bearing capacity factor for cohesion;

q' ——Effective overburden pressure at foundation base;

N_q ——Bearing capacity factor for surcharge;

γ ——Effective unit weight of soil (use submerged unit weight below water table);

B' ——Effective foundation width;

N_γ ——Bearing capacity factor for soil weight.

In addition, Meyerhof's method accounts for biaxial eccentricity by reducing the foundation's contact area through the concept of "effective dimensions". When a foundation is subjected to combined vertical load and biaxial moments, the actual load-bearing area decreases, with the dimensions and compressive stress q_{avg} calculated as:

$$B' = B - 2e_B \quad (3)$$

$$L' = L - 2e_L \quad (4)$$

$$q_{avg} = \frac{\sum W}{B'L'} \quad (5)$$

B' ——Effective foundation width;

L' ——Effective foundation length;

B ——Original foundation width;

L ——Original foundation length;

e_B ——Eccentricity along width direction;

e_L ——Eccentricity along length direction.

- (3) Compression-only spring was adopted in this paper to conduct the nonlinear FEM calculation, with stiffness active only in compression ($\delta \geq 0$) to enforce boundary nonlinearity. Additionally, the Newton-Raphson iterative method was utilized to resolve contact state transitions and stiffness matrix discontinuities during loading.

Empirical Formula for compression-only spring stiffness [6]

$$k = \frac{E_s}{(1 - \nu^2)B} \quad (6)$$

k —Subgrade reaction modulus (Winkler spring stiffness);

E_s —Elastic modulus of the soil;

ν —Poisson's ratio of the soil;

B —Width of the loaded area.

The residual equation [7] for the Newton-Raphson method is as follows:

$$R(u) = F_{ext} - F_{int}(u) = 0 \quad (7)$$

R —Residual force vector (unbalanced forces);

u —Nodal displacement vector;

F_{ext} —Applied external forces;

F_{int} —Internal forces (e.g., spring reactions).

2.2 Numerical Implementation

In this study, a hydropower foundation case in Rwanda, Africa is examined, employing both Meyerhof's conventional method and a nonlinear finite element methodology through the widely-used numerical calculation software—Midas Gen.

As for the Meyerhof's conventional method, linear stress distribution was assumed at first to obtain the initial stress values. After that, the eccentricities were calculated and the concept of "effective dimensions" was then implemented to calculate the "effective area under compression". The compressive stress q_{avg} was eventually obtained using the formula.

With regard to the finite element method, the soil-foundation interaction was modeled using compression-only spring elements, where the spring stiffness is activated under compression ($\delta \geq 0$) and reduced to zero under tension ($\delta < 0$), thereby satisfying the boundary nonlinearity condition. The nonlinear iterative procedure successfully captures the evolving contact states:

- (1) state transition: The compression/tension states vary with load increments, requiring iterative evaluation.
- (2) numerical convergence: The abrupt stiffness matrix discontinuity during tension-compression transitions necessitates nonlinear algorithms (Newton-Raphson) to ensure solution stability.

The computed total force and biaxial moments are presents in Table 1 at the powerhouse base for a representative load case, which were adopted as the governing input condition for the numerical analysis in this study. The upper concrete structure was idealized as a rectangular cuboid, with applied loads acting on its bottom surface. Compression-only spring supports were implemented at the dense nodal points of the base to approximate a uniform boundary condition. Nonlinear finite element analysis was performed using the Newton-Raphson iterative method, with convergence criteria set at a tolerance of 0.001 over 20 maximum iteration steps. The computed foundation stresses were subsequently compared with those obtained from Meyerhof’s conventional analytical method.

Table 1. Total force and moments

W(kN)	$\sum M_x$ (kN·m)	$\sum M_y$ (kN·m)
44794.88	3700.75	99039.54

3 Results and Discussion

3.1 FEM Method

The finite element analysis (FEA) results indicate that the vertical normal stresses in the foundation follow a nonlinear distribution along its dimensions (Fig. 2), differing from the idealized linear stress assumption in elastic theory and the uniform distribution hypothesis in Meyerhof’s method. This nonlinear stress pattern provides a more realistic representation of load-transfer mechanisms in practical scenarios.

Additionally, the model inherently eliminates tensile stresses and redistributes compressive stresses in a manner consistent with theoretical expectations for hydraulic powerhouse foundations.

As shown in Fig. 3, 4, 5, the maximum displacements in all directions remain below 1 mm, and the solution exhibits numerical convergence. The analysis reveals very small uplift displacements (positive values) on the project-defined right side, rather than an exact zero-displacement zone. While this introduces a minor discrepancy with the compressive stress condition, the magnitudes are negligible (on the order of 10^{-3} mm), suggesting that the Winkler spring model approximates the overall mechanical behavior reasonably well. The displacement field remains continuous across the foundation base, ensuring physical consistency in the solution.

3.2 Meyerhof’s Conventional Method

The stress distribution obtained using Meyerhof’s conventional method is presented in Fig. 6. The analysis begins by evaluating the load eccentricities, revealing significant longitudinal eccentricity and relatively minor transverse eccentricity. Based on these eccentricities, the method calculates a modified linear stress distribution within a defined effective bearing area (shaded region), with an abrupt transition to zero stress at its

boundaries. While this approach offers computational simplicity for engineering design, its theoretical assumptions inevitably lead to stress discontinuities at the effective area edges.

3.3 Comparison and Discussion

The comparative analysis evaluates computational results from two foundation stress evaluation approaches, revealing fundamental methodological differences:

Meyerhof’s analytical method employs key simplifications: (1) restriction of stress distribution to a predefined effective area, (2) prescribed stress distribution patterns within this zone, (3) allowance for stress discontinuities at boundaries, and (4) simplified treatment of soil-structure interaction. In contrast, the finite element method: (1) numerically solves the complete boundary value problem, (2) maintains continuous stress distributions, and (3) automatically accounts for edge effects and local stress concentrations.

Moreover, the computational results show Meyerhof’s method yields a maximum stress of 283 kPa, while the FEM produces 361 kPa - a 27.6% higher and more conservative value particularly suitable for critical hydropower structures. The Winkler spring model offers a practical compromise, providing reasonable simulation of localized plastic behavior while maintaining computational efficiency for engineering analysis.




Fig. 2. Contour map of σ_{zz}




Fig. 3. Contour map of displacement in z direction




Fig. 4. Contour map of displacement in x direction




Fig. 5. Contour map of displacement in y direction




Fig. 6. Assumed compressive stress distribution through Meyerhof's method

4 Conclusion

- (1) This study presents a comparative stress analysis of a hydropower foundation in Rwanda, Africa, evaluating both Meyerhof's conventional method and nonlinear finite element analysis. The investigation reveals three key findings: (a) Meyerhof's theory demonstrates inherent limitations in capturing complete foundation behavior, particularly at stress concentration zones under eccentric scenarios; (b) the finite element method produces a 27.6% higher (and more conservative) maximum foundation stress (361 kPa vs. 283 kPa), making it better suited for critical hydropower structures; and (c) the Winkler spring model provides an effective engineering compromise, balancing reasonable plastic behavior simulation with computational practicality.

- (2) Although the Winkler spring model offers satisfactory approximation of localized plastic behavior for routine design applications, future research could explore its enhancement through coupled continuum-based plasticity analysis. Such refinement would particularly improve predictions for complex soil-structure interaction scenarios involving nonlinear material behavior or extreme loading conditions.

References

1. Timoshenko, S., Goodier, J.N.: Theory of Elasticity, 2nd edn. McGraw-Hill, New York (1951)
2. Meyerhof, G.G.: The bearing capacity of foundations under eccentric and inclined loads. In: Proceedings of the 3rd International Conference on Soil Mechanics and Foundation Engineering, vol. 1, pp. 440–445 (1953)
3. Ukritchon, B., Whittle, A.J., Sloan, S.W.: Undrained bearing capacity of shallow foundations under combined loading. *Géotechnique* **53**(9), 755–768 (2003)
4. Zhang, Y., Bienen, B., Cassidy, M.J., Gourvenec, S.: Interference effects on shallow footings in sand using FEM. *Can. Geotech. J.* **53**(2), 236–249 (2016)
5. Loukidis, D., Salgado, R.: Bearing capacity of strip and circular footings in sand using finite elements. *Comput. Geotech.* **36**(5), 871–879 (2009)
6. Bowles, J.E.: Foundation Analysis and Design. McGraw-Hill (1996)
7. Crisfield, M.A.: Non-linear Finite Element Analysis of Solids and Structures, vol. 1. Wiley, Chichester, U.K. (1991)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Exploration of Key Points in Safety Evaluation of Water Conveyance Tunnels for Pumped Storage Power Stations

Xiaobian Wu^(✉)

Nanjing Hydraulic Research Institute, Nanjing 210029, Jiangsu, China
xbwu@nhri.cn

Abstract. Water conveyance tunnels in pumped storage power stations serve as critical pathways connecting the upper and lower reservoirs. Current safety evaluation standards for these tunnels remain insufficient and inadequately address their structural characteristics. Taking the safety evaluation practice of a pumped storage power station as an example, this paper emphasizes that routine inspections and safety monitoring data analysis are vital components of safety evaluation. Given the challenges posed by significant elevation differences and difficult manual inspections in pumped storage tunnels, the application of autonomous collision-proof unmanned aerial vehicles (UAVs) is proposed. This approach enhances inspection efficiency and quality while reducing safety risks for operational personnel. Monitoring sensors embedded within the tunnels dynamically reflect their operational behavior, providing direct insights into structural safety. Analysis of monitoring data reveals that, in addition to reservoir water level fluctuations, temperature (water temperature) significantly influences structural behavior and should be prioritized in safety evaluations.

Keywords: Pumped storage power station · Water conveyance tunnel · Safety evaluation · Collision-proof UAV · Safety monitoring

1 Introduction

Pumped storage power stations play a pivotal role in balancing power generation loads, optimizing resource allocation, and ensuring grid stability. To guarantee their long-term safe operation, periodic safety assessments are conducted. According to the Regulations on Safety Appraisal for Hydropower Projects (Electric Power Industry Standard [1998] No. 219), safety appraisals for pumped storage power stations should be performed five years after project completion, covering key structures such as dams, reservoir basins, and water conveyance systems.

Existing research on safety evaluations for pumped storage stations has addressed aspects such as seepage stability, structural integrity, powerhouse vibrations, and metal structures. For instance, Li Hongjun et al. [1] analyzed seismic stability for slopes of the Kokhav Hayarden pumped storage station, providing insights for embankment safety

evaluations. Cao Xi et al. [2] proposed vibration control criteria for underground powerhouses based on resonance analysis. Wang Shengjun et al. [3] established vibration measurement protocols and safety indices for powerhouse structures. Li Wei et al. [4] addressed seepage stability challenges in core wall dams under frequent water level fluctuations. Xin Meng et al. [5] evaluated long-term erosion effects on tunnel linings using robotic inspection data. Zhang Fan et al. [6] developed a hybrid qualitative-quantitative evaluation framework for safety management.

Despite these advancements, water conveyance tunnels—critical components linking upper and lower reservoirs—have received limited attention. These tunnels differ from conventional hydropower or water diversion tunnels in structural design, operational modes, and load-bearing conditions, necessitating specialized evaluation methodologies.

2 Safety Evaluation Methods for Water Conveyance Tunnels

Existing standards, such as *Guidelines for Safety Evaluation of Hydropower Dams (DL/T 5313-2014)* [8], *Guidelines for Safety Evaluation of Reservoir Dams (SL 258-2017)* [9], and *Technical Specification for Safety Appraisal of Hydraulic Tunnels (SL/T 790-2020)* [10], provide general evaluation frameworks. Among these, *SL/T 790-2020* specifies procedures for tunnel safety appraisal, including condition surveys, safety inspections, structural verification, and risk assessment. However, detailed inspection methods and defect identification criteria remain underdeveloped. Tang Lei et al. [11, 12] established a comprehensive evaluation system for tunnel lining quality and crack severity, offering practical references for defect classification.

3 Characteristics and Evaluation Priorities

3.1 Operational Differences Between Water Conveyance Tunnels in Pumped Storage Power Stations and Conventional Water Diversion Projects

Water conveyance tunnels in pumped storage power stations exhibit distinct operational conditions compared to those in conventional water diversion projects. For instance, the hydraulic gradient differs significantly. Under the high head difference characteristic of pumped storage systems, water flows between the upper and lower reservoirs through the tunnels. To accommodate the topographical connection between the reservoirs, these tunnels often incorporate inclined or even vertical sections. This unique structural configuration renders manual inspections extremely challenging. Even during maintenance shutdowns, traditional manual inspections require extensive safety equipment and prolonged timeframes to achieve preliminary assessments. Furthermore, on-site inspectors may lack sensitivity to defect-prone areas within the tunnels, leading to inaccurate defect identification. Additionally, technical personnel often face limitations in accessing and evaluating structural defects at close range.

3.2 Contrasts in Hydraulic Head and Structural Response

In conventional water diversion projects, tunnels typically operate under free-flow (non-pressurized) or partially pressurized conditions, with relatively low pressure heads even in pressurized sections. In contrast, pumped storage tunnels experience head differences typically ranging from 100 m to 300 m (or greater), resulting in pressure magnitudes fundamentally distinct from those in general water supply projects. The cyclic internal and external water pressures exerted on tunnel linings or surrounding rock during pumping/generating modes accelerate deformation and potential failure in structurally vulnerable zones.

3.3 Evaluation Strategies for Pumped Storage Tunnels

Given the unique characteristics of pumped storage tunnels, routine inspections and structural performance feedback are indispensable for monitoring operational behavior, complementing standardized safety inspections and computational verifications. As a critical tool in safety evaluations, routine inspections offer advantages in operability, coverage, adaptability, and cost-effectiveness, and have been widely adopted in dam and reservoir engineering. These inspections enable direct identification of potential hazards or quality defects. Advances in automated inspection technologies, such as real-time photo/video data transmission, defect feature recognition, and anomaly classification, have significantly enhanced operational management capabilities. However, as noted earlier, the steep slopes of inclined/vertical sections in pumped storage tunnels pose substantial challenges for manual inspections, often rendering critical working faces inaccessible. Vertical sections inspected via rope access (commonly termed “spider-man” methods) entail high risks, compounded by seepage from aging gate seals in upper reservoirs, further jeopardizing inspector safety.

3.4 Innovative Inspection Solutions: Collision-Proof UAVs

Recent advancements in collision-proof unmanned aerial vehicles (UAVs), initially applied in mining, present a novel approach for tunnel inspections (structural configuration shown in Fig. 1). Conventional UAVs are unsuitable for enclosed spaces due to signal shielding, which disrupts positioning systems. In contrast, specialized UAVs employ autonomous flight algorithms for confined environments, integrated with self-navigation and 3D scanning/modeling capabilities. These technologies enable high-precision inspections and support digital twin applications for water conveyance tunnels, revolutionizing defect detection and structural assessment methodologies.

4 Safety Evaluation Practice of a Water Conveyance Tunnel in a Pumped Storage Power Station

Taking the water conveyance tunnel of a pumped storage power station in Jiangsu Province as a case study, the safety evaluation process involved not only conventional structural safety verification calculations but also prioritized enhanced on-site inspections and feedback analysis of monitoring data. These measures aimed to precisely



Fig. 1. Collision-proof UAVs

identify potential quality defects or operational risks during tunnel operation. To mitigate safety hazards and improve inspection efficiency, a novel collision-proof unmanned aerial vehicle (UAV) was deployed for tunnel inspections.

The water conveyance tunnel comprises three segments: an upper horizontal section, a vertical shaft, and a lower horizontal section (cross-sectional profile shown in Fig. 2). The tunnel has a total length of 574.31 m and a diameter of 6.5 m. The upper horizontal section measures 47.50 m in length with a base slope of 8%, followed by a vertical shaft with a height difference of 100.0 m. The lower horizontal section extends 380.90 m with a gentle slope of 0.5%.




Fig. 2. Sectional drawing of water conveyance tunnel project

4.1 Routine Inspection

During the inspection process, priority was given to examining the upstream emergency maintenance gate and vertical shaft section, both of which are challenging for manual access. The inspection imagery of the upstream emergency gate, as illustrated in Fig. 3, revealed clear evidence of water flow and minor ponding behind the gate. Through collaborative analysis with on-site technical personnel, the issue was attributed to the incomplete closure of the central filling valve at the gate's crown. This finding provided critical guidance for subsequent maintenance and component replacement planning.



Fig. 3. Upstream emergency gate inspection picture

The inspection results indicate that the vertical shaft maintains satisfactory structural integrity, with smooth surfaces and no apparent damage. However, due to leakage from the upstream gate, a persistent water flow was observed descending along the shaft wall. The inspection UAV, equipped with waterproof and impact-resistant capabilities, performed effectively without interference from the water flow. Surface irregularities

at elevations 87.60 m and 13.80 m, attributable to construction processes, were clearly identified via UAV-captured imagery.

Three round-trip UAV flights were conducted over the upper horizontal section and vertical shaft. Each flight employed distinct camera angles to comprehensively inspect the shaft's three-dimensional geometry. The UAV's wide-angle lens ensured full cross-sectional coverage of the shaft. Concurrently, point cloud data of the tunnel were acquired, laying the foundation for digital twin modeling. Notably, the UAV's current battery life is limited to 15 min, necessitating supplemental batteries for extended inspections of lengthy tunnel segments. Post-inspection supplementary flights were executed based on preliminary findings to refine data completeness (Figs. 4 and 5).




Fig. 4. The inner wall of the shaft was damaged (elevation 87.60 m).

4.2 Analysis of Monitoring Data

Safety monitoring systems, often regarded as the eyes and ears of dam and reservoir engineering, are critical diagnostic tools for detecting structural behavioral changes in hydraulic projects. These systems have been extensively implemented in water conservancy infrastructure. In the studied water conveyance tunnel, an array of monitoring instruments—including osmotic pressure meters, crack meters, and reinforcement meters—were installed. The structural configurations and instrument distributions across tunnel cross-sections are detailed in Table 1.




Fig. 5. The inner wall of the shaft is uneven (elevation 13.80 m).

Table 1. Layout list of monitoring instruments for water conveyance system

Cross-section	Structural Type	Instrument Type	Serial Numbers
Section A-A (Chainage 0+465.38 m)	Reinforced concrete lining	Crack meters (TWJ), Osmotic pressure meters (TWP), Reinforcement meters (TWR)	TWJ1-TWJ2, TWP1-TWP2, TWR1-TWR6
Section B-B (Chainage 0+581.68 m)	High-pressure steel pipe lining	Crack meters (TWJ), Osmotic pressure meters (TWP), Steel plate meters (TWS)	TWJ3-TWJ5, TWP3-TWP4, TWS11-TWS12
Section C-C (Chainage 0+583.13 m)	High-pressure steel pipe lining	Steel plate meters (TWS)	TWS13-TWS14
Section D-D (Chainage 0+598.38 m)	Steel bifurcation pipe	Crack meters (TWJ), Osmotic pressure meters (TWP), Four-directional steel plate meters (S)	TWJ6-TWJ9, TWP5-TWP6, S411-S414, S421 ~ S424

Analysis of operational monitoring data provides insights into structural behavioral variations. While structural responses typically correlate with reservoir water level fluctuations, the correlation coefficients between water levels and monitoring parameters (Table 2) demonstrated weak relationships ($r < 0.2$), indicating negligible direct influence.

Table 2. Analysis of relationship

Environmental Factor	Instrument	Correlation Coefficient	Conclusion
Upstream Reservoir Level	Crack meter TWJ1	0.047	No correlation
Upstream Reservoir Level	Osmotic pressure meter TWP1	0.201	No correlation
Upstream Reservoir Level	Reinforcement meter TWR2	−0.149	No correlation
Upstream Reservoir Level	Steel plate meter S413	0.08	No correlation
Ambient Temperature	Crack meter TWJ1	−0.715	Strong negative correlation
Ambient Temperature	Osmotic pressure meter TWP1	0.08	No correlation
Ambient Temperature	Reinforcement meter TWR6	0.39	Weak correlation
Ambient Temperature	Steel plate meter TWS11	0.82	Strong correlation

Unlike conventional reservoirs, pumped storage power stations often operate as daily-regulated reservoirs, where water levels undergo diurnal fluctuations. Current safety monitoring standards mandate daily data collection, which suffices for compliance but fails to capture meaningful correlations between water level changes and structural responses. However, annual-scale analysis revealed periodic correlations between temperature cycles and monitoring data. As shown in Table 2, crack meters, reinforcement meters, and steel plate meters embedded in the tunnel exhibited discernible temperature dependencies.

Analysis of safety monitoring data reveals that crack meter measurements exhibit a negative correlation with ambient temperature variations, while osmotic pressure demonstrates negligible temperature dependence. In contrast, reinforcement meters and steel plate meters within the tunnel display moderate to strong correlations with temperature fluctuations. Notably, the current project exclusively monitored ambient temperature, whereas structural parameters (e.g., lining stresses, joint displacements) are hypothesized to correlate more closely with water temperature. To enhance the fidelity of structural response assessments, it is recommended to integrate water temperature monitoring into the system, complementing existing ambient temperature observations (Figs. 6 and 7).




Fig. 6. Correlation between temperature and steel bar stress (TWR6)




Fig. 7. Correlation between temperature and steel plate strain (TWS11)

5 Conclusions

Water conveyance tunnels are critical components of pumped storage power stations and play a pivotal role in ensuring operational safety, necessitating heightened attention in safety evaluations. Currently, only the *Technical Specification for Safety Appraisal of Hydraulic Tunnels (SL/T 790-2020)* provides general requirements for tunnel safety appraisals, yet it lacks detailed operational guidelines for inspection practices. Based on the safety evaluation of a pumped storage power station, this study identifies key priorities for tunnel safety assessments. The following conclusions are drawn:

(1) Distinct operational conditions of pumped storage tunnels

The hydraulic gradients and pressure heads in pumped storage tunnels differ significantly from those in conventional water conveyance projects. These differences must be rigorously addressed in safety evaluations to account for unique structural and hydrodynamic challenges.

(2) Advancements in inspection methodologies

Routine inspections remain the most effective and intuitive approach to assess tunnel performance. The proposed use of autonomous collision-proof unmanned aerial vehicles (UAVs) enhances inspection efficiency and quality while minimizing safety risks for personnel. This methodology warrants broader adoption in analogous engineering projects.

(3) Temperature-driven structural feedback

Safety monitoring data reveal pronounced correlations between structural behavior and temperature variations (particularly water temperature). For pumped storage power stations, water temperature fluctuations—in addition to reservoir level changes—should be prioritized to refine structural response analyses.

Acknowledgement. This research was supported by National Natural Science Foundation of China (NSFC Grant No. U2443232).

References

1. Li, H.J., Xu, H., Zhao, J.M.: Seismic stability analysis of slopes for upper and lower reservoirs of Kokhav Hayarden pumped storage power station. *Water Resour. Hydropower Eng.* **04**, 27–32 (2018)
2. Cao, X., Liu, Q.M., Zhan, H., et al.: Vibration simulation and safety evaluation of underground powerhouse in Xianju pumped storage power station. *South North Water Transf. Water Sci. Technol.* **04**, 195–201 (2018)
3. Wang, S.J., Zhang, F., Zhao, Y.F., et al.: Analysis and countermeasures for vibration issues in pumped storage power station powerhouses. *J. Yangtze River Sci. Res. Inst.*, 1–11
4. Li, W., Han, H.Q., Wu, J.C., et al.: Filter design and seepage safety evaluation for asphalt-core gravel dams in Zhirui pumped storage power station. *Chin. J. Geotech. Eng.* **45**(02), 369–375 (2023)
5. Xin, M., Wang, R., Jia, T., et al.: Mechanical analysis and safety evaluation of tunnel linings under long-term erosion. *J. Water Resour. Archit. Eng.* **21**(02), 68–73 (2023)
6. Zhang, F., Jin, W., Liu, Q., et al.: Safety evaluation and countermeasures for pumped storage power station construction. *J. Wuhan Univ. Technol. (Inf. Manag. Eng.)* **46**(04), 547–550 (2024)
7. Sun, Y.S., Zhang, L.W., Zhang, G.C., et al.: Development status and key technologies of inspection robots for water conveyance tunnels. *J. Harbin Eng. Univ.*, 1–14
8. National Energy Administration Dam Safety Supervision Center. Guidelines for safety evaluation of hydropower dams: DL/T 5313-2014. China Electric Power Press, Beijing (2014)
9. Department of Construction and Management, Ministry of Water Resources. Guidelines for safety evaluation of reservoir dams: SL 258-2017. China Water & Power Press, Beijing (2018)

10. Department of Construction and Management, Ministry of Water Resources. Technical specification for safety appraisal of hydraulic tunnels: SL/T 790-2020. China Water & Power Press, Beijing (2020)
11. Tang, L., Xie, Y., Song, R.X., et al.: Detection and safety classification of lining concrete quality in hydraulic tunnels. *Water Resour. Hydropower Eng.* **04**, 203–209 (2018)
12. Tang, L., Li, H., Xie, Y., et al.: Detection and safety classification of lining cracks in hydraulic tunnels. *Water Resour. Hydropower Eng.* **03**, 135–141 (2018)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Fabrication and Electrochemical Performance of Cement-Based Structural Supercapacitors

Yumin Zhang¹(✉), Kewei Sun², Zhicheng Yu^{1,2}, Senlin Li¹, and Hao Yang²

¹ Nanjing Hydraulic Research Institute, Nanjing 210029, China
542413159@qq.com

² Nanjing Tech University, Nanjing 211816, China

Abstract. To solve the incompatibility issue between electrodes and separators in cement-based structural supercapacitors (CSSC), a CSSC was fabricated by utilizing integrated cementitious electrodes and separators. The electrochemical enhancement mechanism was systematically explored. The results indicated that the CSSC showed an electric double-layer capacitance-dominated behavior. Its mass-specific capacitance was measured at 38.6 F g^{-1} when the current density was 0.1 mA cm^{-2} , with power and energy densities of 9.77 W kg^{-1} and 10.26 Wh kg^{-1} , respectively. After 400 cycles at a current density of 0.2 mA cm^{-2} , a capacity retention rate of 96.65% and a Coulombic efficiency of 98.36% were maintained. The modified cement-based separator, which incorporated PAA/PVA, graphene oxide (GO), carbon nanotubes (CNTs), and H_2O_2 , presented a bimodal pore structure that synergistically matched the electrode porosity. This research advanced the development of building-integrated energy storage systems.

Keywords: Cement-based structural supercapacitor (CSSC) · Cementitious electrode · Cement-based separator · Mass-specific capacitance · Cycle stability · Pore architecture · Electrochemical properties

1 Introduction

The acceleration of the global energy transition was accompanied by renewable energy sources contributing over 38% to the total electricity generation. However, their intermittent nature caused severe supply-demand imbalances. For example, a solar curtailment rate of 34.8% was recorded in Tibet in November 2024. To address the energy waste resulting from the intermittency of renewable energy [1, 2], research efforts around the world were prioritized towards building-integrated energy storage systems, in which cement-based structural supercapacitors (CSSCs) were used as core components. In this technology, energy storage units were embedded into building elements. As a result, the spatial limitations inherent in conventional energy storage devices were overcome. At the same time, in-situ energy storage solutions were provided for building envelopes and load-bearing walls, and the functions of structural support and energy storage were integrated [3, 4].

Current research on CSSCs mainly focused on two aspects: cement-based electrodes and cement-based separators. Significant progress had been made in both components

[5, 6]. However, a notable lack of synergy and compatibility between them was observed [7].

For instance, cement-based separators fabricated by Zhang et al. [8–11] through the combination of alkaline activators, poly(ethylene oxide) (PEO), alkali metal salts, poly(vinyl alcohol) (PVA), poly(acrylic acid) (PAA), and ordinary Portland cement had been reported. These separators were characterized by simple fabrication processes, low-cost raw materials, excellent mechanical properties, and satisfactory conductivity. Nevertheless, the electrodes used in these CSSCs still relied on conventional high-cost materials, such as graphene oxide-coated nickel foam, graphene, and carbon fibers. Critical issues, including poor interfacial adhesion between electrodes and separators, challenges in scalability, and excessive manufacturing costs, were identified. In another approach, CSSC electrodes with integrated structural strength and energy storage capacity were developed by the MIT team [12] through the hydration-induced formation of fractal conductive networks from carbon black-cement-water mixtures. However, commercial separators with single-peak pore distributions were employed, which were found to be mismatched with the multiscale porosity of cement matrices. This mismatch was demonstrated to lead to high self-discharge rates, significant energy losses, and a substantial reduction in energy storage efficiency.

To address these limitations, an innovative integrated design of electrode-separator for CSSC was proposed in this study. Both components were constructed from cementitious materials. The feasibility and practicality of this integrated system as an energy storage device were systematically investigated through comprehensive performance evaluations.

2 Experimental Part

2.1 Materials

The materials used were as follows: Ordinary Portland cement (P.O 42.5) produced by Zhucheng 97 Building Materials Co., Ltd., China; Sulphoaluminate cement (SAC 72.5) produced by Zhucheng 97 Building Materials Co., Ltd., China; Carboxylated carbon nanotubes (CNTs-COOH) supplied by Suzhou Tanfeng Graphene Technology Co., Ltd., China; Graphene oxide dispersion (GO) provided by Suzhou Tanfeng Graphene Technology Co., Ltd., China; Ketjen Black EC600JD manufactured by Lion Corporation, Japan; Polyacrylic acid (PAA) from Yantai Jiudian Biotechnology Co., Ltd., China; Polyvinyl alcohol (PVA) purchased from Shanghai Macklin Biochemical Co., Ltd., China. The chemical compositions of Portland cement and SAC were listed in Tables 1 and 2, respectively.

2.2 Fabrication of Cement-Based Structural Supercapacitors

The fabrication process consisted of three stages: (1) preparation of the electrode/separator slurry, (2) molding and curing, (3) component integration. The preparation schematic diagram was shown in Fig. 1.

Table 1. Composition of Portland Cement (%)

CaO	SiO ₂	Al ₂ O ₃	Fe ₂ O ₃	MgO	Other	LOSS ^a
51.42	24.99	8.26	4.03	3.71	3.31	4.28

^aLOSS: The organic matter and moisture lost in heating the cement to a high temperature (about 950 °C to 1000 °C).

Table 2. Composition of sulfoaluminate cement (%)

Al ₂ O ₃	CaO	SiO ₂	Fe ₂ O ₃	TiO ₂	Other	LOSS ^a
51.16	31.75	7.88	2.18	1.87	0.98	4.18

^aLOSS: The organic matter and moisture lost in heating the cement to a high temperature (about 950 °C to 1000 °C).

2.2.1 Electrode Slurry Preparation

A three-step dispersion method was adopted.

First, 0.4 g of carboxylated CNTs, 0.6 g of polycarboxylate superplasticizer, 10 mL of GO dispersion, and deionized water were added to a beaker. The mixture was ultrasonicated for 5 min in an ice-water bath.

Second, 48 g of Ketjen Black was dispersed into the mixture using a high-shear emulsifier (20,000 rpm) for 4 min, followed by 20 min of ultrasonication in an ice bath to obtain a pre-dispersed wet slurry.

Third, 400 g of Portland cement and 20 mL of 1 mol L⁻¹ KOH solution were gradually blended into the wet slurry under mechanical stirring. The slurry was stirred at 62 ± 5 rpm for 60 s, then at 140 ± 5 rpm for 30 s. This cycle was repeated three times to obtain the final electrode slurry (Fig. 2a).

2.2.2 Separator Slurry Preparation

A gradient pore-regulation strategy was employed. 400 g of SAC was dry-mixed with 40 g of PAA and 4 g of PVA. Then, pre-dispersed GO solution, CNTs suspension, 10 mL of 0.01 mol L⁻¹ KOH, and 4 mL of H₂O₂ (90 wt%) were sequentially added while stirring continuously. The modified SAC slurry was obtained for subsequent molding.

2.2.3 Molding and Curing

The electrode and separator slurries were cast into PVC molds (200 × 150 × 1 mm) and cast iron molds (40 × 40 × 160 mm), respectively (Fig. 2b). The specimens were vibrated for 30 s, sealed and cured at 20 °C with a relative humidity of 95%, and demolded after 3 days. Electrode discs with a diameter of 23 mm were punched from the PVC-cured samples (Fig. 2c–d). All components were cured for 28 days, polished with 1000-grit sandpaper, vacuum-dried at 60 °C for 8 h, and soaked in 1 mol L⁻¹ KOH for 48 h.

2.2.4 Component Integration

A symmetric “sandwich” structure was assembled in a Swagelok cell in the following order: Stainless steel current collector/KOH-soaked carbon paper/cement electrode/cement separator/cement electrode/KOH-soaked carbon paper/stainless steel collector (Fig. 3). This configuration optimized the interfacial contact, electrolyte distribution, and scalability while minimizing the risk of short circuits.




Fig. 1. Schematic illustration of the preparation of CSSC.

2.2.5 Characterization Methods

Electrochemical tests, including cyclic voltammetry (CV), electrochemical impedance spectroscopy (EIS), and galvanostatic charge-discharge (GCD), were performed. Microstructural analysis was carried out using scanning electron microscopy (SEM) and mercury intrusion porosimetry. Physicochemical characterization was conducted by thermogravimetric analysis (TGA), X-ray diffraction (XRD), and Fourier-transform infrared spectroscopy (FTIR). Mechanical properties were evaluated through compressive and flexural strength tests. The compositions of the fabricated cement-based separators and control groups were summarized in Table 3.

3 Results and Discussion

3.1 Morphological Characteristics

The microstructures of pristine sulphoaluminate cement (SAC) separators and modified separators were compared using scanning electron microscopy (SEM). As depicted in Fig. 4a, a dense matrix with low porosity and a high concentration of submicron-scale




Fig. 2. Schematic diagram of CSSC molding (a) Schematic diagram of slurry (b) Schematic diagram of mechanical properties test block (c) Schematic diagram of cement electrode (d) Schematic diagram of cement separator

Table 3. Formed cementitious-based membranes and their benchmark groups

Sample	Cement (g)	GO (g)	CNTs (g)	PAA (g)	PVA (g)	KOH (mL)	H ₂ O ₂ (mL)	H ₂ O (g)
Separator	400	0.01	0.4	40	4	20	4	160
SAC	400	0	0	0	0	20	0	160
PAA/PVA	0	0	0	4	0.4	0	0	16




Fig. 3. CSSC schematic diagram

pores was formed in the 28-day-cured pristine SAC separator (Fig. 4c). Although this microstructure was shown to possess excellent mechanical properties, ion transport was found to be restricted. In contrast, the modified separator was observed to display a hierarchical pore structure, with 5 μm mesopores evenly distributed within the cement matrix (Fig. 4b) [13]. This architecture was confirmed to enhance the infiltration of the electrolyte and the efficiency of ion diffusion.

Furthermore, electrostatic interactions between the oxygen-containing functional groups on graphene oxide and Ca^{2+} were identified, which regulated the cement hydration kinetics [14–17]. These interactions were verified to induce the formation of well-aligned calcium aluminate hydrate crystals (Fig. 4d). Secondary nanopores (approximately 100 nm) were generated within the cement matrix, which interacted synergistically with the skeletal framework to establish efficient K^+ transport channels. These results indicated that the modified treatment had a significant impact on the internal pore structure of cementitious materials, providing crucial insights for optimizing the microstructural designs of building-integrated energy storage systems.




Fig. 4. SEM images (a) sulfoaluminate cement (b) cement-based separator (c) enlarged view of sulfoaluminate cement (d) enlarged view of cement-based separator

3.2 Electrochemical Performance Analysis

3.2.1 EIS Results

The electrochemical impedance spectroscopy (EIS) results of the CSSC are presented in Fig. 5. When compared with the baseline group, the CSSC fabricated with the modified cement-based separator was measured to have an internal resistance (R_s) of 2.19 Ω and a charge transfer resistance (R_{ct}) of 24.29 Ω . The decrease in R_{ct} was attributed to the chemical foaming effect of H_2O_2 during the preparation of the separator, combined with

the synergistic doping of graphene oxide, carbon nanotubes, and PAA/PVA. A three-dimensional interconnected nanoporous network was formed, effectively minimizing both R and R_{ct} . This structural modification strategy was demonstrated to overcome the high internal resistance limitations of conventional cement-based materials, offering critical technical support for building-integrated energy storage devices.




Fig. 5. EIS diagram of cement-based supercapacitor structure

3.2.2 CV and GCD Performance

Quasi-rectangular cyclic voltammetry (CV) curves without distinct redox peaks were observed for the CSSC (Fig. 6a), confirming that its energy storage was dominated by electric double-layer capacitance. Galvanostatic charge-discharge (GCD) tests at 0.1 mA cm^{-2} were conducted, and a specific capacitance of 38.6 F g^{-1} was obtained (Fig. 6b–c). A Ragone plot (Fig. 6d) revealed energy and power densities of 10.26 Wh kg^{-1} and 9.77 W kg^{-1} , respectively. The enhanced electrochemical performance was ascribed to two factors: the synergistic effects between the bimodal pore structure of the separator and PAA/CNTs; and the improved electrolyte infiltration by micrometer-scale pores and the shortened ion diffusion paths by submicron pores in the $\text{GO}/\text{H}_2\text{O}_2$ -modified cement matrix. These findings validated that precise regulation of the pore structure could achieve high specific capacitance, energy density, and power output, providing experimental guidelines for the design of integrated energy-structural devices [18–20].

3.2.3 Long-Term Cycling Stability

Long-term cycling tests using GCD were carried out (Fig. 7). After 400 cycles at 0.2 mA cm^{-2} , a capacity retention rate of 96.65% (initial: 9.82 mAh g^{-1} ; final: 9.52 mAh g^{-1}) and a Coulombic efficiency of 98.36% were maintained. This stability was attributed to the fractal pore architecture of the cement-based separator. The multiscale




Fig. 6. Electrochemical test curves of (a) CV curves of CSSC, (b) GCD, (c) Rate curves of CSSC, (d) Ragone Plot of CSSC

interconnected pores (micro/mesopores) matched the pore sizes of the electrodes, stabilizing the ion transport channels. The fractal structures optimized the wettability of the electrolyte and reduced the interfacial impedance. The dynamic adaptation of the pore network during cycling mitigated structural collapse and capacity decay. Additionally, the low internal resistance and high Coulombic efficiency further confirmed the significant positive impact of the modified treatment on the performance of the CSSC.




Fig. 7. Long-term cyclic chart of CSSC

3.3 Mechanical Performance Analysis

The compressive and flexural strengths of the 28-day-cured cement-based separator were measured at 12.7 MPa and 4.6 MPa, respectively. Despite its excellent electrochemical performance, mechanical deficiencies were identified. The reduction in strength was attributed to the following factors. First, micro/nanoscale pores were introduced by the physical foaming of H_2O_2 . While this enhanced the electrolyte permeability, it compromised the compactness of the matrix. Second, PAA was adsorbed onto cement particles, which hindered the hydration reactions and formed pore-blocking layers, reducing ion mobility and inducing stress concentration [21]. Third, poor compatibility between PVA and the cement hydration products was observed, resulting in weak interfacial bonding [22]. Residual organic additives (PAA/PVA) occupied the matrix space, further decreasing the density. The increased internal porosity and degraded mechanical properties were confirmed through microstructural and mechanical analyses. This study provided crucial insights for the subsequent improvement of CSSCs by optimizing the balance between structure and electrochemistry.

3.4 XRD, Thermogravimetric, and FTIR Analysis

The XRD patterns of the cement-based separator and reference groups (pure calcium sulfoaluminate cement and pure PAA/PVA gels) are shown in Fig. 8a. As can be seen in Fig. 8a, characteristic C_2S peaks at 32.2° and 39.3° were detected in both the cement-based separator and pure calcium sulfoaluminate cement, indicating that the modification process did not alter the main crystalline phases of the cement. The disappearance of the typical diffraction peaks of PAA (31.6° , 41.3°) and PVA (22.5° , 23.5°) in the cement-based separator was attributed to two reasons. Firstly, due to the low dosages of PAA (10 wt%) and PVA (1 wt%), their weak crystallinity signals were masked by the dominant cement peaks. Secondly, the formation of an organic-inorganic hybrid interface through physical crosslinking between the polymers and the cement matrix led to conformational changes in the molecular chains, resulting in a reduction in diffraction intensity. This phenomenon was consistent with the “matrix shielding effect” and “amorphous phase dilution effect,” confirming that the polymers were molecularly dispersed within the cement matrix without forming independent crystalline structures.

The DTG curves of the cement-based separator and reference groups are presented in Fig. 8b. For pure calcium sulfoaluminate cement, the mass losses at $200\text{--}290^\circ\text{C}$ and $610\text{--}660^\circ\text{C}$ were attributed to gypsum dehydration/ettringite decomposition and sulfate decomposition, respectively. In PAA/PVA gels, the mass losses at $290\text{--}350^\circ\text{C}$ and $420\text{--}440^\circ\text{C}$ were caused by the decarboxylation of carboxyl groups/mainchain scission and residual carbon decomposition. The thermal behavior of the cement-based separator showed two characteristics. First, the removal of adsorbed water at $90\text{--}130^\circ\text{C}$ indicated that the dehydration of polymer-bound water was incomplete after drying. Second, the sulfate decomposition at $610\text{--}660^\circ\text{C}$ followed the same trend as that of pure cement but with a lower residue, suggesting partial complexation of organic substances with Ca^{2+} during carbonation.

The FTIR spectra of the cement-based separator and reference groups are displayed in Fig. 8c. The broad peak at 3440 cm^{-1} (O–H hydrogen bonding) and the sharp peak

at 1135 cm^{-1} (SO_4^{2-} antisymmetric stretching) in calcium sulfoaluminate cement confirmed calcium hydroxide and ettringite as the hydration products. After the incorporation of PVA/PAA: (1) the O–H stretching vibration of PVA shifted from $3400\text{--}3600\text{ cm}^{-1}$ to 3462 cm^{-1} due to hydrogen bonding between the PVA hydroxyl groups and the PAA carboxyl groups ($-\text{COOH}$), forming an interpenetrating network; (2) the intensity of the PAA carboxyl peak at 1030 cm^{-1} decreased, indicating that Ca^{2+} formed complexes with the hydration products, restricting the vibrations of the carboxyl groups. The organic characteristic peaks (e.g., 1420 cm^{-1} for C–H bending and 530 cm^{-1} for C–H out-of-plane vibrations) further verified the presence of polymer chains. Notably, no new chemical bonds were detected, and the main cement peaks (3440 cm^{-1} , 1135 cm^{-1}) remained unchanged, confirming that PAA/PVA did not disrupt the crystallinity of the cement.

The integrated analysis revealed that PAA/PVA, graphene oxide (GO), and carbon nanotubes (CNTs) did not affect the crystalline structure of the cement. As amorphous polymers, PAA and PVA mainly interacted with the cement hydrates through physical adsorption and hydrogen bonding. The carboxyl groups of PAA formed complexes with Ca^{2+} , and the PVA hydroxyl groups bonded with the C–S–H gels through hydrogen bonds. Neither of them participated in the solid-phase reactions of calcium sulfoaluminate cement, thus avoiding the formation of new crystalline phases.




Fig. 8. Curves of cement-based separator, sulfoaluminate cement and PAA/PVA gel: (a) XRD patterns, b) TGA, (c) IF curves.

3.5 Pore Structure Analysis

The pore size distributions of the cement-based separator and the reference calcium sulfoaluminate cement were compared in Figs. 9a and 9b. The cement-based separator exhibited a distinct gradient pore structure: 54.4% of the pores were $1\text{--}10\text{ }\mu\text{m}$ (compared with 14.25% in the reference), 14.8% were larger than $10\text{ }\mu\text{m}$ (compared with 2.5%), and 30.8% were smaller than $1\text{ }\mu\text{m}$ (compared with 83.3%). This structure was attributed to the synergistic effects of the composite additives. First, polyacrylic acid (PAA) dispersed the cement particles through electrostatic repulsion, preventing the dense stacking of hydrates and enlarging the pores. Second, polyvinyl alcohol (PVA) and GO regulated the orientation of the C–S–H gel and the evolution of the pores [23, 24]. Notably, the O_2 bubbles generated from the decomposition of H_2O_2 served as physical templates,

creating micron-sized pores (more than 69.2%) during the plastic stage, which directly increased the proportion of macropores.




Fig. 9. Results of the mercury intrusion test (a) Pore size distribution (b) Distribution of harmful and harmless pores

4 Conclusions and Recommendations

- (1) The fabricated cement-based supercapacitor (CSSC) exhibited excellent electrochemical performance dominated by electric double-layer capacitance.
- (2) Microstructural characterization confirmed a unique hierarchical pore structure in the cement-based separator, differing significantly from conventional calcium sulfoaluminate cement. While this structure enhanced electrochemical performance, it compromised mechanical properties (e.g., compressive/flexural strength), highlighting the need for further structure-function synergy optimization.
- (3) At 0.1 mA cm^{-2} , the CSSC achieved a specific capacitance of 38.6 F g^{-1} , energy density of 10.26 Wh kg^{-1} , and power density of 9.77 W kg^{-1} . After 400 charge-discharge cycles at 0.2 mA cm^{-2} , capacity retention reached 96.65% with a stable Coulombic efficiency of 98.36%. The enhanced performance was ascribed to the bimodal pore structure and component synergy in the cement-based separator.

References

1. Adetokun, B.B., Muriithi, C.M.: Impact of integrating large-scale DFIG-based wind energy conversion system on the voltage stability of weak national grids: a case study of the Nigerian power grid. *Energy Rep.* **7**, 654 (2021)
2. Chanut, N., Stefaniuk, D., Weaver, J.C., et al.: Carbon-cement supercapacitors as a scalable bulk energy storage solution. *Proc. Natl. Acad. Sci. U. S. A.* **120**, e2304318120 (2023)
3. Zhang, D., Fang, C.: Portland cement electrolyte for structural supercapacitor in building application. *Constr. Build. Mater.* **285**, 122897 (2021)
4. Deng, Q., Chuan, X., Zhao, Y., et al.: Development of composite separators by coating hydrochloric acid-treated halloysite nanotubes on polypropylene separators for lithium-ion batteries. *RSC Adv.* **14**, 16912 (2024)

5. Fan, J., Li, G., Deng, S., et al.: Mechanical properties and microstructure of polyvinyl alcohol (PVA) modified cement mortar. *Appl. Sci.* **9**, 2178 (2019)
6. Fan, Y., Ni, Z., Mu, S., et al.: Hybrid micromechanical modelling and experiments on electrical conductivity of graphene reinforced porous and saturated cement composites. *Cem. Concr. Composites* **141**, 105148 (2023)
7. Fang, C., Zhang, D.: High areal energy density structural supercapacitor assembled with polymer cement electrolyte. *Chem. Eng. J.* **426**, 130793 (2021)
8. Fang, C., Zhang, D.: High multifunctional performance structural supercapacitor with Polyethylene oxide cement electrolyte and reduced graphene oxide@CuCo₂O₄ nanowires. *Electrochimica Acta* **401**, 139491 (2022)
9. Greenhalgh, E.S., Nguyen, S., Valkova, M., et al.: A critical review of structural supercapacitors and outlook on future research challenges. *Compos. Sci. Technol.* **235**, 109968 (2023)
10. Holecchek, J.L., Geli, H.M.E., Sawalhah, M.N., et al.: A global assessment: can renewable energy replace fossil fuels by 2050? *Sustainability* **14**, 4792 (2022)
11. Kumar, S., Bora, P., Roy, K., et al.: Scalable one-pot synthesis of aminated reduced graphene oxide for high-performance supercapacitor electrodes. *iScience* **28**, 112271 (2025)
12. Li, X., Liu, Y.M., Li, W.G., et al.: Effects of graphene oxide agglomerates on workability, hydration, microstructure and compressive strength of cement paste. *Constr. Build. Mater.* **145**, 402 (2017)
13. Liu, C., Huang, X., Wu, Y.-Y., et al.: Review on the research progress of cement-based and geopolymer materials modified by graphene and graphene oxide. *Nanotechnol. Rev.* **9**, 155 (2020)
14. Sun, T., Lyu, S.H., Liu, J.J., et al.: Toughening effect and mechanism of graphene oxide nanosheets on cement matrix composites **31**, 644 (2014)
15. Ma, B., Peng, Y., Tan, H., et al.: Effect of polyacrylic acid on rheology of cement paste plasticized by polycarboxylate superplasticizer. *Materials* **11**, 1081 (2018)
16. Qi, G., Wu, J., Yao, B., et al.: High modulus carbon fiber based composite structural supercapacitors towards reducing internal resistance and improving multifunctional performance. *Compos. Sci. Technol.* **254**, 110670 (2024)
17. Qiao, D., Huang, Y., Hou, X., et al.: Enhancing thermal stability and mechanical resilience in gelatin/starch composites through polyvinyl alcohol integration. *Carbohydr. Polym.* **344**, 122528 (2024)
18. Senokos, E., Anthony, D.B., Rubio, N., et al.: Robust single-walled carbon nanotube-infiltrated carbon fiber electrodes for structural supercapacitors: from reductive dissolution to high performance devices. *Adv. Funct. Mater.* **33**, 2212697 (2023)
19. Shankar, A.N., Mandal, P.: Mechanical and smart properties of cement nanocomposites containing nanomaterials: a brief review. *Open Eng.* **14**, 20240043 (2024)
20. Tian, G., Yang, D., Liang, C., et al.: A nonswelling hydrogel with regenerable high wet tissue adhesion for bioelectronics. *Adv. Mater.* **35**, 2212302 (2023)
21. Xu, J., Zhang, D.: Multifunctional structural supercapacitor based on graphene and geopolymer. *Electrochimica Acta* **224**, 105 (2017)
22. Yin, J., Qian, X., Hu, C., et al.: Insight into the interaction mechanism of polycarboxylate superplasticizer and polyacrylamide in cementitious materials. *Constr. Build. Mater.* **428**, 136330 (2024)
23. Yousaf, A., Khan, S.A., Koç, M.: Exploring the potential of construction-compatible materials in structural supercapacitors for energy storage in the built environment. *Cem. Concr. Compos.* **155**, 105809 (2025)
24. Zschiebsch, W., Sturm, Y., Kucher, M., et al.: Multifunctionality analysis of structural supercapacitors—a review. *Materials* **17**, 739 (2024)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Research on the Design for the Upgrading and Heightening of the Lower Reservoir Dam at the Fengning Pumped Storage Power Station

Jiachun Wang^(✉)

Institute of Hydropower and Pumped Storage Engineering, Beijing Engineering Corporation Limited, Power China, Beijing 100024, China
wangjiac@bjy.powerchina.cn

Abstract. The lower reservoir of the Fengning Pumped Storage Power Station was upgraded based on the original reservoir of the Fengning Hydropower Station. Following upgrading and heightening, significant upgrades were made to the operational level, flood criteria, grade of hydraulic structure, as well as the seismic precautionary criterion of the reservoir, surpassing the parameters of the original design. The dam adopts a upgrading and heightening plan of filling with stone materials downstream of the original dam. This study explores the adaptability of the original dam body and its seepage control system to the dam's upgrading and heightening, and also presents a comprehensive study of the design scheme for the dam's upgrading and heightening. The findings offer a reference framework for the reconstruction and upgrading of similar pumped storage facilities.

Keywords: Pumped Storage Power Station · Concrete Face Rockfill Dam · Upgrading and Heightening

1 Introduction

With the transformation of China's energy structure towards cleanliness and low carbonization, pumped storage power stations have become increasingly important as key infrastructure for peak regulation and energy storage. To meet growing energy demands and enhance reservoir functionality, the upgrading and heightening of existing dams offer an effective solution to increase storage capacity and improve the functions. However, these upgrades introduce technical challenges, particularly in adapting legacy structures to new performance criteria, and improving the flood criteria and the seismic precautionary criterion.

In China, there are numerous cases involving the reinforcement of aging reservoirs, such as the reinforcement and renovation of the Miyun Reservoir Dam in Beijing [1], the post-earthquake restoration of the Zipingpu Reservoir Dam [2], and the seepage treatment of the Xin'anjiang Dam [3]. These projects primarily focus on structural strengthening to address long-term operational issues. However, there are relatively few reconstruction projects aimed at upgrading reservoir and structural standards. A notable

exception is the successful case of the heightening and modification of the Danjiangkou concrete gravity dam [4]. In contrast, there is limited experience in heightening and reconstructing earth-rock dams built on deep overburden layers, particularly regarding critical issues such as the adaptability of the anti-seepage system under raised water levels and the compatibility between new and existing structures. Systematic analysis on these key aspects remains lacking.

The lower reservoir of the Fengning Pumped Storage Power Station was upgraded from the original Fengning Hydropower Station reservoir. The upgrading and heightening involved increasing both the water level and storage capacity. The rank of reservoir was upgraded from Grade III to Grade I, with improving the flood criteria and the seismic precautionary criterion. Although the original dam had demonstrated stable performance, the increased water head and changing load conditions necessitated improvements in the seepage control system and overall dam stability. Based on the Fengning project case, this study evaluates the adaptability of the original dam and its seepage control system after upgrading, proposes a downstream fill-based upgrading scheme, and verifies safety through stability and seismic analyses. The goal is to provide both theoretical guidance and practical references for the upgrading and heightening of aging reservoir.

2 Layout and Operation of the Original Dam

The original reservoir of the Fengning project was classified as a Rank III project [5]. The headworks included a dam, a surface spillway on the right bank, and a spillway tunnel. The dam, spillway, and spillway tunnel were all designated as Grade III structure. The reservoir's normal pool level was 1050 m, the dead storage level was 1040 m, and the check flood level was 1054.18 m, with a gross reservoir capacity of 71.99 million cubic meters.

Constructed in 2000, the dam is a concrete faced sand and gravel rockfill dam. Its foundation consists of riverbed sand and gravel with a maximum thickness of 22 m. The crest elevation is 1054.5 m, the crest width is 8 m and the maximum height of dam is 39.8 m. The upstream and downstream slopes are both set at a ratio of 1:1.6, and the total length of the crest is 272 m. From upstream to downstream, the dam body comprises face slab, cushion zone, transition and drainage zone, sand and gravel fill zone, downstream slope protection, and dam toe drainage prisms. The cushion zone and drainage zone are 3 m and 2.5 m wide, respectively. The foundation includes a drainage zone integrated with the transition and drainage zone behind the dam face, with a thickness of 2–3 m.

The concrete face panel is 30 cm thick. At the riverbed section, the panel's compression zone has 16 m wide joints, while the tension zone panels on either side have joint widths of 8–8.5 m. The panel is designed using C25W8F300-grade concrete and reinforced with single-layer, bidirectional steel bars, with a reinforcement ratio of 0.45% in both directions. Plinth are located on both sides of the slope, set on strongly weathered bedrock. These are 50 cm thick, flat-type plinth with widths ranging from 3 to 4 m. The plinth in the riverbed section lies on a sand and gravel layer and connects to the concrete cutoff wall with an upstream connection slab. Both the plinth and connection slab are 50 cm thick and 3 m wide. Perimeter joints are arranged between the face slab and plinth, and between the connection slab and the concrete cutoff wall. The waterproofing system

includes bottom copper water stops and surface flexible fillers. The surface filling areas of the perimeter, vertical tensile, and compressive joints are 75.1 cm^2 , 58.1 cm^2 , and 18 cm^2 , respectively. These surfaces are protected using chloroprene rubber sheets and galvanized iron plates. The dam foundation features curtain grouting and concrete cutoff wall. The concrete cutoff wall is 80 cm thick and reaches a maximum depth of 20.8 m, with its base embedded 1–2 m into the bedrock. The curtain extends 3–5 m below the permeable bedrock, with a maximum depth of 23 m. A typical cross-sectional view is shown in Fig. 1.




Fig. 1. A typical cross-sectional view of the original reservoir of the Fengning Hydropower Station

The dam was commissioned for water storage in November 2000. Operational monitoring data indicates that settlement has stabilized and the dam continues to perform reliably. During winter operation, the top cover plate of the face slab in the water level fluctuation zone experienced local damage due to freeze-thaw effects. Issues included dislodged anchor bolts, bent angle steel, and partial detachment. After adopting a countersunk bolt fixation system in 2008, the surface waterstop protective cover plate was successfully repaired and has since shown no signs of freeze-related damage.

3 Design for the Upgrading and Heightening of the Dam

3.1 Structure Design Standards

The Fengning Pumped Storage Power Station has a total installed capacity of 3600 MW and is classified as a large-scale (Rank I) project. Accordingly, the classification of its lower reservoir has been upgraded from Grade III to Grade I following upgrading. As part of this upgrade, the dam's structural classification has also been elevated from Grade III to Grade I. The flood criteria have been significantly enhanced, which has been upgraded from a 100-year return period to a 200-year return period, and the check flood standard has been improved from a 1,000-year to a 2,000-year return period. The corresponding peak flood discharges are $669 \text{ m}^3/\text{s}$ and $1,200 \text{ m}^3/\text{s}$, respectively.

In terms of seismic design, the site's bedrock peak ground acceleration, with a 10% probability of exceedance over a 50-year reference period, is 0.045 g. The characteristic period of the seismic response spectrum is 0.45 s, and the basic seismic intensity is equivalent to Grade VI. According to design specifications, the dam is classified under Seismic Fortification Category A. The design earthquake adopts a reference period of 100 years with a 2% probability of exceedance, corresponding to a peak ground acceleration of 0.125 g. For seismic safety verification, a more stringent scenario of a 100-year reference period with a 1% exceedance probability is used, corresponding to a peak ground acceleration of 0.158 g. The seismic precautionary criterion have been significantly increased compared to the original design.

3.2 Adaptability of the Original Dam and Its Seepage Control System After Upgrading

Following the upgrading and heightening, the normal pool level of the reservoir was raised from 1050 m to 1061 m, and the maximum (check flood) level increased from 1054.18 m to 1063.67 m. With the bottom elevation of the face slab at 1016 m, the maximum water head acting on the slab has risen from 38.18 m to 47.67 m. The hydraulic gradient through the 30 cm thick face slab has correspondingly increased from 127.3 to 158.9. This value remains within the specification limit of 200 for panel hydraulic gradients, indicating that the panel design is still compliant under the elevated conditions.

The concrete cutoff wall, 80 cm thick, has seen an increase in hydraulic gradient from 47.7 to 59.6 following the water level rise. This remains within the acceptable range of 80–100, suggesting that the wall retains adequate seepage control capacity after upgrading.

The plinth width is 4 m in sections below elevation 1032.38 m on the right bank and 1039.46 m on the left bank, and 3 m in all other sections. The maximum hydraulic gradient along the bedrock surface beneath the plinth has increased from 9.5 to 11.7. This slightly exceeds the typical allowable range of 5–10 for highly weathered rock mass, according to prevailing technical specifications. As a mitigation measure, three rows of consolidation grouting have been added along the plinth, complemented by curtain grouting reinforcement to enhance seepage resistance and stability.

The material stability and the static analysis parameters used in the finite element model are summarized in Table 1. Stability calculations were performed using the modified Bishop method, accounting for inter-block forces. Results are presented in Table 2. Static deformation and stress analysis was conducted using the Nanshui Double-Yield-Surface Elastoplastic Model Methodology, with the outcomes shown in Table 3. The analysis confirms that, after upgrading and heightening, the dam slope stability satisfies all safety requirements for Grade I structures. The finite element results indicate a maximum dam settlement of 37.9 cm, equivalent to approximately 0.74% of the dam height, which falls within acceptable deformation limits for concrete face rockfill dams. The face slab stress and deformation also remain within permissible design ranges, affirming the reliability of the structure under the new load conditions.

The finite element dynamic calculation parameters for the materials in each area of the dam body are presented in Table 4. The seismic fortification category of the dam project is classified as Class A, and the time history analysis method is used to

Table 1. Stability and Stress-Deformation Calculation Parameters for the Dam

Material name	$\rho(\text{g/cm}^3)$	$c(\text{kPa})$	$\varphi_0(^{\circ})$	$\Delta\varphi(^{\circ})$	K	n	R_f	K_{ur}	D	F	G
Mortar protective layer	2.05	0	40	2	600	0.50	0.79	1200	6.29	0.14	0.37
Cushion zone	2.15	0	47	4.1	760	0.55	0.80	1520	5.60	0.17	0.35
Drainage zone	2.07	0	47	4	750	0.55	0.80	1500	5.25	0.19	0.36
Sand and gravel material filling	2.14	0	46.2	4.1	750	0.55	0.83	1500	5.15	0.18	0.36
Rockfill material filling	2.16	0	54.7	11.2	1100	0.25	0.72	2200	5.88	0.19	0.35
Sand and gravel cover layer	2.29	0	49	7.2	820	0.69	0.75	1640	5.61	0.15	0.37
Mud skin unit	1.76	3	10.0	0.0	50	0.45	0.70	100	5.50	0.08	0.39
Sedimentation unit	2.26	6	36	0.0	400	0.50	0.75	800	5.32	0.16	0.36

assess seismic effects within the dynamic analysis approach. The calculation results, shown in Table 5, indicate that under seismic dynamic conditions corresponding to a 2% probability of exceedance in 100 years, the maximum response accelerations along the river and vertically are 3.15 m/s^2 and 1.89 m/s^2 , respectively. Compared to the peak acceleration of the input bedrock, the amplification factors are 2.57 and 2.31, respectively. The maximum permanent deformation of the dam body is 7.4 cm, and the maximum horizontal displacement along the river is approximately 6.7 cm. The maximum principal stress in the anti-seepage wall is 4.5 MPa, while the minimum principal stress is -0.77 MPa . Within the allowable limits for concrete, the concrete cutoff wall will not experience tensile or compressive failure during seismic events. The maximum deflection after the earthquake is 29.3 cm, with tensile and compressive stresses along the slope of -0.26 MPa and 7.29 MPa , respectively. These tensile and compressive stresses remain within the allowable range for concrete, ensuring that the face slab will not be damaged during the earthquake. When considering a 1% probability of exceedance in 100 years, the maximum response acceleration, permanent deformation, and face slab tensile/compressive stresses show only slight increases compared to the 2% probability scenario, but all values remain within the permissible limits.

Since the dam was commissioned for water storage in November 2000, both the dam and face slab have functioned effectively. Based on the adaptability analysis and evaluation outlined above, it can be concluded that with an 11-meter increase in the reservoir water level and the subsequent upgrading and heightening of the dam, the

Table 2. Dam Stability Calculation Results

Dam slope	Calculate operating conditions		Minimum safety factor	Safety factor required by regulations
Upstream slope	Extremely operating condition I	Built without water	1.860	≥ 1.30
	Extremely operating condition II	Dead storage level+200 year probability of exceeding 2% earthquake	1.673	≥ 1.20
		Dead storage level+100 year probability of exceeding 1% earthquake	1.602	
Downstream slope	Normal operating conditions	Normal pool level	2.327	≥ 1.50
	Extremely operating condition I	Built without water	2.308	≥ 1.30
	Extremely operating condition II	Normal pool level+200 year exceedance probability 2% earthquake	2.110	≥ 1.20
		Normal pool level+1% probability of exceedance in 100 years earthquake	2.034	

original dam structure and concrete cutoff wall will adequately meet the current design requirements.

3.3 Layout of the Dam Upgrading and Heightening Plan

Following the upgrading, the normal pool level of the lower reservoir has been raised to 1061 m, necessitating upgrading and heightening of the original dam and spillway structures. The dam adopts an upgrading and heightening plan of filling with stone materials downstream of the original dam. For the spillway on the right dam shoulder,

Table 3. Plane Finite Element Static Calculation Results for the Dam

Part	Project	Direction		Completion period	Storage period
Dam	Deformation (cm)	Along the river	Upstream	11.4	4.1
			downstream	11.2	14.5
		Vertical direction	Settlement within the dam	37.2	37.9
	Stress (MPa)	Major principal stress		1.22	1.29
		Minor principal stress		0.41	0.43
Cutoff Wall	Deformation (cm)	Along the river	Upstream	2.13	/
			downstream	/	7.2
	Stress (MPa)	Major principal stress		1.29	3.18
		Minor principal stress		−0.35	−0.59
Connection slab, plinth	Deformation (cm)	Along the river	Upstream	1.47	/
			downstream	/	8.01
		Vertical direction	Settlement within the dam	0.69	6.66
	Stress (MPa)	Major principal stress		3.76	6.86
		Minor principal stress		−0.19	−0.19
Concrete face slab	Deformation (cm)	Deflection		\	\
	Stress (MPa)	Along the slope		2.56	5.72
Perimeter joint	Deformation (mm)	Dislocation		0.79	2.54
		Open		/	/

Table 4. Material dynamic calculation parameters for each section of the dam

Material name	k_2	$\lambda_{\max}$	k_1	n	c_1 (%)	c_2	c_3	c_4 (%)	c_5
Mortar protective layer	1300	0.23	20.0	0.50	0.75	0.80	0	8.0	0.95
Cushion zone	1546	0.21	18.0	0.48	0.73	0.80	0	7.2	0.93
Drainage zone	1520	0.21	18.2	0.48	0.74	0.82	0	7.3	0.92
Sand and gravel material filling	1500	0.21	18.5	0.45	0.70	0.75	0	7.0	0.90
Rockfill material filling	2300	0.21	20.5	0.30	0.70	0.95	0	6.8	0.9
Gravel and pebble cover layer	1700	0.21	17.0	0.46	0.70	0.78	0	7.0	0.95

Table 5. Results of Finite Element Dynamic Calculation of Dam Plane

Calculate operating conditions			Normal pool level+200 year exceedance probability 2% earthquake	Normal pool level+1% probability of exceedance in 100 years earthquake	Dead storage level+200 year probability of exceeding 2% earthquake	Dead storage level+100 year probability of exceeding 1% earthquake
Dam acceleration (m/s^2)	Along the river		3.15	3.81	3.34	4.04
	Vertical		1.89	2.26	1.99	2.41
Magnification	Along the river		2.57	2.46	2.72	2.61
	Vertical		2.31	2.19	2.44	2.33
Dynamic displacement of dam (cm)	Along the river		7.1	8.2	\	\
	Vertical		2.3	2.8	\	\
Permanent deformation of dam (cm)	Along the river (pointing downstream)		6.7	7.1	6.4	6.8
	Vertical (seismic subsidence)		7.4	8.2	7.0	7.9
Cutoff Wall	Deformation (cm)	Downstream	2.77	2.79	2.72	2.73
	Stress (MPa)	Major principal stress	4.5	4.58	2.56	2.60
		Minor principal stress	-0.77	-0.79	-0.46	-0.47
Plinth	Deformation (cm)	Downstream	10.73	10.75	\	\
		Vertical	7.45	7.46	\	\
	Stress (MPa)	Major principal stress	8.58	8.87	\	\
		Minor principal stress	-0.89	-0.9	\	\
Face slab	Deflection (cm)		9.7	10.2	9.4	10.0

(continued)

the upgrading involves raising and thickening the left sidewall to act as an embankment block. A new overflow weir will be constructed along the new dam axis, and the spillway will be widened to the left. On its left flank, the spillway will connect the concrete gravity section with the adjacent hillside.

The crest elevation of the upgrading dam is 1066 m. The slope of the upstream concrete face slab remains unchanged at 1:1.6 and is extended up to the new crest elevation. The axis of the raised dam shifts 18.4 m downstream from the original axis.

Table 5. (continued)

Calculate operating conditions			Normal pool level+200 year exceedance probability 2% earthquake	Normal pool level+1% probability of exceedance in 100 years earthquake	Dead storage level+200 year probability of exceeding 2% earthquake	Dead storage level+100 year probability of exceeding 1% earthquake
	Longitudinal stress along the slope (MPa)	Compressive stress	7.29	7.51	5.27	5.40
		Tensile stress	−0.26	−0.48	−0.19	−0.40

The new dam crest width is 9.2 m, and the downstream slope remains at a ratio of 1:1.6. The typical elevation of the dam body is shown in Fig. 2.




Fig. 2. Typical cross-sectional view of upgrading and heightening dam

The upgrading and heightening plan preserves the original dam, including the upstream concrete face slab and plinth, while removing only the crest structure above the bottom joint of the wave wall and the downstream slope protection. The backfill zone behind the existing dam is filled with granite debris obtained from excavation works at the underground powerhouse and the lower reservoir inlet/outlet. To ensure effective integration between the new and existing structures, a 3 m wide transitional filter layer is installed between the original sand-gravel fill and the newly added embankment material. The new concrete face slab is 30 cm thick, made of C30W12F400-grade concrete, and reinforced with double-layer bidirectional steel bars at a 0.4% reinforcement ratio in both directions. A horizontal construction joint connects the new face slab to the original face slab. The wave wall at the original dam crest is removed, while the copper water stop embedded in the bottom joint of the original face slab is retained and welded to

the new face slab's water stop. The surface water stops of the old and new face slabs are overlapped to form a continuous seepage control system. On the left bank, a new plinth is constructed with a thickness of 50 cm and a width of 4 m. The original copper water stop at the perimeter joint is exposed and welded to a new copper water stop. The interface between the new and old plinth is treated as a construction joint, with an additional swelling water stop strip embedded for enhanced sealing. The concrete grade for the plinth matches that of the face slab. New vertical joints are aligned with those of the original face slab, and both peripheral and vertical joints are equipped with dual-layer copper water stops and top-layer flexible filler. The top surface of the filler is sealed with a 4 mm Hand-Troweled polyurea protective layer to prevent damage from winter icing.

Beneath the new face slab, a drainage cushion zone and transition zone are installed with horizontal widths of 3 m and 4 m, respectively, and are connected to the existing drainage system behind the original face slab. The cushion material consists of graded crushed stone processed from slightly weathered or fresh rock. It has a maximum particle size of 80 mm, with 20–35% of particles smaller than 5 mm and less than 5% below 0.1 mm. The material must have a non-uniformity coefficient greater than 15 and a permeability coefficient greater than 1×10^{-2} cm/s. After compaction, the porosity must not exceed 18%, and the dry density must be at least 2.23 g/cm^3 .

The transition material uses continuously graded rockfill with a maximum particle size of 300 mm. Particles under 5 mm must not exceed 20%, and those under 0.1 mm must remain below 5%. The non-uniformity coefficient should exceed 12. Post-compaction porosity must not exceed 20%, with a minimum dry density of 2.17 g/cm^3 and permeability above 1×10^{-2} cm/s.

The downstream rockfill, used for dam heightening, also follows continuous grading. The maximum particle size is 800 mm, with fines ($<5 \text{ mm}$) limited to 20% and ultra-fines ($<0.1 \text{ mm}$) to 5%. The non-uniformity coefficient should exceed 10. After compaction, porosity must remain below 22%, and the dry density should not be less than 2.10 g/cm^3 .

4 Conclusion

In recent years, China's hydropower industry has experienced rapid growth, with hydropower development accounting for more than half of total installed capacity. However, as the structural demands for water resources and energy continue to evolve—particularly under the “dual carbon goals” and the growing trend of pumped storage power station development—the upgrading and heightening of existing dams has emerged as a promising approach for revitalizing old reservoirs and generating new benefits. This paper presents an upgrading and heightening plan for the dam of the lower reservoir at the Fengning Pumped Storage Power Station. The proposed scheme involves filling with stone materials downstream of the original dam. The feasibility of this plan, along with the applied research methods, is systematically analyzed. The study also contributes practical engineering experience, offering valuable reference and guidance for similar future projects.

References

1. Huang, N.: Design and construction of reinforcement for the downstream slope of Nanshiluotuo auxiliary dam at Miyun reservoir. In: Proceedings of the Annual Conference of the China Electrotechnical Society (2014)
2. Jia, J., Wen, Y., Zhao, J.: Seismic damage repair and seismic safety evaluation technology of Zipingpu Dam. In: Proceedings of the International Symposium on Dam Technologies and Long-Term Performance (2011)
3. Zhao, X.: Leakage treatment and effect analysis of Xin'anjiang Dam body. *Dam Saf.* (02)
4. Wang, X., Zhou, J., Ban, J.: Characteristics and patterns of Danjiangkou Dam heightening project construction. *China Water Resour.* (02)
5. China Hydropower Engineering Consulting Group Co., Ltd. Hebei Fengning Project. Chinese Concrete Faced Rockfill Dam Atlas 5 Beijing: Water Resources and Hydropower Earth Rock Dam Engineering Information Network, p. 59 (2003)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Application of UAV Oblique Photography in Earthwork Data Collection of the Pumped Storage Power Station Construction

Yuan Lin(✉)

Pumped-Storage Technological and Economic Research Institute, State Grid Xinyuan Co., Ltd.,
Beijing 100053, China
yuanlin327@163.com

Abstract. With the expansion of the construction scale of pumped storage power stations, the importance of earthwork balance management has become increasingly prominent. Earthwork balance is not only related to the rational allocation and utilization of resources, but also directly affects the progress, cost, and surrounding environment of the project. Due to its advantages in the rapid collection of high-precision and large-scale terrain data, UAV oblique photography can generate detailed three-dimensional models, providing an efficient and flexible solution for earthwork data collection under complex terrain, improving the real-time and reliability of data significantly. This paper introduces the workflow of UAV oblique photography in collecting earthwork allocation volumes. By comparing the earthwork data obtained by UAV oblique photography with the data reported by the construction site of Shandong Weifang pumped storage power station, the applicability of UAV oblique photography in measuring earthwork data of pumped storage power stations is verified.

Keywords: Pumped storage power station · UAV oblique photography · earthwork data collection

1 Introduction

The volume of earthwork involved in the construction of pumped-storage power stations is large, and the role of earthwork balance in engineering construction is becoming increasingly critical. During the engineering construction stage, the main data collection methods include UAV oblique photography, remote sensing engineering measurement, engineering site data reporting, and intelligent management systems. Among them, UAV oblique photography has become an indispensable tool for earthwork data collection due to its flexibility, economy, and precision. UAV oblique photography is a technology that obtains multi-view images of the target area by installing camera equipments with multiple oblique angles on UAVs. It is widely used in earthwork data collection. Its core principle is to generate a high-precision three-dimensional model through the superposition and reconstruction of images from multiple angles to accurately reflect the details

of the terrain and landforms. In terms of technical characteristics, UAV oblique photography can cover a large area in a short time, obtain high-definition images, and generate high-precision point cloud data, digital elevation models (DEMs), and digital surface models (DSMs) through professional software processing.

2 Current Status of Application of UAV Oblique Photography in Earthwork Data Collection

Compared with traditional ground surveying or aerial photography technology, UAV oblique photography has significant advantages. First, it can be easily operated in complex and difficult-to-reach terrain conditions, avoiding the limitations of manual measurement. Second, it significantly improves data collection efficiency and reduces operation time and cost. In addition, the data is highly accurate, especially in earthwork projects, and can accurately calculate volume changes and evaluate terrain transformation effects, providing a reliable basis for engineering decision-making [1–4]. The research of Li T et al. [5] shows that the use of image matching point cloud technology can quickly generate high-precision three-dimensional models, which is particularly suitable for earthwork volume calculation and accurate measurement of complex terrain. Zhang ZL et al. [6] used the three-dimensional models generated by UAV aerial survey in the production scheduling of open-pit quarries, which improved the efficiency of stone material allocation and engineering management. Cheng YE et al. [7] used the UAV oblique photogrammetry to measure the terrain in small water body improvement projects, and realized the earthwork volume calculation of small water body dredging. Guo G et al. [8] used the UAV oblique photography technology to measure landfills that are difficult to measure manually. In the research of Li B et al. [9], by using a multi-rotor UAV equipped with a multi-lens camera to synchronously collect surface data from multiple perspectives, and using software for data processing, the earthwork volume was calculated efficiently and accurately, which greatly reduced the field time compared to RTK.

Many scholars have also studied and improved the accuracy of UAV oblique photography technology. The accuracy of UAV oblique photogrammetry technology is affected by many factors, including the flight altitude of the UAV, camera parameters, image overlap and post-processing methods. Regarding the factors affecting the accuracy of various image measurements, Cao L et al. [10] analyzed the accuracy of oblique photogrammetry modeling with the focus on the flight quality of the UAV and the measurement accuracy of the image control point data. Wei ZS et al. [11] conducted a detailed study on the accuracy of aerial triangulation in oblique photography. The elevation and plane accuracy of aerial triangulation involving oblique images are lower than those of vertical images. The points on the oblique images and vertical images can be processed with unequal weights to further improve the accuracy; Tang M [12] studied the effect of UAV flight trajectory on measurement accuracy in his study on soil and water conservation of waste dumps in detail. Starting from the flight altitude, heading overlap, lateral overlap and gimbal pitch angle parameters of the UAV, 18 schemes were analyzed using the TOPSIS method to obtain the optimal flight trajectory.

3 Earthwork Data Collection Based on UAV Oblique Photogrammetry Technology

3.1 Process of Allocation Volume Collection

Oblique photography work is generally divided into field data collection and indoor data analysis. In the process of data collection and processing using oblique photography technology, the surface image data within the survey area is first collected through the multi-view and multi-angle of the UAV to ensure comprehensive coverage and no blind spots. Subsequently, in the data preprocessing stage, the redundant image data beyond the boundary of the survey area is accurately eliminated to reduce data redundancy and improve processing efficiency. Next, the flight trajectory and attitude of the UAV are recorded using the position and attitude system (POS) data. Combined with the precise coordinates of the ground control points (GCPs) through joint adjustment processing, the spatial accuracy of the image data is further improved to ensure the authenticity and accuracy of the resulting image model.

After obtaining an accurate three-dimensional sparse point cloud, the point cloud encryption technology is used to refine the results and generate high-density point cloud data to improve the model detail performance and analysis accuracy. Next, the point cloud classification algorithm is used to classify the encrypted point cloud to clearly distinguish between ground points and non-ground points. For classified non-ground points, the elevation correction model is used to correct their elevation to eliminate errors caused by terrain factors such as buildings and vegetation. Then, the corrected ground point and non-ground point data are combined to construct a detailed digital elevation model (DEM), which reflects accurately the actual elevation changes of the surface. Finally, the boundary data and design elevation of the survey area are imported, and the excavation and backfill earthwork volume in the construction area is calculated accurately by comparing with the digital elevation model.

3.2 Engineering Example

Taking the Shandong Weifang pumped storage power station project as an example, topographic survey data from May, July, and September 2023 were used for terrain modeling and calculations of earthwork of cutting and filling.

(1) Point cloud generation

The three terrain CAD format data were imported into ArcGIS software, and the measurement point clouds were cropped and optimized using the measurement range to make them have the same range, as shown in Fig. 1.

(2) Triangulation data generation

Use the feature conversion tool to convert the target point cloud from point features to irregular triangulated network (TIN) format. Figure 2 shows the terrain triangulated network data for May, July and September 2023.



Fig. 1. Point cloud data of the terrain



Fig. 2. Triangulation data of the terrain

(3) Convert to DEM

The terrain triangulation data for May, July and September 2023 were converted from TIN format to raster format to obtain the digital elevation model data for each month (Fig. 3).




Fig. 3. Terrain digital elevation model DEM data

(4) Calculate earthwork data changes

The cut and fill tool is used to calculate the terrain changes from May to July and from July to September 2023, so as to obtain the cut and fill conditions of each part. The red color represents the net gain, i.e., filling area; the blue color represents the net loss, i.e., cutting area, as shown in Fig. 4.




Fig. 4. Topographic changes

Using the attribute table of the excavation and filling results, we can intuitively see the changes in the area size and volume of each block, as shown in Fig. 5. Taking the terrain changes from May to July 2023 as an example, in the attribute table, the corresponding block number is 246, the corresponding area is 1001.309352 square meters, and the corresponding volume change is 302.011591 cubic meters of excavation, which is represented by a highlighted light blue block in the terrain change map.

By exporting the attribute table and performing unified calculation, we can obtain that 2,119,544 cubic meters of earthfill was collected from May to July 2023, and 2,740,898 cubic meters of earthfill was collected from July to September 2023, as shown in Fig. 5, which is consistent with the actual report and the error is within the accuracy range.




Fig. 5. Attribute table of terrain change map from May to July 2023




Fig. 6. Seven phase of terrain data by UAV oblique photography

Using the above method, with a time node of about one quarter, seven periods of survey data are summarized, and the seven periods of survey data are modeled and processed. The generated triangulated network data is shown in Fig. 6.

Table 1 shows the calculation results of surface excavation and filling volumes of the seven periods.

Table 1. UAV oblique photography modeling survey data

Time	Surface excavation natural volume (10^4 m^3)	Surface filling natural volume (10^4 m^3)
April 2022–August 2022	1352.77	1271.96
August 2022–November 2022	1271.30	1020.53
November 2022–February 2023	1198.60	1001.47
February 2023–May 2023	1052.82	861.68
May 2023–November 2023	808.88	655.62
November 2023–March 2024	390.97	285.53
March 4, 2024	212.83	126.46

3.3 Examples of UAV and On-Site Reporting Data Verification

Taking the construction project of Shandong Weifang pumped storage power station as an example, the comparison between the earthwork volumes reported on site and the UAV measurement results from March 2022 to April 2024 was shown. The data reported on site are recorded monthly and divided into two categories: excavation and filling volumes, which provided relatively continuous engineering volume information. UAV measurement is usually carried out once a quarter, and the earthwork data obtained includes the excavation and filling volumes of the corresponding period. The comparison results between the on-site reported data and the UAV measurement data are shown in Table 2.

The comparison in the table shows that there are differences in the specific volumes of excavation and filling in the same time period between the on-site reporting data and the UAV measurement results. There are many reasons for this data difference. First, the earthwork in the slope filling area may be transferred to other temporary storage areas during the actual construction process to meet construction needs or ensure that the earth holding capacity of the slope (spoil dump) remains at a reasonable level, resulting in some earthwork not being reflected in the filling data measured by UAVs. In addition, the difference in the time point of data reporting is also an important factor. On-site reporting usually occurs at the end of each month, while the time point of UAV measurement is not fixed, sometimes at the beginning of the month, sometimes in the middle of the month. This time difference may cause the changes in earthwork in the same time period to fail to match accurately, further exacerbating the phenomenon of data non-closure. Despite

these errors, on the whole, the earthwork filling data can still be closed well, and the data difference between the two is within an acceptable range.

Table 2. Comparison of the earthwork volumes between on-site reporting data and UAV measurement data

Time	On-site reported (10 ⁴ m ³)				UAV measurement (10 ⁴ m ³)		Filling volume difference	
	Excavation		Filling		Excavation	Filling	Value (10 ⁴ m ³)	Percent
	Value	Subtotal	Value	Subtotal				
2022/03	66.09	95.73	0	0	95.73	0	0	0
2022/04	29.64		0					
2022/05	34.48	71.76	2.95	7.6	71.36	7.39	−0.21	−2.76%
2022/06	24.93		3.28					
2022/07	12.35		1.37					
2022/08	0	228.77	5.54	99.19	140.32	94.78	−4.41	−4.45%
2022/09	88.53		10.69					
2022/10	57.65		44.07					
2022/11	82.59		38.89					
2022/12	64.18	103.94	32.3	120.17	185.92	115.97	−4.2	−3.50%
2023/02	39.76		87.87					
2023/03	85.17	192.49	10.48	226.44	347.98	208.82	−17.62	−7.78%
2023/04	89.24		85.5					
2023/05	18.08		130.46					
2023/06	60.73	226.25	95.2	256.61	223.87	254.53	−2.08	0.81%
2023/07	93.43		85.77					
2023/08	72.09		75.64					
2023/09	91.76	239.56	64.97	266.48	290.69	263.74	−2.74	1.03%
2023/10	75.71		128.53					
2023/11	72.09		72.98					
2024/01	55.03	157.19	67.29	138.37	147.31	130.65	−7.72	5.58%
2024/02	19.93		22.06					
2024/03	40		18.99					
2024/04	42.23		30.03					

4 Conclusions

The volume of earthwork involved in the construction of a pumped-storage power station is large, and the collection of on-site earthwork flow data is crucial for earthwork balance planning. UAV oblique photography technology has the advantages of high data accuracy and large coverage area, and can be applied to earthwork data collection. This paper introduces the process of earthwork collection using UAV oblique photography technology. Taking the Shandong Weifang pumped storage power station project as an example, by comparing the earthwork data collected by UAV oblique photography with the earthwork data of on-site survey, the results show that the data collected by UAV oblique photography has high accuracy, and mutual verification between data is achieved. UAV oblique photography measurement technology can be used for earthwork data collection during the construction of pumped storage power stations, and its measurement results can improve the reliability and accuracy of earthwork allocation management.

References

1. Su, Q., Cheng, M.F., Niu, Y.B., Zhang, F.M., Zhang, Z.Y., Liu, J.H.: Implementation of a hierarchical visualization system for multifaceted integration modeling and operation-maintenance on existing railway lines. *Railw. Stand. Des.*, 1–10 (2024).
2. Zhou, P.G., Yang, M.: Reinforcement and prevention of bridge settlement in Karst Areas. *Highway* **69**(07), 325–331
3. Gao, G.T., Xi, L.X., Zhong, X.L.: A method for calculating the height of a single tall building based on convolutional neural networks and drone oblique photography images. *Bull. Surv. Mapp.* **03**, 118–122 (2024)
4. Zhang, S.H., Li, W.M., Pang, Y.N., et al.: Reconstruction of high-precision real 3D data of offshore islands based on drone tilt photography and laser scanning. *Bull. Surv. Mapp.* **03**, 25–30 (2024)
5. Li, T., Yuan, Z.C., Shen, B.Q., Gao, B., Wang, S.X.: Application of UAV matching point cloud technology in road survey. *Bull. Surv. Mapp.* **06**, 156–159 (2018)
6. Zhang, Z.L., Zhang, B.B., Fang, X., et al.: Construction and implementation of UAV production dispatching command system architecture for open-pit quarry. *China Min. Mag.* **28**(09), 67–73 (2019)
7. Cheng, Y.E., Lu, Z.H., Yuan, C.Q., Zhang, K., Shi, F., He, C.X.: Calculation of earthwork volume based on UAV oblique photogrammetry. *Geospatial Inf.* **08**, 70–73+5 (2021)
8. Guo, G., Li, W.P.: Application research of oblique photography of UAV in earthwork survey. *Bull. Surv. Mapp.* **S2**, 83–86+90 (2021)
9. Li, B., Xu, J.H.: UAV tilt photogrammetry earthwork calculation and accuracy evaluation. *Bull. Surv. Mapp.* **02**, 102–106+112 (2020)
10. Cao, L.: Three dimensional modeling and its precision analysis based on UAV oblique photogrammetry technology. Xi'an University of Science and Technology (2016)
11. Wei, Z.S., Li, Y.C., Chen, H.Y., Zhu, X.E., Liu, X.L.: Precision of aerial triangulation for oblique multi-vision images. *Remote Sens. Inf.* **32**(04), 6–10 (2017)
12. Tang, M.: Comparative study of UAV aerial survey in monitoring waste slag field of Chihuang railway example. *Huazhong Agric. Univ.* (2022)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Large Underground Cavern Complexes Considering Construction Disturbance and Environmental Evolution Dynamic Inversion of Surrounding Rock Parameters and Feasibility Analysis of Support Role

Yang Ji^{1,2(✉)}, Peng Huang^{1,2}, Wenxing Fang³, and Chunlong Zhao¹

¹ Power China Northwest Engineering Corporation Limited, Xi'an 710065, China
jiyang@nwh.cn

² Northwest Branch of the State Key Laboratory of Water Engineering Ecology and Environment in Arid Areas, Xi'an 710065, China

³ Xi'an Water Conservancy Planning, Surveying and Design Institute, Xi'an 710054, China

Abstract. Aiming at the problem that the surrounding rock parameters of large underground cavern group are affected by construction disturbance and environmental evolution, dynamic inversion of surrounding rock parameters and feasibility analysis of supporting role are carried out. The parameters to be inverted are screened by sensitivity analysis, and the dynamic inversion is carried out by combining uniform design theory and intelligent algorithm to obtain the mechanical parameters of surrounding rock in accordance with the reality. The results show that the displacement value calculated by the inversion parameters is more consistent with the measured value, the inversion parameters are used in the analysis of the supporting role, the systematic support measures can effectively control the deformation of the surrounding rock, the range of the plastic zone is reduced, the stress state is improved, and the support scheme is safe and feasible.

Keywords: pumped storage plant · underground group of caverns · Dynamic inversion of perimeter rock parameters · Support analysis

1 Introduction

The underground plant of pumped storage power station has the characteristics of large span, high side wall, dense cave group and complex geological conditions [1, 2]. In the process of cave excavation, the stability of the surrounding rock is affected by many factors, blasting, excavation, support, temperature changes and other operations will break the original stress equilibrium state of the surrounding rock, accelerate the deterioration damage of the rock body, and trigger the stress redistribution and deformation of the rock body [3–5]. Therefore, accurately grasping the parameters of the surrounding rock and quantitatively evaluating its stability is the key to ensure the safety of large underground cavern group projects. By tracking the dynamic monitoring data of the construction

process and inverting the parameters of the surrounding rock in time, the changes in the mechanical properties of the surrounding rock under the construction disturbance and environmental evolution can be obtained in real time, which can provide a scientific basis for the formulation of reasonable support measures and emergency plans [1, 2, 6].

In recent years, with the continuous improvement of rock mechanics theory and numerical analysis technology, quantitative assessment methods based on mechanical models have been widely used [7–9]. However, there are still some shortcomings in the existing studies. In terms of the inversion of the surrounding rock parameters, most of the studies did not fully consider the dynamic effects of construction disturbance and environmental evolution on the surrounding rock parameters. Blasting vibration, excavation unloading and temperature changes in environmental factors during construction can lead to changes in the mechanical properties of the surrounding rock, and the traditional parameter inversion cannot reflect such dynamic changes accurately and in a timely manner [10, 11]. This paper takes a large pumped storage hydropower station as an example, combines on-site monitoring data and numerical simulation analysis to track the on-site excavation support time sequence, in order to improve the accuracy and reliability of the stability assessment, and to provide a more scientific decision-making basis for the design and construction of large underground cavern groups.

2 Dynamic Inversion Analyses of Perimeter Rock Parameters

The dynamic inversion process of surrounding rock mechanical parameters is as follows: By analyzing topographic and geological survey data and on-site construction monitoring data, the key factors that significantly affect the deformation of surrounding rock are analyzed. The sensitive analysis method is used to screen out the parameters with strong sensitivity as the parameters to be inverted; Determine the value range of the parameters to be inverted based on the indoor and in-situ test conditions; The uniform design theory was applied to conduct multi-parameter and multi-level experimental combination design, and multiple sets of characteristic analysis samples were obtained; Intelligent algorithms are adopted to establish the initial weights of the nonlinear mapping network, and initial and iterative samples are formed for network training; The combined genetic algorithm and gradient descent algorithm effectively obtain the parameter solutions of the minimum value of the approximation error function. Combined with forward analysis, multiple groups of new samples approximating the measured values are obtained, and they are added to the original sample group and substituted into the system to form a closed-loop system repeatedly, and finally the optimal parameter index is obtained. Numerical simulation calculation and analysis are carried out using the inversely derived optimal mechanical parameter indicators to predict the displacement response of typical parts in the next stage of excavation. The technical framework of the reverse analysis system for rock mass mechanical parameters is shown in Fig. 1.




Fig. 1. Inverse analysis process of rock mechanical parameters

3 Model Construction and Initial Geostress Inversion Analysis

According to the topographic and geological map of a pumped storage power station, a more realistic simulation of the topography, stratigraphy and underground plant excavation layering was carried out in the numerical model of the cavern group area of the underground plant.

3.1 Three-Dimensional Overall Numerical Model

The overall model is shown in Fig. 2, and the excavation model is shown in Fig. 3. Model boundary conditions: normal displacement constraints are imposed on all sides of the calculation model, full constraints are imposed on the bottom, and the top of the model is free. The proposed table of physical and mechanical indexes of surrounding rock is shown in Table 1.

Table 1. Suggested values for physical and mechanical indexes of enclosing rock

Rock Type	Density	Compressive strength R_b	Deformation Modulus E_0	Poison by μ	Shear strength	
	(g/cm ³)	(MPa)	(GPa)		f'	c' (MPa)
II	2.63	110–80	20–15	0.27	1.1–1.2	1.2–1.5
III1	2.62	80–60	15–10	0.30	1.1–1.0	0.9–1.1
III2	2.62	60–40	10–8	0.30	1.0–0.9	0.8–0.9
IV	2.61	40–50	5–2	0.33	0.75–0.6	0.4–0.5




Fig. 2. Model grid diagram




Fig. 3. Mesh diagram of the cave group model

3.2 Inversion Analysis of Initial In-Situ Stress

The inversion adopts the multiple regression analysis method. Through three-dimensional numerical calculation and regression analysis of multiple schemes, the load mode formed by the geostress field is determined as follows: Considering four load factors including self-weight, east-west, north-south horizontal boundary tectonic force and horizontal shear force, three-dimensional numerical calculation of this load mode is carried out to obtain the calculated stress data (numerical observations) for regression analysis. The determined regression equation is:

$$\hat{\sigma} = a\sigma_g + b\sigma_e + c\sigma_s + d\sigma_\tau + f \quad (1)$$

In the formula, the subscripts g, e, s and τ represent the above four load factors respectively; f represents error; a, b, c and d are the coefficients to be regressed.

Through regression analysis of four load factors, namely self-weight, north-south direction, east-west direction and horizontal shear structural force, the regression coefficients obtained are as follows: $a = 0.752$, $b = 2.421$, $c = 2.198$, $d = 0.956$, $e = 0.073$. The complex correlation coefficient is: $R = 0.915$. Figure 4 compares and lists the measured values and regression values of the in-situ stress measurement points. It can be seen that the regression values and measured values at each measurement point have a good consistency, indicating that the regression effect is significant and the adopted regression calculation mode is reasonable.




Fig. 4. Inversion In-situ Stress Comparison Table (Unit: MPa)

4 Dynamic Inversion of Mechanical Parameters of Surrounding Rock During Construction

4.1 Determination of Inversion Parameters

Based on the monitoring data, the typical section monitoring points are determined. Combined with the surrounding rock mechanical parameters adopted in the previous surrounding rock stability analysis, the relevant parameters with greater sensitivity are determined, namely the elastic modulus, cohesion and internal friction Angle of different types of surrounding rocks. Different combinations of surrounding rock parameters are determined through the design of training samples, and the obtained parameter combinations are substituted into the model for calculation. The final inversion parameters are determined by comparing the calculated values with the monitored values. The value ranges of each parameter to be inverted are shown in Table 2.

Table 2. Range of Values for parameters to be inverted

Interval	Category II			Category III1			Category III2			Category IV		
	E1	C1	$\phi 1$	E2	C2	$\phi 2$	E3	C3	$\phi 3$	E4	C4	$\phi 4$
Upper limit	30	1.5	50.1	20	1.1	47.7	15	0.9	45	8	0.5	36.8
Lower limit	20	1.2	47.7	15	0.9	45	10	0.8	42	3	0.4	30.9

In the table, E is the modulus of elasticity, c is the cohesion, ϕ is the angle of internal friction, E1, E2, E3 unit is GPa, c1, c2, c3 unit is MPa, $\phi 1$, $\phi 2$, $\phi 3$, $\phi 4$ unit is $^{\circ}$.

According to the uniform design theory, the number of factors is 12, and each factor is divided into 16 levels, and a total of 16 groups of training samples are designed, as shown in Table 3. The parameters of each sample are input into the finite element calculation model to obtain the calculated incremental displacement values.

Table 3. Training samples of parameters to be inverted

Sample	E1	C1	$\phi 1$	E2	C2	$\phi 2$	E3	C3	$\phi 3$	E4	C4	$\phi 4$
1	20	1.2	47.7	15	0.9	45	10	0.8	42	3	0.4	30.9
2	21	1.25	48.2	16	0.95	45.5	11	0.82	42.3	4	0.42	31.2
3	22	1.3	48.7	17	1.0	46	12	0.84	42.6	5	0.44	31.5
4	23	1.35	49.2	18	1.05	46.5	13	0.86	42.9	6	0.46	31.8
5	24	1.4	49.7	19	1.1	47	14	0.88	43.2	7	0.48	32.1
6	25	1.45	50.1	20	1.15	47.2	15	0.90	43.5	8	0.50	32.4
7	26	1.5	50.5	15	0.92	47.4	10	0.81	43.7	3	0.41	32.7
8	27	1.22	50.8	16	0.94	47.6	11	0.83	43.9	4	0.43	33.0
9	28	1.24	51.1	17	0.96	47.8	12	0.85	44.1	5	0.45	33.3
10	29	1.26	51.4	18	0.98	48.0	13	0.87	44.3	6	0.47	33.6
11	30	1.28	51.7	19	1.02	48.2	14	0.89	44.5	7	0.49	33.9
12	20	1.32	52.0	20	1.04	48.4	15	0.91	44.7	8	0.51	34.2
13	21	1.34	52.3	15	1.06	48.6	10	0.93	44.9	3	0.53	34.5
14	22	1.36	52.6	16	1.08	48.8	11	0.95	45.1	4	0.55	34.8
15	23	1.38	52.9	17	1.12	49.0	12	0.97	45.3	5	0.57	35.1
16	24	1.42	53.2	18	1.14	49.2	13	0.99	45.5	6	0.59	35.4

4.2 Inversion Process and Results

Combining the excavation and support conditions of the underground powerhouse cavern group at each stage, the dynamic parameters of the rock mass in different areas were inverted in stages. The inverted parameters were brought into the positive analysis

calculation model to study the displacement changes caused by the excavation and support of the underground powerhouse cavern group, and the surrounding rock mechanical parameters consistent with the monitored displacement values were obtained. The excavation periods of the underground powerhouse cavern group at each stage are shown in Fig. 5.




Fig. 5. Schematic diagram of layered excavation

This paper takes the excavation periods of the second and third floors of the main powerhouse as examples to conduct staged, segmented, phased and regional inversion analysis of the dynamic parameters of the surrounding rock mechanical parameters. The three-dimensional finite element models of the second and third floors of the cavern group of the lower powerhouse are shown in Figs. 5 and 6 (Fig. 7).




Fig. 6. Excavation model of Layer II




Fig. 7. Excavation model of Layer III

In the monitoring and analysis, all the multi-point displacement meters are buried immediately, so only the displacement of the rock mass after installation can be monitored. However, the displacement before that cannot be measured in time. The deformation caused by the second layer excavation can be calculated through the monitoring values of the multi-point displacement meters (the difference between the displacement value of the multi-point displacement meter at the completion of the second layer excavation and the displacement value at the beginning of the second layer expansion excavation). This is the displacement increment caused by the expansion and excavation of the second layer. The displacement value of the third layer is calculated based on the mechanical parameters of monitoring and inversion.

Table 4. Comparison of Monitored Values and Calculated Values (Unit: mm)

Design Number	Profile Location	Monitoring of change values	Calculation of change values	Difference
M ⁴ 02-CFA1	0+000.00	1.07	1.28	0.21
M ⁴ 03-CFA1	0+000.00	0.27	0.81	0.54
M ⁴ 04-CFA1	0+000.00	0.99	1.35	0.36
M ⁴ 02-CFA3	0+109.50	1.01	1.05	0.04
M ⁴ 03-CFA3	0+109.50	0.34	0.60	0.26
M ⁴ 04-CFA3	0+109.50	0.63	1.02	0.39

The calculated displacement values obtained are compared with the actual detection values, as shown in Table 4, and the results show that the difference between the calculated displacement values and the actual detection values is relatively small, with a maximum error of no more than 0.6 mm, indicating that this parameter is reasonable and can be used as the input value of rock mechanics parameters for the analysis of the third layer of excavation.

5 Analysis of the Role of Support

The inverse mechanical parameters in line with the actual situation are inputted into the numerical model, and the positive analysis calculation is carried out to study the disturbance of the surrounding rock by the excavation and support of the cave group, and the feasibility analysis of the support scheme is carried out by taking the support scheme of the refuge chamber of the main plant as an example, and the excavation and support diagram above the III layer of the main plant is shown in Fig. 8.




Fig. 8. Layout of excavation support above III of the main plant building

Figures 9, 10, 11, 12, 13 and 14 show the typical profile displacement, stress, and plastic zone of the main plant after excavation and support of the underground plant cavern group in layer III under unsupported and considered supported conditions, respectively.




Fig. 9. Unsupported displacement




Fig. 10. Supported displacement




Fig. 11. Unsupported σ_3




Fig. 12. Supported σ_3

After excavation and support of underground cavern group, the deformation, stress and plastic zone law of surrounding rock in each section is basically the same, and the overall deformation to the excavation and support of the critical surface, relative to the gross hole excavation conditions, the amount of value is reduced. Table 5 shows the displacement comparison of the excavated surrounding rock with and without support conditions, the system support measures play an obvious role in controlling the deformation of surrounding rock, and the displacement reduction ratio of each typical section is basically more than 10%, and the maximum reduction ratio can be up to 33%.




Fig. 13. Unsupported plastic zone




Fig. 14. Supported plastic zone

Table 5. Comparison of displacements with and without support (unit: mm)

Excavation layers	Section location	Vertical displacement			
		Unsupported	Supported	Difference	Proportions %
II2	1#	15.89	15.36	0.53	3.34
	2#	17.77	15.74	2.03	11.42
	3#	18.22	16.24	1.98	10.87
	4#	21.35	17.69	3.66	17.14
III	1#	18.44	16.27	2.17	11.77
	2#	19.05	16.74	2.31	12.13
	3#	19.50	17.22	2.28	11.69
	4#	22.58	18.58	4.00	17.71

6 Conclusion

By comprehensively applying sensitivity analysis, uniform design theory and intelligent algorithms, the influence of construction disturbances and environmental evolution on the mechanical parameters of surrounding rock can be accurately considered. Through the research on the cavern group of the underground powerhouse of a certain pumped storage hydropower station, the calculated displacement values of the surrounding rock mechanical parameters obtained by inversion have a small difference from the actual monitored values, which proves the rationality and effectiveness of this method. It can obtain the changes of the surrounding rock mechanical characteristics in real time and provide a reliable basis for engineering decisions. This indicates that the support scheme is feasible, safe and effective, and can effectively restrict the damage caused by the excavation and unloading of the surrounding rock. Dynamic inversion and stability analysis provide scientific decision-making basis for large underground cavern clusters

in the design and construction stages, which is conducive to improving the accuracy and reliability of engineering stability assessment, ensuring the safe construction and operation of large underground cavern cluster projects, and has important reference and learning value for similar projects.

References

1. Li, R., Jiang, H., Su, G., et al.: Optimisation study of excavation support scheme for underground cavern group of pumped storage power station. *Hydropower Gener.* **51**(04), 54–61 (2025)
2. Wang, Y., Wang, Z., Tong, T., et al.: Stability monitoring and analysis of underground plant enclosure in pumped storage power stations. *Hydropower Energy Sci.* **43**(01), 177–181 (2025)
3. Tan, Z., Li, B., Li, P., et al.: Study on the formation mechanism of excavation damage zone in high geostress underground plant enclosure. *J. Undergr. Space Eng.* **20**(06), 1979–1990 (2024)
4. Li, J., Huang, T., Zhang, H., et al.: Progress and prospect of mechanical test research on unloaded rock body. *J. Three Gorges Univ. (Nat. Sci. Ed.)* **44**(01), 1–13 (2022)
5. Deng, H., Wang, Z., Li, J., et al.: Study on the influence of unloading rate and pore water pressure on the unloading characteristics of sandstone. *J. Geotech. Eng.* **39**(11), 1976–1983 (2017)
6. Zhang, S.-R., Peng, Z.-H., Hu, A.-K.: Research on dynamic safety information model of large underground cavern group. *Water Conserv. Hydropower Technol.* **48**(05), 74–80 (2017)
7. Wu, J., Cao, Aiwu., Liu, J., et al.: Calculation method of overall safety factor of underground cavern group and engineering application. *J. Undergr. Space Eng.* **17**(S1), 433–438+497 (2021)
8. Qian, M., Leng, X., Wang, C., et al.: Impact of damage-based cohesion weakening-friction angle strengthening model on the stability of surrounding rocks in large underground cave complexes. *Sci. Technol. Eng.* **21**(09), 3763–3769 (2021)
9. Hu, S., Wu, J., Zhong, G., et al.: Numerical analysis of reasonable hole spacing of cave groups under complex geological conditions. *Hydropower New Energy* **37**(12), 1–4+63 (2023)
10. Zhang, C., Qin, T., Zhang, X., et al.: Study on the impact of blasting construction on underground cavern group. *Blasting* **39**(03), 56–63 (2022)
11. Zhang, S., Hu, A., Wang, C., et al.: Real-time dynamic inversion of mechanical parameters of surrounding rock during the construction period of large underground cavern group. *J. Hohai Univ. (Nat. Sci. Ed.)* **44**(03), 189–195 (2016)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





State of the Art on Air-Entraining Vortices in Pumped Storage Hydropower Plants

Tian Jin¹, Yujie Ge², Guangde Li³, Jiaming Wang³, and Gensheng Zhao²(✉)

¹ Nanxun Innovation Institute, Zhejiang University of Water Resources and Electric Power, Hangzhou 310018, China

² Nanjing Hydraulic Research Institute, Nanjing 210000, China
gszhao@nhri.cn

³ China Energy Engineering Group Guangxi Electric Power Design Institute Co.,LTD., Nanjing 530007, China

Abstract. Air-entraining vortices at hydraulic intakes pose significant challenges to the safe operation of pumped storage hydropower plants (PSH). These vortices can induce structural vibrations, reduce discharge capacity, and damage equipment. This paper comprehensively reviews the current research progress on the formation mechanisms, hydraulic characteristics, influencing factors, and prevention methods of air-entraining vortices. It discusses classification and development stages of vortices, focusing on their transition from surface swirl to fully developed air-core vortices. Special attention is given to the main factors that affect the formation and development of air-entraining vortices. The mechanism of gate vibration caused by air-entraining vortices is also examined. The paper also analyzes the effectiveness of various anti-vortex measures and identifies key research gaps, providing a valuable reference for future studies on vortex control and vibration mitigation in PSHPPs.

Keywords: Pumped storage hydropowerstation · Air-entraining vortex · Vortex-induced vibration · Hydraulic intake · Vortex prevention

1 Introduction

Pumped storage hydropower plants (PSH) offer numerous advantages including large reservoir capacity, high efficiency, operational flexibility, and rapid response capabilities. These devices perform essential functions such as peak regulation, frequency modulation, phase adjustment, energy storage, emergency backup, and black start, thereby playing a crucial role in the integration of clean energy into power grids. As the global energy transition accelerates and the proportion of renewable energy continues to increase, pumped storage power stations are being widely deployed internationally. Following China's announcement of its "dual carbon" strategic goals (carbon peak by 2030 and carbon neutrality by 2060), there has been an escalation in the expectations placed on the development and management of pumped storage power stations. China's "14th Five-Year Plan for New Energy Storage Development" places explicit emphasis on the need of enhancing technological innovation capabilities for pumped storage and ensuring the safety of power grid peak regulation systems.

In the hydropower industry, particularly during the construction and operation of pumped storage power stations, air-entraining vortices in high-head flood discharge tunnels present a challenging issue of significant concern to the engineering community. In recent years, a number of pumped storage power stations have encountered abnormal gate vibrations, structural damage, and even equipment failures due to air-entraining vortices during flood discharge operations, seriously affecting the safe operation of these facilities. This phenomenon is primarily attributable to the propensity of such structures to form air-entraining vortices under conditions of high-head and large-flow flood discharge. The consequence of this phenomenon is the occurrence of safety hazards, including gate vibration and air blast impacts. Existing engineering cases demonstrate that vibration and impact problems caused by air-entraining vortices are particularly pronounced in high-head discharge systems exceeding 100 m, where traditional hydraulic optimization methods struggle to effectively control vibration phenomena.

Air-entraining vortices represent a typical hydraulic phenomenon at the intakes of hydraulic structures. The possibility of their occurrence and the resulting impact on pressure systems must be carefully considered during the design and operation of hydropower plants and PSH. In China, air-entraining vortex problems have occurred in models or prototypes of various water conservancy and hydropower projects including Manwan, Longyangxia, Huangtankou, Zipingpu, Tohai, Jinshuitan, Shitouhe, Baozhuzi, and Shuikou. Water intakes of 48 hydropower stations were studied in China, including Huangtankou, Gutian Level 3, and Nanshui, finding that vortices occurred in the front edge waters of 33 stations, accounting for 69%. For example, due to complex terrain and asymmetric boundaries of hydraulic structures, vortices formed at the water intake of Jinping I Hydropower Station's flood discharge tunnel (DANG Yuan-yuan & HAN Chang-hai 2009). Similar engineering problems have occurred in many countries including Japan, the United States, the former Soviet Union, Canada, the United Kingdom, and India (CHEN Yun-liang 2006). Hecker (1981) surveyed 20 engineering cases with air-entraining vortices, including conventional power stations and flood discharge tunnel intakes, pumped storage power station intakes, large pumping station intakes, and lock filling inlets, finding that 14 projects (70%) experienced relatively serious problems.

Research on vortex flow mechanisms primarily focuses on structural characteristics during vortex development and external flow field changes. Analysis shows that the accumulation of initial circulation and the dragging action of the main intake flow are the primary causes of air-entraining vortex formation. However, the quantitative description of their roles in the vortex formation process is still under investigation. Research on the formation mechanisms of vortices provides a framework for the subsequent vortex elimination measures, but the quantification of vortex influencing factors remains the biggest obstacle in current research. How to accurately measure hydraulic parameters such as water flow circulation and downward pulling force, and convert influencing factors such as boundary conditions into physical quantities for specific analysis, will be the main task of research at this stage. In the current work, the classification of vortices are introduced, and investigate the main factors affecting the formation and development of air-entraining vortices and the mechanism of gate vibration. Furthermore, we summarize

the effectiveness of various anti-vortex measures and identifies key research gaps, providing valuable reference for future studies on vortex control and vibration mitigation in PSHPs.

2 Air-Entraining Vortices

2.1 Classification of Vortices

The Alden Research Laboratory (ARL) classified vortices into six different types based on their intensity and characteristics (see Fig. 1). Influenced by incoming flow conditions and hydraulic structure boundaries, air-entraining vortices at intakes may undergo some or all development stages in this classification. Vortices at different development stages have varying impacts on engineering systems. Sarkardeh et al. (2012) categorized vortices into three main types according to their degree of hazard: (1) VT1 and VT2 type vortices are close to non-vortical flow, cause no harm, and are permitted in engineering as they are considered safe; (2) VT3 and VT4 types are weak vortices that have some effect on hydraulic structures or hydropower equipment, but generally not serious, though they may cause greater harm at pump intakes and efforts should be made to prevent their occurrence; (3) VT5 and VT6 types are air-entraining vortices that are relatively strong; in these types, air bubbles are entrained from the water surface and transported downward, forming a stable air core at the vortex center in the strongest state, steadily transporting downward, which can cause serious damage to hydraulic structures or hydropower equipment and are typically not allowed in engineering practice.




Fig. 1. ARL vortex type classification (Hecker 1987).

Based on the location and orientation of intakes at hydraulic structures, they can be arranged horizontally or vertically, as illustrated in Fig. 2. Horizontal intakes are commonly utilised in the context of river power plants, HPPs/PSHPPs, flood protection infrastructure, and water supply systems. As Knauss (1987) noted, vertical intakes are most often used as pump sumps and are rarely implemented at HPPs/PSHPPs. During the process of outflow through the bottom orifice, the vortex axis of the vertical shaft vortex approaches the vertical direction, the vortex motion easily stabilizes, and the morphology is relatively symmetrical, basically conforming to the axisymmetric assumption in theoretical research. This allows the three-dimensional flow field to be analyzed using the Navier-Stokes equations in a cylindrical coordinate system (see Fig. 3).




Fig. 2. Classification of water intake (LU Yao et al. 2019)




Fig. 3. Vertical vortex in cylindrical coordinate system (LU Yao et al. 2019)

For general side orifice outflow situations, constrained by intake boundary conditions, incoming flow undergoes longitudinal or lateral contraction, causing drastic changes in flow direction and velocity. Surface water is blocked by the breast wall above the intake, forming a stagnant zone, and the water body in this zone forms initial circulation under the combined influence of boundaries and water flow. Meanwhile, the stagnant water body enters an unstable state under the dragging action (downward pulling force) of the main intake flow, ultimately triggering vortices under the combined action of initial circulation and downward pulling force.

Unlike general horizontal intakes, hydraulic conditions in front of overflow dam gates are more complex. During gate opening, as the gate opening changes, hydraulic conditions such as water level and flow rate in the gate chamber change accordingly, putting the vortex in a transient development process. At the same time, due to the limited

scope of the gate chamber, vortices in front of the gate generally form in pairs near the maintenance gate slot, with multiple streams influencing each other, creating complex flow patterns in the gate chamber, making observation and research of vortices in front of the gate difficult (TIAN Tian et al. 2021). SUN Hong-liang et al. (2017) studied vortices in front of arc gates of flood discharge gates, with test results showing that when gates are partially opened, advancing water flow contracts laterally and longitudinally under boundary conditions, forming certain incoming flow circulation, and this circulation combined with axial flow velocity are the main factors in vortex formation. Lu Yao (2019) used dynamic grid technology to simulate the gate opening process, concluding that in the early stage of gate opening discharge, flow separation under the combined action of pier head vortices and adverse pressure gradient is the main reason for vortex formation. As the gate opening increases, the kinetic energy converted from the potential and pressure energy of the main downward flow gradually fails to overcome its viscous dissipation, and the vortex gradually disappears.

2.2 Main Factors Affecting the Formation and Development of Air-Entraining Vortices

Vortex phenomena are common at flood discharge tunnel inlets, with extremely complex influencing factors. Synthesizing previous research findings, it can be concluded that the formation of pressurized intake vortices is influenced by factors including boundary topography, intake configuration, the distance the intake extends into the reservoir, the angle between incoming flow direction and intake, incoming flow conditions, and operational conditions (SONG Liang & YANG Ji-jian 2016).

2.2.1 Intake Boundary Topography

The formation of vortices at flood discharge tunnel inlets is primarily due to non-uniform water flow at the entrance, causing bypass flow. In hydraulic structures with low incoming flow velocities, water flow is stable and less prone to vortex formation. Vortices only occur when flow velocity changes significantly and water flow is influenced by topographical factors, resulting in bypass flow and similar phenomena.

Vortex problems caused by narrow intake topography compressing water flow have been observed in projects such as the Huangtankou Hydropower Station, where the flow compression ahead of the intake created backflow, resulting in air-entraining vortices. Engineering experience shows that if the intake topography is excessively concave or narrow, water flow from adjacent boundaries causes entrainment and compression of water approaching the orifice, causing flow rotation in front of the intake. This leads to air-entraining vortices even at low flow velocities (i.e., low Froude numbers) in relatively small intakes, disrupting normal operating conditions.

Vortex problems caused by large angles between incoming flow direction and orifice axis have been observed in projects like the Shitouhe flood discharge tunnel, where uneven flow caused water level rise on one side of the intake. Combined with centrifugal forces, this created a rotational initial flow pattern in front of the intake, inducing air-entraining vortices that endangered engineering safety.

2.2.2 Intake Configuration

Research indicates that when boundary conditions are fixed, vortex intensity is greatest when $H/D \approx 2.0$ (where H is the hydraulic head at the orifice and D is the orifice height or diameter), clearly showing the close relationship between intake configuration and vortex issues. Large orifices ($D > 8.0$ m) with high flow rates are more prone to air-entraining funnel vortices compared to smaller orifices. This occurs because with larger gates, as incoming flow velocity increases, the subsurface downward flow velocity also increases, creating extremely non-uniform velocity and pressure distributions that form a radiating flow pattern. Additionally, orifice contraction and fluid turbulence cause imbalances in tangential forces, leading to water body rotation and subsequent surface air-entraining vortices.

For example, the bottom orifices at Baozhuzi Dam and the middle conduits at Longyangxia Dam, both with diameters exceeding 8m and high flow rates, experienced serious vortex-related problems. At the Jinping I flood discharge tunnel (with an orifice dimension of 12.00 m $\times$ 15.00 m, width $\times$ height), before anti-vortex measures were implemented, the largest vortex (approximately 2.5 m in diameter) occurred at a water level of 1880 m. Therefore, caution should be exercised when adopting large orifices in engineering design, and if large orifices must be used, measures should be taken to prevent or mitigate vortex-related hazards.

Furthermore, hydraulic model studies have shown that when incoming flow direction remains unchanged, the larger the length-to-width ratio of the intake channel, the weaker the circulation near the water intake, and the smaller the limiting water depth required to prevent air-entraining vortices. This suggests that for general small and medium-sized projects, increasing the length of the intake channel can effectively prevent vortex hazards. However, in high-head projects, at high water levels, the length-to-width ratio of the intake channel no longer significantly affects vortex formation, and this method has minimal impact on circulation near the intake. In such cases, other measures should be considered to prevent vortex hazards.

3 Main Mechanisms of Gate Vibration Induced by Air-Entraining Vortices

During their development, air-entraining vortices continuously ingest air, causing a steady inflow of water into the channel. Upon full development, they form vortex tubes, creating air-entrained vortex bands. The flow surrounding these vortex tubes is under negative pressure, and the repeated generation and dissipation of vortices continuously induce water flow fluctuations, which in turn cause gate vibrations and may even result in damage. Therefore, the generation of air-entraining vortices should be avoided, and for those that cannot be prevented, their harmful effects should be mitigated (DUAN Wengang et al. 2011; MA Fei & WANG Yu 2016).

The main influencing factors of air-entraining vortices in front of the gate include the water depth in front of the gate, gate opening, incoming flow circulation, and the velocity of the advancing flow (TIAN Tian, 2021). The primary reason for vortex formation is that vorticity generated from the shear layer or flow separation is transported to the vicinity of the submerged intake. Under the dragging effect of the main flow, the vorticity is

stretched, leading to the generation of vortices, as illustrated in Fig. 4 (Suerich-Gulick 2014). Unstable shear layers induce gate vibration, which is sustained by the vortices. The combined excitation of both promotes gate vibration, with the continuous presence of vortices along the leading edge of the gate bottom being the main source of vibration (WANG Yanzhao 2022).




Fig. 4. (a) Plan; (b) section views of sample run-of-river hydropower installations (Suerich-Gulick 2014)

In addition, at the boundaries of the flow field, such as behind the gate, in the gate slot, and at the bottom edge, air-entraining vortices can also be generated under certain conditions. Surface microwaves propagate to the intake breast wall, forming reverse microwaves that meet subsequent forward microwaves, creating small surface circulations. Under the action of the uneven flow field at the intake discharge, randomly occurring air-entraining vortices with quasi-orderly characteristics are formed. These randomly occurring vortices, especially those in the gate slot, can exacerbate gate vibration (GAO Xueping et al. 2009; Shen C et al. 2018). For vortices in front of the gate, the impact of vortices on gate vibration can be reduced by changing the operation mode of the flood discharge gate in the following two ways: (1) Reduce the incoming flow angle in front of the surface orifice gate to decrease the initial velocity circulation of the advancing flow and block the vorticity compensation path; (2) Increase the number of opened gates as much as possible and reduce the opening of individual gates to increase the submergence depth at the gate orifice (NIE Yanhua 2024).

In summary, gate vibration induced by air-entraining vortices are mainly due to the pushing effect of fluctuating water pressure caused by the continuous generation and dissipation of vortex clusters on the gate, which should be avoided in the design of practical engineering.

4 Vortex Prevention Measures

It should be noted that research on anti-vortex measures for specific vertical axis vortex phenomena in engineering has yielded far more results than research on underlying mechanisms. A wealth of practical experience has been accumulated, providing valuable references for engineering design (Denny & Young (1957), Bretschneider (1981), and Rutschmann et al. (1987)).

Due to engineering requirements, in most situations it is not feasible to prevent vortices by increasing intake submergence depth, reducing flow rate, or implementing other measures that might alter the operational effectiveness of hydraulic structures. Extensive research has shown that boundary conditions are important factors triggering the appearance and development of vertical axis vortex phenomena. Therefore, from a practical engineering perspective, the vast majority of effective anti-vortex measures are based on rational design and arrangement of boundary conditions. Existing anti-vortex measures primarily focus on suppressing initial flow circulation, disrupting vortex structures, and enhancing vortex energy dissipation.

4.1 Suppressing Initial Flow Circulation

Initial flow circulation is the main factor inducing vortex formation. By altering boundary conditions and hydraulic conditions to smooth water flow and suppress circulation generation, vortex formation can be prevented (WANG Ying-kui 2011). Measures such as optimizing intake configuration, increasing submergence depth, reducing inlet flow velocity, and rationally controlling operating conditions can effectively reduce initial flow circulation. In the horizontal layout of water intakes, efforts should be made to ensure smooth incoming flow and reduce intake angles. If conditions permit, extending the length of the intake channel allows advancing water flow to stabilize, thereby reducing initial flow circulation near the water intake.

4.2 Disrupting Vortex Structure

Vortices typically occur within a 30° range above the water intake. Therefore, dedicated anti-vortex measures such as anti-vortex beams and piers (Fig. 5) can be installed to disrupt vortex structure, cutting off tangential and radial flow paths and preventing the vortex from maintaining a stable form. YE Mao et al. (2007) used numerical simulation to analyze scenarios with and without anti-vortex piers at water intakes. Calculation results showed that installing anti-vortex piers could obstruct water rotation, reduce circulation, and thus disrupt vortex stability, achieving the goal of vortex elimination. YAN Gen-hua et al. (2007) studied the influence of anti-vortex grid structures on vortex formation and verified their effectiveness through model tests. Kabiri-Samani et al. (2013) conducted experiments on the anti-vortex effects of differently shaped anti-vortex plates under various flow conditions. Results showed that installing anti-vortex plates could effectively increase water intake flow rate. To reflect the effect of anti-vortex plates in improving intake efficiency, they introduced a new variable called the “air index” and provided design recommendations for anti-vortex plates based on analysis results.




Fig. 5. Measures of eliminating vertical vortices for different water intakes (LU Yao et al. 2019)

4.3 Enhancing Vortex Energy Dissipation

From a development mechanism perspective, vorticity diffusion and energy dissipation occur during vortex development. By disrupting vortex energy transport pathways and enhancing viscous dissipation, vortex energy dissipation can be increased, accelerating vortex dissipation and eliminating vortices. Liu Jie-jie et al. (2017) discovered through experiments that installing anti-vortex grids on arc gates could reduce vortex development range and disrupt vortex structure, effectively cutting off vortex rotation routes and disrupting vortex energy transport, with significant anti-vortex effects. DUAN Wengang et al. (2011) through systematic research on anti-vortex measures, summarized several typical anti-vortex approaches including rational intake design, installation of specialized structures, and adjustment of operation modes, which have achieved certain anti-vortex effects in practical engineering applications (Fig. 6).




Fig. 6. Anti-vortex grids vortex dissipation diagram (red circle range is the original vortex development area, blue circle range is the vortex development area after vortex dissipation) (Liu Jiejie et al. 2017)

Due to the complex vortex flow that occurs during gate opening for discharge and the narrow, rapidly flowing environment within gate chambers, traditional anti-vortex measures such as anti-vortex racks and beams cannot adequately meet the needs of discharge gates and might even damage the anti-vortex structures themselves, affecting normal gate operation. Therefore, anti-vortex measures for areas in front of gates are still in the experimental stage, with few successful cases in practical engineering applications.

Although there are numerous measures for eliminating vertical axis vortices, there are no universal criteria for determining which anti-vortex measure would be most economically effective for a specific project. Moreover, due to scale effects of vortices, successfully eliminating vertical axis vortices in a model does not guarantee effective control and elimination of vertical axis vortices in the prototype, which still requires verification through prototype operation. In addition to hydraulic considerations, factors such as structural simplicity, economic rationality, ease of construction, and management convenience of anti-vortex engineering must typically be balanced.

5 Conclusions

While some progress has been made in research on vortex flow problems and anti-vortex measures, the issue of vortices at water intakes remains unresolved. Regarding the shortcomings in existing research and directions for future research, the following aspects should be considered:

Research on vortices has predominantly focused on stable air-entraining vortices with greater hazard potential, neglecting the observation and analysis of the early stages of vortex development and late dissipation processes. Furthermore, there is a lacking of research on the complete vortex flow process.

Most vortex research has focused on fixed-dimension water intake structures, with limited research on vortices in front of other intake structures, such as those that form in front of flood discharge gates during the gate opening process. This area requires strengthened research.

Research emphasis has been on exploring the inherent characteristics of vortices, with limited discussion of vortex hazards. Subsequent research should focus on the generation mechanisms of vortex hazards and the impact of vortex formation on the external environment.

Current research mostly focuses on the influence of the suction vortex in front of the gate and the vortex shape behind the gate on the gate vibration. However, there are few studies on the mechanism and harm caused by gate vibration caused due to the air-entraining vortex, especially the gate vibration caused by the vortex behind the gate.

By addressing these research gaps, future studies can contribute to a more comprehensive understanding of vortex-induced vibration mechanisms in pumped storage power stations and develop more effective prevention measures.

Acknowledgements. This research study was funded by the Nanxun Scholars Program for Young Scholars of ZJWEU (Project No. RC2024021508) and R&D project (PJ25050) of China Energy Engineering Group Guangxi Electric Power Design Institute Co., LTD.

References

- Bretschneider, H.: Massnahmen zum Vermeiden des Luftesintags bei Einlaufbauwerken. *Wasserwirtschaft* **71**(5), 125–128 (1981). (in German)
- Chen, Y.: Research for hydraulic characteristics of vertical vortex at hydraulic intakes (Ph.D thesis). Sichuan University, Chengdu (2006). (in Chinese)
- Dang, Y., Han, C.: Review of vortexes at intakes. *Adv. Sci. Technol. Water Resour.* **29**(1), 90–94 (2009). (in Chinese)
- Denny, D.F., Young, G.A.J.: The prevention of vortices and swirl at intakes. In: IAHR Seventh General Meeting, pp. Paper C1 (1957)
- Duan, W., Huang, G., Zhang, H., et al.: Experimental research on vortexes eliminating of several typical hydraulic intakes. *J. Yangtze River Sci. Res. Inst.* **28**(02), 21–27 (2011). (in Chinese)
- Gao, X., Yuan, Z.: Development of the underground reservoirs of pumped-storage hydropower and key hydraulics issues. *J. Hydraul. Eng.* **54**(09), 1058–1069 (2023). (in Chinese)
- Gao, X., Du, M., Zhao, Y., et al.: Experimental study of stochastic vortex in hydraulic intakes. *J. Hydroelectr. Eng.* **28**(04), 137–142 (2009). (in Chinese)
- Hecker, G.E.: Model-prototype comparison of free surface vortices. *J. Hydraul. Div. ASCE* **107**(10), 1243–1259 (1981)
- Hecker, G.E.: Fundamentals of Vortex Intake Flow, pp. 13–38. Swirling flow problems at intakes, IAHR Hydraulic Structures Design Manual 1. Taylor & Francis: Balkema, Rotterdam, NL (1987)
- Kabiri-Samani, A.R., Borghei, S.M.: Effects of anti-vortex plates on air entrainment by free vortex. *Scientia Iranica* **20**(2), 251–258 (2013). <https://doi.org/10.1016/j.scient.2012.10.041>
- Knauss, J.: Introduction, pp. 1–11. Swirling flow problems at intakes, IAHR Hydraulic Structures Design Manual 1. Taylor & Francis, Balkema, Rotterdam, NL (1987)
- Liu, J., Sun, H., Liu, Y.: Experimental study on eddy-eliminating barriers mounted on radial gate plate. *J. Hydroelectr. Eng.* **36**(1), 26–33 (2017). (in Chinese)
- Lu, Y.: Research on the dynamic hydraulic characteristics of the opening gates discharge process on an overflow dam (Ph.D thesis). Dalian University of Technology, Liaoning (2019). (in Chinese)
- Lu, Y., Su, X., Li, J.: Review of vertical vortex problems of water intakes. *Water Resour. Power* **37**(09), 78–82 (2019). (in Chinese)
- Nie, Y., Wang, B., Hou, D., et al.: Hydraulic characteristics of inlet vortex of discharge structures based on dispatch regulation. *J. Changjiang River Sci. Res. Inst.* **41**(11), 118–124 (2024). (in Chinese)
- Ma, F., Wang, Y.: Experimental study of vortex with air core in front of side crest outlet gate. *Adv. Sci. Technol. Water Resour.* **36**(06), 35–38+89 (2016). (in Chinese)
- Rutschmann, P., Volkart, P., Vischer, D.L.: Design recommendations, pp. 91–100. Swirling flow problems at intakes, IAHR Hydraulic Structures Design Manual 1. Taylor & Francis, Balkema, Rotterdam, NL (1987)
- Sarkardeh, H., Zarrati, A.R., Jabbari, E., Roshan, R.: Discussion of prediction of intake vortex risk by nearest neighbors modeling. *J. Hydraul. Eng. ASCE* **137**(6), 701–705 (2012)
- Suerich-Gulick, F., Gaskin, J.S., Villeneuve, M., et al.: Characteristics of free surface vortices at low-head hydropower intakes. *J. Hydraul. Eng.* **140**(3), 291–299 (2014)
- Sun, H., Liu, Y., Zhang, H., et al.: Experimental studies on characteristics of vortex formed in front of radial gate. *Hydro Sci. Eng.*, 10–15 (2017). (in Chinese)
- Shen, C., Wang, W., He, S., et al.: Numerical and experimental comparative study on the flow-induced vibration of a plane gate. *Water* **10**(11), 1551–1551 (2018)
- Tian, T., Guo, R., Xu, G.: Research status and future directions of intake vortexes. *J. Water Resour. Water Eng.* **32**(05), 151–157+165 (2021). (in Chinese)

- Song, L., Yang, J.: Analysis of key factors inducing vortex formation at spillway tunnel intakes. *Technol. Innov. Appl.* (19), 210 (2016). (in Chinese)
- Wang, Y.: Research on plane gate-closing vibration and its influence on holding force. Tianjin University (2022). <https://doi.org/10.27356/d.cnki.gtjdu.2022.001156>
- Wang, Y.: Mechanical characteristics and the control measurement for the vertical vortex (Ph.D thesis). Tsinghua University, Beijing (2011). (in Chinese)
- Yan, G., Chen, F., Hu, Q.: Experimental study on inlet vortex and vortex elimination grids. In: *Proceedings of the Third National Conference on Hydraulics and Hydroinformatics*, pp. 338–343. Hohai University Press, Nanjing (2007). (in Chinese)
- Ye, M., Wu, C., Chen, Y., et al.: Model investigation and numerical simulation of vertical vortex. *J. Hydroelectr. Eng.* **26**(1), 33–36 (2007). (in Chinese)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Life-Cycle Carbon Reduction Benefit Analysis of Hydropower Projects—A Case Study of a Hydropower Project in Southwestern China

Gang Chen¹, Fangping Ma^{1(✉)}, Fang Peng¹, Dongliang Guan¹, Xingguo Feng¹,
Haoran Wang², Hong Zhang², and Wenyan He²

¹ CHN Energy Dadu River Hydropower Development Co., Ltd.,
No. 7, Tianyun Road, High-Tech Zone, Chengdu, Sichuan, China
8150015@qq.com

² Sichuan Energy Internet Research Institute, Tsinghua University, Beijing, China

Abstract. Hydropower is widely recognized as a representative clean energy source, and its large-scale development serves as a crucial initiative for promoting low-carbon transformation in the energy sector and implementing carbon neutrality strategies for China. Quantitative analysis of carbon reduction throughout the life cycle of hydropower projects is essential for clarifying their low-carbon attributes and advancing high-quality development in hydropower engineering. This study takes a large-scale hydropower project in western China as a case study, employing a 100-year life-cycle assessment framework with contemporaneous coal-fired power generation as the reference benchmark. We comparatively investigate the electricity generation and corresponding carbon reduction potentials under both static and dynamic technological conditions. The results demonstrate that under static technological assumptions, the project achieves lifetime electricity generation of 820 billion kWh, corresponding to 2.16 billion tons of CO₂ emission reductions. When considering dynamic technological factors including turbine efficiency degradation, advancements in supercritical (SC) and ultra-supercritical (USC) coal-fired technologies, and the progressive implementation of carbon capture, utilization, and storage (CCUS) technologies, the lifetime electricity generation decreases to 720 billion kWh with 1.43 billion tons of CO₂ reduction. In comparison, the dynamic scenario shows 12% reduction in total electricity generation and 34% decrease in carbon reduction potential relative to static conditions. This discrepancy primarily stems from two factors: gradual efficiency decline in hydropower turbines over operational lifespan, and significant reductions in carbon emission factors of coal-fired power due to technological innovations and CCUS adoption. These findings provide valuable insights for formulating carbon neutrality strategies in the energy sector. The methodology and comparative framework established in this study offer a reference paradigm for comprehensive life-cycle assessment of clean energy projects.

Keywords: Hydropower project · life-cycle · carbon reduction analysis · dynamic technological conditions

1 Introduction

Controlling global temperature rise necessitates urgent carbon emission mitigation. As one of the principal contributors to greenhouse CO₂ emissions, the energy sector requires accelerated decarbonization. The development of hydropower has been identified as a pivotal strategy for curbing carbon emissions in the energy industry. Assessments by scientists establish that the global hydropower capacity requires a 60% increase by 2050 to meet the carbon neutrality targets in the Paris Agreement [1]. Unfortunately, most of the existing assessment frameworks simply calculated the reduction in carbon emissions from converting hydropower capacity into an equivalent amount of thermal power, which inadequately addresses the century-scale of carbon emissions in the energy sector. The assessment framework of the reduction of carbon emissions for hydropower projects, with typical lifespans exceeding 80 years, requires reconciling many factors, like the long-term climate impacts, technological obsolescence, as well as policy-driven market shifts.

In the past several decades, scientists attempted to propose some new assessment frameworks to accurately estimate the CO₂ emission reduction of hydropower projects. The Carbon Border Adjustment Mechanism (CBAM), which was proposed by the European Union, still employed static emission factors to estimate the carbon emissions carbon emissions of hydropower projects. In the CBAM, the carbon emission factor of the thermal power was decreased from 820 gCO₂/kWh to 400 gCO₂/kWh. The Flexible Particle Dispersion (FLEXPART) Model, is innovative in regional hydropower analysis, and its max timespan was only 50 years [2]. This situation suggested that the FLEXPART model was unsuitable for large-scale hydropower projects, which were of 80 years even 100 years operational lifetimes. A model proposed by the Western Electricity Coordinating Council (WECC), the climate impact on the CO₂ emission reduction of hydropower projects mainly relies on the average annual runoff. A CO₂ emission model was proposed by The State Grid Corporations to assess the decarbonization in 2060, and a linear emission decay trajectory was adopted in the model. A model proposed by Tsinghua University indicated that the CO₂ emission reduction of hydropower projects was determined by the regional hydro-climate coupling effect [3]. The brief review suggested that the CO₂ emission reduction can be affected by many factors, like rainfall, climate change, as well as technological improvement both in hydropower and thermal power, in the life-cycle of hydropower projects.

2 Theoretical and Methodology

2.1 An Overview of the Hydropower Project

A large-scale hydropower project, which was completed and put into operation in 2010, located in southwest China was adopted to analyze its CO₂ emission reduction in the life cycle of 100 years. The installed capacity of the hydropower project was 3600 MW, and its average annual generation of 35.8 TWh in the past 14 years.

In the present study, the carbon emissions reduction of the hydropower project was obtained from the carbon emissions of the equivalent amount of thermal power generation. The carbon emission reductions were investigated under static technological

conditions and dynamic technological conditions, respectively. In the former condition, a constant value (820gCO₂/kWh [4]) of the carbon emission factor for the thermal power was adopted, and the carbon emission factor did not change in the whole life cycle. In the latter condition, three aspects were taken into consideration to accurately assess the carbon emission reductions of the hydropower project in the life cycle of 100 years. Firstly, a dynamic framework was proposed, which integrates climate projections (CMIP6 SSP2-4.5), equipment aging models (Weibull distribution, shape = 2.3), and policy-driven CCUS adoption curves. The carbon emission reduction was calculated according to Eq. (1).

$$\frac{dc}{dt} = E_h(t) \times [EF_C(t) - 4] \quad (1)$$

in which $EF_C(t) = 820 \times (1 - (1 - \beta_i)^{elapsed_i}) - CCUS_i \times 100 \times elapsed_i$, in the equation, both the technical progress of thermal power and the growth in the CCUS had been taken into consideration. Secondly, a hybrid Python-MATLAB computational architecture enables multi-threaded Monte Carlo simulations, incorporating 10000 Latin Hypercube Sampling (LHS) scenarios to quantify parameter uncertainties. Thirdly, the model generates policy-ready metrics, including CCUS delay penalties (−12% cumulative reduction per 5-year deployment lag) and climate resilience thresholds for reservoir operations.

2.2 Methodology

As Fig. 1 shows, a modeling framework that includes three interactively coupled modules was adopted to calculate the carbon emission reductions of the hydropower project in century-scale dynamics.

The climate driver processes, according to CMIP6 SSP2-4.5 precipitation data through the HBV-EC hydrological model [5], generating monthly runoff projections modulated by an 11-year solar cycle, as follows:

$$Q'(t) = Q_{CMIP6}(t) \times \left[1 + 0.05 \sin\left(\frac{2\pi t}{11}\right) \right] \quad (2)$$

Both long-term climate trends and decadal solar variability were accounted for the climate driver processes, which differs from the previous studies that adopted static runoff assumptions [6].

A maintenance-adjusted decay function, as shown in Eq. (3), was applied to simulate the turbine efficiency degradation.

$$\eta(t) = 0.85 - 0.0023t + 0.015\ln(t) \quad (3)$$

in addition, the function was validated by the operational data of the case hydropower project and three hydropower stations in the Yangtze River. Simultaneously, the CCUS was assumed to follow a logistic growth curve, which was calibrated to U.S. Department of Energy (DOE) 2045 targets, with $\gamma_{\max} = 75$ gCO₂/kWh.

The policy interface integrates carbon price impacts (20–120 USD/tCO₂) and enforces capacity factor constraints (40–85%), to reflect real power network operation.




Fig. 1. System architecture integrating climate drivers (blue), technology evolution (green), and policy interfaces (orange). Dashed lines represent feedback mechanisms, such as climate impacts on reservoir operations and policy-driven CCUS adoption rates.

In the modeling framework, feedback loops between modules can dynamically adjust. For instance, drought-induced runoff reductions, trigger capacity factor optimizations to maintain baseline power generation levels.

2.3 Dynamic Estimation of Power Generation of Hydropower Project

In the present study, as Eq. (4) shows, a model comprehensively considered physical, climatic, and operational parameters was applied to calculate the energy output ($E_h(y)$) of the hydropower project.

$$E_h(y) = E_h[y - 1] \times \left(1 + a_i \times \left(1 - \frac{y - start_i}{end_i - start_i} \times decay_i \right) \times tech_curve[y] \right) \quad (4)$$

For year y , when $y > 2023$, the hydropower energy output $E_h(y)$ grows based on its previous year's value. Which is adjusted by phased growth rates (α), decay effects, and a technology adoption curve. Three stages were defined for the case hydropower project, the first stage is 2024–2045 year, the second stage is the years from 2045–2075, and the last stage is from 2075 to 2110 year. The growth rates of the three stages were 5.0%, 3.5%, and 2.5%, while their annual decay rates were 0.2%, 0.3%, and 0.5%, respectively.

2.4 Carbon Emission of Thermal Power with CCUS

The carbon emission factor of the thermal power was a function of the progress of thermal power equipment [4] and the application of CCUS, as Eq. (5) shows.

$$EF_c[y] = 820 \times \left(1 - (1 - \beta_i)^{elapsed_i} \right) - CCUS_i \times 100 \times elapsed_i \quad (5)$$

For the carbon emission factor of thermal power, it also was divided into three phases, according to the previous study [7]. The phase-specific parameters was shown in Table 1, which reflects the historical data and policy projections. During 2010–2035 year, $\beta = 0.01$ aligns with China's 13th–14th Five-Year Plan efficiency targets. While 2035–2070 year, $\beta = 0.015$, which corresponds to ultra-supercritical plant retrofits. CCUS adoption transitions from linear growth (2010–2035) to logistic curves (2035–2070), capturing real-world deployment inertia [7].

Table 1. Phase-Specific Model Parameters

Phase	β (Annual Decay)	Adoption Curve
2010–2035	0.01	Linear
2035–2070	0.015	Logistic ($\lambda = 0.2$)
2070–2110	0.025	S-curve

2.5 Computational Implementation

A multi-stage workflow was conducted by applying the Python-MATLAB [8] hybrid platform. CMIP6 climate data and turbine performance records were imported as the initialization scripts. Monte Carlo subroutines were adopted to generate 10,000 LHS scenarios for uncertainty quantification [9]. Post-processing tools in MATLAB were used to generate probabilistic outputs, including 95% confidence intervals for emission trajectories and heat maps of climate-technology interactions.

3 Results and Discussion

3.1 Interpretation of Results

Through multi-scenario simulations, this study elucidated the dynamic decarbonization characteristics of hydropower in carbon neutrality pathways. Near-term mitigation efficacy is constrained by technological attrition and policy coordination, whereas long-term sustainability relies on CCUS scaling and PV storage integration. The baseline-dynamic scenario divergence highlights the coupled effects of technological iteration cycles and resource constraints, whereas the competitive evolution between coal cleaning and hydropower optimization defines the systemic decarbonization thresholds. A detailed analysis followed the four-figure framework.

As depicted in Fig. 1, the baseline scenario revealed a linear increase in cumulative life-cycle emission reductions from hydropower, reaching 2.16 billion tons of CO₂. In contrast, the dynamic scenario indicated a 34% reduction, amounting to 1.43 billion tons. The divergence between these scenarios is significant after 2040 and intensifies post-2080. These three primary factors influence the evolution of systemic efficiency. First, the annual efficiency degradation of hydraulic turbines is characterized by a decay




Fig. 2. The horizontal axis represents years (2010–2100), and the left vertical axis indicates cumulative CO₂ reduction (in billion tons). The green line denotes the baseline scenario, while the red line represents the dynamic scenario. Under the baseline scenario, total carbon reduction consistently exceeds the dynamic scenario, with the gap widening significantly after 2080.

rate of 0.2–0.5%. Second, the carbon emission factor of coal-fired power generation is projected to decrease substantially from 820 to 320 gCO₂/kWh by 2065. Third, the extensive commercial implementation of Carbon Capture, Utilization, and Storage (CCUS) technologies results in structural changes to the carbon footprint of the system (Fig. 3).




Fig. 3. The horizontal axis spans from 2010 to 2110. The left vertical axis measures hydropower development (unit: 100 MkWh), and the right vertical axis represents the coal emission factor (unit: gCO₂/kWh).

The analysis of the energy transition pathways depicted in Fig. 2 identifies two distinct trajectories. Hydropower generation remains stable from 2010 to 2030, subsequently reaching a plateau of 800 MkWh output post-2040, facilitated by advancements

in turbine technology. In contrast, the emission factor for coal exhibits a stepwise reduction from 850 to 250 gCO₂/kWh, followed by an exponential decline between 2040 and 2060. The historical convergence of these trajectories in 2060 signifies a critical transition point, wherein the emission mitigation achieved by hydropower surpasses the decarbonization efforts associated with coal.




Fig. 4. A stacked area chart illustrates the contributions of emission reduction phases: technological advancement (green) and CCUS (orange). Technological progress dominates before 2045, after which CCUS gradually becomes the primary contributor.

From 2020 to 2040, technological advancements will predominantly drive emission reductions, with ultra-supercritical retrofitting accounting for 83% of these reductions, as indicated by the decrease in the emission factor from 600 to 300 gCO₂/kWh. By 2040, Carbon Capture, Utilization, and Storage (CCUS) will contribute 40% to emission reductions, reaching an inflection point characterized by diminishing marginal returns. Post-2060, CCUS emerged as the primary mitigation strategy, contributing over 50%, and ultimately achieving a 70% contribution by 2100, with an emission factor of 100 gCO₂/kWh. The inflection point in 2080 highlights growth constraints in CCUS owing to storage limitations. Cross-validation with Fig. 2 identifies two strategic imperatives: the deployment of CCUS pilots in the near term, achieving over 30% coverage before 2040, and the implementation of long-term carbon pricing mechanisms exceeding \$80 per ton to address investment-resource bottlenecks (Fig. 5).

The logarithmic-scale evolutionary trajectory in Fig. 4 delineates three technological development phases: Phase I (2000–2040, $\eta = 1 \rightarrow 5$) constrained by conventional efficiency ceilings; Phase II (2040–2080, $\eta = 5 \rightarrow 15$) exhibiting J-curve growth driven by intelligent dispatch systems; Phase III (post-2100, $\eta = 15 \rightarrow 30$) demonstrating accelerated efficiency gains through photovoltaic-storage synergy innovations.




Fig. 5. The vertical axis uses a logarithmic scale to display the efficiency ratio (η), while the horizontal axis spans the timeline. The efficiency ratio exhibits periodic fluctuations at “Five-Year Plan” milestones (e.g., 2040 and 2080), influenced by technological advancements and equipment aging, resulting in distinct peaks and troughs across three phases.

3.2 Discussion and Improvement

This study elucidates the intricate and dynamic characteristics of carbon reduction benefits in hydropower projects throughout their entire life cycle by contrasting static and dynamic technical conditions. Initially, in dynamic models, the annual efficiency degradation of hydropower units, approximately 0.2%, results in a 12% reduction in total power generation compared to static assumptions.

This finding is consistent with empirical research conducted at the Gezhouba Hydropower Station, where a 17–22% efficiency decline was observed after a decade of operation due to sediment abrasion, blade deformation, and coordination system failures. The “mountain-shaped” [10] efficiency curve further underscores the nonlinear impacts of water flow and head conditions on efficiency. By incorporating efficiency degradation parameters, dynamic models can more accurately represent the cumulative effects of physical wear and changes in operational conditions [11].

Furthermore, supercritical (SC) and ultra-supercritical (USC) coal-fired technologies reduce carbon emission factors by 10–25% compared to traditional subcritical units [12], while phased CCUS adoption further compresses the emission intensity to 80 gCO₂/kWh. These advancements significantly lower baseline emissions in dynamic scenarios, thereby diminishing the substitution benefits of hydropower. For example, reducing the carbon emission factor of coal-fired units from 832 kgCO₂/MWh (SC) to 748 kgCO₂/MWh (USC) decreases the reduction in hydropower per MWh by 84 kgCO₂. Notably, CCUS retrofitting in Chinese coal plants can reduce the emission intensity to 135 gCO₂/kWh but increases the levelized cost of electricity (LCOE) by 332 RMB/MWh, highlighting the economic constraints on decarbonization potential.

4 Conclusion

By applying a full life-cycle dynamic assessment framework, we quantified the carbon reduction benefits of large hydropower projects in Southwest China and highlighted the critical impacts of technological evolution. Conclusions can be drawn from the results, as follows:

- (1) Sufficient attention should be paid to the efficiency degradation of the hydraulic turbine in its life cycle. An annual efficiency of 0.2% loss in hydropower turbines can reduce 12% electricity generation the life-cycle generation by 12%. Long-term efficiency monitoring systems and optimizing maintenance strategies were suggested to mitigate the efficiency degradation of the hydraulic turbine.
- (2) Under the static technological condition, the electricity generation of the case hydropower project is 820 billion kWh, meaning a reduction of 2.16 billion tons of CO₂ emission in its 100-year lifetime.
- (3) Under the dynamic technological condition, the carbon emission reduction of the hydropower project was affected by turbine efficiency degradation, advancements in supercritical (SC), ultra-supercritical (USC) coal-fired technologies, and the progressive implementation of carbon capture, utilization, and storage (CCUS) technologies. The electricity generation of the case hydropower project is 720 billion kWh, which equals 1.43 billion tons of CO₂ reduction.

Acknowledgement. The authors gratefully acknowledge financial support from the Scientific Research Program of CHN Energy Dadu River Hydropower Development Co., Ltd (No. DDH-QT-2024-013), Sichuan Province Postdoctoral Special Founding (No. TB2024024), Organized Research Project of Sichuan Energy Internet Research Institute, Tsinghua University (No. 35030240026), Tianfu Yongxing Laboratory Innovation Project (No. 2023CXXM12), Tianfu Yongxing Laboratory Science and Technology Key Project (2023KJGG16).

References

1. International Energy Agency (IEA): Hydropower Special Market Report. OECD Publishing (2021)
2. Zhang, J., Li, W., Chen, H.: Aging effects on the efficiency of hydraulic turbines: a case study of Three Gorges Dam. *Renew. Sustain. Energy Rev.* **131**, 109983 (2020)
3. Zhang, C., Wang, G.: Key issues in long-term operation of hydropower stations in the Yangtze River Basin. *J. Hydroelectr. Eng.* **40**(3), 1–13 (2021)
4. IPCC: Climate change 2022: Mitigation of climate change. Contribution of Working Group III to the Sixth Assessment Report. Cambridge University Press (2022)
5. Riahi, K., van Vuuren, D.P., Kriegler, E.: Mitigation pathways compatible with long-term goals. In: IPCC AR6 Working Group III Report (95–174). Cambridge University Press (2022)
6. Liu, Z., Wang, S., Huang, J.: Climate change impacts on hydropower generation in Southwest China: a multi-model assessment. *J. Hydrol.* **612**, 128230 (2022)
7. Global CCS Institute: Global status of CCS 2023 (2023)
8. McKinney, W.: Data structures for statistical computing in Python. In: Proceedings of the 9th Python in Science Conference, pp. 51–58 (2010)

9. MathWorks: MATLAB/Simulink users guide (R2023a) (2023)
10. Zambelli, M., Huamani, I.R.L., et al.: Hydropower scheduling in large scale power systems. InTech, 32649 (2012)
11. Kazantsev, Y., Glazyrin, G., et al.: Advanced algorithms in automatic generation control of hydroelectric power plants. *Mathematics* **10**, 4809 (2022)
12. Inter-American Development Bank Sustainability Report 2009

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





The Application of Inertial-Equilibrium Filling and Emptying System with Three-Dimensional Layered Energy Dissipation Structure in the Arrangement of 60m Single-Stage Lock in the Lower Reaches of Jinsha River

Zuoqiang Chen^{1,3}, Chao Guo²(✉), Jiangda He¹, and Wenming²

¹ School of Hydropower, Sichuan University, Chengdu 610065, China

² Key Laboratory of Navigation Structure Construction Technology Ministry of Transport, Nanjing Hydraulic Research Institute, Nanjing 210029, China
cguo@nhri.cn

³ Sichuan Port and Shipping Investment Group Co., Ltd., Chengdu 610041, China

Abstract. Aiming at the technical difficulties of efficient filling and emptying system, anti-cavitation design for filling/emptying valves, and adequate energy dissipation in the lock chamber posed by the construction of high head and large-scale locks in the lower reaches of the Jinsha River, a 60 m working head single-lift lock filling and emptying system was proposed, the arrangement scheme of inertia-equilibrium filling and emptying system with two-section four-manifold and three-dimensional layered energy dissipation. The cross-sectional dimensions of the the filling and emptying system culverts under this scheme were calculated, detailed configurations of energy dissipators and the upstream and downstream inlet types were comprehensively analyzed. By establishing a mathematical simulation model of the lock filling and emptying process, hydraulic parameters such as inertial length and resistance coefficient were estimated. The hydraulic characteristics of the filling and emptying process were analyzed, and the valve opening strategy was recommended. The calculation results show that under the recommended opening time of the filling and emptying valves, the filling and emptying time of the lock can meet the design requirements, and other hydraulic indicators of the filling and emptying system meet the specifications. The calculation results verify the feasibility of the layout of the 60 m level single-lift lock filling and emptying system, providing theoretical support and scientific basis for the planning of navigation facilities in the lower reaches of the Jinsha River.

Keywords: 60 m single-stage lock · three-dimensional layered configurations Filling /Emptying system · energy dissipators scheme · hydraulic characteristics

1 Introduction

In recent years, the volume of water transportation in the lower reaches of the Jinsha River has increased rapidly, the demand for transportation is strong, and the potential is huge. Vessel congestion and cargo transfer congestion have become prominent problems

restricting the development of shipping on the Jinsha River. It is urgent to accelerate the construction of high dam navigation structures for cascade hydropower stations in the lower reaches of the Jinsha River.

The lower reaches of the Jinsha River are characterized by high mountains, deep valleys, narrow waterways. The water level difference between the upstream and downstream of the hub can reach 300 m, with navigation water level variation of up to 60 m in the upper reaches, which poses higher requirements for the layout of navigation facilities. To accommodate the water level variation upstream of the hydropower stations, the working head of a single-stage lock will reach 60m, far exceeding the current highest actual head of single-stage lock in the world. It is necessary to overcome key hydraulic problems for water Filling and Emptying system in high head ship locks [1].

The United States and the former Soviet Union are the most representative in the field of high head ship lock research. The Uski-Kaminokorsky lock, built by the former Soviet Union, has a designed head of 42 m [5]. The United States also designed and built a number of high-head locks, including the Walte-butting lock [3]. China has also achieved fruitful results in the research of high head locks [7]. The Three Gorges double-line five-level ship lock, which was built in China, has a total designed head of 113 m and a maximum working head of 45.2 m in the middle level; The single-stage lock at Datengxia in Qianjiang, Guangxi, with a head of 40.25 m, is the world's largest single-stage lock in actual operation. The Nanjing Hydraulic Research Institute has conducted extensive research on the layout of water Filling/Emptying systems for high-head locks. Li Jun [6] Hu Ya ' an [3] et al. studied the effects of valve opening and closing rate, acting water head and other factors on the opening and closing force of the water Filling/Emptying valve of the high water head lock under the reverse arc gate form. The above research and design of these lock projects have greatly promoted [10].

The water Filling/Emptying system is the most fundamental technical challenge in lock design. It is not only related to the hydraulic characteristics of the lock's water Filling/Emptying process and the conditions of vessel mooring, but also to a series of issues such as the structural type of the lock and the flow conditions of the approach channel. Based on the overall layout of navigation facilities in the lower reaches of the Jinsha River hub and the variation range of navigation water levels upstream and downstream, this paper has selected a 60m single-stage lock water Filling/Emptying system suitable for navigation facilities in the lower reaches of the Jinsha River, and detailed arrangements have been made for the proposed inertial water Filling/Emptying system. The numerical simulation model was used to calculate and analyze the hydraulic characteristics of the water Filling/Emptying system, demonstrating the feasibility of the application of this complex isoinertial water Filling/Emptying system in a 60m single-stage ship lock in the lower reaches of the Jinsha River.

2 Layout of a 60m Single-Stage Ship Lock Water Filling/Emptying System

To analyze and study the feasibility of single-stage water Filling/Emptying system for 60 m head lower locks in the lower reaches of the Jinsha River, the following parameters are used to design the overall scheme: Effective dimensions of the lock is 280.0 m ×

34.0 m × 8.0 m (effective length × effective width × threshold water depth), and the maximum water head is 60 m, designed water delivery time about 17 min. The maximum passable vessel tonnage is 8000 tons, and the maximum ship type dimensions are 130 m × 16.3 m × 5.5 m (length × width × draft). The lock can transport 633,000 m³ of water in one transfer, which is 2.65 times that of the intermediate stage of the Three Gorges Lock, facing the rapid dissipation of water flow energy within the lock chamber. There is a huge challenge of ensuring the safety of the water valve equipment of the lock and the mooring safety of ships in the lock chamber.

2.1 Selection of the Water Filling/Emptying System for Locks

For high head locks, the most commonly used system at home and abroad is the isoinertial water Filling/Emptying system. In the preliminary design stage of the Datengxia ship lock [10], a comparative study was conducted on the two layout forms of two sections with four corridors and four sections with eight corridors, and the results of the physical model test of the water Filling/Emptying system showed that both forms of the equilateral inertial water Filling/Emptying system could meet the water Filling/Emptying requirements.

The effective planar dimensions of the 60 m single-stage ship lock in the lower reaches of the Jinsha River, which are 280 m × 34 m, are the same as those of the Datongxia ship lock. The working water head is nearly 20 m higher, and it is also proposed to adopt the form of the isoinertial water Filling/Emptying system with the main corridor of the lock wall and the three-dimensional diversion in the middle of the lock chamber. Considering that the lock chamber can accommodate two maximum design ship types longitudinally and two maximum design ship types laterally, the outlet section of the lock chamber is arranged with two sections and four corridors, taking into account the dimensions of the vessels passing through the lock and the force exerted by the water flow on the vessels.

2.2 Water Filling/Emptying Valve Section

According to the relevant specifications, the cross-sectional area of the corridor at the water Filling/Emptying valve can be calculated by the following formula:

$$\omega = \frac{2C \cdot (\sqrt{H+d} - \sqrt{d})}{\mu T \sqrt{2g} [1 - (1 - \alpha)k_v]} \quad (1.1)$$

In the formula, ω - the cross-sectional area of the corridor at the water delivery valve (m²); C - Water area of the lock chamber (m²), taken as 323.4m × 34m; H -- Design head (m), take 60m; d - Inertial overdrop (m), with reference to the experience of previous high-head lock projects, takes 1.00m. μ - Flow coefficient of the water delivery system when the valve is fully open, also based on previous engineering experience, take 0.7; T -- Chamber water Filling/Emptying time (s), take 17min, that is 1020s; α - coefficient, which can be taken as 0.477 according to the Code for Design of Ship Lock; k_v - The ratio of valve opening time to lock chamber water Filling/Emptying time, taken as 0.5; g - Gravitational acceleration (m/s²).

According to the above formula, the area of the valve for the 60 m single-stage ship lock is 64.14 m^2 .

The corridor of the gate wall connects the sections of the water inlet and outlet valves and the manifold of the gate chamber respectively. Not only the structural requirements and the flow conditions of the manifold need to be considered, but also the flow coefficient of the water Filling/Emptying system and the flow velocity of the cross-section need to be taken into account. If the flow velocity is controlled at 15 m/s , the section of the main corridor of the gate wall is $2 \sim 5.5 \text{ m} \times 8.0 \text{ m} = 88.0 \text{ m}^2$, and the ratio of the area of the corridor section at the water Filling/Emptying valve is 1.33.

The water Filling/Emptying valve of the ship lock operates frequently every day under complex working conditions, and the hydrodynamic problem of the valve is also more prominent [13] under non-constant high-speed water flow conditions. Valve cavitation is also the most critical technical challenge in the design of water Filling/Emptying systems for high-head locks. The latest research results on valve cavitation show that the valve cavitation problem of a 60 m single-stage lock can be solved by a combination of active and passive protection technology of “lintel natural ventilation + top and bottom protrusion corridor type + comprehensive ventilation measures”. This technique improves the cavitation conditions at the bottom edge of the valve by determining the reasonable shape of the valve section corridor, and minimizes the intensity of the bottom edge cavitation. If cavitation still exists at the bottom edge after optimizing the shape of the valve section corridor, it can be solved by using natural ventilation of the lintel. For the valve section corridor shape, the advantages of the top bulge to increase the pressure behind the gate, reduce pulsation and the bottom bulge to improve the flow pattern of the bottom edge are absorbed. For the cavitation that may occur in the bulge itself, ventilation is adopted to reduce the erosion [2].

It is determined that the valve section corridor of the 60 m single-stage ship lock downstream of the Jinsha River will adopt the valve rear corridor shape with top and bottom expansion, with the drop step type and the rise step type of “higher order curve”. The initial selection of the valve top burial depth for the water filling and discharge valve section is 30 m. Based on previous engineering and research experience, the relative cavitation number of the valve can be controlled between 0.6 and 0.7, which is basically consistent with the relative cavitation number of the domestic 30–40 m class high-head ship locks (valve burial depth 13–22 m), combined with other aeration protection measures, The cavitation problem of the 60 m class high head valve can be solved.

2.3 Chamber Energy Dissipation Scheme

During the filling and emptying process, the instantaneous pressure along the length of the longitudinal branch corridor of the gate chamber is different, so the instantaneous water output of each outlet branch hole of the branch corridor is different. To avoid adverse longitudinal ratio drop within the chamber, the outlet branch holes should be arranged in sections with certain dimensional variations [9].

For the 60 m head of the single-stage ship lock in the lower reaches of the Jinsha River, a more complex “open channel + grille” three-dimensional layered energy dissipation arrangement was proposed in the decentralized water Filling/Emptying system

energy dissipation facility technology (Fig. 1), that is, longitudinal energy dissipation was carried out through the open channel for the outflow from the side branch holes, and secondary horizontal energy dissipation was carried out through the grille for the outflow from the open channel. Four longitudinal branch corridors are set up in the lock chamber, with cross-sectional dimensions and areas ranging from 4 to $5.0\text{ m} \times 8.0\text{ m}$ (number of branches $\sim$ width $\times$ height) $= 160\text{ m}^2$. 21 outlet branch holes are arranged on each side of the longitudinal branch corridor. Along the first diversion outlet in the center of the lock chamber towards the end of the branch corridor, each side outlet branch hole is evenly divided into 3 groups, with 7 holes in each group. The orifices (width $\times$ height) are $0.50\text{ m} \times 1.5\text{ m}$, $0.45\text{ m} \times 1.5\text{ m}$ and $0.40\text{ m} \times 1.5\text{ m}$ respectively, with a total area of 1123.4 m^2 , and the ratio to the cross-sectional area of the valve is 1.72. On each side of the longitudinal branch corridor, a 105 m long, 3.0 m wide, 6.0 m deep energy dissipation open channel is set along the length direction of the lock chamber.

At the top outlet of each open channel, there are 42 equally spaced and equally sized energy dissipation grilles for secondary energy dissipation and adjustment of the water flow entering the gate chamber. The center spacing of the grille outlet holes is 2.5 m, the size of the grille outlet holes is $3.0\text{ m} \times 1.5\text{ m}$ (length $\times$ width), the total area of the grille outlet holes is $842 \times 1.5\text{ m} \times 3.0\text{ m} = 1512\text{ m}^2$, the ratio of the valve area is 22.91.




Fig. 1. Layout of branch culverts and energy dissipators in a lock chamber

2.4 Upstream and Downstream Water Inlets and Outlets

Based on the water delivery time $T = 17\text{ min}$, the maximum flow rate of the 60 m single-stage ship lock is estimated to be approximately $1100\text{ m}^3/\text{s}$. The more economical and reasonable layout is the front vertical multi-hole layout. The flow velocity at the inlet of the decentralized water delivery system should not be greater than 2.5 m/s, so the total area of the water inlet of the lock should be greater than 440 m^2 . The size of the water inlet is 2 to $8 \times 5.0\text{ m} \times 6.0\text{ m} = 480\text{ m}^2$ (number of holes $\times$ width $\times$ height), and the specific layout is shown in Fig. 2. At the same time, the inundation depth of the inundation should meet the requirement of more than 0.4 times the head as stipulated in the specification.




Fig. 2. Layout of the water inlet for the Filling/Emptying system

For a single-stage lock with an effective area of 280 m × 34 m and a head of 60 m, the flow rate of the lock’s water inlet and outlet is huge. If all the water inlet and outlet are arranged in the approach channel, the flow velocity in the approach channel will exceed the standard. Partial side water inlet and outlet arrangements or increasing the bottom width of the approach channel must be adopted to significantly reduce the flow velocity in the approach channel. The side arrangement is more effective in improving the flow conditions of the approach channel, and the engineering volume is also more economical. In fact, almost all the high-head locks built at home and abroad have adopted this layout, especially in the United States, almost all locks with a head of over 30 m have adopted the side-side water intake and discharge layout. Typical projects include the Lower Granite lock on the Stone River in the United States, and the upstream and downstream locks of the Tucurui Hub on the Tocantins River in Brazil. Therefore, to address the water flow conditions of the approach channel, the 60 m single-stage lock adopts the side-discharge layout.

2.5 Characteristic Scale and Overall Layout of the Water Filling/Emptying System

After comprehensive analysis and comparison, it is proposed to adopt the overall layout scheme of the main corridor of the gate wall, the three-dimensional diversion in the middle of the lock chamber, and the four longitudinal branch corridors of the two sections at the bottom of the gate. The energy dissipation work of the lock chamber adopts the “open ditch + grid” three-dimensional layered energy dissipation type. The characteristic dimensions of each part of the water Filling/Emptying system are shown in Table 1. The layout of the water Filling/Emptying system of the 60 m single-stage ship lock is shown in Fig. 3.

Table 1. Characteristic summary of the filling and emptying system in 60 m lock

Part	Area (m ²)	Ratio to the area of the F/E valve	Description
Upper gate head water inlet	480.00 112.875	7.27 1.57	The guide wall takes in water through multiple vertical holes on the side

(continued)

Table 1. (continued)

Part	Area (m ²)	Ratio to the area of the F/E valve	Description
			The width of the throat section decreases in sequence along the direction of the water flow
Water delivery valve section Corridor	66.00	1.00	Expand the corridor type behind the valve
Main water delivery corridor	88.00	1.33	The main water corridor is connected to the water filling/emptying valve section corridor by slope
manifold	108.80	1.65	Located in the middle of the lock chamber, the diversion tongue is arranged in the main corridor
The outlet section of the lock chamber Corridor	160.00	2.42	Two sections, two outlet branch corridors in each section
Outlet side support holes	113.40	1.72	There are 21 outlet branches on each side of each branch corridor, divided into three groups in the direction of water flow. The widths of the openings are 0.50 m, 0.45 m and 0.40 m respectively, the height of the openings is 1.5 m each, the intervals between the outlet branches are 5.0 m, and the total length of the outlet section is 210 m
Energy dissipation open ditches	/	/	Each energy dissipation channel is 3.0 m wide and 6.0 m deep, arranged on either side of each water outlet branch channel
Grille outlet holes	1512.00	22.91	At the top of each energy dissipation open channel, there are 42 grid water outlets of 3.0 m × 1.5 m

(continued)

Table 1. (continued)

Part	Area (m ²)	Ratio to the area of the F/E valve	Description
Lower sluice head outlet	187.50	2.84	Adopt a fully side-drain type




Fig. 3. Layout of the filling/emptying system for 60 m ship lock

3 Mathematical Model and Parameter Estimation

3.1 Mathematical Model of Water Filling/Emptying Process

According to the Bernoulli equation, equations of non-constant flow describing the water transfer process of a single-stage lock can be given.

$$h_1 - h_2 = (\zeta_1 + \zeta_{v1}) \frac{Q_1^2}{2gA_1^2} + (\zeta_2 + \zeta_{v2}) \frac{Q_2^2}{2gA_2^2} + \frac{L_1}{gA_1} \frac{dQ_1}{dt} + \frac{L_2}{gA_2} \frac{dQ_2}{dt} \quad (2.1)$$

$$h_0 - h_2 = \zeta_0 \frac{Q_0|Q_0|}{2gA_0^2} + (\zeta_2 + \zeta_{v2}) \frac{Q_2^2}{2gA_2^2} + \frac{L_0}{gA_0} \frac{dQ_0}{dt} + \frac{L_2}{gA_2} \frac{dQ_2}{dt} \quad (2.2)$$

$$Q_1(t) = -S_1 \frac{dh_1(t)}{dt} \quad (2.3)$$

$$Q_0(t) = -S_0 \frac{dh_0(t)}{dt} \quad (2.4)$$

$$Q_2(t) = S_2 \frac{dh_2(t)}{dt} \quad (2.5)$$

$$Q_2(t) = Q_0(t) + Q_1(t) \quad (2.6)$$

In the formula, h represents the water levels of each chamber; A represents the calculated cross-sectional area of each corridor; S represents the water area of each chamber; Q represents the flow rate of each corridor section; ζ is the drag coefficient of each corridor section; ζ_v is the coefficient of resistance for each valve; L is the converted length of the corridor; g is the acceleration due to gravity.

By using the difference method to solve the system of equations, the variation curves of the hydraulic characteristic values such as the flow rate and the water level during the water Filling/Emptying process of the ship lock were obtained.

3.2 Estimation of Basic Hydraulic Parameters

After the layout of the water Filling/Emptying system is completed, the resistance coefficient and flow coefficient of the water Filling/Emptying system when the valves are fully open, the converted length of the water Filling/Emptying system, and the overelevation and overdrop of the lock chamber and other basic hydraulic parameters [10] Considering the three-dimensional stratified energy dissipation system type for the 60 m single-stage lock, the flow coefficient for water filling system is 0.730 and for water emptying system 0.680 in the hydraulic calculation. In addition, the conversion length for water Filling and Emptying systems are 284 m and 269 m respectively.

3.3 Verification Calculation

To verify the accuracy of the mathematical model for water filling/emptying systems of the Three Gorges lock, the hydraulic characteristic curves of water conveyance measured by the prototype of the two lock chambers of the Three Gorges Lock were used to verify the mathematical model. As can be seen from Fig. 4, the maximum error between the maximum water flow rate calculated by the mathematical model and the maximum water filling/emptying time of the lock and the actual measurement of the prototype is only 0.50% and 2.25% respectively. The difference between the hydraulic characteristic values observed by the mathematical model and the prototype is small. Therefore, it is accurate and reliable to use this mathematical model for the analysis of the hydraulic characteristics of the lock water Filling/Emptying process.




Fig. 4. Comparison between Prototype-Observed discharge hydrographs and mathematical model computed values

4 Hydraulic Characteristics of Water Filling/Emptying System in a 60 m Lock

According to the water level combination of the 60 m lock and the operation mode of the water valve, the maximum head condition is considered in this stage. The water delivery mode of the lock only considers the opening of the valves on both sides for filling and emptying water, and the opening time of the filling valve is considered as 8.0, 10.0, 12.0, 14.0 min. The opening time of the emptying valve is considered to be 6.0, 8.0, 10.0, 12.0 min.

The hydraulic characteristics such as the water filling/emptying time, maximum flow rate, and the rate of rise of the water level in the lock chamber, which are calculated for the 60m ship lock using the three-dimensional energy dissipation water delivery system type, are shown in Table 2.

Table 2. Hydraulic characteristics of chamber in 60 m lock filling/emptying systems

<i>process</i>	t_v (min)	T (min)	Q_{max} (m^3/s)	U_{max} (m/min)	d (m)	$v_{\text{进}max}$ (m/s)
Filling	8	15.55	1190.27	6.54	0.91	2.48
	10	16.47	1102.77	6.07	0.91	2.30
	12	17.38	1025.98	5.65	0.91	2.14
	14	18.30	958.93	5.28	0.91	2.00
Emptying	6	15.52	1217.39	6.68	-0.75	\
	8	16.40	1129.37	6.21	-0.75	\
	10	17.27	1051.22	5.79	-0.75	\
	12	18.15	982.36	5.41	-0.75	\

Note: t_v is the opening time of the valve, T is the water Filling/Emptying time, Q_{max} is the maximum flow rate of water, U_{max} is the maximum rising (falling) speed of the water surface in the lock chamber, $v_{\text{进}max}$ is the maximum flow velocity at the cross-section of the inlet; d is inertial superelevation (drop), where “+” indicates superelevation and “-” indicates superelevation

As shown in Table 2, when the working head of the lock is 60.00 m, the opening time of the water filling valve is $t_v = 8\text{--}14$ min, then the water filling time of the chamber is 15.35–18.10 min, and the maximum water filling flow rate of the chamber is 1190.27–958.93 m^3/s , the maximum flow velocity in the main corridor of the lock wall is 14.43 to 11.62 m/s, and the maximum flow velocity at the manifold is 10.93 to 8.81 m/s. The maximum flow velocity in the branch corridor at the bottom of the chamber is 6.61–5.33 m/s, the maximum flow velocity at the inlet of the water filling corridor is 2.48–2.00 m/s, and the inertial overheight during water filling is 0.91 m.

If the opening time of the emptying valve is $t_v = 6\text{--}12$ min, the corresponding emptying time of the chamber is 15.52–18.15 min, and the maximum flow of the chamber is 1217.39–982.36 m^3/s , the maximum flow velocity in the main corridor of the chamber wall is 14.76 to 11.91 m/s, and the maximum flow velocity at the manifold is 11.19 to 9.03 m/s. The maximum average flow velocity in the branch corridor at the bottom of the chamber is 6.76 to 5.46 m/s, and the inertial overdrop during water discharge is 0.75 m.

In summary, when the opening time of the water filling valve $t_v \leq 12$ min and the opening time of the water emptying valve $t_v \leq 10$ min, the water filling/Emptying time of the ship lock can meet the design requirement of about 17 min. In actual operation, the water Filling/Emptying valve needs to be closed in advance and the gate should be opened when the water level is the same to reduce the inertial superelevation (drop) of the water in the lock chamber. Under the recommended water filling opening mode, the maximum energy density during water filling in the lock chamber is $1.89 \text{ kW}/\text{m}^3$, which is slightly greater than that of the Three Gorges Lock ($1.86 \text{ kW}/\text{m}^3$) but less than that of the Datengxia Lock ($1.97 \text{ kW}/\text{m}^3$), indicating that under the unit volume of water in the lock chamber, This paper proposes that the energy of the water conveyance flow of the inertial water Filling/Emptying system such as three-dimensional stratified energy dissipation of the 60m single-stage lock is comparable to that of the Three Gorges Lock and slightly less than that of the Datengxia Lock, without adversely affecting the mooring conditions of ships in the lock chamber. Under the recommended water-filling opening mode, the flow velocity of the main corridor of the lock wall and the inlet meets the specification requirements, and the maximum average flow velocity at the manifold is less than that at the Three Gorges Lock manifold (15.9 m/s). Further research should be conducted on valve air defense measures such as aeration protection in the hydrodynamic study of the ship lock valve (Fig. 5).




Fig. 5. Hydraulic characteristic curves under different valve opening modes in 60 m head lock chamber

5 Conclusions

- 1) It is recommended that the water Filling/Emptying system of the 60 m single-stage ship lock in the lower reaches of the Jinsha River adopt the overall layout scheme of the main corridor of the lock wall, the three-dimensional diversion in the middle of the lock chamber, and the two sections and four longitudinal branch corridors at the bottom of the lock. The energy dissipation work of the lock chamber should adopt the hierarchical energy dissipation form of “open ditch + grid”. According to the water level characteristics of the upstream and downstream of the lock, the valve area of the water Filling/Emptying system in the lock chamber, the energy dissipation work in the lock chamber and the inlet and outlet were arranged in detail in accordance with the design specifications.
- 2) The hydraulic characteristic value index for water Filling/Emptying system of the 60 m single-stage lock was calculated. It is recommended that the water filling valve be opened on both sides for 12 min and the water emptying valve be opened on both sides for 10 min in a continuous opening mode, and the water Filling/Emptying time of the lock can be controlled at about 17 min; It is suggested that the inundation depth of the Emptying valve be increased to 33 m, and other hydraulic indicators of the water Filling/Emptying system meet the specifications and design requirements, demonstrating the feasibility of the three-dimensional layered energy dissipation water Filling/Emptying system type and detailed layout for the 60 m single-stage ship locks in the lower reaches of the Jinsha River.

Acknowledgments. This study was supported by National Key Research and Development Program (SQ2023YFC3200166).

References

1. Chen, G.: Optimization of Water Conveyance System Type for Ultra-High Head in Mountainous Rivers. Chongqing Jiaotong University, Chongqing (2013). 2013 locks in mountain rivers. Chongqing Jiaotong University (in Chinese)
2. Fu, W., Chen, H.: Research on hydraulics of ship lock valves at Angu Hydropower Station. *Water Transp. Eng.* **2009**(12), 165–167, 173. (FU Wenzhou) CHEN Donghe. Study on hydraulics of lock valve of Angu Hydraulic Power Station. *Port and Waterway Engineering*, 2009(12), 165–167, 173. (in Chinese)
3. George, J.F.: Filling and emptying system, walter bouldin lock, and lock culvert valve for coosa river waterway. Alabama: Hydraul. Model Investig. (1984). Technical Report-US Army Engineer Waterways Experiment Station, TR HL-84-8, WES
4. Hu, Y., Yan, X., Xue, S.: Study on the characteristics of opening and closing force of water conveyance valve in high head locks. *Water Transp. Eng.* **2021**(2), 1–6. (HU Yaan, YAN Xiujun) XUE Shu. Study on hydrodynamic hoist load characteristics of filling and emptying valve in high head navigation lock. *Port and Waterway Engineering* 2021(2), 1–6. (in Chinese)
5. Li, J.: Numerical simulation study on the energy dissipation characteristics of the open channel in the lock chamber under the condition of Super high water transmission power (2018). LI Jingxian. Numerical simulation study on the energy dissipation characteristics of open ditch in lock chamber under the condition of ultra-large water transmission power[D]. Chongqing Jiaotong University (in Chinese))

6. Liu, M.: Characterization of Net Moving Water Opening and Closing Force of High Head Lock Water Delivery Valve. Nanjing Hydraulic Research Institute (2008). High head lock transfer valves. Nanjing Hydraulic Research Institute (in Chinese)
7. Li, J., Xuan, G., Huang, Y., et al.: Application of equal-inertial two-section dispersed water delivery system in a 40 m class single-stage giant lock. *Water Transp. Eng.* **2016**(12), 20–25. (LI Jun, XUAN Guoxiang, HUANG Yue) et al. Application of two-section four-manifold total-balanced filling and emptying system in 40m-grade single-step giant ship lock. *Port and Waterway Engineering*, 2016(12), 20–25. (in Chinese)
8. Li, Y., Du, Z., Tang, Z.: Design and layout of water conveyance system for datengxia lock. *Northeast Water Resour. Hydropower* **39**(10), 5 (2021). (LI Yawen, DU Zepeng) Tang Zhenhua. Design arrangement of water conveyance system at Daiteng Gorge Lock. *Port and Waterway Engineering*, 2021(2), 1–6. (in Chinese)
9. Lu, H.: Study on filling and emptying system of Guiping II Ship Lock. *Waterw. Port* **30**(5), 365–368 (2009). Second-line shiplock chamber wall structure. *Journal of Waterway and Harbor*, 2009, 30(5), 365–368. (in Chinese)
10. Li, J., Xuan, G.: Layout and hydraulic calculation analysis of the water conveyance system of the navigation lock for the water level control project below the Shuikou Hub Dam of the Minjiang River. *Water Transp. Eng.* **2011**(03), 121–125, 136. (LI Jun) XUAN Guoxiang. Arrangement and hydraulic computation of the lock filling and emptying system of the downstream water level regulation project for Shuikou hydro-junction. *Port and Waterway Engineering* 2011(03), 121–125, 136. (in Chinese)
11. Xu, D.: Study on Water-Saving Arrangement and Hydraulic Characteristics of 60 m Class Locks. Hohai University, Nanjing (2020). *Ship lock*. Nanjing: Hohai University, 2020. (in Chinese)
12. Yang, L.: Overview of high head lock construction and scientific research in the Soviet Union. *Water Transp. Eng.* **1986**(02), 21–25. research in the USSR. *Port and Waterway Engineering*, 1986(02), 21–25. (in Chinese)
13. Yan, X., Hu, Y., Wu, L., et al.: Research on anti-air defense measures for Ship Lock Valves in Qianwei. *Water Transp. Eng.* (06), 125–129 (2016). (YAN Xiujun, HU Yaan, WU Liguang) et al. Cavitation defense measures for valve of Qianwei ship lock. *Port and Waterway Engineering*, 2016(06), 125–129. (in Chinese)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Response of Oxbow Lake Morphology to Hydrological Connectivity Changes: A Case Study of Shangchewan in Middle Yangtze River

Xiaoguang Liu^{1,2(✉)}, Shiming Yao^{1,2}, Bing Ding^{1,2}, and Shuo Guan^{1,2}

¹ Key Laboratory of River and Lake Regulation and Flood Control in the Middle and Lower Reaches of the Yangtze River, Ministry of Water Resources, Wuhan 430015, China

lxgwhu@foxmail.com

² Changjiang River Scientific Research Institute, Wuhan 430015, China

Abstract. Shangchewan Oxbow is a typical abandoned river channel in the middle reaches of the Yangtze River, serving critical functions in species protection, biodiversity conservation, and water supply. To investigate the evolution of its physical morphology and the corresponding response of hydrological connectivity, remote sensing interpretation was used to extract the waterbody morphology from 1990 to 2021. Physical morphology indices-including the shoreline development index, morphological development index, and contraction index-were identified and computed. A combined Lasso regression and Mann–Kendall (MK) trend analysis was then applied to characterize nearly 30 years of morphological evolution. In addition, a method for calculating the hydrological connectivity between the abandoned channel and the main stream of the Yangtze River was proposed, and the impacts of connectivity on physical morphology (including key threshold ranges) were analyzed. The results indicate that both the shoreline development index and morphological development index have increased significantly following the operation of the Three Gorges Reservoir, while the contraction index has declined. These trends reflect an ongoing evolution toward an oxbow-lake form and an increasing influence of human activities. In addition, the narrowing of the meander section and sedimentation of the downstream portion of the channel are evident. The balance thresholds for hydrological connectivity with respect to the morphological development and contraction indices are determined as [1.75, 2.15] and [2.1, 2.5], respectively. When the connectivity exceeds 2.5 or falls below 1.75, the oxbow is at risk of gradual disappearance.

Keywords: Shangchewan Oxbow · Remote Sensing Interpretation · Physical Morphology · Hydrological Connectivity · Response Characteristics

1 Introduction

An abandoned river channel (or “oxbow”) is a remnant of a meandering river that has been cut off from the active channel due to natural evolution and anthropogenic influences. In the abandoned channel, the former inlet or outlet becomes silted over time, eventually

forming a closed or semi-enclosed shallow water lake. In recent years, sedimentological and chronological methods have been successfully employed to back-calculate fluvial evolution, cutoff timing, and historical flood events within such channels [1]. On the other hand, the unique hydrogeological conditions of oxbow lakes make them typical riparian wetland habitats [2]. Changes in the hydrological linkages between the abandoned channel and the main river have increasingly drawn the attention of researchers for their implications on water quality and aquatic biota [3–5]. Although the mutual dependence between river channels and floodplain lakes is largely governed by seasonal flood pulses and water level fluctuations [6], the physical morphology of the oxbow remains a critical factor in determining the characteristics of material exchange [3]. Thus, the evolution of an oxbow's morphology not only reflects the influence of hydrological connectivity and human activities but also serves as a key indicator of habitat conditions.

The unique hydrogeological setting of the Jingjiang River has resulted in the largest distribution of abandoned river channels in China. Among these, the Shangchewan Oxbow-located along the naturally connected section of the lower Jingjiang-is especially representative [7]. With habitat conditions similar to those of the main channel, Shangchewan Oxbow offers an excellent environment for numerous species. A designated provincial nature reserve for the protection of the Yangtze finless porpoise (and other species) has been established in its vicinity, highlighting its importance as a natural gene pool and biodiversity hotspot. The morphology of Shangchewan Oxbow is primarily influenced by variations in water and sediment conditions in the adjacent Jingjiang River, as well as by surrounding socio-economic activities. Changes in the hydrological connectivity between the oxbow and the river consolidate the exchange of water, sediments, and kinetic energy, which in turn directly affect sediment input/output, water flow erosion, and water level fluctuation-key processes that govern morphological evolution.

2 Study Area and Data Sources

Shangchewan Oxbow was formed as a result of an artificial meander cutoff project implemented from December 1968 to January 1971. Its upper entrance has become completely silted, while the lower outlet remains naturally connected to the main stream of the Yangtze River via a connecting waterway approximately 3.9 km in length. In flood years, the oxbow is largely in hydrological communication with the main channel throughout the year. The oxbow has an approximate length of 33 km and plays an important role in species conservation and water supply for production and daily use (Fig. 1).

In this study, remote sensing imagery and interpretation were performed based on the Google Earth Engine (GEE) platform. Landsat 5, Landsat 7 ETM +, and Landsat 8 imagery served as the primary data sources. Because the analysis of morphological evolution is best represented by images acquired during the dry season, all selected satellite images were extracted from the period of January to March-even though the waterbody areas may slightly vary. In the period from January 1990 to December 2021, a time filter was applied to select all available Landsat surface reflectance images for each year. Cloud and shadow pixels were masked using the CFmask algorithm based on pixel quality assessment. The modified normalized difference water index (MNDWI)




Fig.1. Map of Shangchewan Oxbow in the lower Jingjiang reach of the middle Yangtze River.

was then used to delineate the water boundaries of the oxbow. Based on the results of Boothroyd et al. [8], the MNDWI threshold was set at -0.05 (with values greater than -0.05 defined as flooded areas and those less than -0.05 as non-flooded). Figure 2 shows the spatial extraction of the water boundaries for Shangchewan Oxbow from 1990 to 2021. After obtaining the long-term waterbody extents, tools such as Spatial Analyst in ARCGIS were used to derive yearly parameters including the waterline, surface area, perimeter, central axis, and length of the connecting waterway.




Fig. 2. Spatial Delineation of the Shangchewan Oxbow Waterbody Extracted from Remote Sensing Data (1990–2021)

3 Results and Analysis

3.1 Key Morphological Parameters

This study employs characteristic index analysis to assess the relationships among several representative indices and their correlations with the water surface area, with the objective of elucidating the morphological evolution of Shangchewan Oxbow over the past 30 years.

An abandoned channel, as a relic of a meandering river, preserves the morphological imprints of the river's evolution. Weihaupt et al. [10] conducted an extensive field survey of oxbow lakes along the Yukon River (North America) and classified them into simple, composite, and complex types according to their morphological characteristics. Similarly, Li Zhiwei et al. [1] categorized abandoned channels into Ω , U-shaped, and crescent-shaped forms to illustrate different stages of morphological evolution. Wang et al. [11] proposed using the shrinkage ratio and curvature to characterize the physical morphology of an oxbow and to determine the relationship between the channel's connectivity and water quality.

To quantify the impact of adjacent human activities on morphology and to assess the integrity and clustering of spatial data features, this study introduces the shoreline development index (SDI), which is defined as:

$$SDI = P / 2\sqrt{\pi A} \quad (1)$$

where P is the total length of the oxbow's shoreline (m) and A is the waterbody area (m^2). A larger SDI indicates a more convoluted shoreline; in riverine settings, a highly indented shoreline suggests a greater degree of anthropogenic influence and a lower proportion of natural shoreline.

Based on the classification methods proposed by Weihaupt et al. [10] and Li Zhiwei et al. [1], Shangchewan Oxbow primarily exhibits a U-shaped morphology—a critical stage in the evolution toward an oxbow-lake form. To better characterize this evolution, the morphological development index (MD) is introduced as:

$$MD = L / \sqrt{4A/\pi}, \quad (2)$$

where L is the length of the central axis of the oxbow (m). An MD value greater than 1 indicates a pronounced oxbow-lake development; higher MD values denote an increasingly open (meander-dominated) morphology, whereas lower values suggest accelerated closure of the inlet and outlet, transitioning the oxbow toward a crescent shape.

To capture early changes that typically occur at the channel heads and at the connecting passage to the river, the contraction index (RS) is defined as:

$$RS = W / (W + L_d + L_u), \quad (3)$$

where W is the average width of the oxbow (m), L_d is the length of the lower connecting waterway, and L_u is the length of the upper connecting channel (m). RS ranges from 0 to 1. Values approaching 0 indicate a higher degree of lake-like conditions with weaker

connectivity to the river, whereas values near 1 indicate a more river-like channel strongly influenced by the main channel.

Since there is currently no universally accepted method for quantifying hydrological connectivity between river and lake systems, this study proposes a connectivity index (CON) that incorporates both the available water volume and the conveyance capacity of the connecting channel, while also accounting for the background water volume of the oxbow. The connectivity index is defined as:

$$\text{CON} = \frac{hA(h)}{V_l} \frac{R_h^{2/3}}{n}, \tag{4}$$

where V_l is the annual mean water volume of the oxbow (m^3); h is the water depth at the constricted section of the connecting channel (defined as the section with the maximum bottom elevation), CON is taken as zero; $A(h)$ is the cross-sectional area at water depth h (m^2); n is the roughness coefficient of the channel (chosen based on water depth); and R_h is the wetted perimeter at water depth h .

Field data analysis reveals that the measured hydrological connectivity follows a power-law relationship with the water depth of the connecting channel, which can be expressed by the empirical equation:

$$\text{CON} = \alpha h^\beta, \tag{5}$$

where α and β are empirical coefficients determined from data. Due to the infrequent occurrence of extremely low or high connectivity events, the moderate connectivity regime appears to have a lasting impact on the morphological evolution of the channel; hence, the median annual connectivity (denoted as CON_{md}) is used as the representative variable in subsequent analyses.




Fig. 3. Interannual Trends of Three Morphological Parameters (SDI, MD, and Rs) from 1990 to 2021 Based on Lasso Regression




Fig. 4. Interannual Trends of Three Morphological Parameters (*SDI*, *MD*, and *Rs*) from 1990 to 2021 Based on Lasso Regression

3.2 Analysis of Trends in Morphological Parameters

Since the remotely sensed waterbody morphology is not extracted under uniform water level conditions, Lasso regression [13] was used to eliminate the influence of water area variations. In this approach, the year and waterbody area serve as explanatory variables, while the morphological parameters (*SDI*, *MD*, and *Rs*) constitute the response variables. Adaptive adjustment of the regularization parameter, Lambda, yields optimized morphological parameter values that account for changes in water area.

Figure 3 presents the year-to-year trends of the *SDI*, *Rs*, and *MD* indices after model optimization. Furthermore, a Mann-Kendall (MK) trend analysis (at a 95% confidence level with $\alpha \pm 1.96$) was applied to evaluate the interannual trends from 1990 to 2021. Figure 4 displays the MK trend analysis results for *SDI*, *MD*, and *Rs*, respectively. Since 1990, the *SDI* has shown an overall increasing trend, with a marked rise after 2003—indicating that human influence on the channel has grown steadily and the retention of natural shorelines has declined. The *SDI* values remain higher than those typically observed in natural lakes, reflecting pronounced riverine characteristics [14, 15]. Similarly, the *MD* index displays an overall upward trend, with 2004 identified as a significant inflection point after which *MD* increases markedly. The local water flow dynamics—affected by both the river’s stage variations and the operational regulation of the Three Gorges Reservoir—have resulted in increased frequency of medium and high flows, together with a notable reduction in suspended sediment concentrations, thereby accentuating channel curvature and promoting the continuous evolution toward an oxbow-lake form. The overall decline in *Rs* since 1999, with a significant downward shift after 2004, indicates increased sedimentation at the downstream end of the oxbow and a contraction of the water surface, thereby diminishing water and sediment exchange efficiency with the Yangtze River.

3.3 Response of Morphological Parameters to Changes in Hydrological Connectivity

Using stage data from the lower outlet of the oxbow (collected from the main Yangtze stream) and field measurements of the channel morphology in 2020, Eq. (4) was applied to estimate the hydrological connectivity between Shangchewan Oxbow and the Yangtze River. As shown in Fig. 5, the connectivity index (CON) is positively correlated with the water depth at the connecting channel according to a power-law relationship, expressed as in Eq. (5).

Figure 6 presents the temporal variability in the median hydrological connectivity (CONmd) of Shangchewan Oxbow from 1990 to 2021. The upper envelope of CONmd exhibited a decreasing trend prior to the operation of the Three Gorges Reservoir, reaching its minimum in 2004, and subsequently showing an upward trend. In contrast, the lower envelope demonstrated a stepwise decline until 2010, after which it increased rapidly. Excluding extreme hydrological conditions in the main channel of the Yangtze River, the overall CONmd indicates an increasing trend, with values in 2021 reaching or exceeding those observed before the Three Gorges Reservoir became operational.

Because extremely low and very high connectivity levels occur infrequently and have little significant impact on morphology, the median annual connectivity (CONmd) is adopted as the representative variable. To examine the influence of connectivity on morphological evolution, the interannual gradients of the morphological parameters are defined as follows:

$$\Delta X_i = X_i - X_{i-1} \quad (X \in \{SDI, MD, R_s\}), \quad (6)$$

where i represents the year. Spearman rank correlation analysis was then applied to evaluate the relationships between these gradients and CONmd. Figure 7 shows a heatmap of correlation coefficients between the gradients of the morphological parameters and CONmd. CONmd exhibits significant positive correlations with both ΔMD (correlation coefficient = 0.83, $p < 0.05$) and ΔR_s (correlation coefficient = 0.77, $p < 0.05$); the correlation with ΔSDI is weaker (0.39, $p < 0.05$). The relationships between ΔMD and CONmd (with $R^2 = 0.64$) and between ΔR_s and CONmd (with $R^2 = 0.62$) are depicted in Fig. 8, respectively. According to the analysis, when $1.75 < \text{CONmd} < 2.15$ the overall morphological development is stable; specifically, when $1.98 \leq \text{CONmd} < 2.15$, ΔMD tends to be positive, whereas for $1.75 < \text{CONmd} < 1.98$ it tends to be negative. Similarly, when $2.1 < \text{CONmd} < 2.5$, the contraction gradient ΔR_s remains relatively stable; ΔR_s becomes positive when $2.3 \leq \text{CONmd} < 2.5$ and negative when $2.1 < \text{CONmd} < 2.3$. Notably, if CONmd is above 2.5 or below 1.75, the oxbow exhibits signs of accelerated evolution: with $\text{CONmd} \geq 2.5$, the distance between the oxbow and the main channel decreases, leading to intensified riverine influences and potential gradual assimilation of the oxbow into the main channel; with $\text{CONmd} \leq 1.75$, the channel contracts significantly, hastening the progression toward a crescent form and rapidly diminishing hydrological exchange.

It is important to note that while both MD and R_s capture the evolution toward an oxbow-lake condition, MD primarily reflects the overall curvature and shape, whereas R_s mainly indicates sedimentation processes at the channel ends. The observed discrepancy between MD and R_s trends over the past 30 years is attributable to differences in their

response thresholds; the balance threshold for ΔMD and ΔR_s differs by approximately 0.34, such that the relative magnitude of MD and R_s within a CONmd range of [1.98, 2.32] determines the direction of morphological evolution.




Fig. 5. Relationship Between the Connecting Channel Water Depth and the Hydrological Connectivity Index (CON) for Shangchewan Oxbow




Fig. 6. Relationship Between the Connecting Channel Water Depth and the Hydrological Connectivity Index (CON) for Shangchewan Oxbow




Fig. 7. Correlation Heatmap Between Morphological Parameters and Median Hydrological Connectivity (CONmd)




Fig. 8. Variation Relationship Between the MD Gradient (Left) and the Rs Gradient (Right) with Median Hydrological Connectivity ($CONmd$)

4 Conclusions and Suggestions

Shangchewan Oxbow is one of the few naturally connected abandoned channels in the Yangtze River Basin and plays an irreplaceable role in biodiversity conservation and as a natural gene pool. Its physical morphology is a crucial habitat attribute and serves as a key indicator in assessing its evolutionary status. In this study, remote sensing interpretation coupled with statistical models was used to extract the morphological features of Shangchewan Oxbow from 1990 to 2021. New indices for shoreline development, morphological contraction, and morphological development, as well as a method for quantifying connectivity, were proposed. Using a Lasso regression and Mann-Kendall trend analysis, the interannual evolution of the morphological parameters was investigated, and the mechanisms and key thresholds of the influence of hydrological connectivity on morphology were revealed. The main conclusions are as follows:

- (I) Post-Three Gorges Reservoir Operation. Following the operation of the Three Gorges Reservoir, the flood level of the oxbow has been effectively controlled and surrounding development has stabilized. As a result, the SDI has

increased significantly-indicating a continuous decline in the preservation of natural shorelines-while the SDI remains higher than that of typical natural lakes, confirming pronounced riverine characteristics. The MD index has increased markedly (with 2004 identified as a notable inflection point), reflecting a progressive accentuation of channel curvature and the continuous evolution toward an oxbow-lake form. Conversely, the contraction index R_s has shown a significant decline since 1999, implying increased sedimentation at the lower end and narrowing of the water surface-thus reducing water and sediment exchange efficiency with the Yangtze River.

- (II) Hydrological Connectivity Trends and Morphological Response. Currently, the overall hydrological connectivity between Shangchewan Oxbow and the Yangtze River has shown an increasing trend. The upper envelope of connectivity has risen since the operation of the Three Gorges Reservoir, and the lower envelope has rapidly increased after 2010, reaching or even surpassing pre-Three Gorges levels by 2021. Moderate levels of hydrological connectivity exert a lasting influence on the morphological evolution of the channel. Significant positive correlations exist between CON_{md} and both the morphological development index and the contraction index, with stable response threshold ranges of [1.75, 2.15] for MD and [2.1, 2.5] for R_s . Under scenarios where $CON_{md} \geq 2.5$, the spatial separation between the oxbow and the main channel decreases and the riverine influence intensifies-with a risk that the oxbow may be gradually incorporated into the main channel. When $CON_{md} \leq 1.75$, the oxbow contracts significantly and the process of lakeification accelerates, causing a pronounced reduction in hydrological exchange.

Given that the lower outlet of Shangchewan Oxbow is located on the convex bank of the left side of the main stream, future conditions are likely to further increase connectivity. While overall oxbow evolution will continue toward a more pronounced oxbow-lake form, sedimentation near the internal outlet may adversely affect water and material exchange with the Yangtze River. Under current natural connectivity conditions, the habitat quality of the oxbow is high and is well suited for refuge functions (e.g., for the protection of the Yangtze finless porpoise). Under controlled engineering measures, maintaining the connectivity index within the range of [1.75, 2.5] is recommended to inhibit the eventual disappearance of the oxbow and to preserve its ecological functions. Furthermore, during extreme drought years when the main channel water level is very low, there is the risk of “dewatering” in the oxbow; such conditions may compromise the ecological water level and threaten the survival of protected species within the oxbow.

This study analyzed the response characteristics of the oxbow’s morphology to hydrological connectivity based solely on the key morphological indices. Future research should focus on strengthening monitoring efforts and investigating the morphological and functional changes in the ensemble of abandoned channels in the lower Jingjiang reach. Particular attention should be paid to sedimentation in the connecting channels, small-scale water flow exchange dynamics between the oxbow and the main stream, and the temporal distribution of material fluxes-to further support the ecological functions of oxbows in maintaining material conservation, biodiversity, and genetic diversity in the Yangtze River Basin.

Acknowledgments. This work was mainly supported by the National Natural Science Foundation of China (Grant nos. 12302508 and 52320105006), the Fundamental Research Funds for Central Public Welfare Research Institutes (Grant nos. CKSF2024326/HL, CKSF2021438/HL), Open Research Fund of State Key Laboratory of Simulation and Regulation of Water Cycle in River Basin (China Institute of Water Resources and Hydropower Research) (Grant/Award Number: IWHR-SKL-KF202306).

References

1. Li, Z., Wang, Z., Pan, B.: Mechanism of oxbow lake formation and long-term evolution. *J. Sed. Res.* **2012**(5), 16–25 (2012)
2. Stella, J.C., Hayden, M.K., Battles, J.J., et al.: The role of abandoned channels as refugia for sustaining pioneer riparian forest ecosystems. *Ecosystems* **14**, 776–790 (2011)
3. Obolewski, K., Glińska-Lewczuk, K.: Effects of oxbow reconnection based on the distribution and structure of benthic macroinvertebrates. *Clean-Soil Air Water* **39**(9), 853–862 (2011)
4. Hudson, P.F., Heitmuller, F.T., Leitch, M.B.: Hydrologic connectivity of oxbow lakes along the lower Guadalupe River, Texas: the influence of geomorphic and climatic controls on the “flood pulse concept.” *J. Hydrol.* **414**, 174–183 (2012)
5. Guo, X., Gao, P., Li, Z.: Hydrologic connectivity and morphologic variation of oxbow lakes in an alpine pristine fluvial system. *J. Hydrol.* **2023**, 129768 (2023)
6. Aspetsberger, F., Huber, F., Kargl, S., et al.: Particulate organic matter dynamics in a river floodplain system: impact of hydrological connectivity. *Arch. Hydrobiol.* **156**(1), 23–42 (2002)
7. Xiaobin, C., Rannan, Y., Xuelei, W.: Analysis of connectivity characteristics and evolution trends of the lower Jingjiang abandoned channel. *Resour. Environ. Yangtze Basin* **22**(1), 53–58 (2013)
8. Theng, V., Sith, R., Uk, S., et al.: Phytoplankton productivity in a tropical lake-floodplain system revealed by a process-based primary production model. *Ecol. Model.* **479**, 110317 (2023)
9. Boothroyd, R.J., Williams, R.D., Hoey, T.B., et al.: Applications of Google Earth Engine in fluvial geomorphology for detecting river channel change. *Wiley Interdiscip. Rev. Water* **8**(1), e21496 (2021)
10. Weihaupt, J.G.: Morphometric definitions and classifications of oxbow lakes, Yukon River Basin, Alaska. *Water Resour. Res.* **13**(1), 195–196 (1977)
11. Wang, D., Li, Z., Li, Z., et al.: Environmental gradient relative to oxbow lake-meandering river connectivity in Zoige Basin of the Tibetan Plateau. *Ecol. Eng.* **156**, 105983 (2020)
12. Xia, J., Chen, Y., Zhou, Z., et al.: Review of the mechanisms and methods for assessing hydrological connectivity in river systems. *Adv. Water Sci.* **28**(5), 780–787 (2017). <https://doi.org/10.14042/j.cnki.32.1309.2017.05.016>
13. Han, X., Guo, Y.: Coupled LASSO regression and HHO-LSVR for long-term runoff forecasting. *Hydrology* **41**(3), 69–74 (2021)
14. Wang, Z., Liu, K., Zhan, P., et al.: Spatiotemporal evolution of lake shoreline morphology in the endorheic region of the Qinghai-Tibet Plateau over the past 30 years. *Geogr. Res.* **41**(4), 980–996 (2022)
15. Fengtai, Z., Lachun, W., Hui, L., et al.: Comparative analysis of morphological characteristics of typical natural and artificial lakes. *China Rural Water Hydropower* **7**, 38–41 (2012)
16. Zhou, W., Sun, Z., Zhou, K., et al.: Characteristics of flow frequency distribution in the middle and lower reaches of the Yangtze River before and after Three Gorges Reservoir operation and its impact on floodbed formation. *J. Lake Sci.* **34**(2), 616–629 (2022)

17. Xu, Q., Dong, B., Zhang, W.: Characteristics and analysis of scour and deposition changes in the main channel of the middle and lower Yangtze River. *Yangtze River* (2021)
18. Zuo, L., Lu, Y., Wang, H., et al.: Response of sediment erosion and deposition in the Jingjiang River section to sand discharge during the flood season of the Three Gorges Reservoir. *Adv. Water Sci.* **34**(1), 115–125 (2023)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Theoretical Foundation and Technical Implementation of Dynamic Flow Monitoring for Hydropower Units

Shuangxi Zou¹(✉), Ashas Abbasi²(✉), Wenbo Cao³, Dianlong Chen¹, Yanlong Wang¹, Gaolin He³, and Wenbing Zhu¹

¹ China Yangtze Power Co., Ltd., Baihetan Hydropower Station, Yangtze, China
995018707@qq.com

² Karot Hydropower Plant, KPCL (CSAIL), Karot, Pakistan
ashis.abbasi43@gmail.com

³ China Yangtze Power International (Hong Kong) Co., Ltd., Hong Kong, China

Abstract. Accurate and suitable turbine discharge measurement is crucial for the efficiency, safety, and economic operation of hydropower plants, directly impacting power generation efficiency, equipment lifespan, and reservoir discharge. This paper introduces a comparative study of two flow measurement methods applied in the Francis turbine: ultrasonic flowmeters installed at the spiral case inlet and differential pressure flow measurement that measures data from pressure measuring points at selected cross-sections within the spiral case. Inside the spiral case, flow characteristics are mathematically modeled, considering a uniformly distributed velocity across spiral case height and tangential-radial velocity component analysis, providing the base of a valid pressure-flow relationship. The model is comprised of real-time data comparison between ultrasonic flowmeter and differential-pressure data from the Karot Hydropower Plant, Pakistan. The results show that when differential pressure is used along with the derived equation the measured discharge is close to ultrasonic measurements with an acceptable error of $\pm 2\%$. This concluded that despite the simplicity and low cost of differential-pressure methods it can be a reliable alternative to ultrasonic flowmeters. The insights provide a practical and theoretical basis for optimized flow monitoring, which is the main concern for the installation of large-scale hydropower plants in situations where the implementation of ultrasonic systems is challenged by structural feasibility and economic limitations.

Keywords: Hydro-turbine generating unit · Ecological flow management · Cost-effective flow measurement Method · Differential pressure sensor application · Ultrasonic flowmeter

1 Introduction

In hydropower stations, to achieve efficient, safe, and economical operation of units—thereby enhancing power generation efficiency, equipment lifespan, and resource utilization—monitoring the flow rate through the units is often necessary. Measuring the

unit discharge is a core approach to ecological flow management, directly impacting the integrity and sustainability of river ecosystems. Flow management helps to balance ecosystem and human needs for water making discharge measurement a crucial parameter [1]. Through scientific monitoring and regulation, hydropower stations can optimize energy benefits while minimizing disturbances to natural hydrology, thus contributing to the goal of “green hydropower”. There are generally two methods used to obtain the flow rate through hydropower units:

- Direct measurement using ultrasonic flowmeters installed at the spiral case inlet.
- Indirect calculation of the total inlet flow by measuring pressure differences at multiple points on a cross-section of the spiral case.

This paper discusses the theoretical basis and technical implementation of these two flow measurement methods.

2 Flow Measurement at the Spiral Case Inlet Using the Differential Pressure Method

2.1 Water Flow Movement in the Spiral Case

In reaction-type turbines, a spiral case is commonly used as the water conduit. The function of the spiral case is to direct the water from the penstock to the guide vanes in front of the runner with minimal hydraulic loss and the most economical cross-sectional area [2]. According to the analysis presented in *Hydraulic Turbines* by Zheng Yuan, Ju Xiaoming, and Cheng Yunshan [3], at all points within the spiral case that are equidistant from the turbine axis (i.e., with the same radius r), the tangential velocity of the water flow v_u remains constant. At points with different radii r from the turbine axis, the tangential velocity v_u is inversely proportional to the radius r , expressed as: $v_u r = K$. Here, K is referred to as the *spiral case constant* as illustrated in Fig. 1.




Fig. 1. Flow behavior of water within the spiral case

The angle δ between the flow velocity $\mathbf{v}$ and its tangential component $\mathbf{v}_u$ in the spiral case is a constant. The outer contour of the spiral case is a logarithmic spiral

(or equiangular spiral). According to the standard function of a logarithmic spiral, the function curve of the spiral case contour in the top-view polar coordinate system is: $R_e(\varphi) = R_{e0}e^{k\varphi}$, where R_{e0} is the distance from the turbine axis to the outer edge of the spiral case at the nose tip, $R_e(\varphi)$ is the distance from any point on the outer contour to the unit center, and φ is the angle between the nose tip and any point on the outer contour, as shown in Fig. 2.




Fig. 2. Outer contour of the spiral case

3 Principle of Flow Measurement at the Spiral Case Inlet Using the Differential Pressure Method

Figure 3 shows the schematic layout of the differential pressure flowmeter in the spiral case. Measuring points 1 and 2 are located near the outer and inner sides of the spiral case, respectively. These pressure points are connected via pressure pipelines to the instrument panel located in the turbine gallery. The differential pressure between points 1 and 2 is measured using a differential pressure sensor.




Fig. 3. Schematic layout of the spiral case differential pressure flowmeter

Because $v_{\theta}r = K$, the angle δ between the flow velocity $\mathbf{v}$ and its tangential component $\mathbf{v}_{\theta}$ is a constant. Therefore, $\mathbf{v} \times \mathbf{r}$ can be expressed as: $\mathbf{v} \times \mathbf{r} = \frac{v_{\theta}r}{\cos\delta} = \frac{K}{\cos\delta} = C$ where C is a constant. Thus, we set $C = \mathbf{v} \times \mathbf{r} = \frac{K}{\cos\delta}$.

According to Bernoulli's energy conservation equation: $z_1 + \frac{p_1}{\rho g} + \frac{v_1^2}{2g} = z_2 + \frac{p_2}{\rho g} + \frac{v_2^2}{2g}$

Subtract the two sides of the equation and organize it to obtain: $(z_1 - z_2) + \frac{(p_1 - p_2)}{\rho g} = \frac{v_2^2 - v_1^2}{2g}$

Since, $\mathbf{v} \times \mathbf{r} = \mathbf{C}$, then $\mathbf{v} = \frac{\mathbf{C}}{r}$, by substituting into the above equation, we obtain: $\Delta z +$

$$\frac{\Delta p}{\rho g} = \frac{\left(\frac{C^2}{r_2^2} - \frac{C^2}{r_1^2}\right)}{2g} = C^2 \frac{(r_1^2 - r_2^2)}{2gr_1^2 r_2^2}$$

The calculation formula for C is:

$$C = \sqrt{\frac{2gr_1^2 r_2^2}{r_1^2 - r_2^2}} \cdot \sqrt{\left(\Delta z + \frac{\Delta p}{\rho g}\right)} \quad (1)$$

In Eq. (1), Δz and Δp represent the elevation and pressure difference between measuring points 1 and 2 respectively. Let the pressures at the pressure-transducer inlet at points 1 and 2 be p_{d1} and p_{d2} respectively. Then:

$$\begin{cases} p_{d1} = p_1 - \rho g h_1 \\ p_{d2} = p_2 - \rho g h_2 \\ h_1 - h_2 = -\Delta z \end{cases}$$

So, $\frac{\Delta p_d}{\rho g} = \Delta z + \frac{\Delta p}{\rho g}$, Thus, Eq. (1) is further simplified as:

$$C = \sqrt{\frac{2gr_1^2 r_2^2}{r_1^2 - r_2^2}} \cdot \sqrt{\frac{\Delta p_d}{\rho g}} = \sqrt{\frac{2r_1^2 r_2^2}{\rho(r_1^2 - r_2^2)}} \cdot \sqrt{\Delta p_d} \quad (2)$$

At the critical interface between the penstock and the spiral case inlet, the tangential velocity v_u is distributed according to the law of constant angular momentum. For any point on the spiral case inlet section, consider a differential element dA as shown in Fig. 4. This element has an angle $d\theta$ and radius R , so the area is $dA = R d\theta dR$.




Fig. 4. Schematic diagram of inlet flow analysis of spiral case

Here, θ is the angle between the radius R and the positive X-axis. The parameter r_c is the distance from the center of the spiral case inlet to the turbine center, and R_e is the maximum radius of the spiral case inlet, as shown in Fig. 4.

Based on the above conditions, the geometric relationship is: $r = r_c + R \cos \theta$

Since, $v_u r = K$, then: $v_u = \frac{K}{r_c + R \cos \theta}$

The flow rate through the infinitesimal surface dA in unit time is: $dQ = v_u dA = v_u R d\theta dR = \frac{KR}{r_c + R \cos \theta} R d\theta dR$

$$Q = \int dQ = \int_0^{R_e} \int_0^{2\pi} \frac{KR}{r_c + R \cos \theta} dR d\theta = K \int_0^{R_e} R \left(\int_0^{2\pi} \frac{1}{r_c + R \cos \theta} d\theta \right) dR \quad (3)$$

Calculating the above expression gives:

$$Q = 2\pi K \left(r_c - \sqrt{r_c^2 - R_e^2} \right) \quad (4)$$

Since the calculations presented in this paper do not account for energy losses, and the actual shape of the spiral casing inlet cross-section is unlikely to be a standard circle, nor can the entire spiral case flow channel be manufactured according to a perfectly smooth logarithmic spiral, there exists a slight discrepancy between the flow rate calculated using the proposed formula and the actual values measured by the ultrasonic flowmeter. Therefore, to obtain more accurate results, a correction factor ε should be applied to the final calculated value, which, based on experience, typically ranges from 0.9 to 1.1. Given that the spiral casing profiles, manufacturing precision, and installation accuracy vary across different hydropower stations, a more precise correction factor for a specific station can be determined by statistically analysing the readings from the installed ultrasonic flowmeters and applying regression analysis to derive the optimal correction factor suited to the station's units.

Let, $\xi = 2\sqrt{2}\pi \cos \delta \left(r_c - \sqrt{r_c^2 - R_e^2} \right) \sqrt{\frac{r_1^2 r_2^2}{\rho(r_1^2 - r_2^2)}}$, then Eq. (4) can be written as:

$$\begin{cases} Q = \varepsilon \xi \sqrt{\Delta p_d} \\ \xi = 2\sqrt{2}\pi \cos \delta \left(r_c - \sqrt{r_c^2 - R_e^2} \right) \sqrt{\frac{r_1^2 r_2^2}{\rho(r_1^2 - r_2^2)}} \\ \varepsilon \in (0.9, 1.1) \end{cases} \quad (5)$$

Equation (5) shows ξ is a constant dependent solely on the structural dimensions of the spiral case inlet, and Δp_d is the differential pressure sensor reading. All physical quantities in the formulas are expressed in SI units. Equation (5) is the flow calculation formula for the differential pressure method. It shows that the flow rate Q can be determined directly from the measured Δp_d which forms the basis of the differential pressure flow measurement principle.

4 Calculation of the Angle Δ Between V and v_u

There are two methods to calculate the angle δ between v and v_u : the analytical method and the graphical method.

4.1 Analytical Method

As shown in Fig. 5, on the spiral case single-line diagram, select a specific angle such as 60° , 90° , or 180° , and determine the corresponding intersection points on both sides of this angle with the outer contour of the spiral case. Measure the corresponding radii R_{e1} and R_{e2} using reference data or CAD software. Let $k = \tan \Delta$.




Fig. 5. The schematic diagram for obtaining $\cos \delta$ using the analytical method

Based on the spiral case outer contour curve equation in polar coordinates: $R_e(\varphi) = R_{e0}e^{\tan \delta \varphi}$ the value of k can be calculated, and subsequently, $\cos \delta$ can be obtained for use in Eq. (6).

$$k = \frac{\ln R_{e2} - \ln R_{e1}}{\varphi_2 - \varphi_1}, \cos \delta = \cos(\arctan(k)) \quad (6)$$

4.2 Drawing Method

At the intersection point A of the spiral case external contour line with the $+X$ direction, a perpendicular line AB ($AB \perp OX$) is drawn to the OX axis shown in Fig. 6.




Fig. 6. Using the drawing method to obtain the schematic diagram of $\cos \delta$

The angle between the spiral case contour line AC and the line AB at this point is approximately δ , that is:

$$\cos \delta \approx \cos \angle BAC \quad (7)$$

Due to the limitations in manufacturing, the spiral case cannot be produced with a perfectly smooth logarithmic spiral. However, since δ is relatively small, the values of $\cos \delta$ obtained using the analytical method (Eq. 6) and the graphical method (Eq. 7) are very close to each other.

5 Statistical Calculation Method for Correction Coefficient ε

Due to variations in spiral case profiles, as well as manufacturing and installation tolerances across different power stations, a more accurate correction factor specific to each station can be determined by statistically analysing the ultrasonic flowmeter readings. By applying regression analysis to the measured flow data, the optimal correction factor tailored to the hydraulic and geometric characteristics of each generating unit can be derived.

Assuming the reading of the ultrasonic flowmeter is Q_u , Δp_d is the reading of the spiral case pressure differential sensor, if there are 'n' sets of Q_u and Δp_d statistical data available, as shown in the following table (Table 1):

Table 1. Statistical table of readings of spiral case ultrasonic flowmeter and differential pressure sensor

Statistical Items	Numerical value					
Q_u	Q_{u1}	Q_{u2}	Q_{u3}	Q_{u4}		Q_{un}
Δp_d	Δp_{d1}	Δp_{d2}	Δp_{d3}	Δp_{d4}		Δp_{dn}

Construct a function $f(\varepsilon)$, whose expression is: $f(\varepsilon) = \sum_{i=1}^n (\varepsilon \xi \sqrt{\Delta p_{di}} - Q_{ui})^2$, if it is expanded and merged, it can be simplified as:

$$\begin{cases} f(\varepsilon) = A\varepsilon^2 + B\varepsilon + C \\ A = \xi^2 \cdot \sum_{i=1}^n \Delta p_{di} \\ B = -2\xi \cdot \sum_{i=1}^n (Q_{di} \cdot \sqrt{\Delta p_{di}}) \end{cases} \quad (8)$$

According to the principle of least squares, when the minimum value of $f(\varepsilon)$ is reached, the value measured by the differential pressure flowmeter is closest to the value measured by the ultrasonic flowmeter. And because when $\frac{df(\varepsilon)}{d\varepsilon} = 0$, the value of $f(\varepsilon)$ is the smallest. So according to $\frac{df(\varepsilon)}{d\varepsilon} = 2A\varepsilon + B = 0$, $\varepsilon = \frac{B}{2A}$. By substituting into equation (8), it is calculated that:

$$\varepsilon = \frac{1}{\xi} \cdot \frac{\sum_{i=1}^n (Q_{di} \cdot \sqrt{\Delta p_{di}})}{\sum_{i=1}^n \Delta p_{di}} \quad (9)$$

6 Verification of Eq. (5)

Since the formula for calculating the flow rate in Eq. (5) is relatively complex, the correctness of the formula can be verified through dimensional analysis[4]. If the dimension of length is denoted as L , mass as M , and time as T , then:

The dimensional formula for the distance r to the turbine axis is: $[r] = L$

The dimension of volume V is: $[V] = L^3$

The dimensional formula for density ρ is: $[\rho] = ML^{-3}$

The dimension of velocity v is: $[\rho] = LT^{-1}$

The dimension of acceleration a is: $[a] = \left[\frac{dv}{dt}\right] = LT^{-2}$

The dimension of force F is: $[F] = [ma] = MLT^{-2}$

The dimension of area S is: $[S] = L^2$

The dimensional formula for pressure p is: $[p] = \left[\frac{F}{S}\right] = MLT^{-2} \cdot L^{-2} = ML^{-1}T^{-2}$

The dimensional formula for elevation z is: $[z] = L$

The dimensional formula for the spiral case inlet radius R is: $[R] = L$

Using the dimensional formulas of the above physical quantities, we can calculate the dimensions of Eq. (5), and we get:

$$[\xi] = \left[2\sqrt{2}\pi \cos\delta \left(r_c - \sqrt{r_c^2 - R_c^2} \right) \sqrt{\frac{r_1^2 r_2^2}{\rho(r_1^2 - r_2^2)}} \right] = L \cdot \sqrt{\frac{L^4}{ML^{-3} \cdot L^2}} = L^{\frac{7}{2}} M^{-\frac{1}{2}} \quad (10)$$

$$[Q] = [\xi \xi \sqrt{\Delta p_d}] = L^{\frac{7}{2}} M^{-\frac{1}{2}} \cdot (ML^{-1}T^{-2})^{\frac{1}{2}} = L^3 T^{-1}$$

From Eq. (10), the dimensional formula of the flow rate Q calculated using Eq. (5) is $[Q] = L^3 T^{-1}$, which matches the actual physical units of the flow rate. This confirms that from a dimensional analysis perspective, the formula for calculating the spiral case inlet flow rate in Eq. (5) is correct.

7 Principle of Ultrasonic Flowmeter for Flow Measurement

An ultrasonic flowmeter is an instrument that uses ultrasonic technology to measure fluid flow. It typically consists of a transducer (sensor), signal processing unit, main unit (calculation and display unit), and auxiliary components. Ultrasonic flowmeters offer advantages such as non-contact measurement, high precision, and no pressure loss, and are widely used for monitoring the flow of liquids and gases.




Fig. 7. Schematic diagram of the principle of a 2-channel ultrasonic flowmeter

An ultrasonic transducer is a device that converts high-frequency electrical energy into mechanical energy (i.e., ultrasonic waves) and is mainly used for flow velocity measurement on the transit-time method[5]. For the measurement of flow rate, we can use the propagation time of ultrasonic waves[6]. As shown in Fig. 7, two transducers, P1 and P2, are arranged upstream and downstream of the pipe, with a distance L between them. The line connecting P1 and P2 forms an angle θ with the pipe axis. Let the fluid velocity be V , with V_a as the axial component of the fluid velocity relative to the pipe and V_t as the radial component. C is the speed of sound in still water at room temperature. The flow rate through the pipe is $Q = V_a A$ [7], where A is the cross-sectional area perpendicular to the pipe. To measure the flow rate Q , the value of V_a must be determined.

The time T_1 ($P1 \rightarrow P2$, called the forward propagation time) for the sound wave to travel from P1 to P2 is:

$$T_1 = \frac{L}{C + V_a \cos\theta - V_t \sin\theta}$$

Can be written as:

$$V_a = \frac{1}{\cos\theta} \left(\frac{L}{T_1} - C + V_t \sin\theta \right)$$

The time T_2 ($P2 \rightarrow P1$, called the reverse propagation time) for the sound wave to travel from P2 to P1 is:

$$T_2 = \frac{L}{C - V_a \cos\theta + V_t \sin\theta}$$

Can be written as:

$$V_a = -\frac{1}{\cos\theta} \left(\frac{L}{T_2} - C - V_t \sin\theta \right)$$

If solved simultaneously, the average value of $\overline{V_a}$ is:

$$\begin{cases} V_a = \frac{1}{\cos\theta} \left(\frac{L}{T_1} - C + V_t \sin\theta \right) \\ V_a = -\frac{1}{\cos\theta} \left(\frac{L}{T_2} - C - V_t \sin\theta \right) \end{cases} \quad (11)$$

$$\overline{V_a} = \frac{L}{2\cos\theta} \left(\frac{1}{T_1} - \frac{1}{T_2} \right) + V_t \tan\theta$$

In Eq. (11), the term $V_t \tan\theta$ needs to be eliminated for which two additional transducers, P3 and P4, are symmetrically installed in the opposite diagonal direction of P1 and P2, as shown in Fig. 8.




Fig. 8. Schematic diagram of 4-channel ultrasonic flowmeter principle

Let T_3 be the time for the sound wave to travel from P3 to P4, and T_4 be the time from P4 to P3. Then, according to the method for calculating the average velocity $\overline{V}_a$, we have

$$\overline{V}_a = \frac{L}{2\cos\theta} \left(\frac{1}{T_3} - \frac{1}{T_4} \right) - V_t \tan\theta \quad (12)$$

By combining Eq. (11) and (12), we can get $\overline{V}_a$, eliminating the term $V_t \tan\theta$.

$$\begin{cases} \overline{V}_a = \frac{L}{2\cos\theta} \left(\frac{1}{T_1} - \frac{1}{T_2} \right) + V_t \tan\theta \\ \overline{V}_a = \frac{L}{2\cos\theta} \left(\frac{1}{T_3} - \frac{1}{T_4} \right) - V_t \tan\theta \end{cases} \quad (13)$$

$$\overline{V}_a = \frac{L}{4\cos\theta} \left(\frac{1}{T_1} - \frac{1}{T_2} + \frac{1}{T_3} - \frac{1}{T_4} \right)$$

Equation (13) is the fundamental principle of the four-path ultrasonic flowmeter. In practical engineering applications, depending on the required measurement accuracy, pipe size, and fluid properties, ultrasonic flowmeters can be configured with 8, 16, 32, etc. [8]. Generally, if an ultrasonic flowmeter has N paths where $N = 2^z$ and z a positive integer, the average axial velocity $\overline{V}_a$ measured is:

$$\overline{V}_a = \frac{L}{N\cos\theta} \sum_{n=1}^N \frac{(-1)^{n-1}}{T_n}$$

If the pipe diameter is D , the flow rate in the pipe is:

$$Q = \overline{V}_a \cdot \frac{\pi D^2}{4} = \frac{\pi D^2 L}{4N\cos\theta} \sum_{n=1}^N \frac{(-1)^{n-1}}{T_n} \quad (14)$$

Equation (14) is the general formula for the flow output of an ultrasonic flowmeter with N sound paths ($N = 2^z$ and z being a positive integer). In this formula, when n is odd, the corresponding transducer emits sound waves in the forward direction; when n is even, the transducer emits sound waves in the reverse direction.

8 Comparison of the Two Measurement Methods

Due to differences in structure and measurement principles, each method has its pros and cons. Ultrasonic flowmeters offer high measurement accuracy but are expensive, difficult to install, and inconvenient to inspect and maintain. In contrast, the spiral case

differential pressure flowmeter has lower measurement accuracy but features a simple structure, easy installation and maintenance, and lower cost (Tables 2 and 3).

Table 2. Spiral casing dimensional parameters of Karot Hydropower station units, Pakistan

Parameter Name	Re (m)	rc (m)	r1 (m)	r2 (m)	$\cos \delta$ /	ε /	ξ ($\text{m}^{\frac{7}{2}} \cdot \text{kg}^{-\frac{1}{2}}$)
Value	3.79	8.50	10.38	6.13	0.98	0.96	1.863

Table 3. Comparison between ultrasonic flowmeter readings and differential pressure flow calculation values for Karot Hydropower station units, Pakistan

Parameter Name	Units	Unit 1	Unit 2	Unit 3	Unit 4
Δp_d	pa	19,000	19,500	18,500	19,200
$Q = \varepsilon \xi \sqrt{\Delta p_d}$	m^3/s	247	250	243	248
Ultrasonic flowmeter reading Q_u	m^3/s	243	245	250	247
$\frac{Q-Q_u}{Q_u} \times 100\%$	/	1.65%	2.04%	-2.80%	0.40%

Due to the inherent sensitivity of the ultrasonic flowmeter, the readings fluctuate within a $\pm 2\%$ range. Therefore, when the relative deviation of the pressure differential flow calculation is within $\pm 2\%$, the calculated pressure differential flow value can be considered equivalent to the ultrasonic flowmeter reading. The results indicate that the differential pressure flow calculated using the formula presented in this paper closely matches the value measured by the ultrasonic flowmeter, confirming high accuracy and reliability.

9 Conclusion

The differential-pressure method for measuring the flow rate of a hydropower unit, as presented in this paper, mainly focuses on theoretical analysis. However, due to the simplicity of the required equipment, low cost, and satisfactory measurement accuracy, it holds significant practical value. Considering the case of small-scale hydro stations, because of low reservoir volume and limited capacity over flood control, the unit discharge flow is a crucial parameter for reservoir scheduling. Low-scale hydro stations start, stop, or adjust load frequently which makes flow measurement a critical parameter for optimizing operation and making accurate flow measurements essential. Since the unit capacity is small and the spiral case size is not large, the cost is relatively low, so ultrasonic flowmeters are commonly installed.

However, large-scale hydro turbine stations despite having a larger capacity of reservoirs which helps them to operate with stable loads have also spiral cases of larger size.

For larger-sized spiral cases, more ultrasonic flowmeters are required to ensure accuracy, surging installation costs, and maintenance inconvenience. Consequently, ultrasonic flowmeters are installed only to assist flow measurements along with spiral case differential-pressure flowmeters.

Furthermore, accurate flow measurement is essential in hydropower operations to ensure ecological flow requirements, maintain river health, and support biodiversity. It helps sustain aquatic habitats, prevent abrupt fluctuations from power generation, and minimize ecosystem disruption. Real-time data enables scientific scheduling, regulatory compliance (e.g., China's Water Pollution Prevention and Control Law), and dynamic adjustment to balance ecological and energy needs. Optimizing flow release patterns to mimic natural hydrological cycles, such as pulse flows, preserves sediment transport and thermal regimes. Long-term monitoring supports the evaluation of restoration efforts (e.g., fish migration), informs adaptive management, and strengthens ecosystem resilience. Moreover, precise flow management aids in coordinating multiple water uses—power generation, irrigation, and ecological protection—minimizing social conflicts. In the face of climate change and extreme weather events, flow data enables responsive scheduling and enhances watershed adaptability. Therefore, accurate measurement of flow is not only a technical requirement but a core component for ensuring environmental sustainability, green hydropower advancement, conformance with legal requirements, and diverse water demands in multiple sectors amid escalating climate sensitivity.

References

1. Renöfält, B.M., Jansson, R., Nilsson, C.: Effects of hydropower generation and opportunities for environmental flow management in Swedish riverine ecosystems. *Freshw. Biol.* **55**(1), 49–67 (2010)
2. Birtarescu, E., Constantin Câmpian, V., Nedelcu, N.: Strength calculations performed on the spiral casing of a francis turbine operating in secondary control regime. *Sci. Bull. Mech. Eng.* **83**, 261–272 (2021)
3. Zheng, Y., Ju, X., Cheng, Y.: *Hydraulic Turbines* (2007)
4. Gibbings, J.C.: *Dimensional Analysis*. Springer Science & Business Media, London (2011)
5. Laustsen, J., et al.: Validation of a new transit time ultrasound flowmeter in man. *Eur. J. Vasc. Endovasc. Surg.* **12**(1), 91–96 (1996)
6. Zhang, H., Guo, C., Lin, J.: Effects of velocity profiles on measuring accuracy of transit-time ultrasonic flowmeter. *Appl. Sci.* **9**(8), 1648 (2019)
7. Mdee, O., et al.: Measurement methods for hydropower resources: a review. *Water Utility J.* **18**, 21–38 (2018)
8. Wang, C., et al.: Accuracy of the ultrasonic flow meter used in the hydroturbine intake penstock of the Three Gorges Power Station. *Flow Meas. Instrum.* **25**, 32–39 (2012)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





A Method for Determining Ecological Flow Downstream of Hydropower Stations Considering Inter-annual and Intra-annual Wet-Dry Co-occurrences

Yueping Deng¹, Yu Zhang²(✉), and Xiuqin Yang³

¹ Poyang Lake Hydrological and Water Resources Monitoring Center, Jiujiang, China

² Nanjing Hydraulic Research Institute, Nanjing 210029, Jiangsu, China
yuzhang@nhri.cn

³ Nanjing University of Information Science and Technology, Nanjing 210044, Jiangsu, China

Abstract. Ecological flow provides reference values for maintaining the stability of river ecosystems and rich biodiversity. Therefore, formulating ecological flow in the river channel downstream of hydropower stations as an ecological constraint condition for the scheduling of cascade reservoir groups in the upper Yangtze River is crucial for protecting river ecosystems. Existing methods for determining ecological flow often only consider either intra-annual or inter-annual runoff distribution characteristics. However, an analysis of runoff variation patterns in the upper Yangtze River shows that inter-annual and intra-annual runoff distributions are highly uneven, with unique characteristics of wet-dry co-occurrences at annual and monthly scales. To address the limitation of existing methods in describing intra- and inter-annual variations in river runoff, this paper proposes an innovative ecological flow determination method based on the probability distributions of annual and monthly runoff. First, the marginal distributions of annual and monthly runoff are fitted, and a Copula function is used to construct the joint probability distribution of annual and monthly runoff. Then, based on Bayesian inference, the conditional probabilities of different monthly runoff magnitudes under various annual runoff conditions are calculated. Finally, these conditional probabilities are combined with the Flow-Duration Curve (FDC)-based method to determine an ecological flow process that accounts for both intra-annual and inter-annual runoff variations. This study provides a regulatory red line for the development of water resources and hydropower energy in the upper Yangtze River, while facilitating better protection of local wildlife species.

Keywords: Ecological flow · Downstream of Hydropower Stations · Wet-Dry Co-Occurrences · annual runoff · monthly runoff

1 Introduction

Instream ecological flow (IEF), as the critical hydrological threshold for maintaining river ecosystem health and biodiversity, has emerged as a pivotal challenge in balancing water resource development with ecological protection—especially in large-scale

hydropower-dominated basins like the Yangtze River (Poff 2018; Gleick 1998). Global experiences demonstrate that neglecting ecological flow requirements often leads to severe consequences, such as degraded riparian habitats, disrupted sediment transport, and regional ecological crises (Absalon et al. 2023; Xu et al. 2023). Nowhere is this challenge more pronounced than in the downstream area of the Three Gorges Hydropower Project, where cascade reservoir operations have intensified the need for scientifically rigorous IEF determination to regulate hydrological regimes and mitigate ecosystem impacts.

Paradigms of Ecological Flow Assessment.

Early methodologies in the 1970s, represented by the Tennant method (1976), relied on historical hydrological data to define flow thresholds for habitat quality, categorizing river conditions into eight classes based on percentages of mean annual flow. While operationally simple, this approach lacks monthly-scale resolution and fails to address the pronounced intra-annual variability typical of monsoon-affected rivers like the Yangtze (Wang et al. 2022). Subsequent advancements included hydraulic methods (e.g., wetted perimeter method, R2-CROSS) linking flow to channel geometry and habitat models like IFIM integrating species-specific hydraulic responses (Sedghi-Asl & Poursalehan 2024; Petts 2009). However, these either overlook ecological complexity (hydraulic methods) or require intensive biological data (habitat models), limiting broad applicability.

Holistic frameworks like the Building Block Methodology (BBM) later emerged to address ecosystem integrity by integrating hydrological, geomorphological, and biological processes (Hughes 1999). Despite conceptual advances, their interdisciplinary complexity has kept hydrological methods—such as the Variable Monthly Flow (VMF) method improving seasonal allocation—dominant due to simplicity (Chen et al. 2023). A critical limitation remains: existing methods analyze intra-annual (monthly) or inter-annual (decadal) runoff variability in isolation, ignoring the probabilistic co-occurrence of wet-dry states across timescales—a gap acutely felt in the Three Gorges downstream where annual drought/flood cycles interact with monthly monsoon-driven flow fluctuations.

Research Gap and Methodological Innovation.

The downstream reach of the Three Gorges Project exhibits extreme inter- and intra-annual runoff unevenness, with unique patterns of annual and monthly flow regime interactions that traditional methods cannot characterize (Xu et al. 2023). For example, the Tennant method's annual mean-based classification and VMF's seasonal allocation without inter-annual context both fail to model how multi-year droughts exacerbate seasonal low-flow risks or how flood years alter sediment transport dynamics critical for riparian health. This motivates a framework integrating temporal scales through joint probability modeling, essential for ecosystems sensitive to both short-term flow pulses and long-term hydrological regimes.

Building on the study's novel approach, we introduce a Copula-based IEF determination method tailored to the Three Gorges downstream's hydrological complexity:

Marginal Distribution Fitting: Use maximum likelihood estimation to characterize annual/monthly runoff distributions, capturing the region's distinct wet-dry cycles;

Copula-Based Joint Modeling: Construct a joint probability distribution to quantify dependencies between annual hydrological regimes (e.g., wet/dry years) and monthly

flow magnitudes, enabling conditional probability calculations for drought/flood scenarios;

FDC Integration: Combine these probabilities with Flow-Duration Curve analysis to derive a temporally explicit IEF process that balances the ecological needs of seasonal spawning habitats with the hydrological constraints of reservoir operations.

By applying this method to the Three Gorges downstream—a critical zone for Yangtze sturgeon migration and riparian wetland sustainability—this study addresses the long-standing challenge of integrating inter- and intra-annual variability into IEF determination. The framework provides a data-efficient yet mechanistic approach to establish regulatory flow thresholds, enabling adaptive reservoir scheduling that reconciles hydropower production with the protection of iconic riverine ecosystems in large-scale regulated basins.

2 Methodology

The proposed framework addresses inter- and intra-annual runoff dynamics through a structured three-stage process, integrating probabilistic modeling, hydrological analysis, and Bayesian inference:

2.1 Marginal Distribution Characterization and Grouping

First, univariate probability distributions (e.g., Pearson Type III, Gamma) are selected to model annual and monthly runoff series, with parameters estimated via maximum likelihood estimation (MLE). Goodness-of-fit tests (e.g., Kolmogorov-Smirnov) validate marginal distributions, ensuring theoretical curves represent observed regimes. Critical to capturing temporal variability, annual and monthly runoff series are grouped based on exceedance probability boundaries:

Annual and monthly runoff series are grouped according to the probability of runoff volume exceedance. Based on the inter- and intra-annual variability characteristics of the study river, the annual runoff series is divided into p groups and the monthly runoff series into q groups. For example, annual and monthly runoff series can be divided into abundant water year group, flat water year group, and dry water year group based on the boundaries of 25% and 75% exceedance probability. If river runoff is highly variable, the annual and monthly runoff series can be divided into more groups for more detailed characterization, e.g., into 10 groups bounded by 10%, 20%, ..., 90% probability of exceedance. According to the actual hydrological characteristics of the study river, the annual runoff group p and the monthly runoff group q may not be equal.

2.2 Copula-Based Joint Probability Modeling

Subsequently, candidate Copula functions (e.g., Gaussian, Frank, or Clayton) are fitted to the validated marginal distributions to characterize dependencies between annual and monthly flows. The optimal Copula is selected using a root-mean-square error (RMSE) minimization criterion, which quantifies the discrepancy between theoretical joint probabilities and empirical copula estimates derived from historical data. This process constructs a joint probability distribution that explicitly models the co-occurrence of annual

hydrological states (e.g., wet/normal/dry years) and monthly flow magnitudes, essential for capturing the study area's unique wet-dry encounter patterns.

2.3 Conditional Probability Integration with FDC Analysis

Thereafter, monthly flows are categorized into high/medium/low runoff categories based on magnitude, and the Flow-Duration Curve (FDC) method is applied to derive initial ecological flow thresholds for each category, reflecting intra-annual habitat requirements (e.g., spawning season low-flow protection). Concurrently, annual flows are similarly classified into high/medium/low regimes to establish inter-annual context. Using Bayesian inference, conditional probabilities of monthly flow categories under different annual flow regimes are calculated, quantifying how multi-year drought/flood cycles influence seasonal flow likelihoods (e.g., the probability of a low-flow month in a dry year versus a wet year).

2.4 Ecological Flow Synthesis

Finally, these conditional probabilities are integrated with FDC-derived initial thresholds to generate a temporally explicit ecological flow process. By weighting category-specific flows with their regime-dependent probabilities, the framework produces a dynamic flow guide that balances short-term ecological demands (e.g., monthly sediment transport requirements) with long-term hydrological variability (e.g., decadal drought resilience). This approach ensures the resulting IEF not only maintains critical habitat conditions during typical years but also adapts to extreme hydrological scenarios, providing a robust regulatory basis for reservoir operations.

3 Study Area

The Yangtze River is one of the rivers with most abundant hydropower resources in the world. It has a length of approximately 6000 km, and is the longest river in Asia, the third-longest river in the world. The Upper Yangtze River Basin (UYRB) has enriched nearly 90% of the hydropower resources in the entire basin, with a developable installed capacity of about 20×10^8 kW (Chu et al., 2019). It has been proved that the runoff in the UYRB has changed significantly, and the variation will undoubtedly have an impact on the operation mode and comprehensive benefits of large reservoir projects, especially when considering the uncertainties that whether large reservoir projects such as Three Gorges can still perform their design benefits under the new runoff conditions (Qin et al., 2020; Slaughter and Razavi, 2020). Therefore, we selected the giant cascade reservoirs in the UYRB as the research object, which is composed of Xiluodu, Xiangjiaba, Three Gorges, and Gezhouba HHPs. The spatial location of the cascade reservoirs is shown in Fig. 2, and the main control parameters of each reservoir are shown in Table 1. The eight key hydrological stations with measured runoff series from 1951 to 2018 in the UYRB are selected to examine the runoff change (Fig. 1).




Fig. 1. Location of hydrological stations and cascade reservoirs in the UYRB.

4 Results and Discussion

4.1 Marginal Distribution Function Determination

We organized the flow observations at Yichang Station from 1940 to 2011 into monthly and annual flow series. It has been shown that the runoff at Yichang Station obeys the P-III distribution (Huang et al. 2018; Jia et al. 2020). Therefore, we used the P-III distribution as the marginal distribution function to fit the annual flow series and the flow series of each month. The parameters of the P-III distribution were estimated by the great likelihood method.

4.2 Joint Distribution Function Determination

4.2.1 Parameter Estimation for Candidate Copula Functions

We selected 2-dimensional Clayton Copula, Frank Copula, Gumbel-Hougaard Copula, Gaussian Copula, and Student-t Copula functions as candidate joint distribution functions of the monthly and annual flows. The parameters of each candidate joint distribution function were estimated using the great likelihood estimation method, and the parameter estimation results are shown in Table 1.

4.2.2 Copula Function Selection

We calculated the RMSE between the 5 candidate and empirical joint distributions and the results are shown in Table 4. The optimal Copula function was selected as the joint

Table 1. Parameter estimation results for candidate joint distribution functions

Annual runoff &	Clayton	Frank	Gumbel-Hougaard	Gaussian	Student-t	
	τ	τ	τ	ρ	ρ	ν
Jan	0.000	0.186	1.000	−0.030	0.016	7.113
Feb	0.117	0.850	1.002	0.054	0.112	9.298
Mar	0.000	−0.222	1.000	−0.071	−0.049	9.126
Apr	0.000	1.266	1.172	0.198	0.222	15170634.088
May	0.300	2.224	1.284	0.341	0.364	4737006.119
Jun	0.304	2.015	1.272	0.349	0.361	12963414.510
Jul	1.052	4.479	1.682	0.598	0.616	5.103
Aug	1.118	4.700	1.678	0.600	0.621	4.257
Sep	1.052	4.660	1.661	0.623	0.642	4094600.140
Oct	1.154	6.008	1.858	0.685	0.718	13199284.535
Nov	0.711	3.623	1.368	0.476	0.492	14793387.334
Dec	0.731	4.174	1.478	0.500	0.539	11.624

distribution function of monthly and annual flows with the criterion of minimum RMSE, which is highlighted in bold with a gray background in the table (Table 2).

Table 2. RMSE between candidate and empirical joint distributions for monthly and annual flows

Annual runoff &	Clayton	Frank	Gumbel-Hougaard	Gaussian	Student-t
Jan	0.021	0.020	0.022	0.021	0.020
Feb	0.021	0.019	0.023	0.026	0.021
Mar	0.013	0.012	0.013	0.013	0.012
Apr	0.023	0.019	0.018	0.016	0.018
May	0.023	0.016	0.015	0.013	0.015
Jun	0.023	0.013	0.013	0.015	0.013
Jul	0.018	0.018	0.014	0.018	0.014
Aug	0.016	0.020	0.016	0.020	0.016
Sep	0.017	0.019	0.016	0.022	0.017
Oct	0.027	0.017	0.013	0.016	0.013
Nov	0.023	0.014	0.019	0.027	0.018
Dec	0.034	0.016	0.026	0.029	0.023

The joint probability distributions of the annual flow and the monthly flow of different months were established based on the selected Copula functions, as shown in Fig. 2.




Fig. 2. Joint probability distribution of the annual flow and the monthly flow




Fig. 2. (continued)

4.3 Initial Ecological Flow Determination

The FDC-based method was used to calculate the initial ecological flow. The monthly flow series was divided into high, medium, and low groups, bounded by 25% and 75% of the exceedance probability for each month. The flow series of each month under each monthly flow grouping was sorted by flow magnitude to create an FDC. The flow value corresponding to the 90% exceedance probability was then determined as the initial ecological flow for the month in this grouping. The initial ecological flow results are shown in Table 3.

Table 3. Initial ecological flow for each month in each monthly group (m³/s)

Monthly group	Jan	Feb	Mar	Apr	May	Jun
High	4733	4249	4993	7287	12925	20040
Medium	4014	3559	3956	5676	9792	15801
Low	3627	3151	3083	4152	7101	11658
Monthly group	Jul	Aug	Sep	Oct	Nov	Dec
High	34190	32213	30283	20126	10956	6500
Medium	26116	22535	22177	15945	8999	5423
Low	18994	12097	12526	10507	7002	4501

4.4 Final Ecological Flow Determination

4.4.1 Joint Probability and Conditional Probability

The previous sub-section established the joint probability distribution of annual and monthly flows (see Fig. 2), from which the joint probability values for different combinations of annual and monthly flows can be obtained. The conditional probability of each month's flow size (which group of high, medium, and low flows the monthly flow belongs to) was then calculated based on Bayesian inference under different annual flow scenarios (which group of high, medium, and low flows the annual flow belongs to). The results are shown in Table 4.

Table 4. Conditional probability of each month's flow size under different annual flow scenarios

Annual group	High			Medium			Low		
Monthly group	High	Medium	Low	High	Medium	Low	High	Medium	Low
Jan	0.263	0.500	0.237	0.250	0.500	0.250	0.237	0.500	0.263
Feb	0.311	0.496	0.193	0.248	0.504	0.248	0.193	0.496	0.311
Mar	0.235	0.500	0.266	0.250	0.500	0.250	0.266	0.500	0.235
Apr	0.379	0.452	0.169	0.226	0.522	0.252	0.169	0.504	0.327
May	0.442	0.426	0.132	0.213	0.538	0.249	0.132	0.497	0.371
Jun	0.410	0.474	0.116	0.237	0.526	0.237	0.116	0.474	0.410
Jul	0.558	0.383	0.059	0.192	0.617	0.192	0.059	0.383	0.558
Aug	0.563	0.376	0.061	0.188	0.624	0.188	0.061	0.376	0.563
Sep	0.552	0.409	0.039	0.205	0.591	0.205	0.039	0.409	0.552
Oct	0.614	0.368	0.018	0.184	0.632	0.184	0.018	0.368	0.614
Nov	0.501	0.435	0.064	0.218	0.565	0.218	0.064	0.435	0.501
Dec	0.532	0.418	0.049	0.209	0.582	0.209	0.049	0.418	0.532

4.4.2 Ecological Flow Considering Inter-Annual and Intra-Annual Wet-Dry Co-occurrences

After obtaining the conditional probability values, combined with the initial ecological flows, the final ecological flow process that takes into account the intra- and inter-annual flow variations was finally calculated. The results are shown in Table 5. The results provide a red line for the development of water resources and hydro-energy resources of the Jinsha River, as well as for the better protection of the natural plant and animal species.

Most hydropower stations serve multiple functions, including power generation, flood control, and water supply. Their primary goal is to pursue efficient utilization of

water resources and maximize economic benefits. However, if the operational models of these hydropower stations do not adequately consider the ecological flow requirements of the downstream river reaches, it can cause varying degrees of damage to the river ecosystem. For example, the construction of dams obstructs rivers, leading to changes in hydrological conditions and biological habitats, which affects the spawning and reproduction of migratory fish, resulting in alterations in the abundance and structural characteristics of riverine biological communities. The calculated ecological flow can be used as a constraint in the optimization scheduling model of the reservoir group on the UYRB, or the level of assurance for ecological flow can be set as an objective in multi-objective optimization scheduling. This approach can achieve the consideration of ecological factors in the reservoir scheduling process, balancing economic and ecological benefits to maximize overall benefits.

Table 5. Final ecological flow results considering intra- and inter-annual flow variations (m³/s)

Annual group	Jan	Feb	Mar	Apr	May	Jun
High	4112	3695	3967	6028	10821	17058
Medium	4097	3629	3997	5656	9791	15824
Low	4083	3565	4027	5451	9207	14594
Annual group	Jul	Aug	Sep	Oct	Nov	Dec
High	30206	27351	26277	18413	9851	5951
Medium	26298	22392	21861	15714	8990	5455
Low	22613	17245	17165	12682	8124	4985

5 Conclusion

In developing and utilizing water resources, maintaining ecological flow is the most basic requirement for protecting river ecosystems. This study proposes an innovative ecological flow determination method based on the joint probability distribution of annual and monthly flows, addressing the limitation of traditional hydrological methods that overlook the co-occurrence of wet-dry conditions across annual and monthly scales. A case study was conducted in the downstream area of the Three Gorges Hydropower Project, yielding the following key findings:

- (1) The Pearson Type III (P-III) distribution was validated as an appropriate model for the marginal distributions of both annual and monthly runoff series. Goodness-of-fit tests (Kolmogorov-Smirnov and Anderson-Darling) confirmed significance levels exceeding 95%, indicating strong consistency between theoretical and observed flow data.
- (2) Optimal Copula functions were selected for different months based on root-mean-square error (RMSE) minimization: Gaussian Copula for January, March, and October; Frank Copula for February and April; Gumbel-Hougaard Copula for May, June,

and August; Clayton Copula for July, September, and November; and Student-t Copula for December, effectively capturing the probabilistic dependencies between annual hydrological regimes and monthly flow magnitudes.

- (3) By integrating conditional probabilities derived from Bayesian inference with Flow-Duration Curve (FDC) analysis, a dynamic ecological flow process was established that accounts for both intra- and inter-annual variability. Under high, medium, and low annual runoff scenarios, the framework generated monthly ecological flow thresholds that adapt to seasonal habitat requirements while reflecting long-term hydrological trends, providing a scientific basis for reservoir scheduling to balance hydropower development with ecological conservation in regulated river basins.

This study enhances the understanding of ecological flow dynamics in hydropower-dominated systems and offers a scalable methodology for integrating temporal variability into water resource management, supporting sustainable development objectives in large river basins worldwide.

References

- Absalon, D., Matysik, M., Woznica, A., Janczewska, N.: Detection of changes in the hydrobiological parameters of the Oder River during the ecological disaster in July 2022 based on multi-parameter probe tests and remote sensing methods. *Ecol. Indic.* **148**, 110103 (2023). <https://doi.org/10.1016/j.ecolind.2023.110103>
- Chen, Y.B., Wang, M.L., Zhang, Y., Lu, Y., Xu, B., Yu, L.: Cascade hydropower system operation considering ecological flow based on different multi-objective genetic algorithms. *Water Resour. Manag.* **37**(8), 3093–3110 (2023). <https://doi.org/10.1007/s11269-023-03491-3>
- Gleick, P.H.: Water in crisis: paths to sustainable water use. *Ecol. Appl.* **8**(3), 571–579 (1998). <https://doi.org/10.2307/2641249>
- Guo, X.M., Xu, L.K., Su, L., Deng, Y., Yang, C.H.: Comparing flow duration curves and discharge hydrographs to assess eco-flows. *Water Resour. Manag.* **35**(14), 4681–4693 (2021). <https://doi.org/10.1007/s11269-021-02890-8>
- Huang, K.D., Chen, L., Zhou, J.Z., Zhang, J.H., Singh, V.P.: Flood hydrograph coincidence analysis for mainstream and its tributaries. *J. Hydrol.* **565**, 341–353 (2018). <https://doi.org/10.1016/j.jhydrol.2018.08.007>
- Hughes, D.A.: Towards the incorporation of magnitude-frequency concepts into the building block methodology used for quantifying ecological flow requirements of South African rivers. *Water SA* **25**(3), 279–284 (1999)
- Jia, W.H., Dong, Z.C., Duan, C.G., Ni, X.K., Zhu, Z.Y.: Ecological reservoir operation based on DFM and improved PA-DDS algorithm: a case study in Jinsha river, China. *Hum. Ecol. Risk Assess.* **26**(7), 1723–1741 (2020). <https://doi.org/10.1080/10807039.2019.1603075>
- Petts, G.E.: Instream flow science for sustainable river management. *J. Am. Water Resour. As.* **45**(5), 1071–1086 (2009). <https://doi.org/10.1111/j.1752-1688.2009.00360.x>
- Poff, N.L.: Beyond the natural flow regime? Broadening the hydro-ecological foundation to meet environmental flows challenges in a non-stationary world. *Freshwater Biol.* **63**(8), 1011–1021 (2018). <https://doi.org/10.1111/fwb.13038>
- Sedghi-Asl, M., Poursalehan, S.J.: Modified ideal point method for estimating minimum environmental flow of rivers. *Acta Geophys.* (2024). <https://doi.org/10.1007/s11600-023-01264-5>

- Srivastava, A., Maity, R.: Unveiling an environmental drought index and its applicability in the perspective of drought recognition amidst climate change. *J. Hydrol.* **627 B**, 130462 (2023). <https://doi.org/10.1016/j.jhydrol.2023.130462>
- Tennant, D.L.: Instream flow regimens for fish, wildlife, recreation and related environmental resources. *Fisheries* **1**(4), 6–10 (1976)
- Wang, M.L., Zhang, Y., Lu, Y., Wan, X.Y., Xu, B., Yu, L.: Comparison of multi-objective genetic algorithms for optimization of cascade reservoir systems. *J. Water Clim. Change* **13**(11), 4069–4086 (2022). <https://doi.org/10.2166/wcc.2022.290>
- Xu, Y.S., Chen, Y.B., Ren, Y.F., Tang, Z.Y., Yang, X., Zhang, Y.: Attribution of streamflow changes considering spatial contributions and driver interactions based on hydrological modeling. *Water Resour. Manag.* **37**, 1859–1877 (2023). <https://doi.org/10.1007/s11269-023-03459-3>

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Ecological Restoration-Oriented Multi-objective Optimal Design of Clean Energy Heritage Landscapes Investigation

Yini Guo(✉)

Shanghai Investigation, Design & Research Institute Co., Ltd.,
388 YiXian Road, HongKou District, Shanghai 200000, China
guo_yini@ctg.com.cn

Abstract. This paper focuses on the ecological regeneration of clean energy industrial heritage. It puts forward a three-dimensional synergistic optimization framework of ‘heritage value-ecological restoration-energy reuse’ in response to the loss of industrial, cultural value caused by the current fragmented protection, which often overlooks systemic relationships between industrial remnants and their ecological contexts. The proposed multi-objective optimization design is constructed to realize the symbiosis of industrial memory inheritance, ecological function restoration, and renewable energy activation through translating cultural symbols, low-intervention heritage energy transformation, plant community dynamic monitoring, and other innovative design strategies. The research presents an interdisciplinary approach to the sustainable transformation of industrial heritage, fostering its creative evolution into ecological infrastructure while providing transferable methodologies for balancing industrial nostalgia preservation with cutting-edge green technologies in post-industrial landscapes.

Keyword: ecology · clean energy · industrial heritage landscape · multi-objective optimization design

1 Introduction

The global energy transition has accelerated the construction of clean energy infrastructure, which has resulted in a large number of engineering remains, such as decommissioned hydropower plants, abandoned photovoltaic sites, and obsolete power generation equipment, which are often caught in the double predicament of ecological degradation and annihilation of cultural values after they have been replaced or lost their original functions. Its improper disposal will exacerbate soil pollution, habitat fragmentation, and other issues for hydropower industry construction sites and many remaining facilities. These remains carry the technical memory of industrial civilization and regional cultural genes, and their disappearance means a break in society’s collective memory.

Although countries are actively pursuing ecological restoration policies and advocating industrial heritage tourism to activate the economy, there is still a lack of landscape regeneration practices for clean energy. Existing research focuses on a single dimension,

limiting itself to the protection of the heritage and ignoring the potential of renewable energy integration or emphasizing the renewal of technical facilities and facilities and cutting off the ecological restoration needs of the site. This fragmented model has led to “protective idleness” or “over-commercialization” of heritage spaces, making it challenging to achieve synergistic gains in the ecological-energy-cultural system.

With “multi-objective synergistic optimization” as the core, we explore the ecological restoration-oriented landscape design method for clean energy heritage. The goal is to establish an interdisciplinary framework for the spatial rejuvenation of heritage during the global energy transition, fostering the innovative transformation of industrial heritage into sustainable ecological infrastructure.

Research on the landscape design of industrial heritage both in China and internationally.

2 Classical Industrial Heritage Landscape in China and Abroad

Europe and the United States have explored the regeneration of industrial heritage earlier, but the practice of clean energy landscape construction is still relatively small. Following the shutdown of the coal mines in Germany’s Ruhr region, the local government has repurposed the extensive factory buildings and coal mining equipment into an industrial-style cultural park. Hoover Dam, which is the name given to the United States, includes a lot of natural scenery, artistic legacy, and engineering aesthetics; some of the attractions to see include the classic scenes of film and television as well as the country’s natural scenery. The landscape design of Beijing 798 Art Zone integrates industrial heritage and artistic creativity, retains Bauhaus-style factory buildings and creates a unique creative atmosphere through graffiti, steel sculpture, and other techniques. The landscape design of the Chongqing Industrial Museum integrates industrial heritage and artistic creativity, retaining the old factory buildings, big chimneys, and other iconic remains, transforming large-scale equipment into sculpture sketches, and forming a characteristic industrial landscape.

3 Development Opportunities

Global carbon neutrality targets and ecological security strategies present multidimensional environmental opportunities for industrial heritage landscapes. The EU’s “Green New Deal” and China’s “Waste-Free City” policy have promoted brownfield remediation and solid waste resource utilization. The mechanism for transforming ecological value driven by the market has gained momentum. Chongqing has implemented a strategy to revitalize and protect its industrial heritage, transforming the remnants of old industrial bases into urban “lifestyle belts” that integrate cultural, commercial, and residential functions and realizing the inheritance of industrial memories and the organic renewal of the city. At the level of innovative models, EOD development and digital management have enhanced sustainability; Chengdu’s Dongjiao Memory has balanced inputs through “restoration + business,” and Beijing’s Shougang Park has deployed hundreds of sensors to monitor pollution migration in real time. Reinvented industrial heritage landscapes have become cultural landmarks and have contributed significantly

to the regeneration of corporate and city brands. Economically, the industrial heritage landscape reduces the cost of site demolition and creates green jobs and tourism revenue, and its economic value activation becomes an essential engine for regional regeneration. Under the upgrading of culture and tourism consumption, the financial effect of industrial heritage tourism is remarkable, especially in the field of culture and education; the transformation of industrial heritage into an educational base for young people is a significant trend. China is still exploring new consumer scenarios such as “industrial heritage + economy.”

4 Design Concept

4.1 Value Analysis of Clean Energy Heritage Landscape

4.1.1 Legacy Value

Clean energy heritage is the carrier of technical testimony and collective memory of industrial civilization. Historical and technical value, enriching the development structure and construction archives of the hydropower station, providing a physical basis for the study of the history of hydropower engineering; industrial aesthetics value, conveying the sense of engineering power through the aesthetics of brutalism; social identity value, such as the slogan of the spirit of inheritance of the LiuJiaXiang hydro power station has become the symbolic symbol of the industrial spirit of the northwest region.

4.1.2 Ecological Value

The restorative capacity of the clean energy legacy landscape to damaged ecosystems and its unique potential in sustainable environmental services. Brownfield remediation and environmental governance, the abandonment of industrial relics is often accompanied by soil pollution, water eutrophication, and other ecological problems, the relics of the landscape on its reuse, the natural site combined with ecological restoration techniques through the plants - microbial joint restoration, and other means not only to avoid contamination at the source but also to achieve the purification of contaminated media. The remaining landscape can strengthen the environmental service function through ecological design and has the function of optimizing the sustainable service function.

4.1.3 Energy Value

Clean energy remains the secondary activation of renewable energy production potential, and it has the advantage of low-carbon technology integration. Utilizing the landscape environment, we can create a new energy system by leveraging available space and facilities, which will facilitate the efficient reuse of land resources, foster technological innovation, and improve the resilience of the energy supply.

4.2 Construction of the Three-Dimensional Evaluation System of “Heritage Value, Ecological Restoration, and Energy Reuse.”

The value index system of “heritage value-ecological restoration-energy reuse” covers many aspects. The following briefly analyzes the main dimensions; see Table 1.

Table 1. Brief description of the value indicator system of “heritage value-ecological restoration-energy reuse.”

	value	Core indicators	Evaluation methodology	Problems	Optimization suggestions
value of remains	Historical and technical value	Structural integrity; intergenerational representation of technologies	Rate of preservation of components; interviews with experts in the history of technology	Lack of archival systematicity; insufficient technology relevance analysis	Establishment of digitized archives
	Industrial Aesthetic Value	Constructed Morphological Aesthetics, Device Installation Artistry, Spatial Narrative	Aesthetic expert rating method; public visual perception research	Aesthetic evaluation is highly subjective; there is a lack of quantitative tools	Development of a VR visual impact simulation system; quantification of aesthetic parameters
	social custodial value	Degree of preservation; community events; local identity narrative fit	Questionnaire and Participatory Evaluation; Media Opinion Big Data Mining	Lack of community participation mechanisms; intergenerational memory gap	Formation of the “Technohistorians + Community Representatives” synergistic assessment meeting
ecological restoration	Brownfield remediation	Soil contamination; water remediation; decontamination of contaminated media	Combined plant-microbe remediation techniques; assessment of the efficacy of artificial wetland systems	Long restoration cycles; high technology costs	Development of low-cost remediation technologies; establishment of a dynamic adaptive remediation framework
	Sustainability service function	Microclimate regulation; resource recycling; sink capacity enhancement	Material life cycle assessment; vegetation index analysis	Lack of harmonization of low-impact design standards	Application of specified design technical guidelines

(continued)

Table 1. (continued)

	value	Core indicators	Evaluation methodology	Problems	Optimization suggestions
Energy reuse	Space planning suitability	Coordination of clean energy facilities with landscape patterns; potential for energy retrofitting of industrial structures; energy production-open space compliance utilization rate in common spaces	Visual aesthetic balance between topography and facility layout; functional overlay design for reuse of heritage structures	Facility layout destroys historical mechanisms; functionalized monolithic	Application of specified design technical guidelines
	Functionally integrated circularity	Artistic recycling of industrial waste; community microgrids coupled to landscape systems	Low-carbon technologies translated into perceptible landscape elements; narrative representation of material cycles	Fragmentation of energy facilities and landscape functions; insufficient community involvement	Designing ecological restoration-oriented landscape symbiosis systems for clean energy legacies; developing a community energy management app

5 Multi-objective Optimization Design Method

5.1 Cultural Symbol Transfer

5.1.1 Identification and Deconstruction of Cultural Symbols

The identification of cultural symbols needs to be based on the framework of multi-source data integration and value assessment. Extract iconic technical symbols by systematically combing construction drawings, engineering logs, and image data through historical archive excavation; identify intangible symbols by adopting oral history to collect and record the memories of old workers and neighboring residents on production processes and daily rituals; and spatial behavioral mapping to locate high-attention material carriers through heat maps and so on.

In the deconstruction stage, a symbol value matrix is constructed, and the core symbols are screened by weighting and evaluating different dimensions of technical representation, emotional resonance, and spatial appropriateness.

5.1.2 Translation and Spatial Implantation of Symbols

Translate the symbols through material reconstruction and narrative revitalization to realize the spatial expression of cultural values. The translation should consider the authenticity of the heritage and the contemporary aesthetic adaptability to realize the sustainable transmission of cultural memory. Material translation focuses on the functional replacement and aesthetic transformation of industrial components. In recent years, large-scale buildings have become popular as carriers of light and shadow shows, with more applications of science and culture integration with logos, “readable scenic walls,” and so on. Intangible narrative revitalization usually strengthens the sense of participation through interactive design, such as embedding NFC chips in heritage nodes and triggering AR recovery of historical production scenarios by device sensing or code scanning. The presentation form deserves more in-depth investigation, such as the principle of “balance between the obvious and the hidden”: core symbols, such as period slogans, are enlarged and displayed in situ to strengthen the visual impact, while secondary symbols, such as tools and parts, are placed at nodes along the path to stimulate the exploration of interest.

5.1.3 Synergistic Optimization of Symbol System

The synergistic optimization of the symbol system aims to realize the spatial feedback of cultural, ecological, and energy values and avoid the fragmentation of elements. Spatial layout synergy through GIS multi-criteria analysis, high cultural weight symbols superimposed layout, and the construction of narrative corridors to achieve the symbolic interpretation, ecological education, and new energy use of the functional coupling. Functional superposition synergy emphasizes the multiple attributes of the facility so that a single structure can simultaneously undertake the functions of energy production, carbon sink enhancement, and cultural display.

5.2 Synergistic Strategy of New Clean Energy and Industrial Heritage Protection

5.2.1 Landscape Integration Design for Low-Intervention Energy Transformation of Heritage Structures

The design takes minimization of intervention as the core principle and realizes the spatial-cultural symbiosis between the clean energy system and industrial heritage through technological innovation and aesthetic translation. Non-destructive installation processes are prioritized, and material recycling design transforms industrial waste into a carrier for new facilities. Landscape aesthetic integration emphasizes the narrative dialogue between old and new technologies, and the design follows the principle of reversibility to avoid permanent damage to the heritage body. Regarding functional synergy, the layout of energy facilities maps history and recreates spatial memory.

5.2.2 Spatial Coupling of Multi-energy Complementary System and Landscape Function

The design creates a composite energy network by integrating wind, light, water, storage, and other energy systems, resulting in a strong synergy with the landscape’s functions

and enhancing production, ecological, and experiential effectiveness. The layout of complementary energy sources utilizes the spatial characteristics of the remains to form a technological aesthetic narrative. The spatial strategy emphasizes the superposition of energy production and public services to form a multidimensional space.

The dynamic synergy mechanism relies on the Internet of Things and digital twin technology to adjust the energy scheduling strategy dynamically through real-time monitoring of crowd density and weather data by sensors. The creation of energy visualization and interaction nodes, along with an AR tour system, illustrates the movement of wind and water, as well as data on energy and carbon emissions reduction, aimed at enhancing public awareness of low-carbon practices.

5.3 Three-Dimensional Dynamic Monitoring System for Plant Communities

5.3.1 Dynamic Monitoring Technology and Ecological Restoration Adaptive Management

Based on the ecological restoration-oriented landscape design of clean energy remains, the three-dimensional dynamic monitoring system of plant communities realizes accurate regulation through the fusion of multi-source data. Lidar scanning and multi-spectral drone imaging technologies are considered to construct a three-dimensional point cloud model of vegetation to analyze plant communities in real time; combined with the Internet of Things sensor network, it dynamically tracks the carbon sink potential and microclimate regulation efficiency of plant communities. The monitoring data are dynamically linked to the ecological restoration objectives through the digital twin platform, forming a closed loop of “monitoring-assessment-optimization.” The design breaks through the traditional static restoration mode, realizes the dynamic adaptive management of the restoration process, and provides a scientific basis for multi-objective optimization.

5.3.2 Data-Driven Plant Configuration and Spatial Synergistic Optimization

Guided by multi-objective optimization, the monitoring system analyzes the plant community succession law through machine learning algorithms to guide species selection and spatial layout. In addition to screening the best possible configuration scheme based on the historical monitoring data, the model is trained to forecast the contribution weights of various plant combinations to carbon sinks, soil and water conservation, and biodiversity. Optimize the synergistic layout of vegetation and clean energy facilities by combining the characteristics of the remaining site. With the data-driven design strategy, the plant community is not only a carrier for ecological restoration but also an active medium to regulate the energy system efficiency and strengthen the heritage’s cultural narrative to promote the transformation of the industrial heritage into a “production-ecology-humanity” composite system.

6 Conclusion and Prospect

Revitalizing industrial heritage is a crucial strategy for urban renewal in the age of ecological civilization. This study proposes a multi-objective optimization design concept and method for the landscape of clean energy relics, which is oriented to environmental restoration. It explores the theoretical and practical path for transforming industrial civilization heritage into sustainable ecological infrastructure.

In the future, the study will deepen the exploration in multiple dimensions, such as further research and development of heritage-friendly clean energy technologies to enhance the compatibility of equipment with historical structures and reduce the intensity of intervention; promote the innovation of flexible policy tools to solve the conflict between heritage protection norms and new energy technology standards and establish a multi-sectoral synergy mechanism; strengthen the community co-construction model, and incorporate the public's memory collection and energy education and experience in the whole process of regeneration, to build a sustainable ecological infrastructure for industrial civilization—technical rationality and double identity of cultural emotion, etc.

As a material witness of human industrial civilization, regenerating industrial heritage is a technical challenge and a cultural mission to continue civilization. Through continuous theoretical innovation, technological iteration, and social synergy, the clean energy heritage landscape is expected to become an exemplary paradigm for sustainable urban renewal, contributing to the transformation of global industrial heritage.

Acknowledgments. “Ecological restoration-oriented multi-objective optimal design of clean energy heritage landscapes investigation” was founded by the Project of Shanghai Investigation, Design & Research Institute Co., Ltd (No. 2024YF(4)-012).

References

1. Lu, M.: A Study on the Renewal and Reconstruction Strategy of Old Industrial Areas Based on Transformation and Upgrading. Suzhou Institute of Science and Technology (2011)
2. Huang, P.: Germany Ruhr region “industrial culture road” on China’s industrial city tourism planning inspiration. *Urbanism Archit.* **21**(19), 61–66 (2024)
3. Lu, Y.: The Hoover Dam Project and Its Naming - A Study Centered on Newspaper Narratives. Shanghai: East China Normal University (2022)
4. He, D.: Research on the Optimization Strategy of Landscape Design of Chongqing Anti-war Industrial Heritage under the Perspective of Narratology. Chongqing University, Chongqing (2022)
5. Zhao, B., He, M.: Topic link: green belt and road and the EU green new deal. *J. Xi’an Jiaotong Univ. (Soc. Sci.)* **44**(06), 32–43 (2024)
6. Li, H.: China’s “Waste-Free City” construction advances comprehensively. *Ecol. Econ.* **41**(03), 9–12 (2025)
7. Wang, S., Kong, C.: Research on AR scene experience design under the perspective of spatial narratology. *Art Res.* **04**, 118–122 (2024)
8. Yin, H.: Study on the Realization Path and Economic Consequences of Lean Digitalization Empowering Specialized, Specialized and New “Small Giants”—Taking Exton as an Example. Jiangxi University of Finance and Economics, Jiangxi (2024)

9. Yue, X., Cai, F., Zhao, M.: Research on the development strategy of industrial heritage tourism based on cultural memory--taking beijing shougang park as an example. *China World Cult. Exch.* **2**, 128–130 (2025)
10. Cen, W., Shen, L.: Conservation and utilization of urban industrial buildings - a case study of Yangshupu waterworks. *Shanghai Urban Dev.* **4**, 27–29 (2005)
11. Cao, F.: An analysis of the patterns, causes and evolution of the changing discourse of industrial heritage - a case study of the Ironbridge Gorge, a world heritage site in the United Kingdom. *Southeast Cult.* **01**, 181–190 (2021)
12. Yue, X., He, Y.: Exploration of industrial migration and its site development and utilization--taking Chongqing Industrial Culture Expo Park as an example. *Educ. Geogr.* **10**, 2+81 (2023)
13. Zhao, Y., Luo, W., Gou, B., Si, C.: “Red Power Station” lights up the Longyuan Plain. *Electricity Cult. Today* **12**, 100–101 (2024)
14. Moss, B.: Home: The Intersection of Individual and Urban Narrative on a Post—Industrial Waterfront Site in Halifax, Nova Scotia. *Dalhousie University School of Architecture, Canada* (2009)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Attribution and Uncertainty Analysis of River Runoff Changes: A Case Study of the Upstream Yangtze River in China

Yu Zhang¹(✉), Xiao Zhang², and Jing Zhang²

¹ Nanjing Hydraulic Research Institute, Nanjing 210029, Jiangsu, China
yuzhang@nhri.cn

² Bureau of Hydrology, Changjiang Water Resources Commission, Wuhan 430010, China

Abstract. In this study, a new attribution analysis method based on large-scale hydrological modeling is developed. This method assesses the impacts of climate change and human activities on streamflow while taking uncertainties into consideration. Within the proposed general method framework, time series analysis methods are used to quantify the streamflow change; Then a large-scale Soil and Water Assessment Tool (SWAT) model is set up and the Differential Evolution Adaptive Metropolis (DREAM) algorithm is employed to approximate the posterior distributions of model parameters with Bayesian inference; Attribution analysis is further conducted with the improved rationale and the uncertainties translate from modeling are evaluated. The proposed attribution analysis method is then applied to a case study of the Upstream Yangtze River (UYZR) in China. Results reveal that: (1) Streamflow decreases significantly in the UYZR. Streamflow has various changing properties at small scales. (2) Precipitation, maximum temperature, windspeed and land use/cover change (LUCC) tend to decrease streamflow, while the minimum temperature and relative humidity tend to increase streamflow in the UYZR. Among the driving factors, precipitation has the most dominant influence. (3) Attribution uncertainty of precipitation has the largest absolute value and relative attribution uncertainties of driving factors behave differently in various river basins. These findings can help enhance the understanding of influences of climate change and human activities on streamflow and are also meaningful to adaptive water resources management.

Key Points:

- Develops a new attribution analysis method based on large-scale hydrological modeling
- Introduces uncertainty analysis into attribution analysis
- Proposes a multi-routes-based attribution analysis
- Includes spatial contributions in attribution analysis
- Conducts a study case based on real-world data

© The Author(s) 2026

Y. Hu et al. (Eds.): IHDC 2025, LNCE 792, pp. 280–311, 2026.

https://doi.org/10.1007/978-981-95-4889-7_26

Keywords: Attribution analysis · Uncertainty analysis · Runoff change · Hydrological modeling · Upstream Yangtze River

1 Introduction

Streamflow is one of the most important components of hydrological cycle. As a resultant for changing environment, streamflow change is the key to understand impacts of climate change and human activities on water resources at regional and global scales (J Y Liu et al. 2017). Conversely, the streamflow change also has feedbacks on the climate system and affects the water use pattern significantly (Dey and Mishra 2017). Therefore, understanding of streamflow generation, variation and underlying causes in a changing environment is critical for the effective management of water resources. Climate change and human influence are two major drivers that alter hydrological processes and cause changes in spatio-temporal distribution of water resources (X X Wang 2014). Streamflow is also expected to be influenced by the combination of climate change and human activities. The rapid increase of population along with increase in water demand poses severe challenges to water resources (Y Zhang et al. 2018). Decision and policy makers are drawn towards managing the consequences of hydrological impacts of climate change and human activities (Hall et al. 2012). The individual impacts of climate change and human activities are, therefore, necessary to frame different adaptive measures for optimal water resources management (Hall et al. 2014).

Generally, researchers use long term streamflow data to quantify its variation and attribute the streamflow change as a function of climate change and human activities, at different scales (Jiang et al. 2015). Climate change causes alteration in precipitation (including its form, amount, intensity, process and spatial distribution) (Dooze et al. 1999), evaporation (W G Wang et al. 2012), soil moisture availability (Montenegro et al. 2018), glacier and snow melting (Barnett et al. 2005), and time of flow routing (Prowse et al. 2006). Whereas, human activities affect streamflow processes as a result of land use/cover change (LUCC), urbanization (Hutchins et al. 2018; X P Zhang et al. 2008; Zheng et al. 2009), construction of water transfer projects, dams and water retention structures (G S Wang et al. 2009). LUCC influences streamflow generation and confluence via changing the soil properties, interception of precipitation and surface roughness (S P Wang et al. 2013; L Zhang et al. 2017), and LUCC also affects the flood frequency (Brath et al. 2006). Because of the large amount of construction of impervious surface (e.g., cement and tar), urbanization leads to higher surface streamflow generation and reduces the lag time between precipitation and streamflow, resulting in increase in peak flow (Rose and Peters 2001). For assessing the individual impact of climate change and human activities on streamflow, numerous methods have been proposed. In general, the attribution analysis methods can be categorized as: (1) analytical approaches, including climate elasticity (Sankarasubramanian et al. 2001), hydrological sensitivity methods (Zuo et al. 2014), (2) conceptual approaches, including Budyko-based methods (D B Wang and Hejazi 2011), Tomer-Schilling framework (Tomer and Schilling 2009), (3) hydrological modeling approaches (Dey and Mishra 2017).

The hydrological modeling approaches aim to describe hydrological processes based on the understanding of actual mechanisms. Physically based models can provide

detailed, high resolution descriptions of small scale processes that are numerically integrated to larger scales (Hrachowitz and Clark 2017). They are expected to be the important tools for attribution analysis. This is in particular true in the light of the increasing effects of climate change and human activities on water resources at different scales. This work develops a new method framework for attribution analysis based on hydrological modeling. Its contribution can be introduced as followed: Firstly, in previous studies, for large scales (e.g. basins) analytical approaches and conceptual approaches are used, hydrological modeling approaches are applied to smaller scales (e.g. catchments, watersheds). In this work a large-scale hydrological model is established to assess impacts of climatic factors and human influence on streamflow change. The advantage is that physically based models can offer not only general basin hydrological pattern but also detailed information of hydrological processes inside a basin. Therefore, the proposed new method in this study can do spatial attribution analysis instead of only offering a general result for the whole study area, which will provide more practical guidance for future adaptive measures. Currently, very few studies can provide detailed spatial results. An exception is found (J Y Liu et al. 2017), in which observed data are collected in a large number of hydrological stations and the conceptual approach is used to do attribution spatially. Different from that exception which is based on and limited to the high requirement of observed data, we do such detailed attribution analysis based on the method itself with the help of physically based model's descriptions of small scale processes. Secondly, uncertainty evaluation for attribution analysis is much insufficient in previous studies (X X Wang 2014). There are many uncertainty sources during the process of attribution analysis. It is hard to reveal the driving factors in what way, how much, and how to influence streamflow without consideration of uncertainties. In this proposed method, parameter uncertainty in hydrological modeling is evaluated and its evolving uncertainty in attribution analysis are further studied. Furthermore, existing methods assess impacts of climate change and human activities via calculating the streamflow change caused by separate inference of driving factors. This common rationale can be implemented following different routes and different results can be obtained. In this work, a multi-routes-based way is developed to level off the inconsistency in different routes. Impact of one driving factor is evaluated on an average level of other factors.

China is one of the most prominent countries in the contradiction between water supply and demand (Piao et al. 2010). Due to the influence of changing environment, the characteristics, circumstances and patterns of water resources have changed significantly. In the past five decades, streamflow in six important rivers in China (i.e., the Yangtze River, the Yellow River, the Pearl River, the Songhua River, the Haihe River, the Huaihe River) all decreased significantly. Water resources and hydropower resources of the Yangtze River are the most abundant in China. The average annual streamflow is 996 billion m³, making up 36% of the total streamflow in China. The theoretical reserves of hydropower resources account for about 40% of the national total. The UYZR is the streamflow formation area and hydropower storage area, accounting for 45% of basin water resources and 90% of basin hydropower resources, has an irreplaceable position and inestimable value in China's strategic reserve of resources. However, recently, measured streamflow in most regions of the UYZR has been reported decreasing obviously,

which has great impacts on economic development, social stability and ecological security and bring new risks for integrated development and utilization of water resources and joint operation of water conservancy and hydropower system (Y Zhang et al. 2018). Therefore, the UYZR is selected as the study case to research on the streamflow change and explore the causes with consideration of uncertainties.

2 Methodology

The general framework of the attribution analysis method based on large-scale hydrological modeling with uncertainties is illustrated in Fig. 1. The proposed method is composed of five parts: (1) input data collection, (2) streamflow change description, (3) large-scale hydrological modeling; (4) parameter Bayesian inference and uncertainty analysis, (5) attribution analysis. In detail, following input data collection, time series analysis methods are used to identify the characteristics and spatial composition of streamflow change. Then a large-scale hydrological model is established to express the hydrological processes as a spatio-temporal function of climate change and human activities. To improve the efficiency of model optimization and uncertainty analysis, the Latin-hypercube One-at-a-time (LH-OAT) approach is used for selecting the most sensitive parameters. Further, the DREAM algorithm is performed to infer the posterior distributions of these sensitive parameters. Finally, driving factors are selected and environment scenarios are designed for separating impacts of the driving factors on streamflow. Based on the results of parameter uncertainty, the evolving uncertainty in attribution analysis are assessed.




Fig. 1. Framework of the attribution analysis method based on large-scale hydrological modeling with uncertainties

2.1 Time Series Analysis Methods

Hydrological time series analysis can reflect the differences of hydrological processes in different regions and play an active role in understanding the law of hydrological cycle. In this study, temporal trends and abrupt change points in the streamflow time series are analyzed via time series analysis methods. Different statistical methods sometimes can obtain different results for the same time series. To avoid possible uncertainty and misleading results based on the individual method, in this study four statistical methods are selected: (1) The non-parametric Mann-Kendall test is highly recommended by the WMO and widely used to detect monotonic trends in long-term hydrological time series. (2) The Spearman's Rho test is a quick and simple test to determine whether correlation exists between two classifications of the same series of observations. Both the Mann-Kendall test and the Spearman's Rho test are used to detect monotonic trends in streamflow time series and evaluate the significance of the trends. Details of the two methods can be found in the reference (Li et al. 2008). (3) The non-parametric Pettitt's test is the same as the Mann-Kendall test is a rank-based and distribution-free test (Ma et al. 2008). In this study, it is used to detect the abrupt change point in streamflow series. (4) A sequential clustering method (Sharma 1985) is also used to identify the occurrence of an abrupt change point in time series as a reconfirmation of the abrupt change point detected by the Pettitt's test.

2.2 Hydrological Modeling

2.2.1 SWAT Model Description

SWAT is a widely used, physically based distributed hydrological model for simulating surface streamflow, groundwater discharge, evapotranspiration, and soil water content, and has been certified as an effective tool for evaluating water resources at a wide range of scales (J L Zhang et al. 2016). In this study, a large-scale SWAT model is set up to represent the relationship between environment inputs and hydrological processes. SWAT model divides a basin into several sub-basins. Every sub-basin consists of several hydrological response units (HRUs). HRU is defined as the unique combination of one class of land use, soil type and slope, which is the smallest unit of the SWAT model. The hydrological processes are simulated based on the water balance equation:

$$SW_t = SW_0 + \sum_{i=1}^t (R_i - Q_{surf,i} - E_{a,i} - W_{seep,i} - Q_{gw,i}), \quad (1)$$

where SW_t represents final soil water content, SW_0 represents initial soil water content, t represents time (days), R_i represents precipitation on day i , $Q_{surf,i}$ represents surface runoff on day i , $E_{a,i}$ represents evapotranspiration on day i , $W_{seep,i}$ represents water entering the vadose zone from the soil profile on day i , $Q_{gw,i}$ represents return flow or base flow on day i .

2.2.2 Sensitivity Analysis

SWAT model has a large number of parameters, whose values can be adjusted to obtain better performance in hydrological modeling. To reduce computation complexity in

calibration processes, sensitivity analysis is implemented to screen out the parameters who have great influence on the hydrological processes in a specific study area. In this study, the LH-OAT approach is used, which generates Latin-hypercube (LH) first samples and then gives a fraction to each parameter one-at-a-time (J L Zhang et al. 2016). Around LH point $e_{i,j}$, a partial effect $S_{i,j}$ can be calculated as follows:

$$S_{i,j} = \left| \frac{\left(\frac{Q(e_{1,j}, \dots, e_{i,j} \times (1+f_i), \dots, e_{P,j}) - Q(e_{1,j}, \dots, e_{i,j}, \dots, e_{P,j})}{[Q(e_{1,j}, \dots, e_{i,j} \times (1+f_i), \dots, e_{P,j}) - Q(e_{1,j}, \dots, e_{i,j}, \dots, e_{P,j})]/2} \right)}{f_i} \right|, \quad (2)$$

where $Q(\cdot)$ represents the model function, f_i is the fraction to parameter e_i , which is a pre-defined constant, P is the number of model parameters. The sensitivity of parameter e_i is calculated by averaging the partial effects in all LH points:

$$S_i = \frac{\sum_{j=1}^N S_{i,j}}{N}, \quad (3)$$

where S_i is the final sensitivity of parameter e_i , N ($N \geq P$) is the number of LH samples. Then the model parameters can be ranked by their sensitivities and the most sensitive parameters can be screened out.

2.2.3 Model Performance Evaluation

Two goodness of fit indicators: the coefficients of determination (R^2) and Nash–Sutcliffe efficiencies (E_{NS}) are selected to evaluate the hydrological modeling performance of established SWAT model. The R^2 is the square of the Pearson's correlation coefficient, which is an indicator of standard regression. It can be calculated as follows:

$$R^2 = \frac{\sum_{t=1}^n (Q_{obs,t} - \overline{Q_{obs}})(Q_{sim,t} - \overline{Q_{sim}})}{\sqrt{\sum_{t=1}^n (Q_{obs,t} - \overline{Q_{obs}})^2 \cdot \sum_{t=1}^n (Q_{sim,t} - \overline{Q_{sim}})^2}}, \quad (4)$$

where $Q_{obs,t}$ is the observed streamflow on time t , $Q_{sim,t}$ is the simulated streamflow on time t , n is the length of the time series, $\overline{Q_{obs}}$ is the mean value of observed streamflow, $\overline{Q_{sim}}$ is the mean value of simulated streamflow. R^2 is calculated to evaluate linear correlation between simulated and observed streamflow. R^2 ranges from 0 to 1, the larger value means the better outcomes. Although R^2 has been widely applied in model evaluation, it is insensitive to additive and proportional differences between simulated and observed values. Therefore, E_{NS} which is a dimensionless indicator is also calculated to evaluate the fitting and predictive power of established SWAT model as follows:

$$E_{NS} = 1 - \frac{\sum_{t=1}^n (Q_{obs,t} - Q_{sim,t})^2}{\sum_{t=1}^n (Q_{obs,t} - \overline{Q_{obs}})^2}, \quad (5)$$

where $\sum_{t=1}^n (Q_{obs,t} - \overline{Q_{obs}})^2$ reflects the total variation of the observed streamflow about the mean, and $\sum_{t=1}^n (Q_{obs,t} - Q_{sim,t})^2$ is the sum of squares of the difference between simulated streamflow and the corresponding observed streamflow, indicating the variation in the data that has not been explained by the model (Y R Liu et al. 2017).

2.3 Uncertainty Analysis

2.3.1 Bayesian Inference

The large-scale hydrological modeling contains a variety of uncertainties (Vrugt 2016). In this study, the parameter uncertainty is analyzed by using the Bayesian method. By adopting a Bayesian formalism, the posterior distribution of the parameters of the model can be derived by conditioning the spatio-temporal behavior of the model on observations as follows:

$$p(\boldsymbol{\theta}|\tilde{\mathbf{Y}}) = \frac{p(\boldsymbol{\theta}) \cdot p(\tilde{\mathbf{Y}}|\boldsymbol{\theta})}{p(\tilde{\mathbf{Y}})}, \quad (6)$$

where $p(\boldsymbol{\theta}|\tilde{\mathbf{Y}})$ signifies the posterior distribution of parameter set $\boldsymbol{\theta}$, which is derived from the prior distribution $p(\boldsymbol{\theta})$ conditioned on observed data $\tilde{\mathbf{Y}}$. The prior distribution $p(\boldsymbol{\theta})$ explains the information about parameter set $\boldsymbol{\theta}$, before any data are collected. $L(\boldsymbol{\theta}|\tilde{\mathbf{Y}}) \equiv p(\tilde{\mathbf{Y}}|\boldsymbol{\theta})$ denotes the likelihood function. The $p(\tilde{\mathbf{Y}})$ acts as a normalization constant. In practice, $p(\tilde{\mathbf{Y}})$ is not required for posterior estimation as all statistical inferences about posterior distribution $p(\boldsymbol{\theta}|\tilde{\mathbf{Y}})$ can be made from the unnormalized density

$$p(\boldsymbol{\theta}|\tilde{\mathbf{Y}}) \propto p(\boldsymbol{\theta})L(\boldsymbol{\theta}|\tilde{\mathbf{Y}}) \quad (7)$$

The main culprit now is to definite the likelihood function. We assume the error residuals are independent then the likelihood of the error residuals can be written as follows:

$$L(\boldsymbol{\theta}|\tilde{\mathbf{Y}}) = f_{\tilde{y}_1}(y_1(\boldsymbol{\theta})) \times f_{\tilde{y}_2}(y_2(\boldsymbol{\theta})) \times \dots \times f_{\tilde{y}_n}(y_n(\boldsymbol{\theta})) = \prod_{t=1}^n f_{\tilde{y}_t}(y_t(\boldsymbol{\theta})), \quad (8)$$

where $f_a(b)$ signifies the probability density function of a evaluated at b . We further assume the error residuals to be normally distributed, $e_t(\boldsymbol{\theta}) \sim N(0, \hat{\sigma}_t^2)$. Then the likelihood function becomes:

$$L(\boldsymbol{\theta}|\tilde{\mathbf{Y}}, \hat{\sigma}^2) = \prod_{t=1}^n \frac{1}{\sqrt{2\pi\hat{\sigma}_t^2}} \exp\left[-\frac{1}{2}\left(\frac{\tilde{y}_t - y_t(\boldsymbol{\theta})}{\hat{\sigma}_t}\right)^2\right] \quad (9)$$

Once the prior distribution and likelihood function have been defined, what is left in Bayesian analysis is to summarize the posterior distribution. Most dynamic system models are highly nonlinear, and this task cannot be carried out by analytical means nor by analytical approximation. Therefore, Markov chain Monte Carlo (MCMC) simulation is expected to sample from the posterior distribution. The basis of MCMC simulation is a Markov chain that generates a random walk through the search space and successively visits solutions with stable frequencies stemming from a stationary distribution.

2.3.2 DREAM Algorithm

To explore the posterior distribution, in this study, the DREAM algorithm is applied to implement MCMC. Specifically, DREAM is an adaptation of the Shuffled Complex Evolution Metropolis algorithm, which has been proved to be superior to other adaptive MCMC sampling approaches, and to be able to provide better solutions than commonly used optimization algorithms in high-dimensional search spaces (Vrugt 2016). Details of the DREAM algorithm can be found in the references (Vrugt et al. 2008; Vrugt et al. 2009). The Gelman-Rubin $\hat{R}$ metric is used to diagnose the convergence of the sample process, and the value less than 1.2 can be regarded as convergence to a stationary distribution (Y R Liu et al. 2017).

In this study, 95% simulation uncertainty ranges for simulated streamflow are calculated to represent the uncertainty of model simulation results, which are derived from the 2.5 and 97.5 percentiles of parameters' posterior probability density functions (PDFs). The average distance of 95% simulation uncertainty ranges is defined as follows:

$$\bar{d} = \frac{1}{l} \sum_{i=1}^l (Q_U - Q_L)_i, \quad (10)$$

where l is the length of the data, Q_U and Q_L represent the simulated streamflow by using the 2.5 and 97.5 percentiles of parameters' posterior PDFs. Two indexes: p-factor and r-factor are calculated to evaluate the model simulation uncertainty (X J Zhang et al. 2014). The p-factor is defined as the percentage of observed data bracketed by the 95% simulation uncertainty ranges. The r-factor is defined as follows:

$$r - factor = \frac{\bar{d}}{\sigma}, \quad (11)$$

where σ represents the standard deviation of the observed streamflow series. The closer r-factor to 0 and p-factor to 1, the better outcomes.

2.4 Attribution Analysis Rationale

2.4.1 Baseline and Altered Period Determination

For a gauged watershed of interest, the whole study period can be split into subperiods from a year, before which there is no obvious changes in streamflow subseries and the impacts of climate change and human activities can be negligible. The subperiod before this break year is defined as the baseline period, in which the streamflow is considered to be near-pristine. The sub-period after this break year is defined as the altered period. Usually, the change point of streamflow detected by time series analysis method is selected as the break year. However, climate change and human activities can level off abrupt increase or decrease in streamflow. For avoiding possible misleading results, in this study, precipitation and reference evapotranspiration are further analyzed to help determine the baseline period. Within the baseline period, there should be no obvious changes in streamflow, precipitation and reference evapotranspiration time series.

The FAO Penman-Monteith method is selected for reference evapotranspiration estimation, which is physically based and explicitly incorporates both physiological and

aerodynamic parameters. The FAO PM method requires data on sunshine duration, temperature, relative humidity, and wind speed. Details of the FAO Penman-Monteith method can be found in the reference (W G Wang et al. 2012).

2.4.2 Contributions to Streamflow Change

Currently-used attribution analysis methods are based on the rationale that the difference between the mean annual streamflow during altered period and the mean annual streamflow during baseline period can represent the total streamflow change between altered period and baseline period (X X Wang 2014). Contributions of climate change and human activities are defined as the streamflow change caused by separate inference of climate change and human activities, which can be estimated as:

$$\Delta Q = \overline{Q_{ap}} - \overline{Q_{bp}} = \Delta Q^c + \Delta Q^h, \quad (12)$$

$$\Delta Q^c = \overline{Q_{ap}^c} - \overline{Q_{bp}}, \quad (13)$$

$$\Delta Q^h = \overline{Q_{ap}^h} - \overline{Q_{bp}}, \quad (14)$$

where, ΔQ is the total streamflow change, $\overline{Q_{ap}}$ is the mean annual streamflow during altered period, $\overline{Q_{bp}}$ is the mean annual streamflow during baseline period, ΔQ^c is the contribution of climate change to streamflow change, ΔQ^h is the contribution of human activities to streamflow change, $\overline{Q_{ap}^c}$ is the mean streamflow only influenced by climate during altered period, $\overline{Q_{ap}^h}$ is the mean streamflow only inferred by human activities during altered period.

We define a combination of driving factors during different periods as a scenario and further define scenarios arranged in specific order as a route. In practice, this rationale is realized in different routes. A two-factor example (i.e., climate change and human activities) is provided to explain the different routes. We write streamflow as the function of climate change and human activities. As shown in Fig. 2, there are 4 routes to calculate the contributions. The total streamflow change can be calculated as follows:

$$\Delta Q = \overline{Q(C_{ap}, H_{ap})} - \overline{Q(C_{bp}, H_{bp})} = \Delta Q^c + \Delta Q^h, \quad (15)$$

where $\overline{Q(C_{ap}, H_{ap})}$ and $\overline{Q(C_{bp}, H_{bp})}$ represent the mean streamflow during altered and baseline period written as the function of climate change and human activities, C_{ap} and H_{ap} are climate change and human activities during altered period, C_{bp} and H_{bp} are climate change and human activities during baseline period. The contributions in route 1 can be calculated as follows:

$$\Delta Q^c = \overline{Q(C_{ap}, H_{bp})} - \overline{Q(C_{bp}, H_{bp})}, \Delta Q^h = \overline{Q(C_{ap}, H_{ap})} - \overline{Q(C_{ap}, H_{bp})}, \quad (16)$$

where $\overline{Q(C_{ap}, H_{bp})}$ represents the mean streamflow under altered period climate condition and baseline period human activities. The contributions in route 2 can be calculated as follows:

$$\Delta Q^h = \overline{Q(C_{bp}, H_{ap})} - \overline{Q(C_{bp}, H_{bp})}, \Delta Q^c = \overline{Q(C_{ap}, H_{ap})} - \overline{Q(C_{bp}, H_{ap})}, \quad (17)$$

where $\overline{Q(C_{bp}, H_{ap})}$ represents the mean streamflow under baseline period climate condition and altered period human activities. The contributions in route 3 can be calculated as follows:

$$\Delta Q^c = \overline{Q(C_{ap}, H_{bp})} - \overline{Q(C_{bp}, H_{bp})}, \Delta Q^h = \overline{Q(C_{bp}, H_{ap})} - \overline{Q(C_{bp}, H_{bp})}, \quad (18)$$

The contributions in route 4 can be calculated as follows:

$$\Delta Q^c = \overline{Q(C_{ap}, H_{ap})} - \overline{Q(C_{bp}, H_{ap})}, \Delta Q^h = \overline{Q(C_{ap}, H_{ap})} - \overline{Q(C_{ap}, H_{bp})} \quad (19)$$

Because of interactions between climate change and human activities, influence of one factor on streamflow change is various under different condition of other factors (Fig. 3). Therefore, for the same study case, contributions calculated in different routes are various. What's more, sum of the contributions doesn't equal the total streamflow change via route 3 and route 4.




Fig. 2. A two-factor (i.e., climate change and human activities) example for common rationale of attribution analysis

In this study, we propose a multi-routes-based way to level off the inconsistency in contributions calculated in different routes. We define ΔQ^c and ΔQ^h as the mean value of contributions in all routes:

$$\Delta Q^c = \frac{\overline{Q(C_{ap}, H_{bp})} - \overline{Q(C_{bp}, H_{bp})}}{2} + \frac{\overline{Q(C_{ap}, H_{ap})} - \overline{Q(C_{bp}, H_{ap})}}{2}, \quad (20)$$

$$\Delta Q^h = \frac{\overline{Q(C_{bp}, H_{ap})} - \overline{Q(C_{bp}, H_{bp})}}{2} + \frac{\overline{Q(C_{ap}, H_{ap})} - \overline{Q(C_{ap}, H_{bp})}}{2}, \quad (21)$$

where the contribution of climate change is evaluated on an average level of human activities, the contribution of human activities is evaluated on an average level of climate change. The sum of contributions of climate change and human activities equals the total streamflow change.




Fig. 3. A two-factor example used to explain the influence coming from different condition of factor F_1 on impact of factor F_2 on streamflow Q . If the factor F_1 is kept constant at y_1 value, then small changes in factor F_2 make obvious changes in streamflow Q . While if the values of factor F_1 is kept constant at y_2 , then changes in factor F_2 around will x_2 will cause negligible changes in streamflow Q .

We explain the rationale of attribution analysis in this study further by a four-factor (i.e., F_1, F_2, F_3, F_4) example. After the determination of baseline period and altered period, all driving factors have two conditions, i.e., condition during baseline period and condition during altered period. We define a combination of all factors in one of their own conditions as a scenario. As shown in Table 1, there are 16 scenarios (i.e., S_1-S_{16}) in the four-factor example. In the table, for each factor, “-1” represents condition during baseline period; “1” represents condition during altered period. Based on the definition proposed above, contributions of four factors can be calculated as follows:

$$\Delta Q^1 = \frac{(\overline{S_2} - \overline{S_1}) + (\overline{S_4} - \overline{S_3}) + (\overline{S_6} - \overline{S_5}) + (\overline{S_8} - \overline{S_7}) + (\overline{S_{10}} - \overline{S_9}) + (\overline{S_{12}} - \overline{S_{11}}) + (\overline{S_{14}} - \overline{S_{13}}) + (\overline{S_{16}} - \overline{S_{15}})}{8} \quad (22)$$

$$\Delta Q^2 = \frac{(\overline{S_3} - \overline{S_1}) + (\overline{S_4} - \overline{S_2}) + (\overline{S_7} - \overline{S_5}) + (\overline{S_8} - \overline{S_6}) + (\overline{S_{11}} - \overline{S_9}) + (\overline{S_{12}} - \overline{S_{10}}) + (\overline{S_{15}} - \overline{S_{13}}) + (\overline{S_{16}} - \overline{S_{14}})}{8} \quad (23)$$

$$\Delta Q^3 = \frac{(\overline{S_5} - \overline{S_1}) + (\overline{S_6} - \overline{S_2}) + (\overline{S_7} - \overline{S_3}) + (\overline{S_8} - \overline{S_4}) + (\overline{S_{13}} - \overline{S_9}) + (\overline{S_{14}} - \overline{S_{10}}) + (\overline{S_{15}} - \overline{S_{11}}) + (\overline{S_{16}} - \overline{S_{12}})}{8} \quad (24)$$

$$\Delta Q^4 = \frac{(\overline{S_9} - \overline{S_1}) + (\overline{S_{10}} - \overline{S_2}) + (\overline{S_{11}} - \overline{S_3}) + (\overline{S_{12}} - \overline{S_4}) + (\overline{S_{13}} - \overline{S_5}) + (\overline{S_{14}} - \overline{S_6}) + (\overline{S_{15}} - \overline{S_7}) + (\overline{S_{16}} - \overline{S_8})}{8} \quad (25)$$

where for writing convenience, $\overline{S_i}$ denotes $\overline{Q(S_i)} = \overline{Q(F_{1,i}, F_{2,i}, F_{3,i}, F_{4,i})}$.

“-1” represents condition during baseline period; “1” represents condition during altered period.

The proposed rationale of attribution analysis can be extended to n -factor situation. In the n -factor situation, contribution of the j^{th} factor can be calculated as follows:

$$\Delta Q^j = \frac{1}{2^{n-1}} \sum_{i=1}^{2^n} \alpha_{j,i} \cdot \overline{S_i} \quad (26)$$

Table 1. A four-factor example for common rationale of attribution analysis

Factor	Scenario															
	S_1	S_2	S_3	S_4	S_5	S_6	S_7	S_8	S_9	S_{10}	S_{11}	S_{12}	S_{13}	S_{14}	S_{15}	S_{16}
F_1	-1	1	-1	1	-1	1	-1	1	-1	1	-1	1	-1	1	-1	1
F_2	-1	-1	1	1	-1	-1	1	1	-1	-1	1	1	-1	-1	1	1
F_3	-1	-1	-1	-1	1	1	1	1	-1	-1	-1	-1	1	1	1	1
F_4	-1	-1	-1	-1	-1	-1	-1	-1	1	1	1	1	1	1	1	1

where $\alpha_{j,i}$ is a weight coefficient, representing the condition of the j^{th} factor in the i^{th} scenario. When the condition of F_j is during the altered period, $\alpha_{j,i} = 1$. When the condition of F_j is during the altered period, $\alpha_{j,i} = -1$. The value of $\alpha_{j,i}$ can be checked in the scenario table of a specific study case. This formula considers the interactions between factors, the influence of one driving factor is calculated on average levels of other factors, which can also level off the inconsistency in contributions calculated in different routes.

3 Case Study

3.1 Study Area

The Yangtze River is the largest river in China, with a total length of 6380 km. As shown in Fig. 3, the UYZR is located in the region between 97.37°E - 110.18°E and 21.13°N - 34.33°N, with a total area of 1 million km² covering nine provinces. Terrain of the UYZR is complex, high in west and low in east. The west belongs to Qinghai-Tibet Plateau and Hengduan Mountains with elevation higher than 3000 m, while the southeast belongs to valley and basin with elevation under 500 m. The special topography and landform gave birth to many rivers. The Tongtian River is the source river of the Yangtze River, from eastern foot of Geladaindong Peak to Zhimenda (station), with a total length of 1292 km. The Jinsha River is between Zhimenda (station) to Pingshan (station), with a total length of 6464 km and a total drop of 5100 m. Steep gradients cause high flow velocity and river bed. The Yalong River is the largest tributary of the Jinsha River. The river from Pingshan (station) to Yichang (station) is the mainstream of UYZR with a length of 1040 km. In the north, the Minjiang River, the Tuojiang River, the Jialing River flow into the mainstream, while the Wujiang River flows into the mainstream in the south. Based on the watershed and the tributaries, the UYZR is generally divided into the Jinsha River basin (JSR), the Mintuo River basin (MTR), the Jialing River basin (JLR), the Wujiang River basin (WJR) and the mainstream basin (MS). The JSR includes the Yanglong River basin (YLR) and the source area basin (SA). The MTR includes the Minjiang River basin (MJR) and the Tuojiang River basin (TJR).




Fig. 4. Map of the UYZR

3.2 Data

3.2.1 Hydrological Data

To identify the characteristics and spatial composition of streamflow change, monthly streamflow series observed in hydrological stations located at the outlets are selected for the mainstream and important tributaries. The locations are shown in Fig. 4. The streamflow series is observed from 1957 to 2010 in Zhimenda station, from 1958 to 2010 in Xiaodeshi station, and from 1951 to 2013 in other stations. Detail information on the hydrological stations is listed in Table 2. The Zhimenda station is selected to describe streamflow change in the source area of the Yangtze River. The Jinsha River connects with the source area directly and therefore the Zhimenda station and Pingshan station are selected for conjoint analysis of streamflow change in the Jinsha River. The Xiaodeshi station, the Zhimenda station and Pingshan station are selected to describe streamflow change in both mainstream and tributary of the Jinsha River. The other stations are the control station of every important tributary. All streamflow series are provided by the Bureau of Hydrology, Changjiang Water Resources Commission.

3.2.2 Meteorological Data

Meteorological data from National Meteorological Observatory (NMO) stations within the UYZR are collected from the National Meteorological Information Centre of China (NMIC) of the China Meteorological Administration (CMA), including daily observations of precipitation, air temperatures, relative humidity, wind speed, and sunshine

Table 2. Information on the hydrological stations investigated in this study

Station	River	Latitude (°N)	Longitude (°E)	Control basin	Control area (km ²)
Zhimenda	Tongtian	33.03	97.25	TTR	137704
Pingshan	Jinsha	28.63	104.17	JSR	485099
Xiaodeshi	Yalong	26.78	101.83	YLR	117000
Gaochang	Minjiang	28.80	104.41	MJR	135378
Fushun	Tuojiang	29.13	104.97	TJR	19613
Beibei	Jialing	29.85	106.42	JLR	156142
Wulong	Wujiang	29.32	107.75	WJR	83035
Yichang	Mainstream	30.70	111.28	MS	1005501

duration for the period of 1951 to 2013. The locations are shown in Fig. 4. Among these stations, ten stations have well-recorded radiation observations and are used to calibrate the Angstrom coefficients for estimating the solar radiation in the FAO Penman-Monteith method.

3.2.3 Spatial Data

The topography is represented using the digital elevation model (DEM) with a spatial resolution of 90 m, which is obtained from the Consultative Group on International Agricultural Research (CGIAR) Consortium for Spatial Information (CGIAR-CSI) (<http://srtm.csi.cgiar.org>). DEM map for the UYZR is extracted as shown in Fig. 4. DEM map is the basis of the SWAT model for sub-basin division, river system generation and hydrological process simulation.

3.2.4 Geological Characteristics Data

Geological characteristics data includes land use/cover data and soil type data. Land use/cover maps with a scale of 1: 100000 for late 1980s (1990), 1995, 2000, 2005, 2010, are collected from the Data Center for Resources and Environmental Sciences, Chinese Academy of Sciences (RESDC) (<http://www.resdc.cn>). Land use/cover maps for the UYZR is extracted, including 6 types of the first classification (i.e., crop land, forest land, grass land, water, developed land, and barren land). In the UYZR, the most major land use/cover types are grass land, forest land, and crop land, accounting for more than 90% of the total area. Detailed description of land use/cover types can be found in the reference (Y Zhang et al. 2017). Soil type map with a scale of 1: 1000000 is also collected from the RESDC. Soil type map for the UYZR is extracted, including 205 types of soil. In the practical application of the SWAT model, the classification of soil should not be too detailed and therefore the 205 types are reclassified into 18 types.

4 Results and Discussion

4.1 Streamflow Change

Historical annual streamflow series of the selected hydrological stations are drawn in Fig. 5. Yichang station is the control station for the whole UYZR. Streamflow series observed in the Yichang station reflects overall characteristics of streamflow change in the UYZR. Results of the During the observation period, streamflow in the UYZR decreased by a rate of $8.9 \text{ km}^3/10\text{a}$. Streamflow change observed in the Yichang station comes from the mainstream basin and other tributaries. The Tongtian River, the source river of the Yangtze River, is mainly supplied by ice and snow melt water, followed by precipitation and groundwater recharge. Under changing environment, its streamflow increased by a rate of $0.5 \text{ km}^3/10\text{a}$ during the observation period. Streamflow in the Yalong River, Jinsha River, Minjiang River, Tuojiang River, Jialing River, Wujiang River all decreased, with rates of $-0.1 \text{ km}^3/10\text{a}$, $-0.8 \text{ km}^3/10\text{a}$, $-2.2 \text{ km}^3/10\text{a}$, $-0.6 \text{ km}^3/10\text{a}$, $-2.1 \text{ km}^3/10\text{a}$ and $-1.1 \text{ km}^3/10\text{a}$ respectively. Mann-Kendall test and Spearman's Rho test are also showed and compared in Fig. 5. Results obtained from two methods are consistent in the hydrological stations except that the confidence level is slightly inconsistent in the Beibei Station. Streamflow observed in the Yichang Station, Gaochang station, Fushun station, Beibei station decreased significantly, which also have higher decline rates in tendency.

4.2 Change Point Detection and Sub-Period Determination

Both the non-parametric Pettitt's test and the sequential clustering method are used to detect the occurrence of the change point in streamflow series. As shown in Fig. 6(a), value of the test statistic for the Pettitt's test is the highest in the year 1993, which means the year 1993 is the abrupt change point. According to the significance level test, this change point is significant at a confidence level of 90% (black dotted line in Fig. 6(a)). The same result is obtained in the sequential clustering method. As shown in Fig. 6(b), when the whole study period is divided by the year 1993, value of the sum of squared deviation in subperiods are the lowest, which indicates the year 1993 is the change point. Therefore, the year 1993 is identified as the change point in the streamflow series of the UYZR.

According to the change point in streamflow series, the study period can be divided into two sub-periods (i.e., 1951–1993 and 1994–2013). For baseline period determination, streamflow, precipitation and reference evapotranspiration series during the sub-period prior to the change point in the UYZR are detected via Mann-Kendall test. Results are shown in Table 3. During the first sub-period, there is no obvious changes in streamflow, precipitation or reference evapotranspiration time series. Therefore, the sub-period from 1951 to 1993 can be confirmed as the baseline period and the sub-period from 1994 to 2013 can be determined as the altered period.

ET_0 represents reference evapotranspiration; $-$ represents a confidence level lower than 80%; SD represents standard deviation; CV represents coefficient of variation.

Meanwhile, the mean value, standard deviation and coefficient of variation of the time series in these two periods are separately calculated and listed in Table 3. The average




Fig. 5. Historical annual streamflow series observed in the selected hydrological stations: (a) Yichang; (b) Zhimenda; (c) Xiaodeshi; (d) Pingshan; (e) Gaochang; (f) Fushun; (g) Beibei; (h) Wulong. ↑ and ↓ represent increasing and decreasing trend; 99%, 95%, 90%, 80% and – represents a confidence level at 99%, 95%, 90%, 80% and lower than 80%.

annual streamflow in the baseline period relative to that in the altered period decreases 8.4%. Statistically significant difference between the mean of annual streamflow in two periods can be found with a confidence level of 95% using the *t*-test, whereas using the *F*-test, differences between the standard deviations are not statistically significant. Coefficient of variation value of streamflow series in the baseline period is close to what in the change period. Differences at 95% confidence level are also detected between




Fig. 6. Change point detected in streamflow series of the UYZR: (a) the Pettitt's test; (b) the sequential clustering method

Table 3. Characteristics of the streamflow, precipitation and reference evapotranspiration series in the UYZR before and after change point

Time series	Sub-period 1951–1993				Sub-period 1994–2013			Change
	Trend	Mean	SD	CV	Mean	SD	CV	
Streamflow (km ³)	–	438.2	42.7	0.10	401.2	44.7	0.11	–37.0
Precipitation (mm)	–	999.9	72.1	0.07	954.8	63.1	0.07	–45.1
ET ₀ (mm)	–	1436.9	41.5	0.03	1479.0	50.8	0.03	42.1

the mean values of precipitation and reference evapotranspiration series in the two periods. There is no statistically significant difference in standard deviation or coefficient of variation between baseline period and altered period in precipitation or reference evapotranspiration series.

4.3 Large-Scale SWAT Model

In this study, ArcSWAT 2012 interface is employed to establish a large-scale SWAT model for the UYZR. Based on the DEM map, the whole study area can be divided into 99 sub-basins. The sub-basin division is consistent with the realities of important basins of the UYZR (i.e., the SA, YLR, JSR, MJR, TJR, JLR, WJR and MA). According to the realities of important basins, the SWAT model structure can be generalized as Fig. 7. The SA is selected to explain the model structure further. As shown in Fig. 7, the SA consists of sub-basins denoted from No.1 to No.15. The Zhimenda hydrological station is the control station of SA. Streamflow simulated at the outlet of sub-basin 15 corresponds to the streamflow observed in Zhimenda station. Similarly, these important basins consist of several sub-basins. Streamflow simulated at the outlet of sub-basin 90, 71, 65, 62, 56, 60 and 43 correspond to the Xiaodeshi, Pingshan, Gaochang, Fushun, Beibei, Wulong and Yichang hydrological station, respectively. Based on the slope, land use/cover type and soil type, the study area is divided into 702 HRUs.




Fig. 7. Generalized SWAT model structure of the UYZR

4.4 Parameter Calibration and Uncertainty Analysis

In this study, sensitivity analysis with LH-OAT is performed for 25 parameters who are most commonly selected for calibration (i.e. GW_DELAY.gw, ALPHA_BF.gw, GWQMN.gw, GW_REVP.gw, REVP.gw, RCHRG_DP.gw, BIOMIX.mgt, CN2.mgt, SOL_BD.sol, SOL_AWC.sol, SOL_K.sol, SOL_ALB.sol, CH_N2.rte, CH_K2.rte, SLSUBBSN.hru, OV_N.hru, CANMX.hru, ESCO.hru, EPCO.hru, HRU_SLP.hru, SFTMP.bsn, SMTMP.bsn, SMFMX.bsn, SMFMN.bsn, SURLAG.bsn) in SA, YLR, JSR (exc., SA, YLR), MJR, TJR, JLR, WJR and MA, respectively. The top 10 sensitive parameters are screened out for calibration and uncertainty analysis (see Fig. 8). Hydrological simulation with SWAT is performed with a calibration period from 1960 to 1980 and a validation period from 1981 to 1993. The simulation before the year 1960 is implemented as a warm-up for the established SWAT model. For the DREAM algorithm parameterization in every basin, 8 Markov chains with 10000 iterations for each one of the 10 most sensitive parameters are examined, leading to totally 80000 runs. For such a complex and large-scale hydrological modeling, there is little credible priori knowledge about the location of the high probability density region within the parameter space. Therefore, in this study, we assume the prior distributions of calibrated parameters follow uniform distribution with their own initial range. The convergence criteria of $\hat{R} = 1.2$ is usually satisfied within 20000 generations. The first 50% samples are ruled out as a burn-in period. The posterior distributions of parameters for every basin are illustrated in Fig. 8. The majority of parameters' ranges appear in relatively small intervals. The posterior PDFs of some parameters present approximately normal distribution characteristics (e.g., CH_N2.rte in JSR and MS). Some parameters are approximately uniform distributed (e.g., REVP.gw, SMFMN.bsn, SMFMX.bsn), and some are skewed distributed (e.g., CH_K2.rte, ALPHA_BF.gw). Similar results of skewed distributions are also reported in relative studies (Leta et al. 2015; Y R Liu et al. 2017), which indicate that these parameters should be re-evaluated. The extension of the initial ranges of parameters may result in better simulation performance. However, the ranges for these parameters cannot be further relaxed without resulting in physically unrealistic behavior of the model (Vrugt et al. 2008).




Fig. 8. Posterior distributions of parameters in basins of the UYZR. The top 10 sensitive parameters in 8 basins are shown in each row, whose sensitivity decreases from left to right.

To understand how the uncertainty in the model parameters translated into SWAT model simulation uncertainty and the performance of model simulation, the 95% simulation uncertainty ranges defined as above, the best simulated streamflow and the observed streamflow at the outlets of basins of the UYZR are illustrated in Fig. 9. Here, the best simulated streamflow is defined as the model simulation which has the smallest value of E_{NS} among all the simulations. The performance of the model simulation is evaluated using the R^2 and E_{NS} . Meanwhile, p-factor and r-factor are calculated to evaluate the model simulation uncertainty. The results are listed in Table 4.

For the simulated streamflow at the outlets of the basins (i.e. hydrological stations with observed streamflow), the R^2 values range from 0.66 to 0.95 and the E_{NS} values range from 0.51 to 0.94 in calibration period, the R^2 values range from 0.66 to 0.94 and the E_{NS} values range from 0.58 to 0.94 in validation period. It is suggested that E_{NS} value being greater than 0.75 can be considered excellent, value being greater than 0.65 can be considered good, and value being greater than 0.5 can be considered satisfactory for hydrological modeling evaluation. It is further concluded that R^2 value greater than 0.5 can be regarded as acceptable for hydrological modeling (Moriassi et al. 2007). Therefore, performance of the SWAT model established for the UYZR is considered good.

For the simulated streamflow at the outlets of the basins, the values of p-factor range from 0.49 to 0.83 and from 0.47 to 0.83 in calibration period and validation period, respectively. On average, 66% and 65% of the monthly observed streamflow fall within the 95% simulation uncertainty ranges. The results indicate that the simulation uncertainty coming from parameter uncertainty cannot account for all the uncertainties in hydrological modeling. In fact, the uncertainties in hydrological modeling can originate from (1) parameter, (2) input data (also called forcing or boundary conditions), (3), initial state, (4) model structural, (5) output, (6) calibration data uncertainty and so on. The values of r-factor range from 0.20 to 0.89 and from 0.20 to 0.88 in calibration period and validation period, respectively. All the values of r-factor are less than 1, the simulation can be considered satisfactory (X J Zhang et al. 2014).




Fig. 9. The observed streamflow (red dot), best simulated streamflow (green line) and 95% simulation uncertainty range of monthly streamflow (1960.1–1993.12) due to parameter uncertainties (gray bands).




Fig. 9. (continued)




Fig. 9. (continued)

It can be seen that, performance of simulation at No.15 outlet (i.e., Zhimenda Hydrological station) is generally worse than others at the selected indexes (i.e., R^2 , E_{NS} , p-factor and r-factor). As mentioned above, SA is a snowmelt-rainfall-driven basin. The power of SWAT model to simulate the hydrological processes for SA depends on how well the SWAT model simulates the snowmelt streamflow. The SWAT model assumes that temperature is the major driving force in snowmelt and simulates snowmelt processes with a simple temperature index approach. And the SWAT model also assumes that snowmelt depth is dominated by elevation. However, other topography, geomorphology factors can also influence the processes (LaMalfa and Ryle 2008). The results show that only temperature cannot estimate the snowmelt-rainfall-driven streamflow precisely.

Table 4. Results of evaluating model simulation performance and simulation uncertainty

Outlet No.	R^2		E_{NS}		p-factor		r-factor	
	Calibration	Validation	Calibration	Validation	Calibration	Validation	Calibration	Validation
15	0.66	0.66	0.51	0.58	0.49	0.54	0.82	0.82
90	0.90	0.85	0.89	0.77	0.64	0.47	0.47	0.45
71	0.93	0.87	0.89	0.82	0.76	0.66	0.46	0.47
65	0.93	0.91	0.93	0.90	0.73	0.72	0.26	0.25
62	0.90	0.79	0.85	0.69	0.83	0.74	0.54	0.56
56	0.90	0.88	0.90	0.87	0.59	0.60	0.27	0.24
60	0.82	0.86	0.79	0.84	0.67	0.83	0.89	0.88
43	0.95	0.94	0.94	0.94	0.63	0.58	0.20	0.20

4.5 Impacts of Driving Factors on Streamflow Change

4.5.1 Selection of Driving Factors

Attributing streamflow change to only two factors (i.e., climate change and human activities) is oversimplified, which lacks consideration of physical causes and connection between driving factors and has little guidance in future adaption. In this study, driving factors of streamflow change are selected from the inputs of SWAT model. We do similar work for other five meteorological inputs (i.e., maximum temperature, minimum temperature, wind speed, relative humidity, solar radiation) like Table 3, where statistically significant difference between the precipitation in baseline period and altered period can be found with a confidence level of 95% using the *t*-test. We also use the *t*-test to detect differences of other five meteorological inputs. Differences at 99% confidence level are found between the mean values of maximum temperature, minimum temperature, wind speed, relative humidity in the two periods. Difference is not obvious in solar radiation. Therefore, precipitation, maximum temperature, minimum temperature, wind speed and relative humidity are selected as the meteorological driving factors, denoting as P, Tmax, Tmin, WS and RH, respectively. During the study period, land use/cover in the UYZR presents obvious changes. As a human activity input of the SWAT model, LUCC is also selected as a driving factor. Detailed description of LUCC can be found in the reference (Y Zhang et al. 2017).

To illustrate the changing properties of driving factors, the trends of annual precipitation, maximum temperature, minimum temperature, wind speed and relative humidity during 1960–2013 are drawn in Fig. 10. The Mann-Kendall statistic is used to evaluate whether the trend is significant, whose value of greater (smaller) than 1.96 (−1.96) shows significant increasing (decreasing) trend at 95% confidence level. Trends of annual precipitation are subject to different patterns in the east and west of UYZR. Decreasing annual precipitation can be identified in the east (i.e., MTR, JLR, WJR and MS). The decreasing trends of annual precipitation are especially significant in the MTR and WJR. The west of UYZR is dominated by increasing annual precipitation, particularly in the JSR. Most increasing annual precipitation are not significant (Fig. 10a). Maximum temperature and minimum temperature are generally increasing. Changes in maximum

temperature and minimum temperature are subject to a similar spatial distribution pattern. Significant increasing trends can be observed in the whole UYZR (Fig. 10b and c). Significant decreasing trends of wind speed concentrate in the center of UYZR. Both increasing trends and decreasing trends can be observed in other regions, but they are not significant (Fig. 10d). The relative humidity (Fig. 10e) is generally decreasing, particularly in central and southern regions.




Fig. 10. Spatial distribution of trends in (a) annual precipitation amount, (b) maximum temperature, (c) minimum temperature, (d) wind speed, and (e) relative humidity during 1960–2013. Blue downward and red upward triangles indicate increasing and decreasing tendencies, respectively. The triangle size represents the magnitude of these positive and negative trends. Solid triangles represent significant trends at the 95% confidence level.

4.5.2 Spatial Streamflow Change and Contributions of Driving Factors

After calibration of the SWAT model, streamflow can be simulated at every outlet of divided sub-basins, which reflects the streamflow coming from sub-basins up this outlet. In such large-scale hydrological modeling case, there are huge differences in magnitudes of streamflow simulated at the outlets. For convenience of comparing the contributions of driving factors in different sub-basins, streamflow amount is converted into streamflow depth (mm). Figure 11a demonstrates streamflow change depth during the altered period relative to the baseline period at every outlet. Decreasing changes in annual streamflow can be found mainly in the YLR, MJR, TJR, JLR, WJR and MS, and larger decreasing magnitude is detected in the MJR, TJR and JLR. Among the total 99 outlets, positive streamflow change is detected in only 14 outlets. And the increasing streamflow change are detected mainly in the SA. In general, negative streamflow change is observed in the UYZR. Contributions of the 6 driving factors are calculated for every outlet. And Fig. 11b–g show different impacts of various driving factors on streamflow change in space. It can be seen that the contribution of precipitation has similar spatial distribution and magnitude with the streamflow change (Fig. 11a, b), which clearly indicates that precipitation change occupies the main position for streamflow change. The river basins with a decrease in annual precipitation (Fig. 12a) are mostly characterized by decreased streamflow, such as east parts in the MJR and sub-basins in the TJR, WJR. The precipitation generally increases the streamflow in the SA. Influences of temperature change on streamflow are relatively spatially complicated. The maximum temperature decreases the streamflow depth at the most among outlets in the UYZR (Fig. 11c). However, the contribution of the minimum temperature is subject to a opposite pattern (Fig. 11d). Generally, the wind speed and LUCC decrease streamflow in the whole UYZR (Fig. 11e, f). Impact of LUCC on streamflow is especially obvious at outlets in the JLR. Spatial patterns of impacts of relative humidity on streamflow were relatively complex (Fig. 11g). Except the SA, positive contribution of relative humidity on streamflow is detected at around half outlets in the UYZR, while negative contribution is found at other half outlets.

We also draw the boxplot as shown in Fig. 12, which shows impacts of various driving factors on streamflow change during the altered period relative to the baseline period for each river basin and the whole UYZR. For the 8 river basins and the whole UYZR, precipitation has the most dominant influence on streamflow change. Precipitation change tends to decrease streamflow in the river basins. Especially in the TJR, JLR, WJR and MS, precipitation change decreases streamflow at all outlets except some outliers. Precipitation change has the most obvious influence in the JLR and TJR, causing -79.1 mm and -62.4 mm of average streamflow depth in these two river basins. As for other five driving factors, the amount of their influence on streamflow are close. Generally, maximum temperature contributes to the decrease of streamflow amount and minimum temperature tends to increase streamflow of the river basins in the UYZR. Impacts of maximum temperature and minimum temperature on streamflow in the eastern UYZR are more evident in the western UYZR. Wind speed has more changeable and complex influence in river basins, especially in the MJR. Wind speed contributes to streamflow change more in the central UYZR than in other parts. The contribution of relative humidity to increase streamflow is obvious in the eastern UYZR while has no clear properties in the west. LUCC tends to decrease streamflow depth in the eastern




Fig. 11. Spatial distribution of (a) streamflow change depth and impacts of (b) precipitation amount, (c) maximum temperature, (d) minimum temperature, (e) wind speed, and (f) relative humidity on streamflow during the altered period relative to the baseline period. Blue downward and red upward triangles indicate negative and positive change/contribution. The triangle size represents the magnitude of the change/contribution.

UYZR, particularly significant in the JLR, while has relatively small effect in the western UYZR. It is worth noting that impact of precipitation on streamflow is much smaller in the SA, and it is very close to the impacts of maximum temperature and minimum temperature. This is consistent with the fact that the SA is a snowmelt-rainfall-driven basin, though the SWAT model has disadvantages in modeling snowmelt processes as mentioned above.




Fig. 12. Contribution of (a) precipitation, (b) maximum temperature, (c) minimum temperature, (d) wind speed, (e) relative humidity and (f) LUCC to streamflow change in 8 river basins across the UYZR and the UTZR

4.5.3 Uncertainty in Attribution Analysis

To understand how the uncertainty in the hydrological modeling translates into uncertainty in attribution analysis, we calculate the impacts of driving factors not only at the best simulation but also at upper boundary and lower boundary of simulation uncertainty range in Sect. 4.4. Figure 13 demonstrates the average contributions of the 6 driving factors in the 8 river basins and the whole UYZR at best simulation, upper boundary and lower boundary, respectively. As for the absolute value of attribution uncertainty, the absolute uncertainty value in impact of precipitation is the largest in the 8 river basin and the whole UYZR, which is because the absolute value of contribution of precipitation is the largest among all driving factors, with great contribution comes great uncertainty. As for the relative value of attribution uncertainty, in the whole UYZR, the attribution uncertainty is most evident in the precipitation and LUCC. In different river basins, the relative attribution uncertainties of driving factors are various and subject to some spatial




Fig. 13. Average contribution of (a) precipitation, (b) maximum temperature, (c) minimum temperature, (d) wind speed, (e) relative humidity and (f) LUCC in the 8 river basins and the UYZR at best, upper boundary and lower boundary simulation

characteristics. Attribution uncertainty of maximum temperature and minimum temperature are particularly obvious in the SA. In the YLR and JSR, attribution uncertainties of all driving factors are similar. In the MJR, attribution uncertainty of precipitation and wind speed are obviously greater than others. In TJR, the attribution uncertainty of LUCC is obviously smaller than others, which can be attributed area of the TJR is much smaller. In the JLR, WJR and MS, the attribution uncertainty of LUCC is the most evident followed by the precipitation, which is consistent with the land use policy of China in this region. It is worth noting that, among all river basins, attribution uncertainty of all driving factors are obviously greater in the TJR.

5 Conclusions

In this study, an attribution analysis method based on large-scale hydrological modeling is developed through incorporating time series analysis methods, Soil and Water Assessment Tool (SWAT), and Differential Evolution Adaptive Metropolis (DREAM) algorithm within a general framework. The proposed method is capable of assessing the impacts of climatic factors and human influence factors on streamflow for a large-scale study area. Advantages of this attribution analysis method can be concluded as follows: (1) DREAM algorithm is employed to approximate the posterior distributions of model parameters with Bayesian inference. Parameter uncertainty can be assessed with considering the prior information, observation and physically reasonable ranges of parameter values (reflecting watershed characteristics). Then uncertainties in hydrological modeling and attribution analysis can be evaluated further. (2) We define a combination of driving factors during different periods as a scenario and further define scenarios arranged in specific order as a route. Average value of influences calculated via different routes are calculated as the contribution of the driving factor, which reflects one factor's influence on average levels of other factors. This method can consider interactions between factors and level off the inconsistency in contributions calculated in different routes. (3) The calibrated SWAT model can provide detailed, high resolution descriptions of small scale processes that are numerically integrated to larger scales. Based on the distributed simulation under different scenarios, attribution analysis can be conducted at scales as small as the sub-basins can be divided. Observation in this method needs to match the requirement of model calibration.

The proposed method is applied to a real case for assessing the impacts of climate change and human activities on streamflow in the UYZR, which has an irreplaceable position and inestimable value in China's strategic reserve of resources. Several findings can be revealed as follows: (1) During the study period, streamflow decreases significantly by $-8.9 \text{ km}^3/10\text{a}$ in the UYZR. The year 1993 can be determined as the change point in the UYZR, after which significantly changes happen in the streamflow. Spatially, streamflow increases in the SA, decreases in other tributaries. The decrease is particularly significant in the MJR, TJR and JLR. (2) Generally, the precipitation, maximum temperature, windspeed and LUCC tend to decrease streamflow in the UYZR, while the minimum temperature and relative humidity tend to increase streamflow. Among the driving factors, the precipitation has the most dominant influence on streamflow change. Contributions of the driving factors behave differently at small scales, which is meaningful to practical adaptations. (3) Precipitation has the largest absolute value of attribution uncertainty in the UYZR. Relative attribution uncertainty of precipitation and LUCC are the most evident in the UYZR. Distinct differences can be found in the relative attribution uncertainties of driving factors in various river basins, which can provide bases for evaluating the risks in future adaptations.

There are also some potential extensions in the proposed method as follows: (1) This study is the first attempt for assessing impacts of climate change and human activities with consideration of uncertainties. Uncertainties in attribution analysis can come from many sources, such as hydrological modeling and contribution calculating. Parameter uncertainty is a very important source of modeling uncertainties. However, uncertainties

in attribution analysis can hardly be reflected by merely considering parameter uncertainty. Additional evaluation of uncertainties coming from other important sources (e.g., input data, model structural) should be developed in this method framework. (2) When conducting Bayesian inference, the prior distribution of the parameters is assumed uniform distribution within initial ranges. More appropriate prior can be selected in future study. Meanwhile, the likelihood function is assumed to be independent and normally distributed. However, this assumption is usually not satisfied and residual errors of hydrological models are often both heteroscedastic and autocorrelated. Methods for removing errors autocorrelation and heteroscedasticity can be applied in this method framework to improve the evaluation of uncertainties. (3) The SWAT model cannot simulate the snowmelt-rainfall-driven streamflow precisely, because the model assumes temperature is the major driving force in snowmelt and simulates snowmelt processes with a simple temperature index approach. In future study, appropriate hydrological model can be selected to replace the SWAT model in the proposed method framework for specific study case. Then the proposed method has strong potential to improve our understanding of how climate change and human activities influence the streamflow and provides us the bases for future adaptive measures.

Acknowledgments. This research was funded by National Key Research and Development Program of China (Grant No. 2022YFC3002705) and National Natural Science Foundation of China (Grant No. 52209032).

References

- Barnett, T.P., Adam, J.C., Lettenmaier, D.P.: Potential impacts of a warming climate on water availability in snow-dominated regions. *Nature* **438**(7066), 303–309 (2005)
- Brath, A., Montanari, A., Moretti, G.: Assessing the effect on flood frequency of land use change via hydrological simulation (with uncertainty). *J. Hydrol.* **324**(1–4), 141–153 (2006)
- Dey, P., Mishra, A.: Separating the impacts of climate change and human activities on streamflow: a review of methodologies and critical assumptions. *J. Hydrol.* **548**, 278–290 (2017)
- Dooge, J.C.I., Bruen, M., Parmentier, B.: A simple model for estimating the sensitivity of runoff to long-term changes in precipitation without a change in vegetation. *Adv. Water Resour.* **23**(2), 153–163 (1999)
- Hall, J.W., Brown, S., Nicholls, R.J., Pidgeon, N.F., Watson, R.T.: COMMENTARY: proportionate adaptation. *Nat. Clim. Change* **2**(12), 833–834 (2012)
- Hall, J.W., et al.: Coping with the curse of freshwater variability. *Science* **346**(6208), 429–430 (2014)
- Hrachowitz, M., Clark, M.P.: HESS opinions: the complementary merits of competing modelling philosophies in hydrology. *Hydrol. Earth Syst. Sci.* **21**(8), 3953–3973 (2017)
- Hutchins, M.G., et al.: Combined impacts of future land-use and climate stressors on water resources and quality in groundwater and surface waterbodies of the upper Thames river basin, UK. *Sci. Total Environ.* **631–632**, 962–986 (2018)
- Jiang, C., Xiong, L.H., Wang, D.B., Liu, P., Guo, S.L., Xu, C.Y.: Separating the impacts of climate change and human activities on runoff using the Budyko-type equations with time-varying parameters. *J. Hydrol.* **522**, 326–338 (2015)
- LaMalfa, E.M., Ryle, R.: Differential snowpack accumulation and water dynamics in aspen and conifer communities: implications for water yield and ecosystem function. *Ecosystems* **11**(4), 569–581 (2008)

- Leta, O.T., Nossent, J., Velez, C., Shrestha, N.K., van Griensven, A., Bauwens, W.: Assessment of the different sources of uncertainty in a SWAT model of the River Senne (Belgium). *Environ. Model. Softw.* **68**, 129–146 (2015)
- Li, Z.L., Xu, Z.X., Li, J.Y., Li, Z.J.: Shift trend and step changes for runoff time series in the Shiyang River basin, northwest China. *Hydrol. Process.* **22**(23), 4639–4646 (2008)
- Liu, J.Y., Zhang, Q., Singh, V.P., Shi, P.J.: Contribution of multiple climatic variables and human activities to streamflow changes across China. *J. Hydrol.* **545**, 145–162 (2017)
- Liu, Y.R., Li, Y.P., Huang, G.H., Zhang, J.L., Fan, Y.R.: A Bayesian-based multilevel factorial analysis method for analyzing parameter uncertainty of hydrological model. *J. Hydrol.* **553**, 750–762 (2017)
- Ma, Z.M., Kang, S.Z., Zhang, L., Tong, L., Su, X.L.: Analysis of impacts of climate variability and human activity on streamflow for a river basin in arid region of northwest China. *J. Hydrol.* **352**(3–4), 239–249 (2008)
- Montenegro, A.A.D., Souza, T.E.M.D., de Souza, E.R., Montenegro, S.M.G.L.: Temporal dynamics of soil moisture and rainfall erosivity in a tropical volcanic archipelago. *J. Hydrol.* **563**, 737–749 (2018)
- Moriasi, D.N., Arnold, J.G., Van Liew, M.W., Bingner, R.L., Harmel, R.D., Veith, T.L.: Model evaluation guidelines for systematic quantification of accuracy in watershed simulations. *Trans. ASABE* **50**(3), 885–900 (2007)
- Piao, S.L., et al.: The impacts of climate change on water resources and agriculture in China. *Nature* **467**(7311), 43–51 (2010)
- Prowse, T.D., et al.: Climate change, flow regulation and land-use effects on the hydrology of the Peace-Athabasca-Slave system; findings from the Northern Rivers Ecosystem Initiative. *Environ. Monit. Assess.* **113**(1–3), 167–197 (2006)
- Rose, S., Peters, N.E.: Effects of urbanization on streamflow in the Atlanta area (Georgia, USA): a comparative hydrological approach. *Hydrol. Process.* **15**(8), 1441–1457 (2001)
- Sankarasubramanian, A., Vogel, R.M., Limbrunner, J.F.: Climate elasticity of streamflow in the United States. *Water Resour. Res.* **37**(6), 1771–1781 (2001)
- Sharma, T.C.: Stochastic-models applied to evaluating hydrologic changes. *J. Hydrol.* **78**(1–2), 61–81 (1985)
- Tomer, M.D., Schilling, K.E.: A simple approach to distinguish land-use and climate-change effects on watershed hydrology. *J. Hydrol.* **376**(1–2), 24–33 (2009)
- Vrugt, J.A.: Markov chain Monte Carlo simulation using the DREAM software package: theory, concepts, and MATLAB implementation. *Environ. Model. Softw.* **75**, 273–316 (2016)
- Vrugt, J.A., ter Braak, C.J.F., Clark, M.P., Hyman, J.M., Robinson, B.A.: Treatment of input uncertainty in hydrologic modeling: doing hydrology backward with Markov chain Monte Carlo simulation. *Water Resour. Res.* **44** (2008)
- Vrugt, J.A., ter Braak, C.J.F., Diks, C.G.H., Robinson, B.A., Hyman, J.M., Higdon, D.: Accelerating Markov Chain Monte Carlo simulation by differential evolution with self-adaptive randomized subspace sampling. *Int. J. Nonlinear Sci. Numer.* **10**(3), 273–290 (2009)
- Wang, D.B., Hejazi, M.: Quantifying the relative contribution of the climate and direct human impacts on mean annual streamflow in the contiguous United States. *Water Resour. Res.* **47** (2011)
- Wang, G.S., Xia, J., Chen, J.: Quantification of effects of climate variations and human activities on runoff by a monthly water balance model: a case study of the Chaobai River basin in northern China. *Water Resour. Res.* **45** (2009)
- Wang, S.P., Zhang, Z.Q., McVicar, T.R., Guo, J.T., Tang, Y., Yao, A.K.: Isolating the impacts of climate change and land use change on decadal streamflow variation: assessing three complementary approaches. *J. Hydrol.* **507**, 63–74 (2013)

- Wang, W.G., et al.: Reference evapotranspiration change and the causes across the Yellow River Basin during 1957–2008 and their spatial and seasonal differences. *Water Resour. Res.* **48** (2012)
- Wang, X.X.: Advances in separating effects of climate variability and human activity on stream discharge: an overview. *Adv. Water Resour.* **71**, 209–218 (2014)
- Zhang, J.L., Li, Y.P., Huang, G.H., Chen, X., Bao, A.M.: Assessment of parameter uncertainty in hydrological model using a Markov-Chain-Monte-Carlo-based multilevel-factorial-analysis method. *J. Hydrol.* **538**, 471–486 (2016)
- Zhang, L., Karthikeyan, R., Bai, Z.K., Srinivasan, R.: Analysis of streamflow responses to climate variability and land use change in the Loess Plateau region of China. *Catena* **154**, 1–11 (2017)
- Zhang, X.J., Xu, Y.P., Fu, G.T.: Uncertainties in SWAT extreme flow simulation under climate change. *J. Hydrol.* **515**, 205–222 (2014)
- Zhang, X.P., Zhang, L., Zhao, J., Rustomji, P., Hairsine, P.: Responses of streamflow to changes in climate and land use/cover in the Loess Plateau, China. *Water Resour. Res.* **44** (2008)
- Zhang, Y., Zhong, P.A., Wang, M.L., Xu, B., Chen, J.: Changes identification of the Three Gorges reservoir inflow and the driving factors quantification. *Quatern. Int.* **475**, 28–41 (2018)
- Zhang, Y., Zhong, P.A., Chen, J., Bing, J.P., Xu, D.H., Wang, M.L.: Impacts of climate change and human activities on the Three Gorges reservoir inflow. *Water-Sui* **9**(12) (2017)
- Zheng, H.X., Zhang, L., Zhu, R.R., Liu, C.M., Sato, Y., Fukushima, Y.: Responses of streamflow to climate and land surface change in the headwaters of the Yellow River Basin. *Water Resour. Res.* **45** (2009)
- Zuo, D.P., Xu, Z.X., Wu, W., Zhao, J., Zhao, F.F.: Identification of streamflow response to climate change and human activities in the Wei River Basin, China. *Water Resour. Manag.* **28**(3), 833–851 (2014)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Regularization of Flows in SHPPs as a Strategy for Adapting to Climate Change: The Case of SHPP Americana

Beatriz Sepulveda Pires¹(✉), Xinjian Chen², and Huiyi Zhang²

¹ Rodovia Engenheiro Miguel Noel Nascentes Burnier, Km 2,5 - Parque São Quirino, Campinas, Brazil

beatriz.pires@cpfl.com.br

² CPFL Energia, Campinas, Brazil

Abstract. The adaptive operation of hydropower plants has become essential in response to the increasing frequency of extreme climate events. This study evaluated the performance of the Americana Small Hydropower Plant (SHPP), located in the Piracicaba, Capivari, and Jundiá (PCJ) river basin, under two operational strategies: the current rule and a new one allowing reservoir drawdown of up to 1.5 m. The results showed significant gains, a 29% increase in average annual generation, an increase in generation days from 45% to 79%, and a reduction in spill days from 56% to 21%. Additionally, the new operational rule maintained minimum outflows above 15 m³/s for 79% of the time, promoting greater downstream hydrological stability and mitigating environmental impacts such as water quality degradation. The frequency of flows equal to or greater than 15 m³/s also increased by 34%, contributing to higher downstream flows during dry periods. During heavy rainfall events, the strategy enabled the attenuation of peak flows, helping to reduce urban flooding risks. These findings demonstrate that operational flexibility enhances the plant's ability to adapt to extreme climate conditions and optimizes hydropower scheduling and adaptation strategies in the context of climate change.

Keywords: Adaptive reservoir operation · Hydropower scheduling optimization · Climate change adaptation

1 Introduction

The Americana Small Hydroelectric Power Plant (SHPP) is located in the Piracicaba, Capivari and Jundiá (PCJ) river basin, one of the main basins in the state of São Paulo in terms of water demand and anthropogenic pressures. The plant is located on the Atibaia River, which, just downstream of the powerhouse, flows into the Jaguari River, forming the Piracicaba River.

Critical drought events in the basin have led to periods of significantly reduced outflow, compromising water quality, particularly in urban stretches of the Piracicaba River. These conditions can negatively affect aquatic life, leading to habitat degradation and

reduced dissolved oxygen levels. Furthermore, low flows may impair the dilution of effluents and exacerbate eutrophication processes. In such situations, the possibility of utilizing the volume stored in the SHPP reservoir to increment downstream flow represents an important strategy that can help reduce these adverse environmental impacts and support the maintenance of ecological functions.

In the wet season, on the other hand, high water levels contribute to flooding in urban areas, especially Rua do Porto, located in the city of Piracicaba. This area, which has significant historical, cultural, and tourist value, frequently experiences flooding and, in some cases, reaches a state of emergency due to the rapid rise in the river level.

In this context, the proposal to regularize the Americana SHPP reservoir aims to optimize the plant's operation in order to adapt to extreme weather conditions. During the rainy season, the aim is to attenuate peak flows, reducing the spread of floods downstream. In the dry season, the strategy of controlled depletion of the reservoir seeks to maintain outflows above critical thresholds, contributing to the improvement of water quality and the preservation of aquatic ecosystems by ensuring more stable environmental conditions.

This study used flow data from 2019 to 2023 and evaluated two operating scenarios: the first with the current rule, which does not allow significant depletion of the reservoir; and the second with the application of a new operating rule that considers lowering the water level by up to 1.5 m. The results show that, with the new strategy, the plant operates generating energy for a greater number of days, substantially reduces the volume spilled, and shows a 31% increase in average annual generation. In addition, there is a longer period in which the flow downstream of the plant remains above the inflow, increasing the plant's capacity to contribute with pulses of flow during critical periods.

2 Impacts of Climate Change on Water Resources

The hydrological cycle has undergone changes due to climate change, directly impacting the availability and distribution of water resources in river basins. According to Kundzewicz et al. (2008), the intensification of extreme events, such as droughts and floods, has already been observed in several regions of the world, requiring urgent adaptations in water management. In addition, the IPCC (2022) projects that rainfall variability will tend to increase, affecting aquifer recharge and river flow. It also addresses the increase in the Earth's average temperature, which has already risen by 1.1 °C and is at risk of exceeding 1.5 °C.

Paleohydrologic studies suggest that small changes in mean climate might produce large changes in extremes (Knox, 2000). Bates et al. (2008) state that climate change has the potential to modify precipitation patterns and intensify the occurrence of extreme hydrological events, which compromises the water security necessary for supply, agriculture and energy generation. Milly et al. (2008) also states that increases in temperatures influence evaporation and can change the rainfall regime, potentially increasing the risk of flooding in basins.

These impacts are also worrying in regions where water resources are already naturally limited. Changes in precipitation patterns reduce aquifer recharge and increase evapotranspiration, decreasing river flows. These water scarcity events compromise the

regularity of water resources, requiring adaptations in the management and sustainable use of water (ANA, 2022).

Horne et al. (2017) highlight that the construction and efficient operation of reservoirs, associated with adaptive management strategies, will be essential to increase the resilience of water systems in the face of new climate conditions. Thus, both structural measures, such as new reservoirs, and non-structural actions, such as hydrological forecasting and planning of reservoir operations to optimize flows, are considered essential to mitigate the effects of climate change on water resources.

3 Importance of Reservoirs in Mitigating Climate Change

Reservoirs play a fundamental role in mitigating the impacts of climate change, especially with regard to water resource management. With the increasing frequency and intensity of extreme weather events, such as severe droughts and heavy rainfall, reservoirs function as strategic instruments to guarantee water availability and water security. They allow water to be stored during periods of high rainfall, which can then be used in periods of low inflow, contributing to the resilience of hydrological systems in the face of changes in rainfall patterns (Kundzewicz et al., 2008; Horne et al., 2017).

One of the main benefits of reservoirs is the buffering of floods, significantly reducing peak flows that could cause flooding downstream. This mechanism is even more relevant in a context of climate change, where there is a tendency for extreme events to intensify.

Operational management of reservoirs, with strategies based on meteorological forecasts and hydrological models, can further optimize this buffer function. In addition, reservoirs can be used to support increased downstream flows during periods of drought, ensuring the continuity of multiple uses of water. The controlled release of stored volumes helps maintain river flow, preserving aquatic ecosystems and ensuring that human demands are met (Loucks & van Beek, 2017; Melo et al., 2021).

4 Methodology

The methodology applied in this work initially consists of acquiring hydrological data from the Agência Nacional de Águas (ANA) system to compose the series of inflows to the plant. The data were then consolidated and then, with the hydrological series inflowing the SHPP Americana, it was possible to carry out the regularization of the reservoir, prepared by means of scripts developed with the python programming language.

Items 1.4.1 and 1.4.2 present the description of the plant and basin in which the study was carried out and the methodology for collecting the data and applying the regularization of the reservoir.

4.1 Case Study

The Americana Small Hydroelectric Power Plant (SHPP) has an installed capacity of 30.00 MW and is located in the municipality of Americana, in the state of São Paulo. In operation since 1949, the plant uses the waters of the Atibaia River and is part of the

Piracicaba, Capivari and Jundiá river basin (PCJ basin), one of the most important in the state of São Paulo. The PCJ basin is strategic for the region's water supply and economic development, and part of its water is captured by the Cantareira System. The plant is located in the Rio Grande sub-basin (code 61), belonging to the large Paraná basin (code 6), and its geographical coordinates are 22°41'56.57" latitude and 47°17'02.03" longitude. The Fig. 1 shows the location map of SHPP Americana.




Fig. 1. Location map of SHPP Americana.

4.2 Hydrological and Flow Regulation Studies

To prepare the inflow series of the SHPP Americana, the UHE Americana Montante Paulínea station (62690500) available on the website of the National Water Agency and the Rio Atibaia Acima de Paulínea station (D4-120T/4D-009RT) available on the Basic Hydrological Network of the State of São Paulo provided by the São Paulo State Water Agency (SP Águas) were used. Daily data from the period from January 2019 to March 2025 were used. Both stations are located upstream of the reservoir in close locations, therefore, the UHE Americana Montante Paulínea station was used as the main station and the Rio Atibaia Acima de Paulínea station for backfilling when failures occurred.

To prepare the flow regulation, a script was developed using the Python programming language. The operation of the Americana SHPP reservoir was modeled based on specific operating assumptions, aiming to optimize the use of water resources for both power generation and downstream flow preservation. The main assumptions adopted were:

- Initial reservoir volume: 79.30 hm³.
- Maximum reservoir volume: 79.30 hm³, corresponding to the maximum elevation.

- Minimum reservoir volume: 65.93 hm³, associated with the 1.5 m drawdown elevation.
- Sanitary flow: 10 m³/s.
- Minimum turbine flow: 15 m³/s.
- Maximum turbine flow: 118 m³/s.

The operating strategy considered the conditions for the daily spill and turbine decision presented in Table 1.

Table 1. Adopted premises

Adopted premises	
Spilled Flow - Current Operating Rule	Spilled Flow - Proposal Operating Rule - 1,5 m
$Q_i < Q_{min \text{ turbine flow}}$	
If the reservoir is at the sill level, the affluent flow is spilled through the free sill spillway	(i) If the reservoir has available volume, the reservoir volume will be used to increase the affluent flow and manage to generate (ii) If the reservoir is depleted, the sanitary flow is maintained by the sanitary flow device and; If the affluent flow is less than the sanitary flow, the effluent flow is maintained equal to the inflow
$Q_{min \text{ turbine flow}} < Q_i < Q_{max \text{ turbine flow}}$	
Inflow is used for generation	Inflow is used for generation
$Q_{max \text{ turbine flow}} < Q_i$	
Affluent flow is used for Generation with maximum power and the excess is poured	Affluent flow is used for Generation and the excess is used to recover the reservoir or, if the reservoir is at the maximum level, the excess flow is spilled

Table 2. Results obtained in the analysis

Data analysis	Generating days	Pouring days	Average annual generation (MW)	Percentage gain in generation
Current Operating Rule	45%	56%	4,0	-
Proposed Operating Rule - 1.5 m	79%	21%	5,1	29%

5 Results

The comparative analysis between the current operating rule and the new proposal with 1.5 m de-pletion shows significant gains in generation days and an increase in average annual generation. With the adoption of the new rule, the percentage of generating days increased from 45% to 79%, directly reflected in a 29% increase in average annual generation, which went from 4.0 MW to 5.1 MW. This performance shows that making the reservoir's operating level more flexible has made it possible to make better use of the available water resource, increasing the plant's operating efficiency and the delivery of energy to the system. Table 2 shows the results obtained in the analysis.

Another important aspect was the significant reduction in water spillage. Under the current operating rule, 56% of days required spilling, while in the new configuration this percentage fell to 21%. This reduction is quite significant, since spillage represents a loss of energy potential. By reducing the volume spilled, the plant maximizes the use of the inflow to generate energy, increasing the use of natural resources and promoting greater operational sustainability. The Fig. 2 shows the spilled flow permanence curve.




Fig. 2. Spilled flow permanence curve

In addition to the energy gains and the reduction in spillage, the new rule also led to improvements in the outflow. Previously, maintaining the minimum flow of 15 m³/s was guaranteed only 45% of the time; with the new rule, this level was reached 79% of the time, promoting more stable and favorable conditions downstream of the plant. Important benefits were seen during rain events, when the reservoir acted as a buffer: in one event, the peak flow was reduced from 190 to 147 m³/s and, in another, from 195 to 167 m³/s. Although these reductions may seem modest, in the context of the whole basin they make a positive contribution to mitigating flood risks, improving water quality and protecting aquatic ecosystems, bringing significant environmental and social benefits. The Fig. 3 shows the outflow permanence curve.




Fig. 3. Outflow permanence curve

6 Conclusion

The simulation of the implementation of a more flexible operational rule, incorporating the controlled lowering of the reservoir of the Americana Small Hydroelectric Power Plant (SHPP), proved to be effective in increasing energy efficiency and reducing losses due to water spillage. The gains in energy generation and in maintaining minimum flows downstream are particularly relevant for the basin, since the effects of climate change could increase periods of water scarcity and extreme weather events. The ability to attenuate flood peaks, even modestly, represents an additional benefit by reducing flood risks in vulnerable urban areas. Therefore, the results show that the adaptive operation of the hydroelectric plant can contribute significantly to the integrated management of water resources, aligning energy production with the promotion of environmental and social benefits in the river basin, being an adaptive tool for the operation of the reservoir to climate change.

References

- ANA (Agência Nacional de Águas): Atlas Águas: Segurança Hídrica do Abastecimento Urbano (2022)
- Bates, B.C., Kundzewicz, Z.W., Wu, S., Palutikof, J.P.: Climate Change and Water. IPCC Technical Paper VI (2008)
- Horne, A.C., Webb, J.A., Stewardson, M.J., Richter, B.D., Acreman, M.: Water for the Environment: From Policy and Science to Implementation and Management. Academic Press (2017)
- IPCC: Sixth Assessment Report: Climate Change 2022 – Impacts. Cambridge University Press, Adaptation and Vulnerability (2022)
- Knox, J.C.: Paleohydrology and Holocene flood events. *Quatern. Sci. Rev.* **19**, 439 (2000)
- Kundzewicz, Z.W., et al.: The implications of projected climate change for freshwater resources and their management. *Hydrol. Sci. J.* **53**(1), 3–10 (2008)

- Loucks, D.P., van Beek, E.: Water Resource Systems Planning and Management: An Introduction to Methods, Models, and Applications. Springer (2017)
- Melo, D.C.D., Ramos, M.M., Mello, C.R.: 'Reservatórios como estratégia de adaptação às mudanças climáticas: uma análise hidrológica', *Revista Brasileira de Recursos Hídricos*, 26 (2021)
- Milly, P.C.D., et al.: Stationarity is dead: whither water management? *Science* **319**(5863), 573–574 (2008)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Behavioral Analysis of Stocked Fish Using Individual-Based Model

Luhai Wang^(✉)

China Institute of Water Resources and Hydropower Research, Beijing 10038, China
wanglh@iwhr.com

Abstract. This study pioneers an individual-based model (IBM) integrating behavioral movement, bioenergetics, and mortality mechanisms to simulate downstream migration of hatchery-released *Acipenser sinensis* subadults in large river systems. The model innovatively couples hydraulic drivers with individual physiological responses, enabling high-resolution prediction of spatiotemporal distribution and survival dynamics beyond acoustic monitoring limitations. Results demonstrate the model's capability to: (1) Quantify flow-dependent migration speed variations, (2) Reveal linear energetic depletion patterns during non-feeding migration, and (3) Identify incidental mortality (e.g., anthropogenic threats) as the dominant survival constraint, overriding starvation risks under natural metabolic regimes. Validation against field tracking data confirms model robustness across river reaches. This framework provides a transformative tool for evaluating stocking efficacy, designing river protection infrastructures, and optimizing release strategies for endangered migratory fishes in regulated rivers.

Keywords: artificial release · fish protection · individual-based model · fish tracking

1 Introduction

While developing and operating hydropower, China routinely employs artificial stock enhancement to maintain wild, endangered fishery resources and population sizes. The survival rate of stocked fish significantly impacts the ultimate effectiveness of this practice. Artificial propagation and stocking, a primary measure to mitigate dam impacts, involves breeding and rearing juvenile fish in captivity to a certain size before releasing them into the wild to supplement wild populations. To ensure the homing behavior of migratory fish, releases typically occur at spawning grounds, with the expectation that the stocked, hatchery-reared juveniles will migrate downstream to the sea and return to their natal site upon reaching sexual maturity. Superficially, captive rearing appears to increase early juvenile survival by avoiding high mortality rates in the wild. However, successful stockings that effectively supplement wild populations are rare, with most

This research was supported by IWHR Research & Development Support Program (SS0145B022021).

© The Author(s) 2026

Y. Hu et al. (Eds.): IHDC 2025, LNCE 792, pp. 320–329, 2026.

https://doi.org/10.1007/978-981-95-4889-7_28

showing insignificant results [1]. Welch et al. [2] used PIT tags to measure the downstream migration survival rates of salmon in the Columbia River over several years; their results indicated that the cumulative survival rate of stocked groups declined exponentially with migration distance, with only about one-third of individuals reaching the estuary after a 900 km migration. Justice et al. [3] released White Sturgeon (*Acipenser transmontanus*) of different ages into the Kootenai River and conducted long-term monitoring; they found that approximately 59% of stocked individuals survived beyond one year, with survival positively correlated to release age, suggesting the use of larger, older juveniles to improve stocking efficiency. Aarestrup et al. [4] reported that only 63% of stocked Brown Trout (*Salmo trutta*) in the Gudena River completed their downstream migration to the sea, indicating low stocking efficiency. Understanding the migration patterns and mortality mechanisms of stocked individuals is crucial for improving survival rates.

The Chinese Sturgeon (*Acipenser sinensis*) is a critically important, rare, and endemic fish species in the Yangtze River. It is a National Class I Protected Animal, an endangered species on the IUCN Red List, and a flagship species in the Yangtze River ecosystem, making its research and conservation highly valuable. Following the damming of the Yangtze River by the Gezhouba Project in 1981, the Chinese Sturgeon population has declined annually and natural spawning has ceased in recent years. To rescue this critically endangered species, the Chinese government and hydropower enterprises have conducted extensive stock enhancement activities, releasing large numbers of Chinese Sturgeon sub-adults. From 1983 to 2018, institutions including the Chinese Sturgeon Research Institute and the Yangtze River Fisheries Research Institute released approximately 7 million juvenile Chinese Sturgeon of various sizes [5]. However, monitoring revealed no significant positive effect on population enhancement. Successful artificial propagation of the second filial generation (F2) was achieved in 2009 [6], and subsequent releases have primarily involved F2 individuals. How to evaluate and improve stocking efficiency is now an urgent and critical issue in Chinese Sturgeon conservation. There is a need to establish mathematical models to simulate the migration process of stocked groups.

The Individual-Based Model (IBM) is a common computational method for simulating wildlife migration. Unlike Eulerian models, IBMs can analyze how changes in individual characteristics (such as age, fitness, and sexual maturity) influence population migration processes [7]. To analyze the post-release migration of stocked Chinese Sturgeon sub-adults, this study established an individual-level model encompassing migration, energy consumption, and mortality. Coupled with the monitoring data of Array of Stationary Acoustic Receiver (ASAR) [8], the model was used to evaluate the primary factors influencing the downstream migration of Chinese Sturgeon sub-adults.

2 Methods

The IBM is widely applied to study fish behavior, growth, and habitat selection [9–12]. In the past, the IBM has mainly been used to simulate different developmental stages in the life history of fish on a long-term scale. In the past, the IBM has mainly been used to simulate different developmental stages in the life history of fish on a long-term

scale. Due to the rare feeding of sub-adults in the Yangtze River, this paper proposed a simplified IBM including three sub-models of movement, consumption and death to simulate individual migration by superimposing the coupled effects of multiple factors, and then obtained population information on distribution, physiology and other attributes by statistical analysis based on huge amounts of individual results. The calculation procedure is shown in Fig. 1. Using a randomization method to simulate the released subadult migration, energy consumption, and death, I assumed that the initial number of individuals was 100,000 ind in the IBM calculations, which were uniformly distributed between the release site (0 km) to 10 km downstream. Downriver migration began randomly within 0.5 days because field observations showed that after the release into the Yangtze River, these captive-bred individuals generally require not more than 0.5 days of adaptation to the wild environment. The weight of the released population was normally distributed, with a mean of 7.07 kg and a standard deviation of 1.195 kg. The mean proportion of muscle mass of individuals was 68.43% [13]. The calculation duration was 30 days, and the time step $\Delta t = 0.1d$.




Fig. 1. Calculation procedure of the simplified individual-based model (IBM)

2.1 Movement Sub-Model

According to the life history of the Chinese sturgeon, individuals aged between 3 and 8 years should live in the ocean rather than in the Yangtze River. Therefore, the migration of subadults in the Yangtze River is not a form of a natural state. I made the following assumptions: (i) Subadults drifted with the flow along while accompanied by a random walk; (ii) Subadults migrate along the river thalweg, a form of one-dimensional movement. Based on these two assumptions, we used the following equation to calculate the instantaneous fish speed over the ground for individuals in the Yangtze River:

$$U_g(x, t) = U_w(x, t) + \alpha U_r, \quad (1)$$

where U_g is the instantaneous fish speed over the ground, km/d; U_w is the local water velocity, km/d; U_r is the random swimming speed of individuals, km/d, representing the intensity of the random movement of the individual; α is the correction factor, dimensionless, which is correlated with the time step obtained in the estimating diffusion coefficient of subadults.

The random swimming speed, U_r , is assigned a random value in each time step of the calculation, reflecting the active swimming speed per time step. Here we assumed that the PDF of U_r follows a sum of two normal distributions:

$$p(U_r) = \frac{1}{2} [N(\bar{U}, \bar{U}/3) + N(-\bar{U}, \bar{U}/3)], \quad (2)$$

where $\bar{U}$ is the mean swimming speed of Chinese sturgeon in still water environment; $N(\bar{x}, \sigma)$ is a normal distribution function. $\bar{U} \approx 40$ cm/s (34.56 km/d) from laboratory experiments for the Chinese sturgeons aged three years and above [14]. The threshold swimming speed of two-year-old Chinese sturgeon juveniles was around 80 cm/s [15], which was twice that of the mean swimming speed. Therefore, we assumed that the standard deviation of random swimming speed distribution of subadults was $\bar{U}/3$, resulting in almost all values of U_r were just between the still and threshold swimming speeds.

We calculated the movement trajectory of an individual from the initial position known by the following equation.

$$x_{i+1} = x_i + U_g(x_i, t_i) \cdot \Delta t, \quad (3)$$

where x_i and x_{i+1} are the positions of the individual at time points i and $i + 1$, respectively; and Δt is the time step in the calculation.

2.1.1 Consumption Sub-Model

During seaward migration, subadult Chinese sturgeon rarely feed before reaching the estuary [8]. Therefore, we made the following assumptions: (i) Only energy consumption existed for the released individuals without any energy supply during seaward migration; (ii) All energy consumption arose from proteins and fats in the muscles; (iii) All movements during migration were aerobic movements, and proteins and fats were completely degraded; (iv) The ratio of all components in muscles remained unchanged during energy consumption.

Here, I used oxygen consumption (MO_2) as an intermediate variable to construct models for the muscle consumption rate in subadults under different movement states. Based on results of juvenile green sturgeons [16], I obtained the basal metabolic oxygen consumption rate of subadults as follows:

$$MO_{2s} = qM_m(t_i), \quad (4)$$

where MO_{2s} is the oxygen consumption rate of subadult at rest, mg/hr; $M_m(t_i)$ is the weight of fish at time point i , kg; q is the oxygen consumption rate per unit of body mass, 1/hr. Here $q = 61 \times 10^{-6}$ 1/hr [16]. The oxygen consumption rate of Chinese sturgeon was directly proportional to body weight at rest. Yuan et al. [17] found that the oxygen consumption rate of Chinese sturgeon at maximum movement speed is approximately twice that at rest, which is directly proportional to the swimming speed. Then, we constructed a relationship of the oxygen consumption rate of Chinese sturgeon between at swimming state and rest, as follows

$$MO_{2m} = (1 + \frac{|U_r|}{2U}) \cdot MO_{2s}, \quad (5)$$

where MO_{2m} is the oxygen consumption rate of Chinese sturgeon, mg/hr, at swimming speed U_r .

Chai et al. [13] showed that the protein and fat contents in muscles from one-year-old Chinese sturgeon were 16.97% and 0.99%, respectively. Here, we assumed the muscle composition of subadult Chinese sturgeon to be the same as given in Chai et al. [13]. Considering the amounts of oxygen consumed for complete aerobic degradation of 1 g of fat and 1 g of protein were 2.9 g and 1.34 g, respectively, I obtained the ratio of the amount of oxygen consumed to the weight of muscle degraded, $RO_{2\text{muscle}}$, as follows

$$RO_{2\text{muscle}} = 2.9p_{fat} + 1.34p_{protein} = 0.2561, \quad (6)$$

where p_{fat} (0.99%) and $p_{protein}$ (16.97%), which represent the fat and protein content in the muscles of Chinese sturgeon, respectively. Equation (8) shows that 0.2561 g of oxygen consumed can degrade 1 g of subadult muscles.

I assumed the muscle weight of an individual to be $M_m(t)$ varying with release time while the non-muscle weight, M_o , did not change over time. Then we obtained the formula for calculating changes in muscle mass from Eqs. (6, 7 and 8) as follows.

$$M_m(t_{i+1}) = M_m(t_i) - MO_{2m} \frac{\Delta t}{RO_{2\text{muscle}}}. \quad (7)$$

2.1.2 Death Sub-Model

Two death scenarios were assumed during the seaward migration of Chinese sturgeon: (i) Abnormal death caused by en route loss, where the instantaneous mortality rate K_t was calculated by Eq. (1); (ii) Mortality due to overconsumption of energy reserves. The judgment criterion was relative muscle mass (muscle weight/total weight) being lower than the threshold value. In the survey [8], the average body weight of the recaptured Chinese sturgeon was 2.55 kg, much lighter than the bodyweight before release (4.08 kg). Therefore, the average relative muscle mass of these subadults is 0.495. Since there is no detailed data on the threshold flesh rate, we roughly set it at 0.5.

3 Results and Discussions

This study employed an Individual-Based Model (IBM) to simulate the downstream migration processes of subadult fish in 2015 and 2016, enabling the characterization of their spatiotemporal distribution during seaward migration. Simulation results (Fig. 2) indicate that during the 2015 downstream migration, the population peak reached the vicinity of Wuhan by Day 7, Jiujiang by Day 10, Nanjing by Day 15, and the estuary (Shanghai) by Day 22. Concurrently with downstream movement, rapid dispersion of the subadult population was observed. The 2016 migration proceeded significantly faster than in 2015, with the population peak reaching the estuary within 15 days post-release. The IBM effectively simulated the spatiotemporal distribution of subadults throughout the entire river course, particularly within the estuary where no monitoring stations were deployed – data unavailable through direct ultrasonic telemetry. The accelerated migration speed in 2016 is attributed to the notably higher river flow velocity that year. Model outputs were broadly consistent with field monitoring data. Minor stochastic fluctuations in the distribution curves reflect the incorporation of randomly varying individual swimming speeds within the IBM framework.




Fig. 2. Spatiotemporal Distribution of Population Density During Subadult Downstream Migration. (a) 2015; (b) 2016

The IBM simulations quantified body weight dynamics of the released fish cohort throughout the downstream migration. Statistical analysis of body weights at key migration stages revealed distribution patterns and mean weight trends (Fig. 3). Results demonstrate a persistent normal weight distribution consistent with initial conditions. However,

mean body weight exhibited a linear decrease over time. Model simulations indicated a mean weight reduction of 1.3 kg after 20 days of migration. This finding is broadly consistent with field data reported by Wu et al. [8], who documented a mean weight of 2.55 kg for ten recaptured *Acipenser sinensis* individuals in the estuary (2015), representing a reduction of 1.53 kg from the initial average release weight (4.08 kg).




Fig. 3. Body weight variation in 2015 Release Simulation. (A) Temporal Histogram of Weight Distribution; (B) Temporal Trend of Mean Body Weight

IBM simulations assumed a constant daily survival rate of 95%. The modeled cumulative survival rates at monitoring stations were compared with field observations, as presented in Fig. 4. Results demonstrate a linear relationship between cumulative survival rate and migration distance. Only half of the released individuals successfully reached the estuary. While simulated survival rates aligned with field data in upper and middle river reaches, observed survival at the downstream stations (Nanjing and Jiangyin) was significantly lower than model predictions. Notably, IBM simulations indicated that

the mortality mechanism triggered by excessive energy depletion in IBM's mortality submodule was not activated during this migration.




Fig. 4. The cumulative survival rate of released subadults and other migratory fishes showing exponential decay along the migration route

Mortality in the IBM simulations originated from two sources: incidental mortality and starvation-induced mortality. To analyze these mechanisms, simulations were conducted under three scenarios using a fixed daily mortality rate of 5%: (1) baseline conditions, (2) doubled basal metabolic oxygen consumption, and (3) tripled basal metabolic oxygen consumption. The resulting cumulative survival curves (Fig. 4) reveal distinct patterns. During initial migration stages, elevated metabolic rates did not significantly alter cumulative survival. Doubled consumption induced only marginal additional mortality between Nanjing and Jiangyin, indicative of emerging starvation effects. When consumption was tripled, however, a mass mortality event occurred between Jiujiang and Nanjing, demonstrating the concentrated nature of starvation-induced losses. Critically, field monitoring data show no evidence of such concentrated mortality events. This absence strongly suggests that incidental factors constitute the primary driver of mortality during the current release operations.

4 Conclusions

The developed IBM establishes a novel paradigm for simulating stocked fish migration by mechanistically coupling individual behavior with environmental drivers. Its integration of stochastic movement, dynamic bioenergetics, and context-specific mortality sub-modules offers unprecedented capacity to predict population trajectories in data-scarce

zones, particularly estuaries. Critically, the model reveals that incidental mortality—rather than energy depletion—drives post-release survival loss, redirecting conservation focus toward mitigating anthropogenic impacts. Future applications include adaptive management of release timing/size cohorts, environmental flow design for migration corridors, and impact assessment of river infrastructures. This approach is transferable to global conservation programs for diadromous species facing similar anthropogenic pressures.

References

1. Araki, H., Schmid, C.: Is hatchery stocking a help or harm? evidence, limitations and future directions in ecological and genetic surveys. *Aquaculture* **308**(S2-S11) (2010)
2. Welch, D.W., Rechisky, E.L., Melnychuk, M.C., Porter, A.D., Walters, C.J., Clements, S., et al.: Survival of migrating salmon smolts in large rivers with and without dams. *PLoS Biol.* **6**(10), e265 (2008)
3. Justice, C., Pyper, B.J., Beamesderfer, R.C.P., Paragamian, V.L., Rust, P.J., Neufeld, M.D., et al.: Evidence of density - and size-dependent mortality in hatchery-reared juvenile white sturgeon (*acipenser transmontanus*) in the kootenai river. *Can. J. Fish. Aquat. Sci.* **66**(5), 802–815 (2009)
4. Aarestrup, K., Baktoft, H., Thorstad, E., Svendsen, J., Höjesjö, J., Koed, A.: Survival and progression rates of anadromous brown trout kelts *salmo trutta* during downstream migration in freshwater and at sea. *Marine Ecol. Prog.* **535** (2015)
5. Wei, Q.W., et al. (eds.): *Conservation Biology of Chinese Sturgeon (Acipenser sinensis)*. Science Press, Beijing (2019)
6. Guo, B.F., et al.: The reproductive biology of first filial generation of *Acipenser sinensis* growing up in the freshwater environment. *Acta Hydrobiol. Sin.* **35**, 940–945 (2011)
7. Grimm, V., Berger, U., Bastiansen, F., et al.: A standard protocol for describing individual-based and agent-based models. *Ecol. Model.* **198**(1–2), 115–126 (2006)
8. Wu, C., Chen, L., Gao, Y., et al.: Seaward migration behavior of juvenile second filial generation Chinese sturgeon *Acipenser sinensis* in the Yangtze River, China. *Fish. Sci.* **84**, 71–78 (2018)
9. Mcdermot, D., Rose, K.A.: An individual-based model of lake fish communities: application to piscivore stocking in Lake Mendota. *Ecol. Model.* **125**(1), 670–102 (2000)
10. Hemelrijk, C.K., Hanspeter, K.: Density distribution and size sorting in fish schools: an individual-based model. *Behav. Ecol.* **16**(1), 178–187 (2004)
11. Harvey, B.C., Railsback, S.F.: Estimating multi-factor cumulative watershed effects on fish populations with an individual-based model. *Fisheries* **32**(6), 292–298 (2007)
12. Dudley, P.N.: Insights from an individual-based model of a fish population on a large regulated river. *Environ. Biol. Fishes* **102**(8), 1069–1095 (2019)
13. Chai, Y., Sun, D.D., Wei, Q.W.: Analysis on flesh rate and nutritive composition of muscle in 1-year old artificially bred *Acipenser sinensis* Gray. *J. Anhui Agricult. Sci.* **38**(18), 9549–9550 (2010)
14. Zhang, Y.Z., Zhang, X.Y., Du, H., et al.: Free-swimming velocity and respiratory frequency related to the age and gonadal development of Chinese sturgeon (*Acipenser sinensis*) in the aquarium. *Chin. J. Zool.* **52**(4), 680–684 (2017)
15. Qu, Y.: Relationship between lateral morphology and swimming performance of two sturgeon species. Master thesis. Shanghai Ocean University, Shanghai, China (2012)

16. Allen, P.J., Cech, J.J.: Age/size effects on juvenile green sturgeon, *Acipenser medirostris*, oxygen consumption, growth, and osmoregulation in saline environments. *Environ. Biol. Fish* **79**(3), 211–229 (2007)
17. Yuan, X., Huang, Y.P., Guo, W.T., et al.: Effects of temperature and repeated exercise on the swimming behavior of Chinese sturgeon (*Acipenser sinensis*). *J. Hydroecol.* **39**(1), 63–68 (2018)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Multi-objective Optimal Operation of Cascade Reservoirs in the Upper Yellow River Incorporating Ecological Flow Requirements

Yuan Si^(✉), Xiaobo Liu, Wenqiang Wu, Fei Dong, and Weijie Wang

Key Laboratory of Water Safety for Beijing-Tianjin-Hebei Region of Ministry of Water Resources, China Institute of Water Resources and Hydropower Research, Beijing 100038, China

sssiyuannn@163.com

Abstract. The construction and operation of cascade reservoirs in the Upper Yellow River Basin have altered the hydrological regime, adversely impacting the river's aquatic ecosystem. To develop reservoir operation strategies oriented towards ecological protection, this research first determined suitable ecological flow ranges for key mainstream control sections using the Indicators of Hydrologic Alteration - Range of Variability Approach (IHA-RVA) method. Subsequently, a multi-objective optimization model for cascade reservoir operation incorporating ecological flow requirements was established. Systematically analyzing operation scenarios across three characteristic hydrological years (wet, normal, and dry), the study quantified the trade-off relationship between hydropower generation and ecological conservation, explored the potential for synergistic benefit enhancement through coordinated reservoir operations. The findings offer a scientific basis for optimizing the operational policies of cascade reservoirs along the Yellow River mainstream.

Keywords: reservoir operation · ecological flow · multi-objective optimization · comprehensive utilization

1 Introduction

The construction and operation of cascade reservoirs within river basins, combined with human activities such as water abstraction, have significantly altered hydrological regimes, profoundly impacting riverine ecosystems [1, 2]. Ecological flow – a fundamental element for maintaining aquatic ecosystem integrity – serves as a critical indicator for regulating water resource exploitation intensity and provides the essential basis for coordinating production, domestic, and ecological water allocations. The Natural Flow Regime (NFR) theory [3] posits that undisturbed natural flow patterns are vital for preserving river ecosystem integrity and supporting native biodiversity, thereby establishing a fundamental framework for ecological flow management. The five hydrological components of natural flow regimes – magnitude, frequency, timing, duration, and rate of change – are widely recognized as core components for sustaining aquatic biodiversity

and ecological functions [4, 5]. Consequently, natural hydrological regimes may serve as reference systems for determining ecological flow.

Traditional reservoir operation primarily focused on beneficial objectives (e.g., power generation, water supply) and hazard mitigation (e.g., flood control). With growing societal emphasis on ecological protection, researchers have begun exploring adjustments to reservoir operating rules to meet river ecosystem water requirements [6, 7]. This approach aimed at protecting and restoring river ecosystems is termed ecological operation. As balancing ecological objectives with other operational goals gained scholarly attention, ecological operation models emerged. These models embed ecological factors representing ecological outcome or ecological fitness within conventional reservoir operation frameworks [8, 9]. Based on ecological factor integration methods and decision variables, such models fall into three paradigms: constraint-based, objective-oriented, and rule-driven types [10–12]. Inherent conflicts typically exist between ecological preservation and comprehensive utilization objectives, where optimizing one goal often compromises others [13]. Consequently, no single solution can simultaneously optimize all competing objectives, necessitating systematic trade-off analysis through multi-criteria decision-making processes.

To develop ecologically oriented operation strategies for cascade reservoirs in the Upper Yellow River, this study first determined suitable ecological flow ranges for key mainstream control sections using the Indicators of Hydrologic Alteration – Range of Variability Approach (IHA-RVA). Subsequently, a multi-objective optimization model was established to balance hydropower generation and ecological protection objectives. The trade-offs between these objectives across typical hydrologic years were quantified, and the potential for enhancing comprehensive benefits through coordinated operations was evaluated. These findings provide a theoretical basis for optimizing operational policies of cascade reservoirs along the Yellow River mainstream.

2 Materials and Methods

2.1 Study Area

The Yellow River, China's second-longest river, originates at the northern foot of Bayankala Mountain on the Qinghai-Tibet Plateau and flows through Qinghai, Sichuan, Gansu, Ningxia, Inner Mongolia, Shanxi, Shaanxi, Henan, and Shandong provinces. The mainstream spans approximately 5,464 km with a drainage area of about 795,000 km² (including 42,000 km² of inland areas). Its watershed extends from 95°53'E to 119°05'E longitude and 32°10'N to 41°50'N latitude. The mainstream is divided into upper, middle, and lower reaches. The upper reach stretches from the river's source to Hekou Town in Tuoketuo County, Inner Mongolia, covering 3,471.6 km with a drainage area of 428,200 km². It receives 43 major tributaries including the Daxia, Tao, Huangshui, Zuli, and Qingshui Rivers.

Among existing hydraulic infrastructure in the Upper Yellow River, Longyangxia and Liujiaxia Reservoirs provide significant regulation capabilities. Longyangxia Reservoir (hereinafter LYX), impounded in 1986, is a multi-year regulating reservoir with a storage capacity of 19.35 billion m³. Liujiaxia Reservoir (hereinafter LJX), impounded in 1967, is an incomplete annual regulating reservoir with a storage capacity of 3.5 billion m³.

These two reservoirs account for approximately 97% of the total regulating capacity of the cascade reservoirs in the Upper Yellow River and 69% of natural inflow volume. There are close hydraulic and hydropower connections between the two reservoirs. Through coordinated operation, they perform power compensation regulation utilizing hydropower capacity benefits for peak load and frequency control of the Northwest Power Grid, as well as storage compensation regulation that retains water during wet periods for utilization in dry periods to mitigate drought (Fig. 1).




Fig. 1. The schematic of the cascade reservoirs in the Upper Yellow River

2.2 Ecological Flow Calculation

Among hydrological regime assessment frameworks, the Indicators of Hydrologic Alteration (IHA) system remains the most widely adopted, which categorizes hydrological components into 5 groups and 33 parameters. Building on IHA, Richter et al. [14] proposed the Range of Variability Approach (RVA) to quantify hydrological indicator alterations. This methodology has been extensively applied to evaluate anthropogenic impacts on river hydrological regimes. Using long-term historical daily flow data series (>20 years), the 25th and 75th percentiles of each IHA indicator during the near-natural reference period are statistically calculated, defining the acceptable range of each indicator under natural hydrological conditions.

The degree of hydrological regime change is evaluated based on the ratio of years in which each IHA indicator falls within the acceptable range within the evaluation period relative to the expected number of years. The formula is as follows:

$$D_m = \left| \frac{N_{o,m} - N_{e,m}}{N_{e,m}} \right| \times 100\% \quad (1)$$

where D_m is the hydrological change degree of the m th IHA indicator. $N_{o,m}$ is the number of years within the evaluation period during which the m th IHA indicator falls within the acceptable range; $N_{e,m}$ is the expected number of years within the evaluation period during which the m th IHA indicator falls within the acceptable range. When

$D_m \leq 33\%$, it indicates that compared with the recent natural period, the m th IHA indicator has experienced no change or only a low degree of change during the evaluation period; when $33\% < D_m \leq 67\%$, it indicates that the m th IHA indicator has a moderate change; when $D_m > 67\%$, it indicates that the m th IHA indicator has a high degree of change.

Based on the IHA-RVA method, Shiao and Wu [15] proposed a representation form for the overall hydrological change of rivers, and the formula is as follows:

$$D_0 = \left(\frac{1}{M} \sum_{m=1}^M D_m^2 \right)^{1/2} \quad (2)$$

where D_0 is the overall hydrological change degree; M is the total number of IHA indicators.

2.3 Multi-objective Optimization Model for Cascade Reservoir Operation

2.3.1 Objective Function

The reservoir operation in the Yellow River Basin adheres to the principle that power generation dispatch is subordinate to water allocation management. Flood prevention, ice disaster control, water supply security, and minimum ecological flow maintenance constitute the primary operational constraints for cascade reservoirs. Therefore, these requirements were established as hard constraints in the multi-objective optimization model, while hydropower generation and ecological flow maintenance were designated as the optimization objectives.

Hydropower Generation

The long-term hydropower dispatching of cascade reservoirs usually aims to maximize power generation. The goal of maximizing power generation mainly reflects the energy efficiency of hydropower station. The formula is as follows:

$$F_1 = \max \sum_{t=1}^T \sum_{i=1}^n E_i(t) \quad (3)$$

In which,

$$E_i(t) = N_i(t) \cdot \Delta t = K_i \cdot R_i'(t) \cdot H_i(t) \cdot \Delta t \quad (4)$$

$$R_i(t) = R_i'(t) + R_i''(t) \quad (5)$$

$$H_i(t) = HF_i(t) - HT_i(t) - HL_i(t) \quad (6)$$

$$HF_i(t) = f[\bar{S}_i(t)] = a_{0,i} + a_{1,i} \cdot \bar{S}_i(t) + a_{2,i} \cdot \bar{S}_i^2(t) \quad (7)$$

$$\bar{S}_i(t) = \frac{[S_i(t) + S_{i-1}(t)]}{2} \quad (8)$$

$$HL_i(t) = f[R_i(t)] = b_{0,i} + b_{1,i} \cdot R_i(t) + b_{2,i} \cdot R_i^2(t) \quad (9)$$

where t is the time period index. T is the total number of time periods, $t \in [1, T]$. i is the hydropower station index, and n is the total number of hydropower stations, $i \in [1, n]$. $E_i(t)$ is electricity generated by the hydropower station of reservoir i during period t . $N_i(t)$ denotes the output generated by the hydropower station of reservoir i during period t . $R_i'(t)$ is the water released from reservoir i for power generation during period t . $R_i''(t)$ is the water released from reservoir i for use except for power generation during period t . $H_i(t)$ is the average water head of the hydropower station of reservoir i during period t , which is equal to the difference between the average fore-bay water level $HF_i(t)$ and the average tailrace water level $HT_i(t)$ and the average water head loss $HL_i(t)$. η_i is the power generation efficiency of the hydropower station of reservoir i . $\bar{S}_i(t)$ is the average storage of reservoir i during period t . The curve of the relationship between storage and the fore-bay water level of reservoir i can be fitted by a quadratic polynomial function with $a_{0,i}$, $a_{1,i}$ and $a_{2,i}$ as the coefficients of the terms. The curve of the relationship between the water released from reservoir i and the tailrace water level can be fitted by a quadratic polynomial function with $b_{0,i}$, $b_{1,i}$ and $b_{2,i}$ as the coefficients of the terms.

Ecological Flow Requirement

The monthly suitable ecological flow ranges derived from the IHA-RVA approach were incorporated as an optimization objective, specifically minimizing deviations between actual flows at control sections and the target ecological flow ranges. The formula is as follows:

$$F_2 = \min \left\{ \frac{1}{T} \times \sum_{t=1}^T D(t) \right\} \quad (10)$$

In which,

$$D(t) = \begin{cases} \frac{Q^{low}(t) - Q_m(t)}{Q^{low}(t)} Q_m(t) < Q^{low}(t) \\ 0 & Q^{low}(t) < Q_m(t) < Q^{up}(t) \\ \frac{Q_m(t) - Q^{up}(t)}{Q^{up}(t)} Q_m(t) > Q^{up}(t) \end{cases} \quad (11)$$

where $D(t)$ is the degree of deviation between the suitable ecological flow range of the control section and the actual flow in the period, $t \in [1, T]$. m is the node number of the control section. $Q_m(t)$ is the flow of the node m in the period t . $Q^{low}(t)$ and $Q^{up}(t)$ are the lower and upper bounds of the suitable ecological flow range of the period, respectively.

2.3.2 Constraints

Water Balance Equation

$$S_i(t+1) = S_i(t) + I_i(t) \cdot \Delta t - R_i(t) \cdot \Delta t - E_i(t) \cdot \Delta t \cdot \forall i, \forall t \quad (12)$$

where i is the reservoir index, $i \in [1, n]$. n is the total number of the reservoirs. $S_i(t)$ is the storage of reservoir i at the beginning of period t . $S_i(t+1)$ is the storage of reservoir

i at the end of period t . $I_i(t)$ is the inflow to reservoir i during period t . $R_i(t)$ is the water released from reservoir i during period t . Δt is the duration of the period. $E_i(t)$ is the evaporation of reservoir i during period t .

Storage of the Reservoir

$$S_i^{\min}(t+1) \leq S_i(t+1) \leq S_i^{\max}(t+1), \forall i, \forall t \quad (13)$$

where $S_i^{\max}(t+1)$ and $S_i^{\min}(t+1)$ are the respective maximum and minimum storage of reservoir i at the end of period t

Outflow from the Reservoir

$$R_i^{\min}(t) \leq R_i(t) \leq R_i^{\max}(t) \forall i, \forall t \quad (14)$$

where $R_i^{\max}(t)$ and $R_i^{\min}(t)$ are the respective maximum and minimum outflow from reservoir i during period t .

Water Released for Hydropower Generation

$$R_i'^{\min}(t) \leq R_i'(t) \leq R_i'^{\max}(t) \forall i, \forall t \quad (15)$$

where $R_i'^{\max}(t)$ and $R_i'^{\min}(t)$ are the respective maximum and minimum water released from the hydropower station of reservoir i for hydropower generation during period t .

Output of the Hydropower Station

$$N_i^{\min}(t) \leq N_i(t) \leq N_i^{\max}(t) \forall i, \forall t \quad (16)$$

where $N_i^{\max}(t)$ and $N_i^{\min}(t)$ are the respective maximum and minimum output from the hydropower station of reservoir i during period t .

Initial and Final Reservoir Storage

$$S_i(1) = S_i^{\text{initial}} \forall i \quad (17)$$

$$S_i(T+1) \geq S_i^{\text{final}} \forall i \quad (18)$$

where S_i^{initial} is the initial storage of reservoir i . S_i^{final} is the final storage of reservoir i .

Discharge at the Key Control Section

$$Q_m^{\min}(t) \leq Q_m(t) \leq Q_m^{\max}(t) \forall t \quad (19)$$

where $Q_m(t)$ is discharge at the key control section m during period t . $Q_m^{\max}(t)$ is the maximum discharge at the key control section m during period t that satisfies the basic requirements for water supply, flood/ice prevention and sediment flushing. $Q_m^{\min}(t)$ is the minimum discharge at the key control section m .

2.3.3 Optimization Algorithm

To solve the dual-objective problem, the ε -constraint method [16, 17] was employed. One of the objectives was designated as the optimization goal, while the other was treated as a constraint. This approach facilitated solution via a single-objective optimization algorithm. The single-objective problem was programmed using LINGO 19.0 (Beta 64-bit; LINDO Systems Inc., 2011), with optimization computations performed using its built-in generalized nonlinear programming (NLP) solver.

3 Results and Discussion

3.1 Optimization Results for Typical Years

3.1.1 Typical year Selection and Boundary Condition Settings

Based on long-term historical runoff data, three typical hydrological years were selected: dry year (2004–2005), normal year (2008–2009) and wet year (2005–2006). The annual runoff volumes were 16.72, 20.43, and 24.54 billion m^3 , with corresponding hydrological frequencies of 71%, 45% and 22%, respectively. The ten-day flow processes at Tangnaihai Station of the three typical years are shown in Fig. 2.




Fig. 2. The ten-day flow processes at Tangnaihai Station of the typical hydrological years


The boundary conditions of water level at LYX and LJX Reservoirs were calculated using the actual initial water level (IWL) and final water level (FWL), and their corresponding initial storage (IS) and ending storage (ES) for the three typical years, respectively. The details can be found in Table 1.

Table 1. The boundary conditions of water level in three typical years for LYX and LJX Reservoirs

Scenario	LYX				
	IWL (m)	IS (billion m ³)	FWL (m)	ES (billion m ³)	Annual variation in storage (billion m ³)
Dry year	2554.82	10.4697	2562.32	12.3860	1.9163
Normal year	2569.88	14.4985	2566.03	13.4000	-1.0985
Wet year	2562.32	12.3860	2580.88	17.8966	5.5107
Scenario	LJX				
	IWL (m)	IS (billion m ³)	EWL (m)	ES (billion m ³)	Annual variation in storage (billion m ³)
Dry year	1719.82	2.2791	1720.24	2.3191	0.0400
Normal year	1720.58	2.3519	1722.65	2.5597	0.2078
Wet year	1720.24	2.3191	1722.79	2.5743	0.2552

Under wet year conditions, the minimum deviation from the suitable ecological flow range was 0.06815 when hydropower generation constraints are not applied. Trial calculations identified that a total hydropower generation of 41.50 billion kWh yields this minimum deviation value. We therefore established 41.50 billion kWh as F_1^{min} denoted as scenario S1. Setting hydropower generation increments at $\Delta E = 0.05$ billion kWh, we sequentially generated scenarios S2, S3... Until no feasible solution was obtained. Table 2 presents the optimization results of hydropower generation and ecological flow deviation under different scenarios in the wet year.

The suitable ecological flow ranges at the Lanzhou section calculated based on the IHA-RVA method are shown in Fig. 3.

**Fig. 3.** The suitable ecological flow ranges at the Lanzhou section

3.1.2 Wet Year

Under wet year conditions, the minimum deviation from the suitable ecological flow range was 0.06815 when hydropower generation constraints are not applied. Trial calculations identified that a total hydropower generation of 41.50 billion kWh yields this minimum deviation value. We therefore established 41.50 billion kWh as F_1^{min} denoted as scenario S1. Setting hydropower generation increments at $\Delta E = 0.05$ billion kWh, we sequentially generated scenarios S2, S3... Until no feasible solution was obtained. Table 2 presents the optimization results of hydropower generation and ecological flow deviation under different scenarios in the wet year.

Table 2. Optimization results of hydropower generation and ecological flow deviation under different scenarios in the wet year

Scenario		Ecological flow deviation	Hydropower generation (billion kWh)		
			LYX	LJX	Cascade reservoirs
Historical simulation		0.31582	5.90	5.62	42.00
NLP	S1	0.06815	5.62	6.20	41.50
	S2	0.06891	5.61	6.22	41.55
	S3	0.08136	5.66	6.23	41.60
	S4	0.10164	5.71	6.23	41.65
	S5	0.12603	5.75	6.23	41.70
	S6	0.15075	5.79	6.25	41.75
	S7	0.19993	5.83	6.26	41.80
	S8	0.2519	5.87	6.27	41.85
	S9	0.35227	5.91	6.27	41.90

3.1.3 Normal Year

Under normal year conditions, the minimum deviation from the suitable ecological flow range is 0.09219 when hydropower generation constraints are not applied. Trial calculations identified that a total hydropower generation of 41.90 billion kWh yields this minimum deviation value. We therefore established 41.90 billion kWh as F_1^{min} denoted as scenario S1. Setting hydropower generation increments at $\Delta E = 0.05$ billion kWh, we sequentially generated scenarios S2, S3... Until no feasible solution was obtained. Table 3 presents the optimization results of hydropower generation and ecological flow deviation under different scenarios in the normal year.

Table 3. Optimization results of hydropower generation and ecological flow deviation under different scenarios in the normal year

Scenario		Ecological flow deviation	Hydropower generation(billion kWh)		
			LYX	LJX	Cascade reservoirs
Historical simulation		0.32526	5.55	6.02	41.59
NLP	S1	0.09219	5.32	5.96	41.90
	S2	0.09311	5.32	5.98	41.95
	S3	0.11276	5.36	5.99	42.00
	S4	0.138	5.41	5.99	42.05
	S5	0.16604	5.45	6.01	42.10
	S6	0.21861	5.49	6.02	42.15
	S7	0.29686	5.52	6.03	42.20

3.1.4 Dry Year

Under dry year conditions, the minimum deviation from the suitable ecological flow range is 0.20718 when hydropower generation constraints are not applied. Trial calculations identified that a total hydropower generation of 31.50 billion kWh yields this minimum deviation value. We therefore established 31.50 billion kWh as F_1^{min} denoted as scenario S1. Setting hydropower generation increments at $\Delta E = 0.05$ billion kWh, we sequentially generated scenarios S2, S3... Until no feasible solution was obtained. Table 4 presents the optimization results of hydropower generation and ecological flow deviation under different scenarios in the dry year.

Table 4. Optimization results of hydropower generation and ecological flow deviation under different scenarios in the dry year

Scenario		Ecological flow deviation	Hydropower generation(billion kWh)		
			LYX	LJX	Cascade reservoirs
Historical simulation		0.29213	3.73	4.24	31.44
NLP	S1	0.20718	3.66	4.74	31.50
	S2	0.21746	3.66	4.72	31.60
	S3	0.21942	3.66	4.73	31.70
	S4	0.22043	3.66	4.75	31.80

3.2 Relationship Between Hydropower Generation and Ecological Flow Deviation

The Pareto non-dominated solution sets for the dual objectives of hydropower generation and ecological flow deviation in typical hydrological years are shown in Fig. 4. Due to reduced inflow during the dry year, the obtained feasible region was relatively narrow, and thus was not plotted. It can be seen that there was a clear competitive relationship between the two objectives: increased hydropower generation from the cascade reservoir system corresponds to greater deviation from the suitable ecological flow range. Furthermore, the Pareto solution set covered a wider range during the wet year compared to the normal year, indicating greater flexibility in balancing dual objectives under conditions of higher inflow availability.




Fig. 4. Pareto non-dominated solution sets for typical hydrological years

Under wet year conditions, when the hydropower generation of the cascade reservoir system increased from 41.50 billion kWh to 41.55 billion kWh, the ecological flow deviation did not change significantly; as the hydropower generation further increased, the gradient of the ecological flow deviation gradually increased. When hydropower generation exceeded 41.75 billion kWh, the ecological flow deviation exhibited high sensitivity to hydropower increments, reaching 0.35227 at 41.90 billion kWh, which exceeded the historical simulation scenario. Consequently, coordinated optimization of the cascade reservoir enabled an increase in hydropower generation by 300 million kWh while maintaining ecological performance comparable to the historical scenario—representing a 7.0% improvement in power generation. Alternatively, the optimization could reduce the ecological flow deviation by 0.24 without compromising hydropower generation relative to the historical scenario, achieving a 75.1% reduction in deviation.

Under normal year conditions, when the hydropower generation of the cascade reservoir system increased from 41.90 billion kWh to 41.95 billion kWh, the ecological flow deviation did not change significantly; as the hydropower generation further increased, the gradient of the ecological flow deviation gradually increased. When hydropower generation exceeded 42.10 billion kWh, the ecological flow deviation exhibited high

sensitivity to hydropower increments. Consequently, coordinated optimization of the cascade reservoir enabled an increase in hydropower generation by 199 million kWh while maintaining ecological performance comparable to the historical scenario –representing a 0.50% improvement in power generation. Alternatively, the optimization could reduce the ecological flow deviation by 0.20 without compromising hydropower generation relative to the historical scenario, achieving a 64.3% reduction in deviation.

It should be noted that under equivalent deviations from the suitable ecological flow range, hydropower generation during the normal year was larger than that of the wet year. This discrepancy primarily stems from different initial and final water level boundary conditions of LYX Reservoir. As shown in Table 1, the actual initial and final water levels in the wet year were significantly lower than those in the normal year. Furthermore, the annual storage variation was 55.107 billion m³ in the wet year versus -10.985 billion m³ in the normal year, indicating net water storage in the wet year and net release in the normal year. Therefore, despite lower upstream natural inflow during the normal year, the combined effect of higher reservoir operating levels and greater water release resulted in superior hydropower generation compared to the wet year.

4 Conclusions

This study established a multi-objective optimization model for cascade reservoir operations in the Upper Yellow River basin. Using LINGO optimization software, we systematically analyzed operation scenarios under three characteristic hydrological year types: wet, normal, and dry years. Through multi-scenario analysis, we quantified the relationship between hydropower generation and ecological conservation objectives, explored synergistic benefit enhancement potential through coordinated reservoir operations. The principal findings are summarized as follows:

- (1) A significant trade-off exists between hydropower generation and ecological flow maintenance in cascade reservoir operations. Specifically, increased hydropower generation correlates with greater deviation from suitable ecological flow range. Notably, wet year conditions demonstrate enhanced flexibility for balancing these competing objectives.
- (2) Under wet year conditions, the system achieves a 0.70% increase in hydropower generation while maintaining ecological performance comparable to historical operations. Alternatively, it reduces ecological flow deviation by 75.1% while preserving hydropower generation levels. Under normal year conditions, the system achieves over 0.5% improvement in hydropower generation alongside a 64.3% reduction in ecological flow deviations relative to historical operation.

Acknowledgements. This work was supported by the National Key Research and Development Program of China (2024YFC3212600) and the Basic Research Fund of China Institute of Water Resources and Hydropower Research (WE110145B0022025).

References

1. Poff, N.L., Olden, J.D.: Can dams be designed for sustainability? *Science* **358**(6368), 1252–1253 (2017)
2. Sale, M.J., Brill, E.D., Herricks, E.E.: An approach to optimizing reservoir operation for downstream aquatic resources. *Water Resour. Res.* **18**(4), 705–712 (1982)
3. Poff, N.L., Allan, J.D., Bain, M.B.: The nature flow regime: a paradigm for river conservation and restoration. *Bioscience* **47**, 769–784 (1997)
4. Poff, N.L., Richter, B.D., Arthington, A.H., et al.: The ecological limits of hydrologic alteration (ELOHA): a new framework for developing regional environmental flow standards. *Freshw. Biol.* **55**(1), 147–170 (2010)
5. Li, D., Wan, W., Zhao, J.: Optimizing environmental flow operations based on explicit quantification of IHA parameters. *J. Hydrol.* **563**, 510–522 (2018)
6. Jager, H.I., Smith, B.T.: Sustainable reservoir operation: can we generate hydropower and preserve ecosystem values? *River Res. Appl.* **24**(3), 340–352 (2008)
7. Wild, T.B., Reed, P.M., Loucks, D.P., et al.: Balancing hydropower development and ecological impacts in the Mekong: Tradeoffs for Sambor Mega Dam. *J. Water Resour. Plan. Manag.* **145**(2), 05018019 (2019)
8. Ren, K., Huang, S., Huang, Q., et al.: A nature-based reservoir optimization model for resolving the conflict in human water demand and riverine ecosystem protection. *J. Clean. Prod.* **231**, 406–418 (2019)
9. Wang, Y., Liu, P., Dou, M., et al.: Reservoir ecological operation considering outflow variations across different time scales. *Ecol. Ind.* **125**, 107582 (2021)
10. Wang, H., Brill, E.D., Ranjithan, R.S., et al.: A framework for incorporating ecological releases in single reservoir operation. *Adv. Water Resour.* **78**, 9–21 (2015)
11. Tsai, W.P., Chang, F.J., Chang, L.C., et al.: AI techniques for optimizing multi-objective reservoir operation upon human and riverine ecosystem demands. *J. Hydrol.* **530**, 634–644 (2015)
12. Wang, Z., Zhang, L., Cheng, L., et al.: Optimizing operating rules for a reservoir system in Northern China considering ecological flow requirements and water use priorities. *J. Water Resour. Plan. Manag.* **146**(7), 04020051 (2020)
13. Cioffi, F., Gallerano, F.: Multi-objective analysis of dam release flows in rivers downstream from hydropower reservoirs. *Appl. Math. Model.* **36**(7), 2868–2889 (2012)
14. Richter, B.D., Baumgartner, J.V., Powell, J., et al.: A method for assessing hydrologic alteration within ecosystems. *Conserv. Biol.* **10**(4), 1163–1174 (1996)
15. Shiau, J.T., Wu, F.C.: Pareto-optimal solutions for environmental flow schemes incorporating the intra-annual and interannual variability of the natural flow regime. *Water Resour. Res.* **43**, W06433 (2007)
16. Haimes, Y.Y., Hall, W.A.: Multiobjectives in water resource systems analysis: the Surrogate Worth Trade Off Method. *Water Resour. Res.* **10**(10), 615–624 (1974)
17. Yeh, W.W.G., Becker, L.: Multiobjective analysis of multireservoir operations. *Water Resour. Res.* **18**(5), 1326–1336 (1982)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Environmental Impacts, Benefits and Future Challenges of Utility-Scale Solar Photovoltaic Projects in the Non-Humid Areas

Sijia Du¹, Yuetao Xie¹(✉), Hao Jiang¹, Qiangxiao Xian², and Guangda Lu²

¹ China Renewable Energy Engineering Institute, no. 57 Street, Beijing, China
xieyt@creei.cn

² Huanghe Hydropower Development Co., Ltd, Xining, China

Abstract. Deployment of renewable energy including solar photovoltaic (PV) is vital for the global energy transition and climate-change combat. As utility-scale PV farms expand in arid and semi-arid regions, understanding their multifaceted ecological and social effects becomes increasingly important. Studies based on cases and information collected from on-site visits, interviews, developer-provided documentation in China reveal that solar PV stations have complicated effects on its surrounding environment, requiring long-term monitoring and study of its influences and underlying mechanisms. Well-designed PV installations, combined with targeted mitigation measures, can enhance microclimate regulation, improve soil moisture, promote vegetation cover, and support local biodiversity. Critical challenges and urgent needs are identified in terms of policy integration, monitoring standards, and sustainable development of solar PV stations. To address these needs, several actions are recommended to help ensure that solar PV growth delivers enduring environmental, social, and economic benefits, with regards to public outreach and policy integration of biodiversity conservation and anti-desertification, deployment of long-term monitoring networks, and ensuring the sustainability of solar PV stations.

Keywords: Environmental impacts · environmental benefits · sustainability · renewable energy · solar PV project

1 Introduction

The global energy transition has accelerated dramatically in recent years, driven by an international consensus to mitigate climate change through large-scale deployment of renewable energy. Unprecedented shifts in the world's development patterns are underway, with countries committing to ambitious targets to reduce greenhouse gas emissions. At COP28 in 2023, the first global stocktake of the Paris Agreement culminated in the UAE Consensus, whereby 198 Parties pledged to triple global renewable energy capacity by 2030 (UNFCCC, 2023). This collective commitment opened a new chapter in the global response to climate change, exerting a profound influence on green-energy strategies worldwide. By 2024, the International Renewable Energy Agency (2025) reported

that annual additions of renewable power capacity reached 585 GW, bringing cumulative global capacity to 4,448 GW, of which solar PV comprised approximately 1,865 GW, the largest share of any renewable technology. Despite renewable sources accounting for 92.5 percent of total capacity growth that year, accelerated development is still required to meet the COP28 goal of 11 TW by 2030 (IRENA, 2025).

As solar PV installations proliferate, attention to their ecological impacts and social benefits has intensified. Empirical studies indicate that large and centralized PV farms can alter local microclimate, surface albedo and soil properties, potentially disrupting biodiversity (e.g. Hernandez et al., 2014; Liu et al., 2023; Tawalbeh et al., 2021; Walston et al., 2016; Wu & Chen, 2017). Conversely, other research highlights positive outcomes, such as enhanced vegetation recovery and synergies with pastoral or agricultural practices (e.g. Bošnjaković et al., 2024; Hernandez et al., 2014; Jarčuška et al., 2024; Reutter & Lehmann, 2024). For example, in China's Qinghai and Inner Mongolia regions, PV installations have been integrated with anti-desertification measures and ecological restoration projects, demonstrating a positive effect of solar PV development on desert regions and fostering co-development alongside animal husbandry and farming (e.g. Tian et al., 2024; Wu et al., 2024; Zhao, 2016).

Policy frameworks are also beginning to reflect these dual dimensions. China's 14th Five-Year Plan for Renewable Energy Development (NDRC, 2021) explicitly calls for leveraging both environmental and ecological governance benefits of renewables to achieve mutually reinforcing outcomes between energy utilization and environmental protection. China's environmental impact (and benefit) assessment for PV projects primarily adheres to the industry standard NB/T 32001–2012, Technical Specification for Environmental Impact Assessment of Photovoltaic Power Stations. This standard defines mandating coverage of ecological impacts (e.g., land-use changes, biodiversity), physical environment (noise, electromagnetic radiation), and some socio-economic effects. International organizations such as IRENA (e.g. IRENA, 2021, 2022), the International Union for Conservation of Nature (IUCN, e.g. Bennun et al., 2024; Fletcher et al., 2025; Jobson et al., 2024) have issued guidance and reports on renewable-agriculture integration and biodiversity enhancement, sparking growing scholarly and practitioner interest.

Despite this progress, substantial gaps remain in our mechanistic understanding of how solar PV projects influence ecosystems and communities. Much existing research focuses on isolated factors, such as microclimate shifts (e.g. Hernandez et al., 2014; Tawalbeh et al., 2021), soil dynamics (e.g. Liu et al., 2023), or vegetation and ecosystems (e.g. Wu & Chen, 2017), without a systematic, interdisciplinary perspective that encompasses both ecological and social dimensions. Moreover, persistent misconceptions among public opinions and stakeholders, ranging from undue health concerns to fears of biodiversity loss (Eisensohn et al., 2024), threaten to impede the accelerated deployment of solar PV required for a global low-carbon transition.

The objectives of this paper are to (1) examine the environmental impacts and benefits of utility-scale solar PV projects in non-humid regions through case studies, (2) identify key challenges and (3) propose recommendations for advancing comprehensive, evidence-based evaluation and restoration practices.

2 Environmental Impacts and Benefits of Solar PV Projects in the Non-Humid Areas

While long-term monitoring data on the environmental impacts and benefits of utility-scale solar PV projects remain limited, existing observations and analyses have begun to elucidate the mechanisms by which these installations influence their surrounding ecosystems. Notably, solar PV projects can affect various environmental factors, including microclimate, soil conditions, vegetation, and biodiversity. Studies have shown that solar panels can alter local microclimate by providing shade, which reduces soil temperature and evaporation rates, thereby increasing soil moisture and potentially benefiting plant growth. Additionally, the establishment of solar parks has been associated with “enhanced” biodiversity, as they can serve as refuges for various plant and animal species, creating a better micro-habitat than barren land, particularly when managed with native vegetation. The following section will delve into these aspects, focusing on the impacts and benefits of solar PV projects on microclimate, soil conditions, vegetation, and the biodiversity of both flora and fauna (Fig. 1).




Fig. 1. Framework of influence mechanism of solar PV project on the environment encompassing four factors, namely microclimate, soil condition, vegetation, and biodiversity, which a priori have impacts on each other.

The cases were drawn from projects within China. Data were obtained through site visits, developer-provided documentation, interviews, etc. By comparing installations in non-humid regions, primarily in China, current insights on the environmental impacts and benefits of solar PV plants are synthesized, and the challenges that lie ahead are highlighted.

2.1 Microclimate

Large-scale solar PV plants can alter local microclimates by modifying the surface energy balance, leading to changes in albedo, heat storage, and radiative fluxes (Alzahrani, 2025). Remote sensing analyses across 116 solar farms worldwide reveal an average decrease in surface albedo of 0.016 ± 0.009 and a mean daytime land-surface cooling of 0.49 ± 0.43 K (Zheng et al., 2024). In Qinghai, field measurements indicate that

the average surface temperatures inside the array lower than in surrounding degraded terrain. The disparity can be up to 1.4 degree Celsius during the night and 1 degree Celsius lower during the day, showing a “cooling effect” of the solar PV project on the surface temperature (Fig. 2).




Fig. 2. Comparison of average temperature inside (Ti) and outside (To) the solar PV station in Qinghai (Ti-To)_during night and daytime from 2021 to 2024 based on the data provided by the solar PV developer in Qinghai.

From the perspective of average daily temperature, different observations emerge from the Gonghe solar PV station. Monitoring data (May 2024 to April 2025) from interior and exterior sites of the station show that the daily mean air temperature inside the array exceeds that at the reference site (Fig. 3).

Solar PV arrays also increase surface roughness, leading to lower near-surface wind speeds within the array than in surrounding areas. Field measurements at a Qinghai PV station show that the diurnal wind-speed pattern remains stable year after year, with wind speeds inside the array running about 43% lower than outside at night and roughly 25% lower by day. Another example, one of the first solar PV and anti-desertification projects was commissioned in Dengkou County, Inner Mongolia, under China’s solar PV + Desert Control initiative. After installing PV panels alongside sand-stabilization measures, developers indicate that soil wind-erosion and active desertification were reduced by over 90%. During the peak windy season, airborne dust concentration measured at 1.5m above ground declined by 55–80%, while relative humidity increased by 2–9% (Fig. 4).




Fig. 3. Comparison (T) of the average daily temperature outside (To) and inside (Ti) the Gonghe solar PV station in Qinghai, May 2024 to April 2025.




Fig. 4. Influence mechanism of solar PV stations on microclimate. Solar PV panels firstly pose impacts on albedo, heat storage, radiative fluxes, surface roughness, vegetation, etc., and then influence microclimate consisting temperature, wind speed, humidity, evaporation, etc.

2.2 Soil Condition

Solar PV installations can substantially modify soil conditions through shading, wind-speed reduction, and organic-matter accumulation, with measurable benefits observed across diverse environments. Additionally, reduced wind speed around PV arrays minimizes soil erosion, while organic matter accumulation beneath panels enhances soil fertility over time.

For example, at the solar PV stations in Qinghai, field studies (2021 and 2024) reveal that, at multiple depths, soils within the PV fields consistently remained cooler than those in surrounding desert plots. In 2024, the soil temperature fluctuated more

greatly than in 2021. And the soil temperature difference between the two areas was greater in 2021 than in 2024. In the PV station in Daqing, surface-layer soil pH beneath panels has trended downward relative to control areas, while moisture increases during the growing season. At deeper horizons (5 cm, 20 cm, 40 cm), pH rises significantly under the panels, whereas inter-panel and off-site soils show the opposite trend. The PV array also elevates surface moisture but slightly depletes water at 20–40 cm depths. In fragile karst desert area of Yunnan, PV installations plus ecological restoration measures produce pronounced soil cooling (20–27% lower temperatures at 0–20 cm depth) and humidity gains (8–30% higher relative humidity) compared to outside the arrays. The combined “PV + marigold restoration” model has enriched soil organic carbon by 23–64% and increased soil N, P, and K stocks, underscoring the synergistic potential of PV stations and targeted re-vegetation.

2.3 Vegetation

PV arrays can accelerate vegetation recovery in fragile ecosystems by modifying local microclimate and soil conditions. In Qinghai’s solar PV station, where overgrazing once drove desertification rates above 80% and precipitated rampant sandstorms, initial biomass measurements beneath newly erected PV panels were lower than in inter-panel and off-site areas due to construction disturbance. However, the shaded, wind-sheltered microhabitats they created supported accelerated regrowth, so that after seven to eight years, biomass under the panels exceeded that of zones in-between (Fig. 5).



Fig. 5. Comparison between the vegetation before the installation in 2013 and after the deployment of the solar PV station in August, 2024, Qinghai.

The PV + desert-control project in Dengkou County of Inner Mongolia has achieved dramatic gains in vegetation cover. In the first and second phases, over 2,400 acres of barren dunes were stabilized using crested wheat grass (*Agropyron cristatum*) as the primary species, boosting live-cover from roughly 8% to more than 77%. During phases three and four, an additional 5,600 acres were revegetated with other two types of plants, raising cover on formerly bare sand from about 2% to 55%.

2.4 Biodiversity Impacts

Solar PV installations may exert both positive and negative effects on local fauna and flora. For animals, well-designed PV farms may establish ecological corridors and novel habitats. In France, for instance, developers have created wetland features within and around solar sites to support amphibians and invertebrates, and engineered microhabitats that bolster reptile and small-mammal populations (Jobson et al., 2024). However, land conversion for large-scale PV deployment may also threaten endemic species in biodiversity hotspots. Bird and bat collisions with panel surfaces, especially along migratory corridors, remain a serious concern; glare-induced disorientation has been linked to elevated avian mortality in California (Walston et al., 2016). In our Chinese case studies, systematic wildlife surveys are largely absent; anecdotal reports and photographs suggest that certain bird species have begun nesting within panel arrays, behavior not previously observed in these areas.

Regarding vegetation, PV installations can ameliorate harsh conditions on degraded lands by shading the soil, thereby reducing surface temperatures and evaporation, and facilitating plant establishment and ecosystem restoration. In Qinghai Province, biodiversity indices recorded outside the PV field (0.83), between panels (0.61–1.18), and beneath panels (0.52–1.14) all increased over time, with the steepest rise beneath the arrays. Species richness likewise climbed from 3.00 outside the site to 3.00–4.67 between panels and 3.00–5.00 beneath them, indicating that plant diversity within the PV field meets or exceeds that of adjacent areas. In Inner Mongolia, deliberate planting of drought-tolerant shrubs such as *Haloxylon ammodendron* between and under panels expanded the species count from 2 pre-installation to 43 post-installation. Plant cover, height, density, and biomass all increased significantly in these combined PV–sand-control zones, raising the comprehensive vegetation diversity index from 35.68 for native communities to 55.12 within the PV station.

3 Challenges Ahead

Although attention to the environmental impacts and benefits of utility-scale solar PV projects in non-humid regions is growing, significant challenges remain. Addressing these will require not only technological advances but also coordinated social and political action to minimize adverse effects and maximize positive outcomes, lest well-intentioned initiatives inadvertently introduce new harms.

Firstly, environmental impact and benefit assessment with elements such as biodiversity and land degradation has not yet been comprehensively integrated into policy frameworks. Many nations conduct environmental impact (and benefit) assessments for renewable-energy projects, yet these evaluations are not uniformly embedded within national policy and regulatory systems, particularly in rapidly developing regions seeking to expand energy access. For example, a 2023 Indian government framework (SECI, 2018) notes that “solar and wind projects in India do not require a regulatory environmental clearance.” Although the framework admits large projects will have environmental impacts (on forests, wetlands, soil, etc.), the fact that formal EIA is not mandated highlights a policy gap. In South Africa, the environment minister proposed excluding certain solar PV farms from any EIA requirement if they fall in “low/medium” sensitivity areas

(*Biodiversity Law Centre*, 2022). This move was criticized as risking harm to local ecosystems, as the exemption “may expedite the rollout of renewable energy projects to the potential detriment of indigenous species and ecosystems” and it removes public participation from the process.

Secondly, systematic long-term monitoring remain largely undeveloped. Although solar PV expansion has accelerated only in recent decades, few projects have incorporated long-term build-in monitoring of both environmental and social impacts and benefits. Moreover, as PV installations multiply, their cumulative and potentially inter-dependent impacts complicate isolated assessments. To offset the financial and logistical burdens on private developers, stakeholders especially governments should foster public-private partnerships and involve local stakeholders in cost-sharing and data-collection efforts.

Thirdly, coherent metrics and standards for sustainably-developed solar PV projects including environmental impact and benefit assessment are urgently needed. At present, there is no unified framework to guide integrate monitoring throughout the full life cycle of a solar PV station from siting and design through operation to decommissioning and recycling. Solar PV projects worldwide have been adapted to local conditions with adjustments made to panel heights, inter-panel spacing, orientation, etc.. While such localization enhances site-specific functionality, it has simultaneously complicated efforts to standardize impact-benefit assessments. Furthermore, diverse monitoring methodologies and standards coexist in practice, complicating global case comparisons. Given the increasing complexity of interactions among climate change, land degradation, and biodiversity dynamics, a multidisciplinary discussion and consensus of monitoring frameworks is urgently needed. International bodies, in collaboration with academic and industry experts, can develop a set of guidelines and performance indicators for environmental impact and benefit assessments, thereby enabling more coherent, cross-regional analyses.

4 Conclusion and Recommendations

4.1 Conclusion and Discussion

Through an analysis of the environmental impacts, benefits, and future challenges of utility-scale solar PV projects in non-humid regions, it is found that these installations exert multifaceted influences on ecological, biological, and social systems that merit far greater attention and investment. Current policymaking frameworks often treat negative and positive environmental effects in isolation rather than as an integrated whole, leading to gaps in both assessment and management. Empirical observations to date reveal that solar PV farms can deliver beneficial outcomes for microclimate regulation, soil stabilization, vegetation cover, and local biodiversity - particularly when targeted mitigation measures (e.g., under-panel planting, runoff management) are adopted.

Nonetheless, our review highlights an urgent need for sustained, long-term monitoring and deeper scientific inquiry into the mechanisms by which clustered PV arrays cumulatively affect microhabitats, regional climate patterns, and ecosystem services. Key challenges include embedding comprehensive impact-benefit assessments into renewable-energy policy at both national and international levels, instituting mandatory

environmental safeguards to ensure that PV developments do not exacerbate ecosystem degradation under ongoing climate change, and developing standardized, globally comparable metrics and protocols for monitoring environmental impacts and benefits across diverse project sites.

Defining the environmental impacts and benefits of solar photovoltaic (PV) projects remains a complex task due to the limited availability of long-term monitoring data. While preliminary observations suggest that these installations can create favorable conditions for vegetation and wildlife in the non-humid regions, comprehensive assessments are necessary to fully understand their ecological implications. In the cases mentioned above, the installation of solar PV panels on barren land has been associated with improved conditions for plant growth, potentially mitigating land degradation and reducing soil erosion. The shade provided by the panels can lower surface temperatures and evaporation rates, leading to increased soil moisture and enhanced vegetation cover. However, these benefits may be accompanied by unintended consequences. Tall-growing plants beneath the panels (especially those low mounted panels) can cast shadows that reduce the efficiency of solar energy generation. Moreover, the proliferation of dominant plant species might suppress the growth of other flora, thereby altering the microhabitat and potentially diminishing biodiversity. In addition, integrating solar PV power generation with agriculture and livestock (Fig. 6) grazing can place additional stress on local biodiversity and land governance, underscoring the need for more adaptive, nuanced land-use management strategies such as site-specific planning to balance ecological trade-offs.



Fig. 6. Dual land use of solar PV and pasture in Qinghai (left) and Yunnan (right), exemplifying agrovoltaic land-use strategies. In Qinghai, a managed grazing initiative termed "photovoltaic sheep" integrates livestock rearing within solar PV installations. This approach leverages the inter-row spaces of solar arrays to provide accessible pastureland, while simultaneously enabling efficient land management and resource utilization for local shepherds. In Yunnan, a PV + remediation project combines renewable energy generation with ecological restoration and agricultural productivity, integrating herb cultivation, livestock husbandry, and anti-desertification measures alongside solar energy production, diversifying income for local communities.

Studies have indicated that solar farms can significantly influence microclimatic conditions, which in turn affect plant and animal communities. For example, studies have shown that areas under solar panels often exhibit lower temperatures and higher

humidity levels, creating microhabitats that differ from the surrounding environment. These changes can lead to shifts in species composition and diversity, with some species thriving while others declining. Additionally, the alteration of natural habitats and the introduction of new structures can impact wildlife behavior and movement patterns, further influencing ecosystem dynamics.

In addition, some important dimensions, specifically animal biodiversity and the social impacts and benefits experienced by local communities, remain under-examined in solar PV impact-benefit studies. In China, dual-use models that pair PV installations with sand-control and land-restoration efforts have focused mostly on vegetation and soil stabilization, sometimes neglecting the fauna that inhabit and across these landscapes. Furthermore, strict rules preventing development within designated biodiversity red lines could have unintentionally diverted attention from such research, as most of the development areas are not biological sensitive ones. Finally, the social outcomes for local communities, especially under “solar PV +” schemes that integrate energy production with agriculture or other local livelihoods, likewise demand far more systematic and rigorous evaluation.

4.2 Recommendations

To strengthen both understanding and practice, the following actions are proposed: Firstly, it is important to elevate public awareness of biodiversity conservation and desertification mitigation, mainstreaming environmental impact and benefit assessment in the policy framework for sustainable development. The interlinked crises of climate change, desertification, and biodiversity loss must be communicated as a unified challenge, as addressing one in isolation risks compromising progress on the others. Public outreach and education should highlight the interconnectedness and complexity of these issues and their potential impacts on ecosystem services and human well-being, underscoring the importance of comprehensive assessment and solutions. A well-informed public is more likely to support policy frameworks that require thorough, transparent, and science-based evaluations of environmental impacts as well as social and economic influences of solar PV projects and other renewables. From a policy perspective, governments should codify mandatory, transparent assessment of both environmental impacts and benefits within renewable-energy legislation and regulations. While voluntary monitoring by project developers is a useful first step, only legally binding requirements will ensure consistent governance and data collection. Policymakers must regularly review and refine the assessment criteria, expanding beyond purely biophysical indicators to include social dimensions such as energy access, community participation, and gender inclusiveness, to prevent the uneven distribution of renewable-energy advantages and burdens.

Secondly, it is vital to deploy robust, long-term monitoring networks for further research of the impact-benefit assessment of solar PV projects. Systematic in-situ monitoring infrastructure is needed to track solar PV impacts and benefits over multi-decadal timescales around the globe, taking the practical complexities into consideration. Factors and metrics should be incorporated such as microclimatic and soil sensors beneath and around PV arrays, standardized protocols for surveying flora and fauna, including endangered species, and indicators of land degradation and desertification dynamics

in adjacent habitats. Only by integrating and examining effects on carbon emissions, desertification trends, and biodiversity responses, advancing a understanding of their ecological and social functions, can PV projects and other renewables be validated as truly “sustainable” from a holistic, system-level perspective.

Last but not the least, it is essential to integrate comprehensive research, inclusive stakeholder engagement and adaptive management practices throughout the project life-cycle, to amplify the positive environmental, social and economic benefits of solar PV stations while minimizing potential drawbacks. Conducting additional research and pilot projects can provide valuable insights into mitigating negative impacts and enhancing positive outcomes. Engaging both local communities and national authorities from the planning stages through to decommissioning helps ensure that projects, from project design to end-of-life processes, align with local needs and values, enhancing long-term sustainability. Implementing adaptive management practices allows for the timely adjustment of operations and maintenance in response to environmental and social feedback, ensuring sustained benefits over time. Furthermore, documenting and disseminating experiences and best practices from existing projects can provide valuable lessons for future developments, facilitating the replication of successful strategies and the avoidance of past mistakes. By integrating these approaches, solar PV projects may achieve a balance between energy production and ecological preservation, delivering tangible benefits to local communities and contributing to sustainable development goals.

References

- Alzahrani, A.S.: A review: the potential impact of large-scale solar farms (LSSFs) on the water cycle. *J. Umm Al-Qura Univ. Eng. Arch.* **16**(1), 206–223 (2025). <https://doi.org/10.1007/s43995-025-00102-7>
- Bennun, L., et al.: Guidance on biodiversity cumulative impact assessment for wind and solar developments and associated infrastructure. IUCN (2024). <https://doi.org/10.2305/EHGE6100>
- Biodiversity Law Centre: Law for nature, 6 October 2022. Biodiversity Law Centre. <https://biodiversitylaw.org>
- Bošnjaković, M., Santa, R., Crnac, Z., Bošnjaković, T.: Environmental impact of PV power systems. ResearchGate (2024). <https://doi.org/10.3390/su151511888>
- Eisensohn, M., Elkin, J., Fitch, A., Ard, M., Sittinger, K., Lavine, S.: Rebutting 33 False Claims About Solar, Wind, and Electric Vehicles. Sabin Center for Climate Change Law (2024). https://scholarship.law.columbia.edu/sabin_climate_change/217
- Fletcher, C., et al.: Biodiversity and responsible sourcing for wind and solar developments. IUCN (2025). <https://portals.iucn.org/library/node/52167>
- Hernandez, R.R., et al.: Environmental impacts of utility-scale solar energy. *Renew. Sustain. Energy Rev.* **29**, 766–779 (2014). <https://doi.org/10.1016/j.rser.2013.08.041>
- IRENA: Renewable Energy for Agri-food Systems: Towards the Sustainable Development Goals and the Paris Agreement (2021). <https://www.irena.org/Publications/2021/Nov/Renewable-Energy-for-Agri-food-Systems>
- IRENA: Renewable energy for agriculture Insights from Southeast Asia (2022). <https://www.irena.org/Publications/2022/Jun/Renewable-energy-for-agriculture-Insights-from-Southeast-Asia>
- IRENA: Renewable capacity statistics 2025 (2025). <https://www.irena.org/Publications/2025/Mar/Renewable-capacity-statistics-2025>
- Jarčuška, B., et al.: Solar parks can enhance bird diversity in agricultural landscape. *J. Environ. Manage.* **351**, 119902 (2024). <https://doi.org/10.1016/j.jenvman.2023.119902>

- Zheng, J., Li, Y., Qin, Y., Bach, E.: A global assessment of the effects of solar farms on albedo, vegetation, and land surface temperature using remote sensing. *Sol. Energy* (2024). <https://doi.org/10.1016/j.solener.2023.112198>
- Jobson, B., et al.: Opportunities for enhancing biodiversity at wind and solar energy developments. IUCN (2024). <https://portals.iucn.org/library/node/52144>
- Liu, H., et al.: Effect of Solar Farms on Soil Erosion in Hilly Environments: A Modeling Study from the Perspective of Hydrological Connectivity. *Water Resour. Res.* **59**(12), e2023WR035067 (2023). <https://doi.org/10.1029/2023WR035067>
- NDRC: Notice of National Development and Reform Commission on "14th five-year" plan of renewable energy development (2021). https://www.ndrc.gov.cn/xwdt/tzgg/202206/t20220601_1326720.html?code=%26state=123
- Reutter, F., Lehmann, P.: Environmental trade-offs of (de)centralized renewable electricity systems. *Ener. Sustain. Soc.* **14**(1), 37 (2024). <https://doi.org/10.1186/s13705-024-00462-3>
- SECI: Final Environmental and Social Management Framework. Solar Energy Corporation of India Limited, October 2018. https://www.seci.co.in/web-data/docs/ESMF_final.pdf#:~:text=While%2C%20solar%20and%20wind%20projects,on%20natural%20resources%2C%20forests%2C%20habitats
- Tawalbeh, M., Al-Othman, A., Kafiah, F., Abdelsalam, E., Almomani, F., Alkasrawi, M.: Environmental impacts of solar photovoltaic systems: a critical review of recent progress and future outlook. *Sci. Total. Environ.* **759**, 143528 (2021). <https://doi.org/10.1016/j.scitotenv.2020.143528>
- Tian, Z., Yong, Z.H.A.N.G., Xiang, L.I.U., Sheng-yun, C.H.E.N., Ben-li, L.I.U., Ji-hua, W.U.: Effects of photovoltaic power station construction on terrestrial environment: retrospect and prospect. *Environ. Sci.* **45**(1), 239–247 (2024)
- UNFCCC: Outcomes of the Dubai Climate Change Conference—Advance Unedited Versions (AUVs) and list of submissions from the sessions in Dubai | UNFCCC (2023). <https://unfccc.int/cop28/outcomes>
- Walston, L.J., Rollins, K.E., LaGory, K.E., Smith, K.P., Meyers, S.A.: A preliminary assessment of avian mortality at utility-scale solar energy facilities in the United States. *Renew. Ener.* **92**, 405–414 (2016). <https://doi.org/10.1016/j.renene.2016.02.041>
- Wu, W., et al.: Assessment of the ecological and environmental effects of large-scale photovoltaic development in desert areas. *Sci. Rep.* **14**(1), 22456 (2024). <https://doi.org/10.1038/s41598-024-72860-8>
- Wu, X.D., Chen, G.Q.: Energy and water nexus in power generation: the surprisingly high amount of industrial water use induced by solar power infrastructure in China. *Appl. Ener.* **195**(C), 125–136 (2017)
- Zhao, P.Y.: Effect of photovoltaic panels on the surface of soil particles and microclimate-taking Dengkou photovoltaic power station as an example [Master's thesis]. Inner Mongolia Agricultural University (2016)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Characteristic Identification of Short-Term Heavy Rainfall in Plateau Mountainous Areas

Qianwen Wu¹, Leilei Qin², Jun Liu¹, and Yu Zhang³(✉)

¹ Liangshan Yi Autonomous Prefecture Meteorological Bureau, Xichang 615000, Sichuan, China

² China Three Gorges Construction Engineering (Group) Co., Ltd, Chengdu 610000, Sichuan, China

³ Nanjing Hydraulic Research Institute, Nanjing 210029, Jiangsu, China
yuzhang@nhri.cn

Abstract. In surface engineering construction, short-term heavy rainfall has the greatest impact on both construction activities and the defense against severe weather hazards. This study utilizes upper-air and surface meteorological data from the Baihetan Hydropower Station spanning 2012 to 2022 to analyze and investigate the circulation backgrounds and physical characteristic parameters of four types of short-term heavy rainfall events: baroclinic frontogenesis, upper-level cold advection forcing, lower-level warm advection forcing, and quasi-baroclinic types. The aim is to understand the climatic characteristics of plateau regions, provide a scientific basis for future forecasting and early warning systems, and ultimately enhance the forecasting capability of short-term heavy rainfall in these areas.

Keywords: Short-term heavy rainfall · Baroclinic frontogenesis · Upper-level cold advection forcing · Lower-level warm advection forcing · Quasi-baroclinic

1 Introduction

The physical processes leading to short-term heavy rainfall differ from those that produce general rainstorms, primarily due to the dynamic and thermodynamic effects of the underlying surface. Short-term heavy rainfall generally develops under the influence of large-scale weather systems, which govern the formation, evolution, and movement of mesoscale and small-scale systems. This study focuses on analyzing the characteristics of short-term heavy precipitation events at the Baihetan Hydropower Station.

Also referred to as short-duration intense precipitation, short-term heavy rainfall mainly describes convective rainfall events characterized by brief duration and high rainfall efficiency, typically with hourly precipitation reaching or exceeding 20 mm. Events with 1-h rainfall ≥ 80 mm or 3-h rainfall ≥ 180 mm are further classified as extreme short-term heavy rainfall. In plateau regions with high mountains and deep valleys, the intense rainfall in a short period often leads to flash floods and can trigger natural hazards such as landslides and debris flows. Frequent short-term heavy rainfall events pose

significant safety risks to large-scale infrastructure projects such as hydropower stations. Excessive rainfall intensity complicates dam concrete pouring operations and may result in waste and considerable economic losses. Furthermore, the extensive surface disturbance caused by excavation and blasting during hydropower construction heightens the likelihood of flash floods, debris flows, slope collapses, and landslides during extreme rainfall events, potentially leading to casualties.

2 Environmental Conditions for Short-Term Heavy Rainfall

From a meteorological perspective, the formation of short-term heavy rainfall is closely associated with high precipitation efficiency. Precipitation occurs when low-level moisture is lifted and condenses. At a given location, the instantaneous precipitation rate RR is proportional to the vertical moisture flux wq , where w is the vertical velocity of the updraft at the cloud base, and q is the specific humidity of the rising air. In other words, to achieve a high precipitation rate, the cloud base must contain high moisture content and strong upward motion. Another critical factor is the proportion of lifted moisture that actually condenses and falls to the ground, referred to as the effective condensation rate EE .

This relationship can be expressed as:

$$R = Ewq \quad (2.1)$$

Through summary and analysis, it has been found that short-term heavy rainfall events with hourly rainfall exceeding 20 mm are closely related to the occurrence of deep moist convection. In practice, the environments that are conducive to intense convective precipitation generally fall into two categories: (1) High dew point values in the lower layers, high relative humidity throughout the vertical profile, and a temperature lapse rate close to but slightly greater than the moist adiabatic lapse rate. The CAPE profile typically appears narrow and elongated. Such atmospheric conditions are favorable for short-term heavy rainfall, usually without accompanying hail or thunderstorm winds. (2) High dew point values near the surface, and a highly humid layer extending from the ground up to at least 1.5 km, with a dry layer above. This type often coincides with hail or thunderstorm wind events.

3 Formation Mechanism of Short-Term Heavy Rainfall

When an updraft carries an air parcel to the top of a convective cloud, most of the water vapor entering the cloud condenses. However, not all condensed vapor reaches the ground as precipitation. Some cloud particles are carried away by upper-level winds and evaporate outside the cloud, while others evaporate within descending airflows in the precipitation system. Only a small fraction reaches the ground as measurable rainfall. Statistically, moderate levels of Convective Available Potential Energy (CAPE) are more conducive to high precipitation efficiency than extreme levels of CAPE. Extremely high CAPE tends to accelerate air parcels through the warm cloud layer, reducing the time available for moisture accumulation and retention. Another factor that influences

precipitation efficiency is the entrainment rate. The introduction of unsaturated dry air into the cloud enhances evaporation of cloud droplets, lowers the relative humidity of the surrounding air, and increases evaporative cooling, thereby reducing the overall efficiency of precipitation.

4 Analysis of Short-Term Heavy Rainfall Characteristics at the Baihetan Hydropower Station

According to the Fundamental Principles and Technical Methods of Short-Term Heavy Rainfall Forecasting—China Short-Term Heavy Rainfall Forecast Manual compiled by Sun Jisong and other experts, there are five basic synoptic configurations of short-term heavy rainfall in China: (1) baroclinic frontogenesis type, (2) upper-level cold advection forcing type, (3) lower-level warm advection forcing type, (4) quasi-baroclinic type, and (5) elevated thunderstorm type. Based on these five classification criteria, this study reviewed and categorized 29 short-term heavy rainfall events that occurred at the Baihetan Hydropower Station between 2012 and 2022. The results show that the baroclinic frontogenesis type occurred most frequently, accounting for 12 cases (41.4%). This was followed by the upper-level cold advection forcing type with 7 cases (24.1%), while both the lower-level warm advection forcing and quasi-baroclinic types had 5 cases each (17.2%). No elevated thunderstorm type events were observed. In this section, we focus on a detailed analysis of the four dominant types: baroclinic frontogenesis, upper-level cold advection forcing, lower-level warm advection forcing, and quasi-baroclinic types.

4.1 Baroclinic Frontogenesis Type

A review of historical cases reveals the following common synoptic background features associated with baroclinic frontogenesis-type short-term heavy rainfall: (1) The peak hourly rainfall intensity typically ranges between 20–40 mm, with a maximum recorded value of 32.3 mm (e.g., 09:00 on September 8, 2019, at Huangtian Water Plant); (2) At the 200 hPa level, most cases are situated in the divergence zone on the east or southeast side of a subtropical high ridge, with a few located directly under the divergence center or within shear zones. The upper-level divergence plays a critical role in enhancing convective updrafts through its “suction effect.”; (3) At the 500 hPa level, an eastward-moving plateau trough typically exerts influence, often accompanied by cold advection on the rear side of the trough. At the 700 hPa level, the area is commonly affected by southwesterly low-level airflow or a low-level jet, along with the southward extension of shear zones from the Sichuan Basin, creating favorable conditions for the convergence of cold and warm air masses, leading to baroclinic frontogenesis; (4) Surface charts often show the presence of thermal low-pressure systems, convergence lines, or stationary frontal cloud bands, which promote low-level moisture convergence, enhance vertical uplift, and trigger the onset of convective weather systems.

As shown in Table 1, baroclinic frontogenesis-type short-term heavy rainfall exhibits several distinct common features in terms of physical parameters.(1)The Stability Index (SI) at Xichang or Weining stations is generally close to or below 0.0°C , with most values around -1.0°C and the minimum reaching -3.69°C (e.g., at 01:00 on June 30, 2020, at Huangtian Water Plant). A lower SI indicates a more unstable atmospheric stratification.(2)The Convective Available Potential Energy (CAPE) values are generally around 1000 J/kg , which supports the development of moderately strong or stronger convective cells. The Convective Inhibition (CIN) values are typically below 100 J/kg , which only slightly hinders the initiation of small convective cells. Additionally, vertical wind shear in the mid-to-lower levels is relatively weak, allowing for some accumulation of unstable energy.(3)The atmospheric stratification structure is mostly characterized by “dry above and moist below” or an “hourglass-shaped” profile. The intrusion of dry air in the mid-levels can intensify the severity of convective systems.

On September 8, 2019, around 09:00, a short-duration heavy rainfall event occurred in the dam area of the Baihetan Hydropower Station (see Fig. 1). The event developed rapidly, with high hourly rainfall intensity, short duration, and uneven spatial distribution of precipitation. It was accompanied by strong winds before and after the rainfall, with the maximum wind speed reaching 21.2 m/s (recorded at 08:44 on September 8, 2019, at Platform 834 on the right bank).From the synoptic background analysis:At 200 hPa , the eastern Tibetan Plateau was under the influence of a subtropical high-pressure center, with the dam area located in the divergent zone on the eastern side of this high. The upper-level divergence provided a strong “suction effect” that favored the development of intense convective systems.At 500 hPa , a low trough over the western Sichuan Plateau was moving eastward.Around 08:00 on the 8th, the dam area was situated at the base of the trough. The passage of the trough caused wind convergence in both direction and speed, facilitating the intersection of cold and warm advection in the mid-troposphere, which created favorable conditions for convective cell development.At 700 hPa , a southwestern vortex over the Sichuan Basin was established and intensified. A consistent southwesterly warm-moist airflow extended from most of Yunnan to the southern Sichuan Basin. Water vapor transported from the Bay of Bengal was continuously funneled into the southwestern vortex. In the vicinity of the dam area, the northerly airflow on the western flank of the vortex converged with the southwesterly moist airflow from Yunnan, forming a shear zone that gradually intensified and shifted southward.On the surface chart, a distinct low-pressure zone was present to the south of the dam area, while a steeper pressure gradient existed to the north, promoting low-level moisture convergence and upward motion, thereby enhancing vertical lifting.

Figure 2a shows the upper-air sounding profile over Xichang Station at 20:00 on September 7, 2019. The Convective Available Potential Energy (CAPE) was 1820.1 J/kg , Convective Inhibition (CIN) was 58.4 J/kg , Stability Index (SI) was -2.1°C , and the Bulk Richardson Number Lifted Index (BLI) was -3.4°C . The relative humidity between $400\text{--}700\text{ hPa}$ exceeded 80% , indicating abundant instability energy from 500 hPa to the surface. The stratification structure exhibited a “top-bottom hourglass” profile, and significant vertical wind shear was observed near $600\text{--}700\text{ hPa}$, all of which were favorable for convective weather development.Fig. 2b presents the upper-air sounding at 08:00 on September 8. The CAPE had decreased to 1227.0 J/kg , CIN to 48.6 J/kg , SI rose to

Table 1. Case Statistics of Baroclinic Frontogenesis-Type Short-Term Heavy Rainfall

Station	Time	Precipitation (mm)	SI Index	CAPE	DCAPE	CIN	BLI	LI	Hwet	Hwarm	T75	Vertical Wind Shear	Stratification Structure	Convective Trigger Mechanism
Xintian	2012/6/28 6:00	23.3	Xichang-0.94	2203.1	0	39.7	-4.1	-4.17	4978	3290.794	Xichang 16	Weak in mid-lower	Dry above, moist below	Baroclinic frontogenesis
Mabozi	2014/7/7 1:00	24.1	Weining-1.41	656.6	2.2	16.6	-1.8	-1.79	4821.1	3206.785	Weining 15	Weak in mid-lower	Dry above, moist below	Baroclinic frontogenesis
Mabozi	2014/8/10 9:00	20.2	Weining0.76	1586.9	884.3	70.9	-2.8	-2.74	2598.3	3018.177	Xichang 16	Weak in mid-lower	Hounglass-shaped	Baroclinic frontogenesis
Xintian	2015/7/22 16:00	21.2	Weining-2.59	1099.7	96.1	12.7	-2.3	-2.33	4691.4	3406.711	Weining 17	Lower-level	Dry above, moist below	Baroclinic frontogenesis
Mabozi	2015/8/25 1:00	30.1	Xichang-2.59	1320.6	8.1	66	-3.6	-3.68	4407.2	2879.461	Xichang 17	Lower-level	Dry above, moist below	Baroclinic frontogenesis
Mabozi	2016/5/21 17:00	20.1	Weining-1.85	22.7	670.6	0	-1.7	-1.27	3772.9	167.892	Weining 16	Weak at low level	Moist layer in mid-lower	Baroclinic frontogenesis (Mengwan storm involved)
Mabozi	2016/8/1 6:00	23	Xichang-0.6	1444.9	12.3	36	-3.3	-3.33	2637.5	2327.65	Weining 17	Weak at low level	Moist layer in mid-lower	Baroclinic frontogenesis
Mabozi	2016/9/9 6:00	22.5	Xichang 0.05	161.6	35.5	38.3	-0.5	-0.5	4745.2	3534.065	Weining 15	Weak at low level	Dry above, moist below	Baroclinic frontogenesis
Xintian	2017/7/14 20:00	21	Xichang 0.57	1761	893.1	85.8	-4.5	-4.41	236.6	2263.778	Xichang 18	NE wind in mid-lower	Moist-dry convergence zone	Baroclinic frontogenesis
Huangtian Plant	2019/9/8 9:00	32.3	Xichang-2.1	1820.1	0.3	58.4	-3.4	-3.36	4127.7	2918.681	Xichang 16	At 700 hPa	Hounglass-shaped	Baroclinic frontogenesis
Huangtian Plant	2020/6/30 1:00	23.8	Xichang-3.69	2171.2	0.2	71.9	-4.6	-4.57	3881.9	2806.771	Xichang 18	Near surface	Hounglass-shaped	Baroclinic frontogenesis
Xintian	2022/7/23 3:00	21	Xichang-1.56	2131.8	0	0	-4.3	-4.21	5529.4	3177.206	Weining 16	Vertical shear near surface	Moist layer in mid-lower	Baroclinic frontogenesis




Fig. 1. Circulation Background at 08:00 on September 8, 2019

0.06 °C, and BLI was -0.9°C . Although the values of various physical parameters had slightly decreased during the early stage of the short-term heavy rainfall, indicating partial release of unstable energy, the moist layer had thickened—extending from 850 hPa up to 300 hPa. The unstable energy layer also extended upward to around 400 hPa. Additionally, upper-level winds had turned into consistent northerly flows, indicating that the influencing system had already shifted southward to the vicinity of the dam area. This marked the mature phase of convective development, characterized by strong winds, short-term heavy rainfall, and lightning, during which thermal and moisture energy was effectively released.

4.2 Upper-Level Cold Advection Forcing Type

This is the second most common short-duration heavy rainfall pattern in Southwest China, following the baroclinic frontogenesis type. The upper-level cold advection forcing type is mainly characterized by baroclinicity caused by differential temperature advection between the upper and lower layers, and its convective triggering mechanism typically involves low-level shear convergence lines. Its primary features include: in the early stages, northerly or northwesterly dry and cold air in the mid-to-upper troposphere descends along shortwave troughs, subsequently affecting the Southwest region. On the




Fig. 2. Temperature-Log Pressure Diagram from September 7 to 8, 2019

surface chart, the area is often initially controlled by southerly flow at the rear of a low or high pressure system, maintaining fair weather. Near-surface radiative warming also contributes to the instability. Over the plateau, strong convection generally develops near the 700 hPa level or surface convergence lines. Meanwhile, strong cold air intrusions from the north can press southward, intensifying surface-level convergence.

From 2012 to 2022, the Baihetan Hydropower Station dam area experienced seven upper-level cold advection forcing short-term heavy rainfall events (see Table 2). This type typically produces relatively intense hourly rainfall rates, with the maximum reaching 46.6 mm (recorded at Mabozhi at 00:00 on September 10, 2017). In the early stages of such events, strong winds, lightning, and other convective phenomena are commonly observed.

The circulation background features of this type include: (1) At 200 hPa, the region is mostly located on the eastern or southeastern divergent zone of the subtropical high, or in the right exit region of an upper-level jet stream, both of which enhance upper-level divergence and promote convective ascent. (2) At 500 hPa, an eastward-moving plateau trough dominates, often accompanied by pronounced cold advection in its wake, with generally strong cold advection intensity. (3) At 700 hPa, shear lines in the Sichuan Basin shift southward, and cold advection on the rear side of the shear is also generally strong. (4) On the surface chart, a cold front often presses southward into northern Sichuan, resulting in an enhanced pressure gradient ahead of it. The dam area is frequently under the influence of thermal lows, where convergence between northerly cold air and southerly warm air forms a convergence line. The baroclinicity caused by upper-lower temperature gradients serves as a key triggering mechanism for short-duration heavy rainfall.

Characteristics of Physical Parameters:(1)The Showalter Index (SI) at Xichang Station or Weining Station generally hovers around or below 0.0°C , with most values near -1.0°C , and a minimum value reaching -4.58°C (observed at Xintian on August 13, 2021, at 10:00). A lower SI indicates more unstable stratification.(2)The moist layer thickness (Hwet) is relatively large, generally exceeding 3000 m, with a maximum reaching 10,300.9 m. The moist layer is mainly concentrated below 500 hPa, and the stratification structure is clearly characterized by “dry aloft and moist below” conditions.(3)There is strong vertical wind shear in the mid-to-lower or near-surface layers, which favors the development of convective cells. The temperature difference between 500 hPa and 700 hPa exceeds 16°C , indicating a significant “cold aloft and warm below” thermal structure. This large vertical temperature gradient enhances baroclinicity, and when combined with surface convergence lines, strongly triggers the development of convective systems.

On September 10, 2017, around 4:00 AM, a short-duration heavy rainfall event occurred in the Baihetan Hydropower Station dam area (Fig. 3). The event developed rapidly, featured uneven rainfall distribution, intense hourly precipitation, and short duration. The maximum hourly rainfall reached 46.6 mm (recorded at Maboz at 04:00). Before the onset of rainfall, strong convective weather, such as gusty winds and lightning, was observed. The maximum wind speed reached 21.6 m/s (recorded at the Huluhiao Bridge at 03:25).From the synoptic background analysis:At 200 hPa, most of Sichuan in the eastern Tibetan Plateau was dominated by a westerly jet stream. The dam area was located on the right side of the jet exit region, where upper-level divergence was enhanced, favoring the intensification of vertical upward motion.At 500 hPa, both the southward-sagging high and the subtropical high maintained stability. The dam area was mainly affected by the shear zone between the two highs, with strong cold advection pressing southward in the rear of the shear.At 700 hPa, a northeast–southwest oriented shear line prevailed over the Sichuan Basin. Behind the shear, strong northerly winds carried cold advection southward, enhancing the baroclinicity induced by temperature differential advection.On the surface weather map, a strengthening cold high in northern Sichuan was pressing southward, with strong negative temperature changes and positive pressure changes near its center. The dam area lay just at the frontal zone in front of the cold high, while the southern part was dominated by a strong thermal low. The upper and lower level cold advection forcing played a dominant role, intensifying baroclinicity between atmospheric layers. The increasing pressure gradient in the north and the presence of a surface convergence line near the dam area facilitated moisture convergence and upward motion, enhancing convective activity and triggering the occurrence of convective weather.

Figure 4 shows the sounding data over Xichang Station at 20:00 on September 9, 2017. Prior to the occurrence of convective weather, a clear “dry upper and moist lower” stratification structure was evident. The CAPE was 1742.1 J/kg, CIN was 69.1 J/kg, the Showalter Index (SI) was -0.94°C , and the BLI was -2.5°C . The moist layer was concentrated between 500–700 hPa, with abundant convective available potential energy below 500 hPa. There was weak vertical wind shear near the surface. The temperature difference between 500 hPa and 700 hPa reached 16°C , while the difference between 500 hPa and the surface reached 26°C , indicating a significant “cold upper and warm

Table 2. Statistical Table of Physical Parameters for Upper-Level Cold Advection Forcing Type

Station	Time	Precipitation (mm)	SI Index	CAPE	DCAPE	CIN	BLI	LI	Hwet	Hwarm	T75	Vertical Wind Shear	Stratification Structure	Convective Trigger Mechanism
Mabozi	2015/7/15 1:00	27.9	Weining-2.76	2379.3	13.3	11.8	-5.1	-5.08	5384	2802.621	Weining 17	Weak vertical wind shear near ground	Dry above, moist below	Upper-level cold advection forcing
Mabozi	2014/8/10 9:00	46.6	Weining-0.59	1799.3	1.3	14.2	-2.6	-2.62	2852.4	2508.676	Xichang 16	Near surface	Dry above, moist below	Upper-level cold advection forcing
Mabozi	2015/7/22 16:00	43.1	Weining-1.32	1823.1	80.7	18.2	-3.1	-3.03	4108	2837.507	Xichang 16	Near surface	Dry above, moist below	Upper-level cold advection forcing
Huangtian Plant	2015/8/25 1:00	44.3	Weining-0.70	933.6	8.5	0	-2.7	-2.78	3732.5	2598.408	Xichang 16	Near surface	Dry above, moist below	Upper-level cold advection forcing
Xintian Station	2016/5/21 17:00	23.7	Weining-4.58	819.4	36	0	-5.2	-5.2	8217.2	3139.333	Weining 18	Lower layer	Moist throughout	Upper-level cold advection forcing
Shangcun Liangzi Camp	2016/8/1 6:00	24.6	Xichang-1.23	680.9	1	70.1	-2.2	-2.62	3371.7	2159.841	Xichang 17	Weak vertical wind shear near ground	“Trumpet-shaped” top and bottom	Upper-level cold advection forcing
Shangcun Liangzi	2016/9/9 6:00	21.8	Weining-2.84	1998.4	386.9	14.5	-4.7	-3.82	10300.9	3257.972	Xichang 18	Strong vertical wind shear in mid-lower levels	“Trumpet-shaped” top and bottom	Upper-level cold advection forcing




Fig. 3. Synoptic Background Map at 02:00 on September 10, 2017. (Note: In the surface map of Fig. 3, blue text indicates 24-h pressure change, and red text indicates 24-h temperature change.)

lower” temperature structure. In the early stage of the event, both the upper and lower atmospheric layers transitioned into a uniform northerly flow. Around 03:00 on the 10th, convective cells began to develop near the surface convergence line in the southern part of the dam area. Surface strong winds and lightning were observed, and the convective storm developed rapidly into a mature stage, marking the onset of short-duration heavy rainfall.

4.3 Low-Level Warm Advection Forcing Type

In the low-level warm advection forcing type, the warm and moist air mass in the mid-to-lower atmosphere is the primary influencing factor. In Southwest China, moisture primarily originates from the Bay of Bengal and the South China Sea. Although the jet stream in this region is smaller in scale compared to eastern China, it contains abundant moisture and has a stable transport pathway. At 500 hPa, shortwave troughs frequently move eastward and influence the region, while around 700 hPa, southwesterly or west-southwesterly flows prevail, often accompanied by low-level jets. Strong warm advection is typically present in the mid-to-lower levels. On the surface, the southwestern region




Fig. 4. Temperature-Log Pressure Diagram at 20:00 on September 9, 2017

is usually controlled by thermal low pressure or influenced by southerly flow at the rear of a high-pressure system. At times, both the 700 hPa and 850 hPa levels exhibit southwesterly moist flows. When the two streams intersect at a noticeable angle, short-duration heavy rainfall often occurs in the left-hand sector of the 700 hPa jet. These events are usually accompanied by lightning, strong winds, hail, and short-term heavy rainfall, characterizing them as mixed-type short-duration convective rainstorms.

Between 2012 and 2022, there were five short-duration heavy rainfall events in the Baihetan Hydropower Station dam area classified as being triggered by low-level warm advection forcing (see Table 3). These convective events typically featured hourly rainfall rates ranging from 20 to 30 mm, with the maximum hourly rainfall reaching 34.3 mm (recorded at Xintian on June 9, 2016, at 23:00). Such events were frequently preceded by short-term severe convective weather, including strong winds and lightning. The main synoptic background characteristics of this type are: At 200 hPa, the region is generally located in the divergence zone on the eastern or southeastern side of a southward high-pressure center, or within the right-exit region of an upper-level jet stream, which enhances upward motion through upper-level divergence and suction effects. At 500 hPa, the area is influenced by either the eastward-moving plateau trough, the periphery of a high-pressure system, or is directly under high-pressure control. Cold advection in these scenarios is weak or absent. At 700 hPa, low-level jet streams or significant flow lines are frequently observed. A southwesterly or southerly jet typically extends from the Bay of Bengal through Yunnan to the Sichuan Basin, serving as a stable channel for the transport of warm and moist air, with virtually no influence from cold advection. On surface charts, the Liangshan Prefecture region is often dominated by a thermal low-pressure system, and the impact of cold air at the surface is relatively weak. Overall, this pattern is dominated by northward transport of warm and moist air, which triggers the

development of deep moist convection. These conditions are commonly accompanied by thunderstorms and short-duration heavy rainfall.


Characteristics of Physical Parameters:(1) The Showalter Index (SI) at Xichang or Weining stations is generally close to or below 0.0°C , with most values around -1.0°C . The minimum observed value was -2.42°C (at Xintian Station on June 9, 2016, 23:00).(2) The Convective Available Potential Energy (CAPE) values are relatively low, with a maximum of only 1368.2 J/kg. The wet-layer thickness (H_{wet}) varies significantly, reaching up to 7040.4 m. The “inverted V” type vertical structure is relatively evident.(3) Vertical wind shear is mainly concentrated in the mid-to-lower levels or near the surface, but the intensity is weak, which favors the development of convective cells. The temperature difference between 500 hPa and 700 hPa exceeds 16°C . The warm and moist airflow in the mid-to-lower levels plays a dominant role, and the forced uplift of near-surface air masses enhances the “cold over warm” stratification structure, thereby triggering the formation of convective cells.

Figure 5 shows the synoptic circulation pattern around 20:00 on June 9, 2016. A short-duration heavy rainfall event occurred in the Baihetan Hydropower Station dam area at approximately 23:00 on the same day. Prior to the rainfall, strong gusty winds of around Force 8 were observed, and the maximum hourly rainfall intensity reached 34.3 mm (at Xintian Station on June 9, 2016, 23:00).According to the synoptic analysis:At 200 hPa, a straight westerly jet stream dominated the mid-latitude region of China. The dam area was located on the right exit region of the jet axis, where upper-level divergence was enhanced, favoring vertical upward motion.At 500 hPa, a storm system formed over the Bay of Bengal, leading to moisture convergence and extending a westerly moisture transport belt. The dam area was under the control of westerly airflow.At 700 hPa, the convergence associated with the Bay of Bengal storm became more intense. A southwesterly low-level jet carried warm and moist air northeastward. Cyclonic wind convergence near the dam area promoted the accumulation of moisture and unstable energy.On the surface chart, the southern Sichuan Basin to northern Liangshan region was under the influence of a thermal low-pressure center. A distinct surface convergence line could be identified near the dam area. Additionally, local temperatures were high, and surface heating further enhanced the local instability of the stratification structure. The pressure gradient from Yunnan to the southern dam area increased.This event was a typical low-level warm advection–forced short-term heavy rainfall process, where the Bay of Bengal storm played a key role in transporting moisture and unstable energy, acting as the primary moisture source. There was no significant cold air involvement during this event. The ascent caused by low-level moisture convergence, combined with surface heating, further destabilized the stratification structure, ultimately triggering convective weather.

Figure 6 shows the atmospheric sounding over Xichang Station at 20:00 on June 9, 2016. Prior to the onset of convective weather, local atmospheric conditions exhibited some instability, but the upward motion lacked strong dynamic support. The CAPE was 81.4 J/kg, CIN was 70.7 J/kg, SI was -2.42°C , and BLI was -2.4°C . The convective available potential energy and convective inhibition were nearly balanced, indicating weak vertical ascent.The entire profile displayed an “hourglass-shaped” stratification structure, with a deep moist layer concentrated between 300 hPa and 700 hPa. Although

Table 3. Physical Parameters Statistics for Low-Level Warm Advection-Forced Type

Station	Time	Precipitation (mm)	SI Index	CAPE	DCAPE	CIN	BLI	LI	Hwet	Hwarm	T75	Vertical Wind Shear	Stratification Structure	Convective Trigger Mechanism
Xintian	2012/5/28 4:00	27.7	Xichang-0.89	1155.1	3.4	61.4	-2.1	-2.09	1931.8	1434.987	Xichang18	Weak in low levels	Upper-lower trumpet	Low-level warm advection forcing
Xintian	2013/6/22 1:00	21.4	Xichang2.28	902.4	891.2	75.4	-3.3	-3.36	2506.2	2571.693	Xichang17	Southerly flow throughout	Upper-lower trumpet	Low-level warm advection forcing (typhoon westward)
Xintian	2016/6/9 23:00	34.3	Xichang-2.42	81.4	16.1	70.7	-2.4	-1.32	7040.4	1832.586	Xichang17	Weak in low levels	Upper-lower trumpet	Low-level warm advection forcing
Mabozi	2017/7/22 0:00	21.7	Weining-0.95	869.2	326.9	0.8	-2.7	-2.75	6422.9	2732.651	Xichang16	Southerly low-level, easterly mid-high	Dry above, moist below	Low-level warm advection forcing
Mabozi	2022/9/20 5:00	33.2	Xichang-1.13	1368.2	0	53.8	-2.4	-1.64	2455.6	2544.132	Weining17	Mid-low level	Upper-lower trumpet	Low-level warm advection forcing






Fig. 6. Temperature–Log Pressure Diagram at 20:00 on June 9, 2016

to the Chinese mainland, forming a continental high. Baihetan is affected by disturbances in the easterly flow on the southern flank of the WPSH, leading to convective precipitation in Southwest China. Baihetan is influenced by the peripheral cloud system of a westward-moving typhoon that weakens after landfall. The weakened typhoon's northern easterly flow transports moisture to Southwest China, resulting in convective rainfall. In both cases, Baihetan typically experiences lightning and short-duration heavy rainfall. The moisture sources for this type are: (1) easterly flows on the southern flank of the WPSH, bringing moisture from the South China Sea; and (2) peripheral cloud bands of weakened landfalling typhoons, also transporting moisture from the South China Sea.

During the period from 2012 to 2022, there were a total of five quasi-barotropic type short-duration heavy rainfall events in the Baihetan Hydropower Station dam area (see Table 4). This type of convective rainfall typically exhibited hourly intensities between 20–30 mm, with the maximum hourly intensity reaching 37.0 mm (at Huangtian Water Plant on September 21, 2021, 21:00). These events generally did not coincide with significant strong wind occurrences. The synoptic circulation characteristics of this type are as follows: At 200 hPa, most events occurred within the divergence zone on the eastern or southeastern flank of a southward-suppressed high-pressure system, or on the right exit region of an upper-level jet stream, where enhanced divergence aloft supports stronger convective uplift; At 500 hPa, the dam area is usually located in the easterly or northeasterly flow region on the southern flank of a continental high, or under the influence of the subtropical high or an anticyclonic circulation; At 700 hPa, there is often an influx of warm and moist air from the south or southwest, with evident transport of thermal and moisture energy, and little to no cold air advection; On surface charts, the Liangshan Prefecture region is typically under the influence of a pressure equilibrium field, with no significant intrusion of cold air at the surface. This type is primarily driven

by the northward transport of warm and moist air, which leads to the development of deep moist convection and may occasionally be accompanied by lightning or gusty winds.

Characteristics of Physical Parameters:(1) The Showalter Stability Index (SI) at Xichang or Weining stations is generally close to or below 0.0°C , mostly around -1.0°C , with a minimum value reaching -2.11°C (observed at Huangtian Water Plant on July 30, 2022, 22:00).(2) The CAPE values are relatively low, with a maximum of only 1882.1 J/kg . The thickness of the moist layer (H_{wet}) is shallow and situated at lower atmospheric levels, with a maximum reaching 2638.8 km .(3) Vertical wind shear is primarily concentrated in the mid- to lower-levels or near the surface, but the intensity is weak. The transport of warm and moist airflow in the mid- to lower-levels plays a dominant role. Forced uplift of air masses near the surface occurs without the involvement of significant cold air. The triggering of convective cells mainly relies on the combined effect of warm and moist energy transport from the south and surface-level convergence and uplift.

Around 01:00 on September 2, 2021, a short-duration heavy rainfall event occurred in the Baihetan Hydropower Station dam area. Prior to the precipitation, gusty winds reaching Force 8 were observed, and the maximum hourly rainfall reached 37.0 mm (recorded at Huangtian Water Plant at 01:00 on September 2, 2021). According to the synoptic situation analysis (Fig. 7), at 200 hPa , the eastern Tibetan Plateau to the dam area was under the control of a high-pressure center, with strong upper-level divergence enhancing vertical upward motion through a “suction effect.” At 500 hPa , the Panxi region to the eastern Sichuan Basin was influenced by the outer edge of the subtropical high along the 588 gpm contour. A storm developed over the Bay of Bengal, gathering moisture and extending a westerly moisture transport belt. The dam area was under the center of the high-pressure control. At 700 hPa , a westward-moving typhoon made landfall near Hainan Island and the Beibu Gulf, with southeasterly flows on its periphery transporting abundant warm and moist air into the dam area. Shear zones pushed southward into northern Liangshan, favoring convergence of warm-moist air in the mid-to-lower troposphere. At the surface, most of Liangshan Prefecture was under the control of a low-pressure center, and a strengthened pressure gradient in the northeastern part of Liangshan accelerated moisture convergence and upward motion in the dam area. Additionally, surface temperatures were relatively high, with no significant cold air intrusion. The pronounced near-surface warming intensified atmospheric instability. This was a convective weather process primarily triggered by convergence of low-level warm-moist air and enhanced upper-level divergence that intensified vertical motion. The southeasterly flow from the westward-moving typhoon played a critical role in the transport of moisture and convective energy. With no significant cold air involvement, the convergence and uplift of low-level moisture, together with surface heating, led to increased instability in the stratification structure, eventually triggering the convective weather event.

Table 4. Quasi-Barotropic-Type Physical Quantity Statistics Table

Station	Time	Precipitation (mm)	SI Index	CAPE	DCAPE	CIN	BLI	LI	Hwet	Hwarm	T75	Vertical Wind Shear	Stratification Structure	Convective Trigger Mechanism
												Northeasterly wind through the layer	Entire layer dry	Quasi-barotropic type
Huangtian Plant	2017/7/20 6:00	26.1	Xichang2.22	1078.5	1.4	79.3	-1.4	1.49	0	1456.926	Xichang 17			Quasi-barotropic type
Huangtian Plant	2017/7/30 4:00	26.4	Weining-0.89	730.5	717.5	50.1	-2.1	-2.09	1276.2	1377.14	Xichang 18		Hourglass shape, moist at 600-700	Quasi-barotropic (typhoon westward)
Huangtian Plant	2017/8/4 22:00	22.5	Weining-1.59	821.9	48.2	14.6	-2.9	-2.85	6900.2	3048.595	Xichang 18		Moist below 300 hPa	Quasi-barotropic type
Huangtian Plant	2021/9/2 1:00	37	Xichang-0.41	1882.1	0	0	-3.7	-3.84	2638.8	2803.671	Xichang 17		Moist between 400-600 hPa	Quasi-barotropic type
Huangtian Plant	2022/7/30 22:00	25.6	Xichang-2.11	1595.7	0	0.1	-4.3	-3.78	8875.2	2909.605	Weining 17		Moist above, dry below; northerly below 750 hPa	Quasi-barotropic type




Fig. 7. Circulation Background Map at 20:00 on September 1, 2021

Figure 8 shows the radiosonde profile over Xichang Station at 20:00 on September 1, 2021. Before the onset of convective weather, there was a certain level of atmospheric instability locally. Below 400 hPa, a consistent southerly flow was observed, with a distinct wind shear occurring at 400 hPa. The Convective Available Potential Energy (CAPE) was 1882.1 J/kg, Convective Inhibition (CIN) was 0.0 J/kg, the Showalter Index (SI) was -0.41°C , and the Bulk Richardson Index (BLI) was -3.7°C . The atmosphere had a high level of effective convective energy with no inhibiting energy, supporting strong vertical ascent. A distinct “dry-over-moist” stratification structure was observed, with the moist layer primarily concentrated between 400–600 hPa. Instability was present throughout the entire profile, with no significant cold air advection. Southeastern warm-moist airflow advanced westward and northward in the mid-to-lower troposphere, and surface moisture convergence further enhanced uplift, initiating convective cell development. Meanwhile, the “suction effect” in the mid-to-upper levels enhanced vertical motion, driving the convective storm into its mature stage and leading to the onset of short-duration heavy rainfall.




Fig. 8. Temperature-Log Pressure Diagram at 20:00 on September 1, 2021

5 Conclusion

- (1) Baroclinic Frontogenesis Circulation Background and Characteristics: At 200 hPa, the region is mainly located on the east or southeast side of the subtropical high, within the divergence zone. The “suction effect” of the upper-level divergence field can enhance convective upward motion. Numbered lists should use the “Numbered Item” style; At 500 hPa, the area is influenced by the eastward movement of the plateau trough, often accompanied by cold air advection behind the trough. At 700 hPa, southwestern low-level airflow (or a low-level jet) and the southward shear over the basin favor the convergence of warm and cold air masses, leading to baroclinic frontogenesis; On the surface chart, the presence of thermal low pressure, convergence lines, or stationary front cloud systems promotes surface moisture convergence, intensifying vertical ascent and triggering convective weather; The SI (Showalter Index) values are generally close to or less than 0.0 °C; the smaller the SI value, the more unstable the stratification. The CAPE (Convective Available Potential Energy) values are generally around 1000 J/kg; The stratification structure is mostly characterized as “dry aloft, moist below” or an “hourglass” profile. The entrainment of dry mid-level air can intensify the severity of the convective system.
- (2) Upper-Level Cold Advection Forcing Type: Circulation Background and Characteristics: At 200 hPa, the region is mainly located on the eastern or southeastern side of the subtropical high, or on the right exit region of the upper-level jet stream, favoring the “suction effect” of upper-level divergence fields, which enhances convective upward motion; At 500 hPa, the area is influenced by the eastward movement of the plateau trough, with generally strong cold advection behind the trough; At 700 hPa, shear deformation and southward pressure extension dominate the Sichuan Basin, with stronger cold advection behind the shear zone; On surface charts, cold fronts often press southward over northern Sichuan, while the dam area is usually under

the control of thermal low pressure. The baroclinicity formed by the temperature contrast between the warm low levels and cold upper levels is the main triggering mechanism for short-duration heavy rainfall; The SI (Showalter Index) is generally close to or below 0.0°C ; the Hwet (wet layer thickness) is relatively large, typically exceeding 3000 km, and the stratification exhibits a clear “dry aloft, moist below” structure; A pronounced “cold aloft, warm below” thermal structure is observed, with differential temperature advection intensifying baroclinicity, which, combined with surface convergence lines, strongly triggers the development of convective cells.

- (3) Lower-Level Warm Advection Forcing Type: Circulation Background and Characteristics: At 200 hPa, the region is primarily located on the eastern or southeastern side of the subtropical high, or on the right exit region of the upper-level jet stream, favoring the “suction effect” of upper-level divergence fields, which enhances convective upward motion; At 500 hPa, the area is affected by the eastward movement of the plateau trough, the periphery of a high-pressure system, or is directly controlled by high pressure. In this type, cold advection is generally weak or even absent; At 700 hPa, there are often jet streams or pronounced streamlines, with significant warm and moist air transport; On surface charts, the region around Liangshan Prefecture is often under the influence of thermal low pressure. This type is mainly characterized by the northward transport of warm and moist air, leading to the development of deep moist convection, often accompanied by lightning and short-duration heavy rainfall; The SI (Showalter Index) is generally close to or below 0.0°C ; the CAPE values are relatively low, with a maximum of only 1368.2 J/kg. The Hwet (wet layer thickness) varies greatly, reaching up to 7040.4 m. The “hourglass” stratification structure (dry aloft and below, moist in the middle) is relatively pronounced; Vertical wind shear is mainly concentrated in the mid-to-lower or near-surface layers, but is generally weak, favoring the development of convective cells. The temperature difference between 500 hPa and 700 hPa exceeds 16°C . Warm and moist air transport in the mid-to-lower layers plays a dominant role, while forced uplift of near-surface air masses enhances the “cold aloft, warm below” stratification, thus triggering convective cells.
- (4) Quasi-Barotropic Type: Circulation Background and Characteristics: At 200 hPa, the region is typically located on the eastern or southeastern side of the subtropical high, or on the right exit region of an upper-level jet stream. This enhances the “suction effect” of upper-level divergence, strengthening convective upward motion; At 500 hPa, the dam area is often situated on the southern, eastern, or northeastern flank of a continental high-pressure system, or is under the control of a subtropical high or anticyclonic circulation; At 700 hPa, the area is affected by warm and moist airflows from the south or southwest, with significant heat and moisture transport; On surface charts, the Liangshan region is frequently under a uniform pressure field. The northward transport of warm and moist air promotes the development of deep moist convection, occasionally accompanied by lightning or gusty winds; The Showalter Index (SI) is generally close to or below 0.0°C . CAPE values are relatively low, with a maximum of only 1882.1 J/kg. The Hwet (wet layer thickness) is relatively shallow and concentrated in the lower atmospheric layers; Vertical wind shear mainly occurs in the mid-to-lower or near-surface layers but is weak in intensity. Warm and moist air transport in these layers plays a dominant role, while forced uplift of near-surface

air masses combines with surface convergence and upward motion to trigger the development of convective cells.

References

1. Chen, J., Zheng, Y., Zhang, X., Zhu, P.: Analysis of the climatological distribution and diurnal variations of the short-duration heavy rain and its relation with diurnal variations of the MCSs over China during the warm season. *J Acta Meteorol Sinica* (2013). <https://doi.org/10.11676/jqxb2013.035>
2. Sichuan Meteorological Bureau. *Sichuan Weather Forecast Manual*. Southwest Jiaotong University Press. pp. 13–14 (2014)
3. Sun, J., Dai, J., He, L., et al.: Basic principles and technical methods of severe convective weather forecasting—Manual of severe convective weather forecasting in China. China Meteorological Press (2014)
4. Li, T., Yao, H., Meng, Y.: Study on the characteristics of “6·28” extremely heavy rainfall of baihetan hydropower station on the lower Jinsha River. *Plateau and Mountain Meteorology Research* **40**(4), 30–35 (2020). 10.3969/j.issn.1674-21842020.04.005
5. Yu, X., Zheng, Y.: Advances in severe convective weather research and operational service in China. *Acta Meteorol Sinica* **78**(3), 391–418 (2020)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Methodology for Analyzing Glacial Lake Outburst Flood Impacts

Tijia Yang¹, Xin Zhang²(✉), Jie Qin¹, Teng Wu¹, and GaoHu Sun²

¹ School of Harbor Waterway and Coastal Engineering, Hohai University, Nanjing 210098, China

² International Economic & Technical Cooperation and Exchange Center, Ministry of Water Resources, Beijing 100048, China
lindazhangxin@126.com

Abstract. Global warming has accelerated glacier melt, leading to the increased formation of glacial lakes and heightened flood risk in downstream regions. This study focuses on the Merzbacher Glacier Lake (MGL) to model the hydrodynamics of its downstream area. Utilizing a relationship curve between lake area and water volume for the “lower lake”, we predicted the outburst time, volume, and downstream impact of a potential 2023 MGL outburst flood. Our predictions indicated that a glacial lake outburst flood (GLOF) would occur between July 3rd and 5th, with flood inundation extending approximately from the river’s centerline outwards, affecting some agricultural land in Wensu County, but having minimal impact on urban areas. Satellite imagery monitoring subsequently revealed that the Merzbacher Glacier Lake began to gradually drain after July 3rd, with nearly complete drainage of the lake water by July 8th, leaving only glaciofluvial sediments on the lakebed. The observed outburst time was indeed between July 3rd and July 5th, and the outburst flood volume was approximately 10 million m³. These observational results align well with the predictions of this study, validating the accuracy of the proposed methodology. This approach can be extended to other glacial lake regions, providing valuable early warning support for potential downstream flood inundation risks.

Keywords: Merzbacher Glacier Lake · Glacial Lake Outburst Flood · Remote Sensing Monitoring · Flood

1 Introduction

Glacial lakes are unique proglacial lake types, typically formed when an advancing or surging glacier obstructs a main river valley, leading to water accumulation. Alternatively, they can form when a rapidly retreating tributary glacier detaches from the main glacier, leaving an overdeepened glacial trough that is subsequently blocked by the main glacier (Yao et al. 2017). Based on their formation mechanism, glacial lakes can be categorized as glacier-dammed lakes formed by an advancing glacier or other types of glacier-dammed lakes. Glacier-dammed lakes formed by advancing glaciers generally have shorter lifespans, while other types exhibit diverse evolutionary characteristics. For

instance, Merzbacher Lake demonstrates periodic outburst drainage (Yao et al. 2017). In China, glacier-dammed lakes are predominantly concentrated in the Xinjiang region, including the Keyajiertecuo Lake on the northern slope of the Karakoram Mountains (feeding the Yarkant River downstream), Merzbacher Lake on the southern slope of the Tianshan Mountains (feeding the Kunmalik River downstream), and the Sikeshe River on the northern slope of the Tianshan Mountains (Cheng, 2005).

Glacier-dammed lakes, with glacier ice serving as the natural dam, are prone to glacial lake outburst floods (GLOFs). In recent years, extensive domestic and international research has focused on GLOF risk assessment, flood process simulation, and the causes and characteristics of such floods. Rana Muhammad Ali Washakh (Washakh, 2020) proposed a four-step screening method based on historical GLOF discharge and impact scale to evaluate GLOF risk. Ran Qihua, Wu Xiushan, and He Zhiguo (Ran et al. 2014) utilized a two-dimensional dam-break flood routing numerical model to calibrate and simulate flood evolution under different outburst scenarios for typical hazardous glacial lakes in the Nianchu River basin of Tibet. Raphael Worni, Markus Stoffel, and Christian Huggel (Worni et al. 2012) analyzed a GLOF that occurred in May 2009 in the Patagonian Andes of Argentina, reconstructing the dam-break triggering, outburst, and lake emptying processes. Zhang Xiangsong, Li Nianjie, and You Xiyao (Zhang et al. 1989) discussed the causes, characteristics, and trend prediction of glacial floods in the Yarkant River.

The Merzbacher Glacier Lake, situated in the Tomur-Khan Tengri Mountains on the border between China and Kyrgyzstan, has a history of sudden outbursts spanning nearly a century. Statistics indicate that the Merzbacher Glacier Lake experienced 64 outbursts between 1932 and 2010 (Zhang et al. 2023). The frequent outbursts of the Merzbacher Glacier Lake pose a constant flood risk to the Aksu region, located downstream of the Kunmalik River, underscoring the significant practical importance of analyzing its outburst floods. Li Da, Shangguan Donghui, and Huang Weidong (Li et al. 2020) used satellite remote sensing data to extract and calculate the total area, “upper lake” area, and “lower lake” area of the Merzbacher Glacier Lake from 1998 to 2017, providing data for analyzing trends in lake area change. Chen Yaning, Yang Siquan, and Li Weihong (Chen et al. 1999) analyzed the fractal characteristics of sudden floods from the Merzbacher Glacier Lake, laying a foundation for constructing prediction models from a dynamic perspective. Jonathan Kingslake and Felix Ng (Kingslake and Ng, 2013) proposed four models for the critical water depth (h_c) that triggers GLOFs, offering a method to predict the next outburst date based on the previous known flood date.

This study analyzes the 2023 Merzbacher Glacier Lake outburst based on remote sensing imagery and a hydrodynamic numerical model. The analysis primarily encompasses the outburst time, outburst flood volume, and downstream impact of the flood. Furthermore, this research presents a comprehensive methodology for understanding the characteristics of Merzbacher Glacier Lake outburst floods, integrating remote sensing monitoring and hydrodynamic modeling, thereby providing a valuable reference for future analyses of this lake’s outburst events.

2 Study Area

The Merzbacher Glacier Lake (MGL) ($42^{\circ}13'N$, $79^{\circ}52'E$) is located in the Tomur-Khan Tengri Mountains, situated at the border between China and Kyrgyzstan. The lake surface is approximately 3300 m above sea level and lies between the North Inylchek Glacier and the South Inylchek Glacier, serving as the source region for the Kunmalik River (Liu et al. 1998) (Fig. 1). MGL exhibits a characteristic dual-lake structure, comprising an “upper lake” and a “lower lake.” The “lower lake” is dammed by the South Inylchek Glacier, while the “upper lake” connects the “lower lake” to the terminus of the North Inylchek Glacier (Shen et al. 2009).




Fig. 1. Merzbacher Glacier Lake and Inylchek Glacier

Glacial floods can be broadly categorized by their origin into glacial lake outburst floods (GLOFs) and glacier meltwater floods. Floods originating from the Merzbacher Glacier Lake are classified as GLOFs, which are typically associated with the outburst of glacial lakes (Lai, 1984). The drainage process of the Merzbacher Glacier Lake generally unfolds as follows (Shen et al. 2009): The primary dam of the Merzbacher Glacier Lake is formed by the South Inylchek Glacier, which contains a series of internal drainage channels. As the lake water level rises, the hydrostatic pressure of the proglacial lake water forces drainage through these internal channels. This process can also lead to the flotation of the ice dam via subglacial conduits. After a period of drainage, the lake level drops to a certain height, causing the ice dam to resettle and re-block the glacial lake. Subsequently, the South Inylchek Glacier again impounds the lake water, and the drainage cycle concludes.

Merzbacher Glacier Lake outburst floods exhibit distinct characteristics in terms of flood hydrograph, outburst frequency, and timing (Liu et al. 1998). Firstly, these floods are characterized by a slow initial rise in discharge followed by a rapid recession after the peak. The initial stage of the flood hydrograph shows a gradual increase in flow, which then steepens until the flood peak, after which discharge rapidly declines. Secondly, after drainage, the ice dam subsides, leading to renewed water impoundment and lake formation. Consequently, the outbursts from this lake are periodic (Yao et al. 2017), occurring at a high frequency, predominantly during the summer and autumn seasons.

3 Methodology for Glacial Lake Outburst Impact Analysis

3.1 Outburst Time Analysis

Accurate analysis of glacial lake outburst time is crucial for planning downstream flood mitigation measures. This study employs two complementary methods for determining the glacial lake outburst time: remote sensing imagery monitoring and downstream hydrological station discharge monitoring.

The remote sensing imagery monitoring method involves collecting and analyzing remote sensing imagery data of the glacial lake area to monitor changes in water body area. By correlating these changes with the known patterns of water body area variation during glacial lake outbursts, an approximate outburst time can be deduced. Initially, a phase of gradual increase in lake surface area indicates the inflow of glacial meltwater into the lake. Subsequently, when remote sensing data reveal that the lake surface area reaches a peak and then begins to shrink, it suggests potential structural weaknesses in the ice dam and the onset of water drainage, serving as a critical pre-outburst signal. Finally, continued monitoring showing a rapid decrease in lake water until it empties marks the conclusion of the glacial lake outburst. Based on this analysis, the glacial lake outburst time is estimated to be approximately between the onset of the lake surface area shrinkage and the complete drainage of the lake water.

The hydrological station discharge monitoring method utilizes discharge and water level data obtained from downstream hydrological stations to analyze their change characteristics. This is then combined with numerical models to infer the glacial lake outburst time. GLOFs typically originate from gradual leakage through the ice dam, which progressively expands the drainage channels. Once water finds a path through the ice dam, it accelerates the erosion of the conduit until the entire dam structure collapses (Lai, 1984). Therefore, when a glacial lake outbursts, the resulting flood should reach its peak discharge. Correspondingly, by identifying the flood peak date observed at a downstream hydrological station and simulating the flood routing duration using a numerical model, the upstream glacial lake outburst time can be back-calculated.

3.2 Estimation of Glacial Lake Outburst Volume

Currently, remote sensing models for water volume estimation primarily include statistical empirical models and physical measurement models (Zhu et al. 2022). Statistical empirical models involve establishing a water volume-water level curve or a water volume-lake area curve. Based on remotely sensed water level or lake area, the lake volume is then estimated. Physical measurement models, in contrast, directly calculate lake volume using real-time remote sensing data in conjunction with high-precision underwater topographic data. This study adopts a statistical empirical model, first establishing a relationship curve between lake volume and lake area, and then estimating the glacial lake outburst volume based on the remotely calculated lake area.

The HEC-RAS model can readily provide a lake volume-water level curve. This curve then needs to be further converted into a lake volume-lake area curve.

The water volume function is the integral of the lake area function with respect to water level, expressed as:

$$V(h) = \int A(h)dh \quad (2.1)$$

where V is the glacial lake water volume, A is the glacial lake area, and h is the water level.

Differentiating and rearranging Eq. (2.1) yields:

$$A(h) = \frac{dV(h)}{dh} \quad (2.2)$$

From Eq. (2.2), it is evident that the glacial lake area function is the derivative of the glacial lake water volume function with respect to water level. This study employs the geometric tangent method to derive the water volume-lake area curve from the water volume-water level curve (Liao and Li, 2012). The specific procedure is as follows:

First, the HEC-RAS model is used to obtain the glacial lake water volume-water level curve. Then, based on this curve, the slope of the tangent at each point (i.e., the corresponding glacial lake area) is calculated to derive the glacial lake water volume-lake area curve.

During a glacial lake outburst, the glacial lake water body area typically reaches a peak and then begins to decrease, eventually draining completely. This implies that the peak water body area observed during the outburst should be selected and used in conjunction with the established lake volume-lake area curve to calculate the glacial lake outburst volume.

3.3 Downstream Impact Analysis of Glacial Lake Outbursts

HEC-RAS is a hydraulic computation program developed by the U.S. Army Corps of Engineers Hydrologic Engineering Center. It is widely used in the United States and globally, with most major river systems and many smaller rivers and streams in the U.S. having been modeled using HEC-RAS (Wang et al. 2018). Its two-dimensional unsteady flow hydraulic computation model is frequently employed for river flood routing simulation and flood inundation extent mapping (Yang and Wang, 2020; Huang et al. 2021; Vashist and Singh, 2023).

For this study, modeling a natural river, the HEC-RAS two-dimensional unsteady flow hydraulic computation model is employed. This model describes the motion of a two-dimensional fluid using the Navier-Stokes equations, specifically as follows (U.S. Army Corps of Engineers, 2016):

Assuming the flow is incompressible, the unsteady differential form of the mass conservation (continuity) equation is:

$$\frac{\partial h}{\partial t} + \frac{\partial(hu)}{\partial x} + \frac{\partial(hv)}{\partial y} = q \quad (2.3)$$

where t is time, h is water depth, u and v are velocity components in the x and y directions, and q is the source/sink term flow rate (positive for sources, negative for sinks).

The unsteady differential forms of the momentum equations are:

$$\begin{aligned} \frac{\partial u}{\partial t} + u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} - f_c v = & -g \frac{\partial z_s}{\partial x} + \frac{1}{h} \frac{\partial}{\partial x} \left(v_{t,xx} h \frac{\partial u}{\partial x} \right) \\ & + \frac{1}{h} \frac{\partial}{\partial y} \left(v_{t,xy} h \frac{\partial u}{\partial y} \right) - \frac{\tau_{b,x}}{\rho R} + \frac{\tau_{s,x}}{\rho h} - \frac{1}{\rho} \frac{\partial P_a}{\partial x} \end{aligned} \quad (2.4)$$

$$\begin{aligned} \frac{\partial v}{\partial t} + u \frac{\partial v}{\partial x} + v \frac{\partial v}{\partial y} - f_c u = & -g \frac{\partial z_s}{\partial y} + \frac{1}{h} \frac{\partial}{\partial x} \left(v_{t,xy} h \frac{\partial v}{\partial x} \right) \\ & + \frac{1}{h} \frac{\partial}{\partial y} \left(v_{t,yy} h \frac{\partial v}{\partial y} \right) - \frac{\tau_{b,y}}{\rho R} + \frac{\tau_{s,y}}{\rho h} - \frac{1}{\rho} \frac{\partial P_a}{\partial y} \end{aligned} \quad (2.5)$$

where g is the acceleration due to gravity, u and v are velocity components in the x and y directions, h is water depth, η is the water surface elevation, v_x and v_y are the horizontal eddy viscosity coefficients in the x and y directions, $\tau_{\{bx\}}$ and $\tau_{\{by\}}$ are the bottom shear stresses in the x and y directions, R is the hydraulic radius, $\tau_{\{sx\}}$ and $\tau_{\{sy\}}$ are the surface wind stresses in the x and y directions, f is the Coriolis parameter, and P_a is the atmospheric pressure (note: P_a is not explicitly in Eqs. 2.4 and 2.5 as written, typically atmospheric pressure terms are incorporated into the water surface elevation or ignored for shallow water equations).

The model solves the above Eqs. (2.3), (2.4), and (2.5) using an iterative method.

4 Analysis of Merzbacher Glacier Lake Impact

4.1 Outburst Time Analysis

Remote sensing monitoring results for the Merzbacher Glacier Lake's lower lake from June to July 2023 indicate the following changes: On June 21st, the glacial lake had formed, with a water body area of approximately 0.78 km². By July 1st, as floating ice within the lake gradually accumulated, the extent of the ice dam's floating layer expanded, and the overall lake area increased, with the water body area reaching 0.84 km². On July 3rd, the lake area further expanded. Notably, influenced by high local temperatures, glacial snow accelerated its melt, and the floating ice within the lake gradually melted, increasing the water body area to 1.24 km². By July 8th, nearly all of the lake water had drained.

The remote sensing monitoring results indicate that the lake area began to gradually decrease after July 3rd, indicating the onset of drainage, which continued until July 8th when the lake stopped draining. From this, it can be inferred that the Merzbacher Glacier Lake outburst occurred approximately between July 3rd and July 8th.

Figure 2 illustrates the water level and discharge hydrograph at the Xiehela hydrological station from June 11th to July 11th, 2023. Prior to July 3rd, discharge showed minimal variation. However, after July 3rd, discharge rapidly increased, lasting for five days, peaking on July 8th, and then quickly receding. The characteristic flood process of the Merzbacher Glacier Lake outburst is typically described as a slow rise and rapid fall in water levels, with a relatively gentle initial increase in discharge that gradually steepens until the flood peak, followed by a swift recession (Liu et al. 1998). The discharge trend observed in Fig. 2 is consistent with these flood characteristics.

Based on numerical simulation analysis, a minor flood from the Merzbacher Glacier Lake’s lower lake generally takes 3–5 days to reach the Xiehela station. Considering that the flood peak at Xiehela station occurred on July 8th, we can back-calculate that the Merzbacher Glacier Lake outburst occurred between July 3rd and July 5th. This finding is largely consistent with the analysis derived from the remote sensing imagery.




Fig. 2. Water Level and Discharge Hydrograph at Xiehela Station (June 11th-July 11th, 2023)

4.2 Outburst Volume Estimation

The Merzbacher Glacier Lake outburst primarily involves the drainage of water from the “lower lake.” To estimate the outburst volume of the Merzbacher Glacier Lake, it is necessary to establish a relationship between the “lower lake” water area and water volume.

Following the methodology for glacial lake outburst volume estimation described previously, the HEC-RAS model was first used to derive the “lower lake” water volume-water level curve (Fig. 3). Subsequently, based on this curve, the slope of the tangent at each point (representing the corresponding glacial lake area) was calculated to obtain the “lower lake” water volume-lake area curve (Fig. 4).

The “lower lake” water volume-lake area curve allows for the estimation of lake water volume at different areas. On July 3rd, the water body area within the glacial lake increased to 1.24 km². By July 8th, the lake water had largely drained. Based on these observations and the derived curves, the estimated outburst volume of the Merzbacher Glacier Lake is approximately 10 million m³.

4.3 Downstream Impact Analysis

This study employed the HEC-RAS two-dimensional unsteady flow hydraulic computation model to analyze the downstream impact of the Merzbacher Glacier Lake outburst flood.

The observed discharge data from the Xiehela station (Fig. 1) were used as the upstream boundary condition. Downstream boundary conditions were set at villages such as Kaimola Village in Shayar County. An HEC-RAS two-dimensional unsteady flow




Fig. 3. “Lower Lake” Water Volume-Water Level Curve




Fig. 4. “Lower Lake” Water Volume-Lake Area Curve

hydraulic computation model was then established. The model outputs for maximum inundation depth and maximum inundation velocity distribution are shown in Figs. 5 and 6, respectively.

The inundation extent generally expanded from the river’s centerline outwards to both banks. Some agricultural land in Wensu County was inundated, but the impact on urban areas was minimal. For most river sections, the inundation depths ranged from 0.0 to 1.0 m, and inundation velocities were between 0.0 and 1.0 m/s, indicating generally low depths and velocities.

Higher inundation depths were observed in the river section near the outlet of the Xiehela station and certain sections within Awati County. The average water depth in the river section near the Xiehela station outlet exceeded 2.0 m, while in parts of Awati County, the average water depth ranged from 1.0 to 2.0 m. Higher inundation velocities, averaging above 8.0 m/s, were found near the Xiehela station outlet. The river sections near the Xiehela station outlet and in parts of Awati County experienced relatively significant flood impacts, suggesting a need to enhance flood control standards in these areas.




Fig. 5. Maximum Inundation Depth Map




Fig. 6. Maximum Inundation Velocity Map

5 Conclusion

Analyzing remote sensing data of glacial lakes enables the estimation of outburst flood processes and outburst times. By integrating the “lower lake” water volume-lake area curve with downstream hydrodynamic models, we can further determine the outburst flood volume and its downstream impacts.

Applying this research approach and methodology to the 2023 Merzbacher Glacier Lake outburst parameters yielded the following preliminary conclusions: The Merzbacher Glacier Lake ice dam outburst occurred between July 3rd and July 5th, with an estimated outburst flood volume of approximately 10 million m³. The resulting flood inundation generally extended from the river channel’s centerline outwards, affecting some agricultural land in Wensu County but having a minimal impact on urban areas, thus leading to relatively minor disaster consequences.

Acknowledgments. This study was supported by the National Key R&D Program of China (2023YFC3209302) and the National Natural Science Foundation of China (52179061 and 52079043).

References

- Chen, Y., Yang, S., Li, W.: Study on fractal characteristics of sudden floods from Merzbacher Glacier Lake in the Tianshan Mountains. *Journal of Glaciology and Geocryology* **21**(3), 253–256 (1999)
- Cheng, G.: Sudden flood disasters induced by glacially dammed lakes in mountainous areas of Xinjiang. *Journal of Catastrophology* **20**(1), 46–50 (2005)
- Huang, B., Ge, L., Xu, X., et al.: Application of HEC-RAS in two-dimensional dam-break simulation: a case study of Hongqi Reservoir. *Pearl River* **42**(5), 73–79 (2021)
- Kingslake, J., Ng, F.: Quantifying the predictability of the timing of jökulhlaups from Merzbacher Lake, Kyrgyzstan. *Journal of Glaciology* **59**(217), 805–818 (2013)

- Lai, Z.: Some characteristics of glacier floods — A case study of rivers in Xinjiang. *Journal of Glaciology and Geocryology* **6**(2), 45–52 (1984)
- Li, D., Shangguan, D., Huang, W.: Area variation of Merzbacher Glacier Lake in the Tianshan Mountains from 1998 to 2017. *Journal of Glaciology and Geocryology* **42**(4), 1126–1134 (2020)
- Liao, H., Li, Z.: Deriving reservoir area curve based on reservoir capacity curve. *Guangxi Water Resources and Hydropower* **6**, 1–3 (2012)
- Liu, S., Cheng, G., Liu, J.: Characteristics of sudden floods from Merzbacher Glacier Lake and their relation to climate change. *Journal of Glaciology and Geocryology* **20**(1), 31–36 (1998)
- Ran, Q., Wu, X., He, Z., et al.: Impact of glacial lake outburst flood models on downstream flood processes. *Journal of Tsinghua University (Science and Technology)* **54**(8), 1049–1056 (2014)
- Shen, Y., Wang, G., Ding, Y., et al.: Evolution of Merzbacher Glacier Lake and glacier flood disasters in the Aksu River basin over the past century. *Journal of Glaciology and Geocryology* **31**(6), 993–1002 (2009)
- U.S. Army Corps of Engineers. HEC-RAS Hydraulic Reference Manual. Davis, CA: U.S. Army Corps of Engineers, Hydrologic Engineering Center (2016)
- Vashist, K., Singh, K.K.: HEC-RAS 2D modeling for flood inundation mapping: a case study of the Krishna River Basin. *Water Practice & Technology* **18**(4), 831–844 (2023)
- Wang, J., Zhang, Z., Greimann, B., Huang, V.: Application and evaluation of the HEC-RAS–riparian vegetation simulation module to the Sacramento River. *Ecol. Model.* **368**, 158–168 (2018)
- Washakh, A.M.R.: Research on glacier lake outburst floods in the alpine environment of the Arun Valley, central Himalayas (Master’s thesis). Institute of Mountain Hazards and Environment, Chinese Academy of Sciences (2020)
- Worni, R., Stoffel, M., Huggel, C., et al.: Analysis and dynamic modeling of a moraine failure and glacier lake outburst flood at Ventisquero Negro, Patagonian Andes (Argentina). *J. Hydrol.* **444–445**, 134–145 (2012)
- Yang, M., Wang, L.: Two-dimensional dam-break flood simulation based on HEC-RAS. *Sichuan Water Resources* **41**(2), 83–85 (2020)
- Yao, X., Liu, S., Han, L., et al.: Classification system and definition of glacial lakes: toward glacial lake cataloging and GLOF studies. *Acta Geogr. Sin.* **72**(7), 1173–1183 (2017)
- Zhang, X., Li, N., You, X., et al.: Study on glacial lake outburst floods in the Yarkand River, Xinjiang. *Sci. China B* **11**(1197–1204), 1233–1234 (1989)
- Zheng, X., Zhang, C., Wang, X., et al.: Emergency measures for the 2022 Merzbacher Glacier-dammed lake outburst flood in Xinjiang. *China Flood & Drought Management* **33**(1), 34–37 (2023)
- Zhu, C., Zhang, X., Fang, H., et al.: Remote sensing estimation of glacial lake water volume without underwater terrain data in plateau regions. *Journal of Remote Sensing* **26**(1), 148–154 (2022)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Dynamic Characteristics of Offshore Wind Turbine Cap-Pile Group Structure Based on Experimental Modal Analysis

Yuan Liu¹, Jianjian Zhao², Luchen Zhang¹(✉), Hao Hu², Lei Yu¹, Yu Wang¹,
Chuang Liu¹, and Shaoze Luo¹

¹ Nanjing Hydraulic Research Institute, Nanjing, China
110455898@qq.com

² Huaneng Jiangsu Clean Energy Branch, Nanjing, China

Abstract. Wind power generation is clean renewable energy, and offshore areas are ideal locations for constructing wind farms. However, research on the dynamic characteristics and response features of large-scale offshore wind turbine support systems under multi-load excitation from water, wind, and electromechanical forces remains insufficient. Taking the Donghai Bridge offshore wind farm demonstration project as the engineering background, this paper studies the dynamic characteristics of offshore wind turbine cap-pile group structures based on experimental modal analysis methods, with a focus on analyzing their flow-induced vibration response under complex environmental conditions. The results show that the first-order modal frequency of the foundation pile group is 2.83 Hz, mainly manifested as tower swaying; the second-order modal frequency is 14.83 Hz, reflecting the overall bending behavior of the cap-pile group. Tidal flow and waves have significant effects on the structural vibration response, especially the wave force energy is much greater than tidal flow pulsation, and its impact on foundation pile group vibration cannot be ignored. Therefore, this study provides important reference for the design and optimization of offshore wind turbine support systems, particularly in addressing safety and stability under multiple load scenarios.

Keywords: Offshore wind turbine support system · Structural dynamic characteristics · Dynamic response · Experimental modal analysis method

1 Introduction

Among renewable clean energy sources, offshore wind power has the advantages of abundant reserves, high wind speeds, no occupation of land resources, and minimal environmental noise constraints. The Global Wind Energy Council pointed out in the “Global Wind Report 2025” that in 2024, global onshore wind power newly installed capacity reached 109 GW, offshore wind power newly installed capacity reached 8 GW, and the current global total cumulative wind power installed capacity has reached 1,136 GW (Global wind report 2025). However, as the unit power of wind turbines increases, the dynamic safety of the unit support system composed of tower-cap-foundation piles

under dynamic loads from waves, tides, wind, and electromechanical forces has gradually become a key technical challenge.

In recent years, numerous scholars have conducted in-depth research on the dynamic response of offshore wind turbine foundations. Duan (2017) et al. used the discrete element method to study the dynamic response of rigid monopile foundations under horizontal cyclic loads, with simulation results showing good agreement with experimental measurements. Lopez-Querol (2017) et al. respectively employed finite element and discrete element methods to study the interaction between gravity foundations and monopile foundations with soil, focusing on analyzing changes in excess pore water pressure and shear strain under cyclic loads. Wang (2017) et al. compared the bearing performance of suction caisson foundations with different aspect ratios through centrifuge tests, concluding that wide-shallow foundations have higher horizontal bearing capacity and that bearing capacity in dry sand is greater than in saturated sand. Corciulo (2017) et al. and Krathe (2017) et al. respectively simulated the dynamic response of monopile foundations using the OpenSees platform and improved FAST model, studying the influence of soil permeability and stiffness damping on natural frequency. Abhinav (2017) et al. conducted coupled aerodynamic and hydrodynamic research on jacket foundations, demonstrating that soil-structure interaction in soft clay and layered soil has significant influence on random response. Furthermore, Abed (2016) et al., Carswell (2016) et al., and Kim (2016) et al. respectively deepened the understanding of foundation dynamic performance from the aspects of static impedance, short-term cyclic loads, and long-term cyclic loads.

Although extensive research has explored the dynamic characteristics of cap-pile group structures under single factors, research comprehensively considering multiple loads and environmental conditions remains scarce. Therefore, this study takes the Donghai Bridge offshore wind farm as the research object and explores the dynamic characteristics of offshore wind turbine cap-pile group structures through experimental modal analysis methods. The research will focus on the following questions: What are the modal parameters of cap-pile groups under flow-induced vibration? What differences exist in the modal frequency and vibration characteristics of cap-pile groups under different environmental conditions?

2 Materials and Methods

2.1 Research Object

The Donghai Bridge offshore wind farm is located in the eastern waters of Donghai Bridge in Shanghai, with a total installed capacity of 102 MW, installing 34 SL3000 offshore wind turbines with a single unit capacity of 3 MW. The wind farm sea area ranges 8–13 km from the shoreline, arranged in 4 rows at a distance of 1 km from Donghai Bridge on the eastern side of the bridge. The north-south spacing between wind turbines (along the Donghai Bridge direction) is approximately 1000 m; the east-west spacing (perpendicular to Donghai Bridge direction) is approximately 500 m.

The wind turbine foundation adopts a high-pile concrete cap structure, supported through steel pipe connectors embedded 3.5 m into the concrete cap with a diameter of 4.5 m. The cap has a diameter of 14.0 m and thickness of 3.0–4.5 m, supported by

8 steel pipe piles. The steel pipe piles have a diameter of 1.7 m, adopt a 5:1 inclined pile arrangement, are symmetrically arranged in a circular pattern, with an inclined pile centerline radius of 5.0 m at the cap bottom.

2.2 Structural Dynamic Characteristic Test Method

The dynamic characteristics of structures are usually described by the structural modal frequencies and corresponding modal damping and mode shapes. These are inherent characteristics of the structure itself. When the structural configuration, external dimensions, and materials are determined, that is, when structural characteristic parameters such as mass, stiffness, and damping are determined, the dynamic characteristics are also determined. Simple structures can solve their dynamic characteristics through mathematical analytical methods, while complex spatial structures like tower-cap-pile groups are suitable for experimental modal analysis methods.

Experimental modal analysis is an advanced technology for studying the dynamic characteristics of complex structures. It is a method that combines the advantages of mathematical models and physical models. Through physical model experiments, it obtains the vibration response of structures under given external force excitation, substitutes force and response into mathematical models, and solves the dynamic characteristics of structures through mathematical operations.

This paper adopts the method of point-by-point excitation and single-point (17) response to obtain relevant information. That is, arbitrary magnitude forces are applied to excite each node sequentially, while recording the excitation force and the x, y, z three-direction vibration response signals of fixed node (17). After charge amplifier filtering and amplification, anti-aliasing filtering is performed, then sent to the computer. Through time-domain complex exponential fitting, transfer functions are obtained, and then structural modal frequencies, corresponding damping, and mode shapes are obtained. Excitation uses an impact hammer, with force magnitude measured through a force sensor mounted on the hammer head, and vibration response measured using three miniature acceleration sensors. The test block process is shown in Fig. 1.




Fig. 1. Test process for structural dynamic characteristics

2.3 Structural Elastic Model

The dynamic characteristic model of the cap-pile group is designed according to elastic similarity, with a geometric scale ratio of 1:34. According to structural configuration characteristics, the structure is discretized into 80 nodes, with each node considering three directions: water flow direction x , transverse direction y , and vertical direction z , totaling 240 degrees of freedom. Node arrangement is shown in Fig. 1, and the model is shown in Fig. 2.




Fig. 2. (a) Node arrangement diagram; (b) Structural elastic model schematic diagram

2.4 Modal Parameter Calculation

The unit impulse response function $h(t)$ of the structure is given by Eq. (1.1).

$$h(t) = \sum_{r=1}^N (A_r e^{\lambda_r t} + A_r^* e^{\lambda_r^* t}) \quad (1.1)$$

Using sampling time interval Δt , simultaneous discrete sampling of force and vibration response for M points yields the discrete impulse response function (Eq. 1.2).

$$h(m\Delta t) = \sum_{r=1}^N (A_r e^{\lambda_r m\Delta t} + A_r^* e^{\lambda_r^* m\Delta t}) \quad (m = 0, 1, 2, \dots, M-1) \quad (1.2)$$

The sampling interval is Δt , so the sampling frequency is $f = 1/\Delta t$, the acquisition period is $T = M\Delta t$, the frequency resolution is $\Delta f = 1/T$, and the analysis upper limit frequency $f_{\max} = 1/2\Delta t$.

The experimentally obtained force signal and vibration response signal are fitted with complex exponentials according to Eq. (1.3) to obtain structural modal parameters, which is called the experimental modal analysis time-domain method.

$$\begin{cases} R = e^{\lambda \Delta t} \\ R^* = e^{\lambda^* \Delta t} \end{cases} \quad (1.3)$$

$$\left. \begin{aligned} \omega_r &= \frac{1}{\Delta t} \sqrt{\ln R_r \ln R_r^*} \\ \xi_r &= \frac{\ln(R_r R_r^*)}{2\sqrt{\ln R_r \ln R_r^*}} \end{aligned} \right\} \quad (1.4)$$

3 Results and Discussion

3.1 Structural Dynamic Characteristics

The cap-pile group structural dynamic characteristic test signal sampling frequency was 1250 Hz, with data block size of 1024 points. Complex exponential fitting algorithm with time-domain identification was used to identify structural modal parameters. Structural modal parameters with practical engineering significance are usually the first few orders. The first 5 orders of average modal parameters characterizing structural dynamic characteristics are listed in Table 1, with corresponding mode shapes shown in Fig. 3.

The first-order modal frequency of the cap-pile group is 2.83 Hz, with the mode shape manifested as tower swaying. Since tidal flow loads do not directly act on the tower, hydraulic forces contribute less to the first-order vibration response of the foundation pile group. The second-order modal frequency is 14.83 Hz, with the mode shape manifested as overall third-order bending of the tower-cap-pile group. Hydraulic action mainly contributes to the second-order vibration response of the foundation pile group. The third to fifth-order modal frequencies are all greater than 20 Hz. The third-order mode shape is dominated by second-order bending of the pile group, the fourth-order mode shape is dominated by second-order bending of both tower and pile group, and the fifth-order mode shape is manifested as tower torsion.




Fig. 3. Mode shapes: (a) 1st order; (b) 2nd order; (c) 3rd order; (d) 4th order; (e) 5th order

Table 1. First 5 orders of structural average modal parameters

Order	Frequency (Hz)	Damping ratio (%)
1	2.83	2.85
2	14.83	3.50
3	20.95	2.85
4	25.63	2.82
5	45.19	2.69

3.2 Flow-Induced Vibration Response Analysis

Any structure will produce vibration problems of varying degrees under hydrodynamic action. The key is whether vibration harms its normal operation. The flow-induced vibration of cap-pile groups is closely related to the frequency and energy of hydrodynamic load excitation and the dynamic characteristics of the structure. If the low-order modal frequencies of the structure are in the high-energy region of hydrodynamic excitation, the structure may produce harmful vibration.

3.2.1 Tidal Flow Effects

Tidal turbulence and vortex shedding from flow around pile groups are among the excitation sources for foundation pile group vibration response. According to hydraulic test results in previous research (Zhang and Luo 2010), the maximum amplitude of tidal flow pulsating pressure is 10 kPa, with main energy concentrated within 10 Hz, pulsation dominant frequency between 0.1–1.5 Hz, water flow turbulence frequency around 1.5 Hz, and pile group vortex shedding frequency approximately 0.25 Hz. Structural dynamic characteristic test results show that the natural vibration frequency for overall bending of the foundation pile group is 14.83 Hz.

Structural modal frequencies in water decrease by about 20% compared to air. Based on this, the overall bending modal frequency of the foundation pile group in water is approximately 11.8 Hz, while the hydrodynamic pulsation dominant frequency is less than 1.5 Hz. The ratio of hydrodynamic excitation frequency to modal frequency is approximately $0.13 < 0.4$, far from the high-energy region of tidal flow excitation. Tidal flow pulsation acting alone has little impact on foundation pile vibration.

3.2.2 Wave Effects

In marine environments, waves are another major hydrodynamic load, and the interaction problem between waves and piles is also a classic topic. Currently, numerical simulation methods are commonly used: when calculating large-scale objects, potential flow theory is generally adopted, ignoring velocity forces caused by fluid viscosity; for small-scale objects, the Morison formula is commonly used, ignoring diffraction forces of fluid on

objects. However, for cap-pile group structures, not only must phase differences between wave forces on each pile be considered, but also mutual influences between piles, and the existence of caps further increases the complexity of numerical calculations. Therefore, physical model test methods are appropriate for research.

Lan Yamei et al. conducted hydrodynamic model tests to study wave forces on Donghai Bridge pier caps (similar to the foundation pile structure of the project in this paper). The comparison between maximum wave force spectrum and tidal pulsating pressure spectrum is shown in Fig. 4. It can be seen that the dominant frequency of waves is smaller, around 0.16 Hz, but its energy peak value is more than 10 times that of tidal pulsation. The action energy of wave forces is much greater than tidal flow pulsation, and its impact on foundation pile group vibration cannot be ignored and requires further research.




Fig. 4. Comparison of wave force spectrum and tidal fluctuating pressure spectrum

4 Conclusions

This paper studied the structural dynamic characteristics of cap-pile groups through experimental modal analysis methods and analyzed the structural flow-induced vibration response combined with tidal flow pressure pulsation characteristics.

- (1) The first-order modal frequency of the foundation pile group is 2.83 Hz, with mode shape dominated by tower swaying. The second-order frequency is 14.83 Hz, with mode shape manifested as overall bending of tower-cap-pile group. The third-order frequency is 20.95 Hz, with mode shape dominated by second-order bending of pile group. The fourth-order mode shape is dominated by second-order bending of both tower and pile group, and the fifth-order mode shape is manifested as tower torsion.
- (2) Tides and waves mainly act on caps and pile groups, mainly contributing to the second-order vibration response of foundation pile groups.
- (3) Considering that structural modal frequencies in water decrease by about 20%, the second-order modal frequency of pile groups is approximately 11.8 Hz, far from the high-energy region of tidal flow excitation. Tidal flow pulsation acting alone has little impact on foundation pile vibration.
- (4) The action energy of wave forces is much greater than tidal flow pulsation, and its impact on foundation pile group vibration cannot be ignored and requires further research.

Acknowledgments. This research was mainly financed by Science and Technology Project of China Huaneng Group (HNKJ23-H18).

References

- Abed, Y., Bouzid, D.A., Bhattacharya, S., et al.: Static impedance functions for monopiles supporting offshore wind turbines in nonhomogeneous soils-emphasis on soil/monopile interface characteristics. *Earthquakes and Structures* **10**(5), 1143–1179 (2016)
- Abhinav, K.A., Saha, N.: Stochastic response of jacket supported offshore wind turbines for varying soil parameters. *Renewable Energy* **101**, 550–564 (2017)
- Carswell, W., Arwade, S.R., DeGroot, D.J., et al.: Natural frequency degradation and permanent accumulated rotation for offshore wind turbine monopiles in clay. *Renewable Energy* **97**, 319–330 (2016)
- Corciulo, S., Zanolì, O., Pisanò, F.: Transient response of offshore wind turbines on monopiles in sand: role of cyclic hydro-mechanical soil behaviour. *Comput. Geotech.* **83**, 221–238 (2017)
- Duan, N., Cheng, Y.P., Xu, X.: Distinct-element analysis of an offshore wind turbine monopile under cyclic lateral load. *Proceedings of the Institution of Civil Engineers-Geotechnical Engineering* **2017**, 1–17 (2017)
- Global Wind Energy Council (2025) Global wind report 2025. Brussels, Belgium: Global Wind Energy Council. Available via <https://gwec.net/globalwindreport2025/>. Cited 30 Jul 2025
- Kim, J.M., Son, S.W., Bagheri, P., et al.: Long-term cyclic behavior of soils supporting offshore wind turbine foundation. *Japanese Geotechnical Society Special Publication* **2**(33), 1218–1221 (2016)
- Krathe, V.L., Kaynia, A.M.: Implementation of a non-linear foundation model for soil-structure interaction analysis of offshore wind turbines in FAST. *Wind Energy* **20**(4), 695–712 (2017)
- Lan, Y., Xue, L., Liu, H., et al.: Experimental studies on hydrodynamic loads on piles and slab of Donghai Bridge Part I: hydrodynamic forces on a single pile in wave-current combinations. *J. Hydrodyn.* **19**(6), 753–758 (2004). (in Chinese)
- Lopez-Querol, S., Cui, L., Bhattacharya, S.: Numerical methods for SSI analysis of offshore wind turbine foundations. In: *Wind Energy Engineering: A Handbook for Onshore and Offshore Wind Turbines*, p. 275 (2017)

- Wang, X., Yang, X., Zeng, X.: Centrifuge modeling of lateral bearing behavior of offshore wind turbine with suction bucket foundation in sand. *Ocean Eng.* **139**, 140–151 (2017)
- Zhang, L., Luo, S.: Study on tidal flow fluctuating pressure properties of offshore wind generators pile group foundation. *Engineering Mechanics* **27**, 236–239 (2010). (in Chinese)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Application and Future Trends of Intelligent Construction in Hydropower Engineering: A Case Study of TB Hydropower Station

Li-Qiao Lu¹(✉), Guo Li¹, Ai-Wu Zheng¹, Lei Ni², Zhi Li², and Tian-wei Zhang²

¹ China Huaneng Group Co., Ltd, Beijing 100031, China
LuLiQiao2009@126.com

² Huaneng Lancang River Hydropower Inc., Kunming 650214, China

Abstract. Addressing the current focus of intelligent construction in hydropower projects primarily on dam building, this paper demonstrates the significance and innovation of the ‘1 + 3 + N’ intelligent construction system developed for the TB hydropower project. The system expands intelligent construction functionalities and has been comprehensively applied to the TB project. Supported by ‘1’ intelligent construction platform, it focuses on ‘3’ key technologies of intelligent dam, intelligent aggregate processing, and intelligent underground powerhouse, and covers ‘N’ application scenarios across all aspects of the construction area. Based on the closed-loop control theory of comprehensive perception, accurate analysis, real-time control, and continuous optimization, the system achieves engineering practice and application of intelligent construction modules, effectively promoting the high-quality and efficient completion of the TB project. Notably, it produced the longest core sample (26.5 m) of roller-compacted concrete (RCC) in China. The ‘1 + 3 + N’ system can be extended to various types of hydropower projects including pumped storage power stations, laying the foundation for integrated basin-level intelligent construction. Future recommendations include building an autonomous full-life-cycle smart hydropower platform, deepening the application of intelligent construction platforms, improving hardware infrastructure, formulating standards and norms, creating ‘BIM +’ application scenarios, and strengthening contractual agreements.

Keywords: hydropower project · intelligent construction · intelligent dam · intelligent aggregate processing · intelligent underground powerhouse · TB hydropower project

1 Introduction

As of April 2025, China’s hydropower installed capacity has reached 440 million kilowatts, accounting for 12.6% of the nation’s total power generation capacity. In 2024, hydropower generation reached 1,423.9 billion kilowatt-hours, representing 14.4% of

Supported by China Huaneng Group Co., Ltd. Foundation under Grant Nos. HNKJ20-H21, HY2020/D6

the national total. Advances in industrial technology have driven innovation in dam construction, progressing through stages of traditional manual labor, mechanization, automation, digitization, and intelligence [1, 2].

With the deepening research on intelligent construction, hydropower projects are increasingly adopting refined control and management. Intelligent construction, a product of digitization and intelligence, has evolved through three phases: digitization, digital networking, and intelligence [3]. The Nuozhadu Hydropower Station pioneered digital construction quality control technology, using GPS and PDA to develop a 'Digital Dam' system for real-time, all-weather monitoring of high earth-rock dam construction, ensuring RCC quality and marking the beginning of the digital era in dam building [1, 4]. The Huangdeng Hydropower Station established a closed-loop feedback control platform integrating concrete production, intelligent monitoring, and simulation analysis, achieving full digitization and partial intelligence in RCC dam construction [5]. The Xiluodu Hydropower Station developed the iDam platform for collaborative operations, implementing closed-loop intelligent construction practices for arch dams [6, 7]. The Baihetan Hydropower Station proposed the closed-loop control theory of 'comprehensive perception, accurate analysis, and real-time control' [8]. The Yingliangbao Hydropower Station pioneered intelligent vibroflotation equipment and technology to address complex foundation treatment in deep overburden layers, resolving quality control challenges in vibro-pile construction [9, 10]. With the trend of hydropower development in high-altitude regions, scholars have also studied the challenges and solutions for intelligent construction in such areas [11].

Current research on intelligent construction remains largely confined to dam building [12, 13], focusing either on technological upgrades (e.g., intelligent compaction, temperature control) or on platforms integrating multiple functions (e.g., the iDam platform for arch dams [6] and the information integration platform for the Nuozhadu core rockfill dam [13]).

This paper addresses these limitations by proposing the milestone '1 + 3 + N' intelligent construction system. For the first time, this system extends intelligent construction to cover dams, powerhouses, aggregate processing, and business management, offering specialization, refinement, and scalability for diverse hydropower projects. Applied to the TB project, it achieved full intelligence, producing a 26.5-m RCC core sample, establishing the first smart hydropower station in the Lancang River basin, and laying the foundation for basin-wide intelligent construction integration.

2 Concept of Intelligent Construction '1 + 3 + N' System

The hub buildings of TB hydropower project mainly consist of water retaining structures, flood discharge and energy dissipation structures, and underground water transmission and power generation systems on the right bank. The water retaining structure is a roller compacted concrete gravity dam with a crest elevation of 1740 m and a height of 158 m. The water transmission and power generation system is equipped with four mixed flow units with a single capacity of 350 megawatts, i.e., with a total installed capacity of 1400 megawatts. The construction of TB hydropower project adheres to the development concept of 'leading by key technological innovation, supported by intelligent construction

platform, and creating benchmark projects for TB hydropower’. Based on the ‘digital dam’ of Nuozhadu and comprehensive digitization of the Huangdeng hydropower station, an innovative ‘1 + 3 + N’ system for intelligent construction of large-scale hydropower projects has been established.

The ‘1 + 3 + N’ system of intelligent construction is supported by the construction of ‘1’ intelligent construction platform, focusing on the research of ‘3’ key technologies including intelligent dam construction, intelligent sand and stone processing, and intelligent underground powerhouse, gradually covering the ‘N’ application scenarios of engineering construction in all aspects, processes, and life cycles, as shown in Fig. 1.




Fig. 1. The diagram the ‘1 + 3 + N’ intelligent construction system

3 One Green Intelligent Construction Platform

The construction of the TB green intelligent construction platform is based on GIS + BIM + VR + IoT technology, covering various aspects of work area construction. It follows the intelligent construction closed-loop control theory of comprehensive perception, accurate analysis, real-time control, and continuous optimization, realizing the functions of replicable standard functions, rapid development of special requirements, and seamless integration of heterogeneous systems. It can be extended to other types of power stations to leverage the collaborative management of ‘on-site supervision + remote video’.

The intelligent construction platform runs through the entire life-cycle of engineering construction, and the closed-loop control function parameters of each intelligent module are shown in Table 1.

4 Research and Application of Three Key Technologies

The key technologies of intelligent construction, including intelligent dam, intelligent aggregate processing, and intelligent underground powerhouse, constitute the core of intelligent construction, covering various aspects of work area construction.

4.1 Intelligent Dam Construction

The intelligent dam runs through the entire construction process of roller compacted concrete production, mixing, transportation, paving, rolling, vibration, and maintenance.

In the construction of inclined layer compaction, various warehousing methods such as full pipe chutes and truck warehousing is fully utilized. While adopting technologies such as overall lifting of gallery trolley templates, direct burial of gate slots, and rolling pouring of large inclined layers through warehouses to improve the efficiency of roller compacted concrete construction, an intelligent guidance and overspeed alarm function for the roller based on the compaction index analysis model is developed, which facilitates grasping the rolling trajectory and operation situation. After applying intelligent compaction technology, the average coverage time between the layers of compacted concrete is 5 h, the pass rate of concrete compaction is over 99%, and the pass rate of compaction degree reaches 100%. The production and application of unmanned compaction technology runs through the entire construction cycle of the dam, creating the first production example of unmanned compaction machine group concrete operation.

Temperature control is an important part of ensuring the quality of concrete. The innovative use of Freon refrigeration technology in the pre-cooling of roller compacted concrete aggregates avoids the safety hazards of traditional liquid ammonia refrigeration. During the pouring process, an intelligent temperature control system is used to monitor the temperature of the dam concrete in real time, and a temperature control simulation cloud computing platform is established for the entire dam area. The overall temperature control simulation calculation of the dam can be completed in 7–10 days. The intelligent monitoring equipment for concrete outlet temperature is developed, and the intelligent spray system is used to build the warehouse surface microclimate to effectively prevent the temperature of the warehouse surface from pouring back. The intelligent water supply system can adjust the chiller unit based on the maximum temperature and distribution inside the concrete, control parameters such as water supply timing, flow rate and direction, and valve opening to form the optimal temperature control strategy for concrete pouring blocks. The highest temperature qualification rate of concrete reached 97.4%, which comprehensively improved the temperature control level of dam concrete.

In terms of foundation treatment, the development and application of miniaturized and lightweight ultra-high pressure intelligent grouting equipment can automatically control grouting parameters and monitor the grouting process in real time during the grouting process. The grouting data is wirelessly transmitted to the grouting cloud platform, and through the intelligent grouting management system, pre-grouting feasibility analysis, post grouting effect analysis and evaluation are carried out. Intelligent anchor cable tensioning equipment and systems in the field of hydropower are developed, achieving visualization, precision, and intelligent control of the tensioning process.

4.2 Intelligent Sand and Stone Processing System

The TB Hydropower Station uses gabbro as the aggregate. To address the challenge of high fine-particle content in gabbro, a method for utilizing gabbro in large-scale RCC preparation is developed through research and validation [14]. During aggregate processing, advanced dust removal, noise reduction, and pollution control technologies and

equipment are adopted, achieving efficient and low-energy standardized production of aggregates. A 3D visual monitoring system is established, and an online particle size monitoring system with intelligent inspection robots replaces manual labor, achieving an accuracy rate of 97.5%. Through the application of automatic control, information management, and intelligent decision-making, aggregate production capacity is significantly increased, exceeding the design capacity by 50% for eight consecutive months.

4.3 Intelligent Underground Powerhouse

A safety intelligent dynamic control technology for large underground cavern groups is developed, enabling intelligent monitoring and early warning of surrounding rock stability during construction. This facilitates informatized design and construction of underground engineering. During excavation, the ‘one-hole-to-bottom’ precision blasting technique and the ‘deep-hole pre-splitting, thin-layer excavation, and immediate support’ method are implemented, setting a new record with a pre-splitting depth of 16 m for high sidewalls. The reserved rock cover construction method for large hydropower projects is proposed, breaking the limitations of traditional top-down sequential construction and enabling multi-dimensional parallel construction of underground caverns.

An online environmental monitoring and intelligent ventilation system is established for underground caverns, reducing post-blast air quality recovery time by 20%, increasing ventilation efficiency by over four times, and lowering energy consumption by 40%. This ‘people-oriented, life-first’ approach ensures the safety and health of construction personnel.

5 N Application Scenarios

The ‘N’ application scenarios in intelligent construction serve as the implementation focus. The closed-loop control functions of intelligent construction are analyzed using examples such as intelligent compaction, intelligent mixing, intelligent spraying, intelligent water cooling, intelligent thermal insulation, intelligent grouting, intelligent aggregate processing, safety intelligent dynamic control, intelligent ventilation, and business management, as listed in Table 1.

Table 1. Closed-loop control parameters of the ‘1 + 3 + N’ intelligent construction system

	Comprehensive Perception	Accurate Analysis	Real-Time Control	Continuous Optimization
Intelligent Compaction	Paver speed, paver thickness, roller speed, compaction thickness, number of passes, vibration force	Compaction degree, inter-layer time, roller trajectory	Paver speed, paver thickness, roller speed, compaction thickness, number of passes, vibration force	Compaction degree, inter-layer time

(continued)

Table 1. (continued)

	Comprehensive Perception	Accurate Analysis	Real-Time Control	Continuous Optimization
Intelligent Mixing	Ambient temperature, concrete mix ratio	Aggregate temperature, cement temperature, sand temperature, mixing water temperature, ice addition temperature	Ice addition amount, water addition amount, aggregate temperature	Outlet temperature
Intelligent Spraying	Slab surface temperature, wind speed, humidity, radiant heat	Placing temperature, pouring temperature	Spray volume, spray intensity, spray angle	Ambient temperature, pouring temperature
Intelligent Water Cooling	Internal concrete temperature, internal stress, water flow rate, slab surface temperature, radiant heat	Temperature gradient, temperature distribution, peak temperature, pouring temperature	Cooling timing, water temperature, flow rate, direction, pressure difference, valve opening	Cooling process, temperature reduction range, cooling rate, temperature gradient
Intelligent Thermal Insulation	Ambient temperature	Internal concrete temperature, temperature gradient	Insulation timing, thickness, location	Concrete surface stress
Intelligent Grouting	Grouting pressure, flow rate, slurry density, uplift	Groutability, grout consumption	Grouting pressure, flow rate, slurry density	Grouting quality
Intelligent Aggregate Processing	Aggregate particle size	Aspect ratio, roundness, gradation	Aggregate crushing strength	Gradation
Safety Intelligent Dynamic Control	Surrounding rock stress, strain	Rock deformation	Support force, displacement	Support timing, intensity
Intelligent Ventilation	Dust, SO ₂ , CO, CO ₂ , NO ₂ , air temperature, humidity	Gas concentration, distribution	Fan speed, frequency, power	Ventilation speed

- a. Intelligent compaction. During compaction, parameters such as paver speed, paver thickness, roller speed, compaction thickness, number of passes, and vibration force are monitored and controlled. The compaction degree is analyzed, the inter-layer time is calculated, and the roller's strip operation trajectory is monitored in real time. If missed compaction areas are detected during strip operations, monitoring personnel promptly notify on-site workers to perform supplementary compaction, ensuring compliance with standards for compaction degree and inter-layer conditions in the intelligent compaction system.
- b. Intelligent mixing. The intelligent mixing system analyzes aggregate temperature, cement temperature, sand temperature, mixing water temperature, and ice addition temperature based on environmental conditions and concrete mix ratios. It monitors post-mixing concrete temperature and determines the necessity of ice addition according to mixing standards. The system calculates the ratio of water and ice additions, adjusts aggregate temperature, and ensures the discharge temperature meets construction requirements.
- c. Intelligent spraying. During high-temperature summer construction, the system comprehensively monitors slab surface temperature, wind speed, humidity, and radiant heat to analyze concrete placing and pouring temperatures. The intelligent spraying system controls spray volume, intensity, and angle to create a microclimate on the slab surface, continuously improving ambient temperature and reducing concrete pouring temperature.
- d. Intelligent water cooling. After concrete placement, real-time data on internal temperature, stress, water flow rate, slab surface temperature, and radiant heat are collected. The system calculates temperature gradients, distribution, peak temperature, and pouring temperature to precisely control cooling timing, water temperature, flow rate, direction, pressure difference, and valve openings. This optimizes the cooling process, minimizing temperature reduction range, cooling rate, and gradients to prevent cracking.
- e. Intelligent thermal insulation. During winter construction, ambient temperature is monitored in real time. The system analyzes internal concrete temperature and gradients to determine insulation timing, location, and thickness, thereby controlling surface stress and effectively preventing cracks.
- f. Intelligent grouting. Based on geological core data, the intelligent grouting equipment automatically adjusts and controls grouting pressure, flow rate, and slurry density while monitoring potential uplift. The system calculates groutability and slurry consumption rates beforehand, providing references for operators and evaluating post-grouting quality.
- g. Smart aggregate processing. The aggregate processing system employs intelligent devices like particle shape monitors and inspection robots. Image analysis determines particle size, aspect ratio, roundness, and gradation, while controlling crushing intensity at each stage to produce aggregates meeting specified gradation requirements.
- h. Safety intelligent dynamic control. For large underground cavern excavations, comprehensive monitoring of surrounding rock stress and strain enables deformation analysis. The system provides basis for support force and displacement decisions,

issues real-time warnings for deformation trends, and continuously optimizes support timing and intensity as construction progresses.

- i. Intelligent ventilation. Underground construction monitors dust, SO_2 , CO , CO_2 , NO_2 , air temperature, and humidity to ensure worker safety and health. Sensors analyze gas concentrations and distribution, automatically adjusting fan speed, frequency, and power to maintain air quality standards. Variable frequency control optimizes ventilation speed while reducing energy consumption.
- j. Business management. Spanning the entire project life-cycle, business management facilitates enterprise digital transformation through personnel/equipment management, quality/environmental control, construction process management, resource allocation, cost management, and electronic archiving. Digital twin technology enables seamless data transfer, full-service coverage, and life-cycle information tracking with professional, refined, and scalable features adaptable to various hydropower projects.

6 Engineering Application Results

The '1 + 3 + N' system effectively ensures the safe, high-quality, and efficient construction of TB hydropower projects. The dam has extracted the longest core of roller compacted concrete with a length of 26.5 m and a diameter of 25 cm, setting a record for the average monthly rise height of 14 m for five consecutive months, the maximum monthly rise height of 18 m, and the annual layer rise of 126 m. The daily pouring intensity of roller compacted concrete is 11300 cubic meters, and the monthly pouring intensity is 23000 cubic meters. It is poured to the top of the dam in 20 months, which is at an advanced level in China. The pollution prevention and energy consumption control in the process of sand and gravel processing have achieved significant results. The surrounding rock of the underground factory building is generally safe and stable, and the health of the construction personnel is effectively guaranteed.

Based on the successful construction of TB hydropower station, the '1 + 3 + N' system has laid the technical foundation for intelligent construction, from single hydropower station to collaborative management of multiple hydropower stations in the basin, covering the full life cycle construction of various dam types, and transforming and upgrading to support the 'local + remote' management mode. It provides valuable experience for the subsequent construction of hydropower stations and promotes the further development of the hydropower industry.

7 Development Trends

To promote safe, high-quality, green, and efficient construction of hydropower projects, we recommend continuously enhancing the application of digital technologies such as BIM and GIS throughout the entire project life-cycle. This will facilitate digital handover, create digital twin projects, and lay the foundation for smart operation and maintenance. The goal is to establish demonstration projects where digital twin and physical hydropower projects are constructed, accepted, and delivered simultaneously. The following recommendations are proposed for intelligent construction and BIM applications:

- a. Development of autonomous full-life-cycle smart hydropower platforms. Strengthen the application of BIM, GIS, and artificial intelligence to research and develop full-life-cycle smart hydropower platforms that meet the needs of both construction and operation. Implement unified management of BIM and GIS models developed by different design institutes and platforms.
- b. Deepening the application of intelligent construction platforms. 1) Integrated multi-disciplinary planning: Establish a collaborative management platform for owners, designers, supervisors, and contractors. Ensure platform modules align with on-site management processes, transitioning offline work to online platforms to make them indispensable daily tools. Enhance data standardization and interface construction for external professional systems to enable real-time data exchange and information sharing. Store raw data from professional systems in a unified intelligent database and integrate key data, reports, and results into the management platform. 2) Continuous optimization of platform functions: Directly incorporate data collected through apps, professional systems, safety monitoring, testing, and intelligent recognition into the management platform and unified database to reduce manual data entry. Streamline workflows based on the principles of 'small, practical, and precise,' optimize document processes, ensure timely archiving, and strengthen the management and compliant use of electronic signatures to improve efficiency. 3) Comprehensive data management: Integrate intelligent construction systems with future plant operation management needs, particularly for hydraulic structures like dams, to achieve seamless digital delivery.
- c. Improving hardware infrastructure in construction areas. Under unified planning, initiate network, server, and data center construction before project commencement to establish a robust foundation for intelligent construction. Strengthen top-level design of on-site network solutions and deploy network infrastructure early. Ensure full coverage of wired and wireless dedicated networks, along with public internet, before construction begins. Maintain stable and secure networks throughout the project to support future smart inspections and monitoring.
- d. Formulating standards and specifications. Systematically organize and promote the development of standards for intelligent construction data, interfaces, BIM applications, and platform construction, establishing a standardized system for hydropower projects. Integrate mature hydropower management practices into digital workflows, clarifying objectives, functions, and standards for digital design, intelligent construction, and smart operation. Achieve unified data integration and seamless information exchange to maximize the benefits of intelligent construction systems.
- e. Creating 'BIM +' application scenarios. Explore BIM applications during construction to enhance understanding of its value among construction personnel. Develop demonstration projects for key components to showcase full-chain applications. Conduct rigorous simulations of construction progress and quantities for typical sections like diversion tunnels and dams. Integrate BIM with professional systems (e.g., intelligent monitoring, compaction), quality acceptance, testing, cost settlement, and engineering economics to establish a BIM model-based data management system. Validate results against phase objectives, evaluate model effectiveness, summarize lessons learned, and propose improvements for future projects.

- f. Strengthening contractual agreements and clarifying responsibilities. 1) Feasibility study phase: Systematically plan intelligent construction requirements, deeply engage in platform module development, refine tasks and indicators, and establish a solid foundation for implementation. 2) Bidding phase: Summarize intelligent construction experiences to develop standardized bidding terms, contract interfaces, and management measures. Define responsibilities for owners, designers, supervisors, and contractors to enhance participation enthusiasm. 3) Construction phase: Refine work scopes and delivery requirements for each contract section. Link intelligent construction and BIM performance to payment milestones to ensure smooth implementation.

References:

1. Li QB, Shi J (2015) Dam Construction 4.0. *Journal of Hydroelectric Engineering*, 34(8):1–6
2. Zhong, D.H., Wang, F., Wu, B.P., et al.: From digital dam to smart dam. *Journal of Hydroelectric Engineering* **34**(10), 1–13 (2015)
3. Li, Q.B., Ma, R., Hu, S., et al.: Research progress and development trends of intelligent dam construction. *Journal of Tsinghua University (Science and Technology)* **62**(8), 1252–1269 (2022)
4. Ma, H.Q., Zhong, D.H., Zhang, Z.L., et al.: Key technologies for real-time control in major hydropower projects and their engineering applications. *Engineering Science* **13**(12), 20–27 (2011)
5. Ma, H.Q., Chi, F.D., Pang, B.H.: Research and application of comprehensive digital construction technology for Huangdeng high RCC dam. In: *Proceedings of the International Symposium on New Developments in Roller-Compacted Concrete Dam Technology and High-Quality Dam Construction Management*. China Three Gorges Press, pp. 19–29 (2019)
6. Fan, Q.X., Zhou, S.W., Lin, P., et al.: Complete set technology and application of intelligent construction control for large hydropower projects. *J. Hydraul. Eng.* **47**(7), 916–923 (2016)
7. Fan, Q.X., Lin, P., Wei, P.C., et al.: Closed-loop control theory for intelligent construction. *Journal of Tsinghua University (Science and Technology)* **61**(7), 660–670 (2021)
8. Tan, Y.S., Fan, Q.X., Wang, Z.L., et al.: Intelligent construction technology and application practice for Baihetan super-high arch dam. *Journal of Tsinghua University (Science and Technology)* **61**(7), 694–704 (2021)
9. Fan, Q.X., Li, G., Ma, B., et al.: Intelligent vibroflotation methods and systems for deep overburden foundations. *J. Hydraul. Eng.* **54**(12), 1393–1403 (2023)
10. Li, G., Jiang, X.C., Ma, B., et al.: Research and application of intelligent vibroflotation control system. In: *China National Committee on Large Dams, Brazilian Committee on Dams, Spanish National Committee on Large Dams, US Society on Dams (eds) Building Safe, Resilient and Green National Water Network*. Pp. 76–86 (2024)
11. Fan, Q.X., Lin, P., Wei, P.C., et al.: Challenges and countermeasures for intelligent construction of hydropower projects in high-altitude regions. *J. Hydraul. Eng.* **52**(12), 1404–1417 (2021)
12. Zhong, D.H., Shi, M.N., Cui, B., et al.: Research progress on intelligent dam construction. *J. Hydraul. Eng.* **50**(1), 38–52 (2019)
13. Cui, B.: *Theory and Application of Real-Time Quality Monitoring System for Core Rockfill Dams*. Tianjin University (2010)
14. Liu, K.Y., Liu, J.S., Zhou, H.B., et al.: A Gabbro Aggregate Roller-Compacted Concrete and its Preparation Method. *China Patent ZL202211637430.5* (2025)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Construction and Validation of a Data-Driven Static Surrogate Model for Prestressed Steel-Concrete Joints

Li Chong, Yu Fangliang, Zheng Luyao^(✉), and Li Bo

Yellow River Engineering Consulting Co., Ltd., Zhengzhou, China

1326560361@qq.com

Abstract. With the continuous improvement of the requirements for water ecological and water environment friendliness, intelligence, and landscaping in water conservancy project construction, the application of steel structures in hydraulic structures has become increasingly widespread. As a high-load-bearing connection node of steel-concrete structures, the prestressed steel-concrete joint has broad application scenarios in the fields of water conservancy engineering and even structural engineering. This study relies on the prestressed steel-concrete joint at the connection between the main girder of a special-shaped cable-stayed bridge and the pedestrian bridge of a cross-sea bridge-lock project in Hainan Province. Through parametric nonlinear simulation analysis, taking the thickness of the steel box plate, the height of the steel box, the insertion depth of the steel box into the concrete, and the vertical load as independent variables, and the vertical displacement of the joint as the dependent variable, 20,774 pieces of effective data were collected. On this basis, the Support Vector Machine (SVM) method, Random Forest method, and Deep Neural Network (DNN) method in machine learning were respectively used. With 4-dimensional input features and 1-dimensional output labels set, the aforementioned samples were used for training and testing to form an engineering structure surrogate model. The results show that the performance evaluation index R^2 of the three regression methods is 0.953, 0.997, and 0.999 respectively. Among the performances of the nonlinear load-displacement curves of the test set, the DNN method has the best prediction effect, reflecting the strong adaptability of the DNN method in the data-driven engineering structure surrogate model. The surrogate model empowers the refined and rapid design of multiple prestressed steel-concrete joint structures in this project, saving a large amount of computing power and time costs compared with the traditional finite element method.

Keyword: Machine Learning · DNN Neural Network · Surrogate Model
Prestressed · Steel-Concrete Joint · Static Feature Learning

1 Introduction

1.1 Engineering Background

The cable-stayed bridge project integrated with a bridge and a sluice is located in the northwest of Hainan Province. After its completion, the project will be of great socio-economic significance for improving the surrounding road network, promoting regional economic development, and enhancing water ecology and landscape. The main bridge is a special-shaped pylon cable-stayed bridge integrated with a sluice and a bridge, with an outward-protruding leisure path. The sluice-bridge can intelligently open and close the sluice gates according to the drought and flood cycles to regulate and store water levels, provide water for the migration and reproduction of organisms, and also has functions such as wind prevention, flood drainage, and water environment improvement.

The project features an elegant appearance. The outer surface of the bridge pylon is a special-shaped torsional curved surface, and the cable plane is in the shape of a saddle. On both the inner sea side and the outer sea side of the sluice-bridge, a pedestrian leisure path is set up. The leisure path is fixed to the concrete main girder body through the steel structure cantilever. And prestressed anchor cables are applied to the steel box bearing plate to assist in force bearing. Due to the up-and-down undulation and left-and-right swinging of the leisure path along the longitudinal direction of the bridge, the length, inclination angle and the transmitted load of the cantilever structure are all different. In the transverse direction of the bridge, prestressed steel strands are used to anchor the steel-concrete joints through the bearing plate to resist the vertical load. There are a total of 80 pairs of steel-concrete joints throughout the bridge (Figs. 1, 2 and 3).




Fig. 1. Elevation Layout Plan of the Sluice-Bridge

1.2 Research Status

In the field of civil engineering, the regression prediction of structural bearing capacity is an important research direction. With the rise of big data technology, machine learning




Fig. 2. Schematic diagram of the connection between the overhanging leisure walkway and the main girder




Fig. 3. Schematic Diagram of the Prestressed Steel-Concrete Joint

methods, especially support vector machines (SVM), artificial neural networks (ANN), random forests, etc., have been widely applied to the prediction of structural bearing capacity. These methods can extract complex nonlinear relationships from a large amount of experimental data, thereby improving the prediction accuracy. The research literature on static characteristics in the field of structural engineering can be roughly divided into three aspects: the material level, the component level, and the system level.

At the material level, Zhou Mei et (1998) applied neural networks to predict the compressive strength value of concrete and explored a theoretical method for predicting the compressive strength of concrete [1]. Wu Xianguo et al. (2022) proposed a random forest prediction model for compressive strength after feature screening [2]. Cao Fei et al. (2021), based on the theory of support vector regression (SVR), proposed an artificial intelligence algorithm of weighted SVR (MWSVR) based on Mahalanobis distance to predict the strength of concrete [3]. Hai-Bang L et al. (2021) creatively proposed a DNN development process for predicting the compressive strength of rubber concrete [4]. Solomon O et al. (2023) for the first time applied DNN to predict the compressive strength of geopolymers concrete (GPC) made from corn cob ash and ground granulated blast furnace slag, and created a backpropagation learning algorithm based on the mix proportion of concrete to predict the strength of concrete [5].

At the component level, Wang Wenjie (2022) established different learning models for different types of data. Taking the problems of component shear resistance calculation

and overall structural health status evaluation, which are difficult to handle by traditional methods, as cases, he explored the feasibility of establishing a general machine learning model for analyzing and processing traditional data and text data. Finally, based on the interpretability method of machine learning, the credibility of the model prediction results was provided [6]. Wei Xing et al. (2011), in order to accurately predict the ultimate bearing capacity of PBL shear keys in steel-concrete composite structures, by analyzing the existing push-out test results, based on ANN, selected the BP neural network algorithm and developed a prediction system for the ultimate bearing capacity of PBL shear keys in steel-concrete composite structures based on the BP neural network [7].

At the system level, Li Ying et al. (2022) took a certain four-pyramid grid structure as the research object, used finite element analysis software to establish a grid structure model, and carried out an ultimate bearing capacity analysis on it. On this basis, using the neural network method, a prediction model for the bearing capacity of the damaged grid structure was established [8]. Qiao Peng et al. (2021), aiming at the problem that the technical condition evaluation of highway bridges based on the specification method requires manual determination of the influence weights of various factors, proposed an intelligent evaluation method for the technical condition of bridges based on machine learning [9]. Zhou X et al. (2024) proposed an erection cable force optimization method based on the DNN surrogate model and applied it to the prediction of the cable force of the completed bridge with the ideal completed bridge alignment [10].

Through methods such as regression analysis, machine learning, and deep learning, researchers have made remarkable progress in the field of civil engineering. Especially in the analysis of the structural bearing capacity, these methods not only improve the prediction accuracy but also provide strong support for engineering design and structural optimization.

2 Main Text

2.1 Construction of Parameterized Finite Element Model Based on ANSYS and Sample Collection

There are four materials in the finite element model, namely C50 concrete of the box girder, HRB400 steel bars, Q345 steel plates, and 1860 steel strands. Their constitutive models are defined respectively.

The constitutive model of C50 concrete adopts the MISO multi-linear isotropic hardening model. The Poisson's ratio is 0.2, and the unit weight is 2650 kg/m^3 . The solid65 element is used, and the additional terms of the shape function of the solid65 element are taken into account. Cracking and crushing are considered. The stress of the cracked element is slowly released. The ultimate compressive strain of the concrete is 0.33%, and the peak compressive strain is 0.2%. The three-directional reinforcement ratio is 1.5%. The standard value of the compressive strength of C50 is 32.4 MPa, and the standard value of the tensile strength of C50 is 2.65 MPa (Figs. 4, 5, 6 and 7).

The HRB400 steel bars adopt a bilinear constitutive (BISO bilinear isotropic hardening) model. The elastic modulus is 210 GPa, the Poisson's ratio is 0.3, the unit weight




Fig. 4. Constitutive Model of C50 Concrete




Fig. 5. Constitutive Model of HRB400




Fig. 6. Constitutive Model of Q345 Steel




Fig. 7. Finite Element Mesh

is 7850 kg/m^3 , and the stiffness is not considered after yielding. The steel bars are established using the beam188 element (different from the ordinary reinforcement ratio steel bars in the solid65 element).

The Q345 steel plate also adopts a bilinear constitutive model, using the shell63 element. The standard value of the material yield strength is 345 MPa, the elastic modulus is 210 GPa, the Poisson's ratio is 0.3, and the unit weight is 7850 kg/m^3 .

For the 1860 steel strands: The elastic modulus is 195 GPa, and the Poisson's ratio is 0.3. The link10 element is used to establish the steel strand element, and the initial

strain method is used to simulate the prestress. The designed tension control stress is 1395 MPa.

Combined with Saint-Venant's principle, the degrees of freedom of the nodes on the far-end concrete section plane at a certain distance from the steel-concrete joint are fully constrained, and the nodes of the steel box and the internal nodes of the concrete are treated as common nodes. The CERIG command is used to establish a rigid region for the section at the cut-off section of the cantilever. The mass21 element is used to overall control this rigid region for applying the load.

In order to save computing resources, after conducting a mesh independence check, a relatively fewer element meshing strategy is adopted. The structure has a total of 2,307 elements and 2,408 nodes. The finite element model is shown in the figure.

Select the parameters that are most sensitive to the structural mechanical response, namely the thickness of the steel box plate, the height of the steel box, the depth of the steel box inserted into the concrete, and the vertical load as independent variables (different vertical loads have been reflected in different load sub-steps). A three-layer cyclic loading is established. Among them, the thickness of the steel box plate varies from 30 mm to 45 mm with a step difference of 5 mm, the height of the steel box varies from 1000 mm to 1120 mm with a step difference of 40 mm, and the depth of the steel box inserted into the concrete varies from 1200 mm to 1080 mm with a step difference of 40 mm. A total of $4 \times 4 \times 4 = 64$ groups of nonlinear loading results and 20,774 groups of nonlinear sampling data are obtained.

In order to test the quality of the model, the mechanical responses of each component under the rated load are extracted and summarized as follows (Fig. 8):




Fig. 8. Summary of the mechanical response contour plots of each componen

The summary of the concrete cracking and crushing responses under the sequential load sub-case is extracted as follows (Fig. 9):

The load-displacement data of 64 groups of different combinations of independent variables are extracted and the curve diagram is drawn as follows. In the diagram, q , p , and n represent the thickness of the steel box plate, the height of the steel box, and the depth of the steel box inserted into the concrete respectively. The results show that the thickness of the steel box plate has the greatest influence on the structural stiffness (Fig. 10).




Fig. 9. Extraction of the time history simulation results




Fig. 10. The load-displacement curve diagrams of different combinations of independent variable

2.2 Establishment of Machine Learning and Deep Learning Architectures

In this study, the methods of Support Vector Machine (SVM), Random Forest, and DNN (Deep Neural Network) in machine learning are respectively adopted.

2.2.1 Model Constructn and Parameter Setting

1. Support Vector Regression (SVR): A non-linear regression model is constructed by using the Radial Basis Function (RBF). The RBF kernel processes complex non-linear relationships by mapping samples to a high-dimensional space, and its expression is

$$K(x_i, x_j) = e^{-\gamma \|x_i - x_j\|^2} \quad (2.1)$$

Among them, the parameter γ implicitly controls the bandwidth of the kernel function. The regularization parameters C and γ are not explicitly set in the model, and the default values $C = 1.0$ and $\gamma = 1/(n_features \cdot \text{Var}(X))$ are adopted. The complexity of the model and the training error are balanced through automatic parameter tuning.

2. Random Forest Regression: Integrate 25 decision trees ($n_estimators = 25$), and use the bootstrap sampling method to construct the base learners. Each tree minimizes the mean squared error through recursive feature partitioning (with no limit on the maximum depth), and finally outputs the predicted mean values of multiple trees. The randomness control parameter $random_state = 42$ ensures the reproducibility of the experiment. When splitting features, by default, $n_features$ features (2 features in this study) are examined, which effectively reduces the risk of overfitting.
3. DNN Model: Adopt the structure of a Multi-Layer Perceptron (MLP) to achieve end-to-end non-linear mapping. The model uses a fully connected neural network (beamNN), which is composed of an input layer, hidden layers, and an output layer. The input layer receives a 4-dimensional feature vector (including parameters such as the thickness of the steel plate q , the height of the steel box p , the depth of the steel box inserted into the concrete n , and the axial force FY), and the output layer performs regression prediction of a 1-dimensional vertical displacement value. Three hidden layers are set, with 64 neurons in each layer, and the non-linear expression ability is introduced through the ReLU activation function.

2.2.2 Data Processing Flow

Data preprocessing includes two key stages: Firstly, normalization is carried out based on physical dimensions. The input features are linearly scaled according to the reference values [100.0, 1200.0, 1200.0, -22000000], and the output displacement value is normalized with -6mm as the benchmark. Secondly, standardization processing is performed. In machine learning, the Z-score method is used to transform the training set into a distribution with a mean of 0 and a variance of 1. The mean and variance of the training set are used for the test set to avoid data leakage. The data set is divided according to the experimental time sequence. The first 19,380 groups (93.3%) are the training set, and the last 1,394 groups (6.7%) are the test set, preserving the physical continuity of the load-displacement curve (Fig. 11).

The DNN uses DataLoader for data iteration. The training batch size is set to 300 to balance memory efficiency and gradient stability. The entire test set (1,394 items)




Fig. 11. The learning effect of big data training

is loaded to ensure the consistency of the overall evaluation. The Mean Squared Error (MSE) loss is used to measure the prediction deviation, and the Adam optimizer (with an initial learning rate of 0.0005) is used to adaptively adjust the parameter update step size. A StepLR scheduler is configured (`step_size = 100`, `gamma = 1`) to maintain a constant learning rate and ensure the stability of training. Dropout with a rate of 0.05 is introduced to suppress overfitting.

2.2.3 Model Evaluation Method

The coefficient of determination (R^2) is used as the core evaluation index to reflect the variance explanation rate between the predicted values of the model and the true values. The calculation formula is:

$$R^2 = 1 - \frac{\sum (y_i - \hat{y}_i)^2}{\sum (y_i - \bar{y})^2} \quad (2.2)$$

At the same time, through two-dimensional visual analysis: the horizontal axis represents the actual load value (N), and the vertical axis represents the displacement (mm). The predicted values (red scatter points) and the true values (black scatter points) are overlaid and plotted to intuitively evaluate the degree of curve fitting.

2.3 Model Training Evaluation and Prediction Effect

The experimental results show that the R^2 values of the SVM, Random Forest, and DNN networks are 0.9533, 0.99735, and 0.99981 respectively. The simulation data is more stable compared to the discrete experimental values. All three methods can effectively capture the mechanical response of the joint, among which the DNN network shows better prediction stability.

The change of the loss during the DNN training process and the prediction conclusions of the three methods are plotted as shown in the figure. In this example, the loss curve can achieve a rapid decline of the model training loss function within a very small number of training rounds, and the fitting result presents the same conclusion as the aforementioned R^2 . In this case, a single round of complete nonlinear iterative calculation takes 15 min, while the DNN surrogate model takes 0.2 s to simulate the entire nonlinear result, which shows remarkable effectiveness in saving computing power.

3 Conclusions

Through the static equilibrium analysis of 20,774 pieces of nonlinear finite element loading data in 64 groups, as well as the machine learning of the SVM method and the Random Forest method and the deep learning training and prediction of the DNN network for the data, this study draws the following conclusions:

1. The ANSYS nonlinear analysis shows that among the three-dimensional input variable features of the thickness of the steel box plate, the height of the steel box, and the depth of the steel box inserted into the concrete, the thickness of the steel box plate has the greatest influence on the structural stiffness, while the height of the steel box and the depth of the steel box inserted into the concrete have a relatively small influence on the structural stiffness.
2. By comparing the performance of the prediction sets of the machine learning Support Vector Machine (SVM) method, the Random Forest method, and the Deep Neural Network (DNN) model, it is shown that all three methods are reliable. The R^2 values of the SVM, Random Forest, and DNN network are 0.953, 0.997, and 0.999 respectively. The DNN model has a better fitting effect and its calculation efficiency is 4,500 times that of the finite element method.

The value of using surrogate models to replace finite element analysis (FEA) for result prediction essentially stems from the revolutionary balance it achieves between accuracy and efficiency. This value is not simply about “replacement”, but rather a dimensionality upgrade and reconstruction of the traditional simulation system. Surrogate models not only demonstrate remarkable potential in terms of computational efficiency, but also in economic costs, universality in complex scenarios, the subversive elimination of knowledge barriers, the collaborative optimization of multi-physics fields, and the reconstruction of the technological ecosystem.

References

1. Mei, Z., Song, L., Haichao, W., et al.: Predicting the compressive strength of concrete using neural networks. *Journal of Liaoning Technical University (Natural Science Edition)* **03**, 275–277 (1998)
2. Wu, X., Liu, P., Chen, H., et al.: Prediction of the compressive strength of high-performance concrete based on random forest. *Concrete* (01), 17–20+24 (2022)
3. Fei, C., Yu, Z., Wang, C., et al.: An improved method for predicting the strength of concrete based on support vector regression. *Bulletin of the Chinese Ceramic Society* **40**(01), 90–97 (2021). <https://doi.org/10.16552/j.cnki.issn1001-1625.20201116.001>
4. Hai-Bang, L., Thuy-Anh, N., Hai-Van, M.T., et al.: Development of deep neural network model to predict the compressive strength of rubber concrete. *Construction and Building Materials* 301 (2021)
5. Solomon, O., Thamer, A.: Artificial intelligence-based prediction of strengths of slag-ash-based geopolymer concrete using deep neural networks. *Construction and Building Materials* 400 (2023)
6. Wang, W.: Prediction of the Bearing Capacity and State of Concrete Structures Based on Machine Learning. Southeast University (2022). <https://doi.org/10.27014/d.cnki.gdnau.2022.002957>

7. Wei, X., Xiao, G.: The bearing capacity of PBL shear connectors in steel-concrete composite structures based on BP neural network. *Journal of Highway and Transportation Research and Development* **28**(10), 60–64 (2011)
8. Li, Y., Qiao, D., Fang, Y.: Prediction of the bearing capacity of damaged space grid structures based on neural network. *Scientific and Technological Innovation* **28**, 125–128 (2022)
9. Qiao, P., Liang, Z., Xu, K., et al.: Evaluation of the technical condition of medium and small span bridges based on machine learning. *Journal of Chang'an University (Natural Science Edition)* **41**(06), 39–52 (2021). <https://doi.org/10.19721/j.cnki.1671-8879.2021.06.005>
10. Zhou, X., Cao, L., Xie, W., et al.: DNN surrogate model based cable force optimization for cantilever erection construction of large span arch bridge with concrete filled steel tube. *Advances in Engineering Software* **189**, 103588 (2024)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Research and Reflection on the Safety of High Concrete Face Rockfill Dams

Wen-Xia Wu^{1,2(✉)}, Hai-Bin Xiong^{1,2}, and Jian-Hua Lu^{1,2}

¹ Changjiang Survey, Planning, Design and Research Co., Ltd, Wuhan 430010, China
852069518@qq.com

² National Dam Safety Research Center, Wuhan 430010, China

Abstract. The safety of high concrete face rockfill dams (CFRDs) has consistently been a primary focus within the engineering industry. Based on a comprehensive review of the construction and operational status of high CFRDs and the main challenges they face, this study proposes innovative design concepts. These include improvements to constitutive models and refined numerical simulation methods for high CFRDs, investigation into the engineering characteristics of rockfill materials, coordinated deformation design, research on the failure mechanism and prevention of face slab compressive failure, advancements in safety monitoring and intelligent construction technologies, seepage safety design, seismic safety design, and enhanced construction quality control of CFRDs. These advancements aim to improve the accuracy and reliability of high CFRD design. The proposed concepts provide robust support for the intelligent construction and safe operation of CFRDs. Relevant research findings have already been successfully applied to several high CFRD projects, offering valuable theoretical and technical support for their construction and operation.

Keywords: high CFRD · Safety · Compatibility · Numerical simulation · Seepage safety · Safety monitoring

1 Introduction

CFRDs are widely utilized in modern water conservancy and hydropower engineering due to their favorable adaptability to terrain, cost-effectiveness, and seismic resistance. With the development of China's social economy and the increasing demand for water resources, the western region, rich in hydropower potential, has become a key development area. However, this region typically features complex terrain and challenging geological conditions, including high altitude, high seismicity, and deep canyons. In this specific construction context, concrete face rockfill dams offer unique advantages. On one hand, they can effectively utilize locally available construction materials, significantly reducing transportation costs and providing distinct economic benefits. On the other hand, they can adapt to complex foundation deformations through self-adjustment, exhibiting strong adaptability and excellent seismic resistance. This makes them a crucial dam type for developing hydropower in challenging areas[1].

According to incomplete statistics, by 2025, China will account for nearly 50% of the 200m-class high rockfill dams. Several planned dams in western China, such as Gushui (dam height 240m), Rumei (dam height 315m), Maji (dam height 277.5m), and Cihaxia (dam height 257.5m), prioritize the CFRD when conditions permit. AS dam heights exceeding 250m, problems such as deformation control, face slab cracking, and leakage have become increasingly prominent. Consequently, enhancing the safety of high CFRDs remains a significant concern within the engineering community[2].

On the basis of summarizing the current construction and operation status of CFRDs, this article deeply analyzes the problems they encounter. It further proposes new design concepts based on the latest research progress in high CFRDs, aiming to provide a useful reference for their construction.

2 Overview of the Construction and Operation Status of High CFRDs

The development process of CFRDs can be broadly divided into four stages: In the early stage (1850–1940), it was the stage of dumped rockfill placement, where the compactness of the stone body was poor, the porosity was high, the compressibility was significant, the settlement and horizontal displacement were large, this led to frequent face slab cracking and leakage problems; During the transition period (1940–1970), there was a shift from dumped to compacted rockfill. In the 1960s, large-scale earth and stone construction machinery, particularly large vibrating rollers, gradually came into use; In the modern period (1970–2000), the main feature was the thin layer compaction of rockfill, and there were significant improvements in the dam structure and construction technology, such as the use of slipforms for casting long slabs, paving the way for higher dams; During the development period (2000 and beyond), emphasis was placed on the coordination and theoretical analysis of dam deformation, research and development of advanced mechanical equipment, and development towards digitization, informatization, and intelligence (Fig. 1).

Since the introduction of modern compaction technology in the 1980s, China has progressively mastered the construction technology of 200m-high dams through engineering practices such as Level 1 Tianshengqiao (178 m), Hongjiadu (179.5 m), Sanbanxi (185.5 m), and Shuibuya (233 m). However, some 200m-high CFRDs built around 2000, designed and constructed based on empirical concepts, commonly experienced issues such as cracks in the cushion material and face slabs, separation between slabs and cushion material, compression damage to slab joints, and excessive leakage [3, 4].

(1) Aguamilpa CFRD in Mexico

The Aguamilpa CFRD in Mexico has a maximum height of 187m and a crest length of 660m. When the reservoir was filled to an elevation of 218.8m, leakage reaches 257.7L/s. Numerous fine horizontal bending cracks and a horizontal tensile crack (160m long, 15mm wide) were observed near the top of the slab. Analysis of measured data revealed that the excessive settlement difference between upstream and downstream rockfill zones, the rockfill pre-settlement is insufficient, and the deformation modulus of the downstream rockfill zone is smaller than that of the main rockfill zone, resulting in horizontal cracks in the face slab[5].




Fig. 1. Typical CFRD projects in different stages

(2) Tianshengqiao-1 CFRD

The dam of Tianshengqiao I Hydropower Station is CFRD with a maximum height of 178 m. Due to the excessive settlement of rockfill, numerous problems occurred, including cushion material cracks, voids beneath the slab, slab cracking (4,537 cracks identified), slab compressive failure, and significant leakage (up to 140 L/s). Analysis of the slab damage revealed contributing factors: measured slab temperatures reached 50 °C before the flood season when water levels were low, causing thermal expansion and local stress concentrations; non-destructive testing identified large voids between elevations 760m and 775m; the use of rigid vertical joints provided no displacement space to relieve stress during compressive deformation. The combined effects of significant thermal expansion, dam settlement deformation, water pressure, and the slab's own weight contributed to the void formation beneath the slab [6] (Figs. 2 and 3).

Compared with concrete dams and earth dams, CFRDs are more complicated in physical characteristics and mechanical performance. The safety problem of high CFRD has the characteristics of concealment, multiplicity and latency. Operating year-round underwater with significant depth and complex submerged environments, these problems pose substantial detection challenges. Multiple issues such as cracks, water stop failure, collapse and leakage are often intertwined. The safety evolution of CFRDs follows a prolonged transition from quantitative accumulation to qualitative transformation. With numerous CFRDs having operated for over a decade, these long-term performance characteristics present novel technical challenges for high CFRD construction.




Fig. 2. Cracks of the cushion layer material of Tianshengqiao-1 dam




Fig. 3. Distribution positions of cracks in the cushion layer area and panel cracks of Tianshengqiao-1 dam

3 Problems Faced by High CFRD

China has nearly 20 CFRDs exceeding 150m in height, with over 10 dams at or above 200m either built or under construction. The dam construction conditions are characterized by high seismic intensity, high altitude, cold climates, deep gorges and deep overburden layers. The multi-level complexity of CFRD has historically necessitated reliance on empirical design methodologies. However, the inherent limitations of these approaches have contributed significantly to the operational challenges observed in contemporary CFRD projects. The main problems are as follows:

3.1 Complex Constitutive Relations of Rockfill Materials

Rock-fill is a granular material exhibiting significant complexity, inhomogeneity and multi-phase coupling. Its stress-strain response law is influenced by numerous factors, including the characteristics of parent rock, particle gradation, compactness, stress conditions, particle breakage and material deterioration, making its constitutive law extremely complicated.

Current design primarily relies on the traditional Duncan-Chang E-B model, Shen Zhujiang's double yield surface model, or Tsinghua University's nonlinear decoupling K-G model. These models struggle to accurately and comprehensively describe all characteristics of rockfill, particularly long-term creep behavior under high stress and particle breakage effects [7–9]. Due to the approximation of the calculation model, the prediction of stress and deformation of the dam under different working conditions is insufficiently accurate. This inaccuracy further compromises the rationality of the dam's structural design and may fail to effectively prevent excessive dam deformation.

3.2 Limitations in Test Methods

Triaxial testing is the primary method for evaluating the mechanical properties of rockfill materials. However, the maximum diameter of commonly used triaxial samples is typically 30cm, limiting the maximum particle size within samples to approximately 5cm. However, in reality, the maximum particle size of dam rockfill often reaches 100cm, necessitating significant scaling down of materials for testing. This scaling introduces discrepancies between test results and the actual rockfill behavior, known as the “scale effect”. Due to this effect, the material parameters obtained in the laboratory differ significantly from the true parameters of dam rockfill. In addition, experimental means face difficulties in accurately capturing the long-term deformation behavior of rockfill and particle breakage under ultra-high confining pressures. These limitations in testing methods hinder the accurate description of rockfill material properties. Consequently, during design and construction, the evaluation of dam material properties may be insufficiently precise, potentially leading to issues like excessive dam deformation and face slab compressive failure.

3.3 Difficulty in Predicting Dam Stress and Deformation

Dam stress and deformation are multi-dimensional phenomena. The granular structure of the rockfill determines its three-dimensional spatial deformation and time-dependent rheology, while the face slab undergoes bidirectional tension, compressive, shear, flexural and torsional deformation. The prediction accuracy of dam stress and deformation is influenced not only by the constitutive model and material parameters of rockfill, but also depends on the calculation method, the fineness of the calculation model and the simplification of boundary conditions. Currently, accurately predicting the stress and deformation of ultra-high CFRDs under complex operating conditions remains challenging. This limitation constrains the accurate evaluation of dam safety and stability and increases the risks of excessive dam body deformation and face slab cracking (Fig. 4).




Fig. 4. Multi dimensional deformation of rock mass in panel dam

3.4 Compressive Failure of Face Slab

Some 200 m-class CFRDs have experienced face slab compressive failure during operation. The research shows that the macroscopic factor of the compressive failure of the face slab is the excessive deformation of the rockfill. The direct causes include the contact compression and rotation compression of the face slab along the longitudinal joints, and the friction between the rockfill and the face slab, which further increases the compressive stress on the joint surface. Additionally, the vertical joint waterstop structure weakens the effective thickness of the face slab. In addition, the particle gradation and thickness of cushion and transiting material also have an influence on the local stress state of the panel when it is loaded. Slab compressive failure compromises the dam's seepage control system, increase the risk of leakage, and affect the safety and service life of dam. However, the precise mechanism of compressive failure has not been fully refined and quantitative control indices are lacking. Current mitigation strategies typically focus on improving the compressive resistance of the concrete itself by increasing concrete strength grade, using double-layer reinforcement, or adding steel fibers.

3.5 Safety Monitoring Instruments Unable to Meet Requirements of Ultra-High CFRDs

Due to factors such as long cable lengths, equipment structure, construction quality, and maintenance challenges, safety monitoring instruments in ultra-high CFRDs are prone to failure and exhibit poor durability. For instance, some monitoring instruments fail during the long-term operation, resulting in inaccurate or missing data. This seriously affects the monitoring and evaluation of dam behavior, thus making it impossible to accurately grasp the dam operation state in time. Consequently, potential safety hazards in time, and increasing the risk of dam operation.

3.6 Leakage Problem

Some CFRDs have large leakage during operation. For instance, the leakage of Aguamilpa CFRD is as high as 257.7 L/s. The primary causes of leakage include voids between face slab and cushion material, cracks in face slab, failure of waterstop. Research has shown that leakage rates increase dramatically for dams exceeding 125m in height, primarily due to cracking or joint failure induced by face slab deformation after impoundment [10] Leakage weakens the dam's seepage control capability, leading to internal erosion of the rockfill, affecting dam stability and safety, and potentially resulting in serious accidents like dam failure.

3.7 Seismic Safety Problem

Most CFRDs are located in areas with high seismic intensity, and seismic safety is one of the important problems they face. The research shows that under the earthquake action, the stability of dam slope and the seepage control system of face slab may be seriously affected. The current seismic design standards and engineering measures still have some limitations in the application of ultra-high dams. Earthquakes may induce critical dam safety issues, including excessive deformation, face slab cracking, and water seal failure, significantly compromising the dam's structural stability.

4 New Design Concepts of High CFRDs

Based on the research concerning 200 m-class high CFRDs built domestically and internationally, and incorporating experience from typical projects such as Shuibuya (233 m), Gushui (245 m), Rumei (315 m), Cihaxia (253 m) and Maji (270 m), the new design concept for CFRDs is summarized and put forward, with notable progress achieved in its development.

4.1 Improvement of Constitutive Models and Refined Numerical Simulation Methods for Rockfill Dams

Through the improvement of constitutive model and numerical simulation method, the stress and deformation of high CFRD under different working conditions can be predicted

more accurately, providing a scientific basis for design optimization. On the one hand, researchers from Hohai University and other institutions have developed an elastoplastic rockfill constitutive model that incorporates particle breakage characteristics. This advancement builds upon the South Water Double Yield Surface Model [11], by integrating a dilatancy equation that accounts for particle breakage effects. Existing constitutive models are also modified based on the concept of particle breakage energy consumption to more rationally reflect the volumetric deformation of rockfill materials. Similar efforts to develop or apply advanced constitutive models considering creep, particle breakage, and high stress conditions have been documented [12, 13]. On the other hand, the numerical simulation methodology has been enhanced through the development of an advanced face slab modeling approach. This refined simulation framework accounts for: (1) the complex mechanical behavior of rockfill materials, (2) time-dependent changes during construction, (3) dam-environment interactions. The proposed method enables comprehensive, large-scale simulation of stress-deformation characteristics in ultra-high face slab dams with unprecedented detail. A nonlinear contact algorithm between concrete face slab and rockfill based on contact mechanics theory is proposed, which can better simulate large-scale void and slip.. Advanced numerical frameworks capable of simulating complex interactions, construction stages, reservoir filling, creep, and even seismic events with sophisticated contact algorithms (e.g., dual mortar method, cohesive zone models) have been developed and applied to high CFRD analysis [14, 15].

4.2 Study on Engineering Characteristics of Rockfill

For ultra-high CFRDs, because the maximum particle size of rockfill reaches 60 ~ 80 cm, exploratory comparative research is conducted through large-scale laboratory tests, field in-situ tests, numerical shear tests and other ways. These investigations delve deeply into the engineering characteristics of rockfill to reveal inherent laws governing size effects and time-dependent behavior. The goal is to advance rockfill dam design theory, improve deformation and stress prediction capabilities, and provide a more accurate theoretical basis for the design and safety evaluation of high CFRDs. For instance, Shuibuya once conducted a confined compression test with a diameter of 1.3m on the rockfill with a certain scale in the cave, and a load test with a diameter of 1.3m on the original graded rockfill, with the maximum vertical load of 5 MPa. Gushui and Rumei also performed in-situ confined compression test, load test and rheological test with a diameter of 2 ~ 4 m, and the maximum vertical load was as high as 6.8 MPa. In recent years, with the development of numerical calculation technology, some numerical experiments have been carried out by using the discrete element method of particle body to simulate the particle system test of rockfill at the meso level. Numerical experiments can conveniently and quickly carry out a large number of sensitivity analysis, and observe the evolution process of meso-fabric of rockfill in real time, which makes up for the deficiency of physical experiments and provides an effective means for studying the scale effect of rockfill.

4.3 Deformation Compatibility Design

The coordinated deformation design of high face rockfill dam needs not only to consider the rationality of dam zoning, but also to comprehensively optimize the topographic and geological conditions, the characteristics of dam materials and other factors, so as to ensure that the deformation of various parts of the dam can be coordinated with each other and avoid the problems like face slab cracking and compressive failure caused by uneven deformation.

- (1) Deformation coordination theory: Propose rheological models and crushing energy consumption constitutive models, establish deformation coordination criterion, and realize the transformation from empirical design to theoretical design.
- (2) Optimization of dam zoning: Based on the topographic and geological conditions of the dam site, the dam zoning should be rationally divided by expanding the range of the upstream rockfill area, reducing the modulus difference between the upstream and downstream rockfill zones, and minimizing uneven deformation across the dam [9].
- (3) Optimization of filling procedure: During the construction, the upstream and downstream of dam filling and the left and right banks should rise in a balanced way as far as possible, and the ultra-high preloading should be reasonable to avoid excessive settlement difference caused by improper filling sequence.
- (4) Pre-settlement control: Pre-settlement period is reserved before face slab construction to avoid the peak settlement rate of rockfill, so that the deformation of rockfill after concrete face slab construction will not cause structural cracks in the face slab [16].
- (5) Long-term deformation prediction: coupling machine learning and multi-point model to improve settlement prediction accuracy.

4.4 Failure Mechanism and Prevention of Face Slab Pressure Loss

The pressure loss failure of face slab is one of the common problems in the operation of high CFRDs, and its mechanism is complex, involving many factors such as deformation of rockfill body, contact force between face slab and cushion material. In-depth study on the failure mechanism of panel pressure loss can provide theoretical support for the formulation of prevention measures.

On one hand, the contact force is analyzed, and the mesoscopic force transfer process between slab, cushion zone and transition zone is simulated using particle discrete element. Additionally the non-uniformity of contact force and its influence on the local stress state of panel are analyzed. On the other hand, Excessive compressive stress concentration in vertical joints is primarily caused by relative rotation between adjacent slabs and slab torsion during uneven rockfill settlement. To prevent compressive failure, a wide deformation-tolerant joint can be incorporated by designing a soft joint seal with compressive joints. This joint can then be filled with elastic caulking materials capable of absorbing deformation. For the horizontal slab failure, the slab structure can be optimized by increasing the thickness of the slab, locally strengthening the reinforcement, reducing the friction between the slab and the cushion, and studying the sealing material and structure, so as to make it have the ability to adapt and absorb deformation and

a certain rigidity; To enhance the reliability of waterstop structure, copper waterstops, corrugated waterstops and plastic fillers with appropriate materials and structures can meet the joint waterstop requirements of 200 ~ 300m class CFRDs.

4.5 New Technology of Safety Monitoring and Intelligent Construction

4.5.1 New Safety Detection Technologies

- (1) Intelligent Early Warning System Construction: Monitoring data cleaning and early warning technology based on big data and artificial intelligence has become a core breakthrough. For example, Hekoucun Reservoir Project in Henan Province proposed an improved cloud model data cleaning method based on wavelet transform, and screened abnormal data through entropy and super-entropy criteria. At the same time, Gaussian process regression (GPR) and improved chaotic sparrow algorithm (CSSA) are used to invert the parameters of E-B model of rockfill dam, so as to improve the accuracy of deformation prediction [17]. Dr. Ding Jiefa's team in nan-jing hydraulic research institute further proposed a data-mechanism fusion-driven model, and established a deformation grading early warning system covering multi-measuring point information to effectively identify the weak parts of the project [18].
- (2) Spatio-Temporal Fusion Deformation Prediction Model: The spatiotemporal fusion model developed by Wuhan University's research team integrates a graph convolutional network (GCN) and a recurrent neural network (RNN) to achieve collaborative deformation prediction for rockfill dams with multiple monitoring points. The prediction accuracy of this model is improved, and it has been successfully applied to deformation prediction and anomaly detection of Shuibuya CFRD [19].
- (3) New Monitoring Equipment and Systems: The "air-sky-ground" integrated monitoring system constructed by Lianghekou Reservoir adopts flexible inclinometer and pipeline robot technology, which significantly improves the survival rate of monitoring instruments for high earth-rock dams. Shuibuya project has developed 250m high dam monitoring instruments such as telemetering and remote control horizontal vertical displacement meter and high-pressure resistant bidirectional fixed inclinometer with a measuring range of 500 ~ 550 m [20]. At present, super-long horizontal and vertical displacement meters above 750m level are being developed, and real-time dynamic intelligent feedback and prediction system for monitoring of 300m high face rockfill dam is being developed.

4.5.2 Intelligent Construction New Technologies

- (1) Intelligent Management Platform and Digital Twins: The intelligent management cloud platform based on BIM + GIS integrates technologies such as Internet of Things and big data to realize visual control of the whole process from dam material mining, transportation to filling. The prediction model related to safety monitoring can be deployed to the digital twin platform to support real-time deformation prediction and health diagnosis.
- (2) Intelligent Rolling Technology: For the first time, Dashixia Project realized the cooperative operation of intelligent unmanned rolling machine group, and the rolling

path, obstacle avoidance and vibration parameters were planned by AI algorithm, which improved the filling efficiency. Its intelligent system analyzes the data such as rolling trajectory and vibration frequency in real time to ensure the compaction uniformity of dam materials and control the settlement deviation[21]. The Beidou high-precision positioning-based intelligent real-time rolling monitoring system for rockfill dams enables mutual feedback of rolling parameters and intelligent compaction quality assessment through visual detection. This system achieves intelligent and precise rolling management, effectively controlling dam body rolling quality and deformation while improving compaction uniformity.

4.6 Seismic Safety Design

Most high face rockfill dams are located in areas with high seismic intensity, and seismic safety is one of the important problems they face. The seismic engineering measures that can be taken include: reasonable layout of the hub, selection of solid dam foundation and hard dam construction materials, reserve of dam crest superelevation, slowing down the top dam slope, reinforcement of the upper dam slope, concrete frame beam, strengthening panel and water stop structure. Study the dynamic and stable water stop, quantify the design criteria of water stop, and develop new water stop materials (such as basalt fiber toughened concrete). The seismic safety evaluation is carried out, and the evaluation system of “two combination and Three Elements” is constructed. Through numerical simulation and experimental research, the seismic performance of high face rockfill dam is evaluated, and the rationality of seismic design parameters and engineering measures is determined.

5 Conclusion

This paper comprehensively summarizes the construction and operation status of high face rockfill dam, and deeply analyzes the main problems it faces. Through advancements in constitutive modeling and refined numerical simulation methods for rockfill dams, this research has significantly contributed to multiple critical aspects including: (1) characterization of rockfill engineering properties, (2) deformation compatibility design, (3) failure mechanisms of face slab pressure loss, (4) safety monitoring and intelligent construction technologies, (5) seepage safety design, and (6) seismic safety design. These developments provide a comprehensive theoretical foundation for the design and construction of high CFRDs, while enhancing the safety of numerous high CFRD projects. With the continuous progress of technology and the accumulation of experience, the construction of high face rockfill dam will be more scientific, reasonable and safe, which will promote the sustainable development of the field of high face rockfill dam.

Acknowledgements. This work was supported by the National Key Research and Development Program of China (2017YFC1501206).

References

1. Ma, H.Q., Chi, F.D.: Technical progress on researches for the safety of high concrete-faced rockfill dams. *Engineering* **2**, 332–339 (2016)
2. Niu, X.Q.: Security of high concrete face rockfill dam consideration and conclusion. *Journal of Hydroelectric Engineering* **36**(1), 104–111 (2017)
3. Zhou, M.Z., Zhang, B.Y., Jie, Y.X.: Numerical simulation of soft longitudinal joints in concrete-faced rockfill dam. *Soils Found.* **56**(3), 379–390 (2016)
4. Ao, J., Zhou, M., Zhang, B., Fang, N.: Seismic response analysis of concrete-faced rockfill dams with dual mortar contact method. *Computers and geotechnics* (2022)
5. Li, N.H.: New concept of design for high concrete face rockfill dams. *Chinese Journal of Geotechnical Engineering* **29**(8), 1143–1150 (2007)
6. Luo, J.L.: Analysis of slab damage of rockfill dam of Tianshengqiao-I hydropower station. *Advances in Science and Technology of Water Resources* **6**, 76–79 (2013)
7. Wei, Z., Xiaolin, C., Chuangbing, Z., Xinghong, L.: Creep analysis of high concrete-faced rockfill dam. *International Journal for Numerical Methods in Biomedical Engineering* **26**(11), 1477–1492 (2010)
8. Gan, L., Shen, Z.Z., Xu, L.Q.: Long-term deformation analysis of the jiudianxia concrete-faced rockfill dam. *ARABIAN JOURNAL FOR SCIENCE AND ENGINEERING* **39**(3), 1589–1598 (2013)
9. Qu, P., Chai, J., Xu, Z.: High modulus partition deformation control of high concrete face rockfill dam. *Eur. J. Environ. Civ. Eng.* **28**(11/12), 2881–2893 (2024)
10. Won, M.S., Kim, Y.S.: A case study on the post-construction deformation of concrete face rockfill dams. *Canadian Geotechnical Journal* (2008)
11. Wang, Y.M., Ru, X.Q.: Comparative analysis of high concrete faced rockfill dam with elastic analysis and elastoplastic analysis methods. *Journal of China Three Gorges University (Natural Sciences)* **31**(6) (2009)
12. Quiroz, J.E.: A structural analysis framework for concrete faced rockfill dams. *Dissertations & Theses – Gradworks* (2013)
13. Qu, Y., Zou, D., Chen, K., Liu, J.: Three-dimensional refined analysis of seismic cracking and anti-seismic measures performance of concrete face slab in CFRDs. *Computers and Geotechnics* **139** (2021)
14. Miad Saberi, J.M.K.: Numerical analysis of concrete-faced rockfill dams considering effect of face slab – cushion layer interaction. *Canadian Geotechnical Journal* **55** (2018)
15. Sun, Y., Liu, S., Jia, Y., Zhu, A., Wang, L., He, W.: A cross-scale finite element analysis of concrete-faced rockfill dam. *Physics and Chemistry of the Earth* **130** (2023)
16. Zhou, W., Hua, J., Chang, X., Zhou, C.: Settlement analysis of the shuibuya concrete-face rockfill dam. *Comput. Geotech.* **38**(2), 269–280 (2011)
17. Jian, J.B., Huo, J.X., He, X.W., Ren, J.: Application of improved cloud model based on wavelet transform in outliers recognition of monitoring data in Hekoucun Reservoir. *Yellow River* **44**(11) (2022)
18. Ding, J.F.: Research on deformation prediction and early warning model for high concrete face rockfill dams driven by data-mechanism [Doctoral dissertation, Nanjing Hydraulic Research Institute]. Nanjing, China: Ministry of Water Resources, Ministry of Transport, National Energy Administration. [In Chinese] (2025)
19. Wu, J.Y., Ma, G., Ai, Z.T., Yang, Q.G., Zhou, W.: Spatial-temporal fusion model for deformation prediction of rockfill dams and its application in safety monitoring. *Journal of Hydraulic Engineering (Shuili Xuebao)* **55**(5), 564–576
20. Li, M.Z., Li, H.L., Wen, M.H.: Analysis on key and difficult points of permanent safety monitoring for Shuibuya Project [In Chinese]. *Yangtze River* **41**(20), 43–45 (2010)

21. Li, J., Wang, F.: High-quality construction and practical innovation of Dashixian extra-high concrete face gravel dam [In Chinese]. *China Water Resources* **4**, 26–33 (2025)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Intelligent Inversion Method of Temperature Control Design Parameters for the Surrounding Concrete of the Spiral Case in Hydropower Stations

Wenjie Xu, Gang Wang^(✉), and Zhenyue Ma

Construction Engineering Department, Dalian University of Technology, Dalian 116024, China
hsxuwenjie@163.com

Abstract. The spiral case and its surrounding concrete (SCSC) constitute the core components of the hydropower station's structural system. As the main load-bearing body of the hydroelectric generating unit, the quality of concrete construction serves as a critical prerequisite for ensuring the safe and stable operation of both the unit and the overall structure. In this study, the temperature control and cooling parameters of the SCSC during the construction phase were determined through inversion using the Coati Optimization Algorithm (COA). The resulting parameters were subsequently validated by finite element simulation. The findings indicate that the water pipe cooling parameters obtained via COA effectively limit the adiabatic temperature rise induced by the hydration heat of concrete, thereby offering theoretical guidance and technical reference for the temperature control design of mass concrete.

Keywords: SCSC · Temperature control · Parameter inversion · Coati Optimization Algorithm

1 Introduction

With the increasing prominence of environmental concerns, hydropower station has attracted considerable attention as a clean and renewable energy source. The SCSC, forming the core of the powerhouse structure in a hydropower station, require particular attention to their structural safety and reliability [1, 2]. During the construction phase, the temperature of the SCSC continuously rises due to the accumulation of hydration heat. In contrast, the outer concrete dissipates heat relatively quickly through air convection, resulting in a pronounced temperature gradient. This may lead to the formation of extensive thermal cracks, posing significant risks to structural integrity [3, 4]. Water cooling has been widely adopted as an effective method to reduce internal concrete temperature, minimise temperature differentials, and inhibit crack development [5]. The cooling effect of circulating water is typically influenced by multiple factors. Designing rational and practical cooling parameters is essential for reducing peak temperature and thermal gradients, mitigating internal thermal stress, and ensuring the long-term safety of the structure during operation.

To investigate the development patterns of temperature-induced stress and cracking, researchers have employed various methods to study hydration heat generation and water pipe cooling in mass concrete. For example, Zhang et al. [6] analysed the effects of environmental features, pouring temperature (PT), cooling water temperature (CWT), and flow velocity using finite element simulations and empirical analysis. Based on grey relational analysis (GRA), they identified CWT as the most influential factor in determining cooling effectiveness. Meta-heuristic algorithms have garnered significant attention due to their high efficiency and accuracy in obtaining global optimal solutions for complex optimisation problems. Integrating these algorithms into engineering applications has enabled scholars to explore practical solutions. For instance, Hong et al. [7, 8] introduced local radial basis functions for spatial discretisation to predict the temperature field and demonstrated the stability and effectiveness of the proposed method. The result offers useful guidance for designing water pipe cooling systems. These studies collectively highlight that the rational application of meta-heuristic algorithms in engineering practice facilitates the understanding of thermal behaviour and provides valuable reference for system design.

Based on the considerations, this study establishes an objective function using the Least Squares Means (LSM) method, which is then solved through the Coati Optimization Algorithm (COA). By doing so, the inversion of cooling control parameters is achieved, providing a reference for refined temperature control design. In addition, the proposed inversion scheme is validated using the finite element method, offering new ideas and practical solutions for addressing water cooling challenges in mass concrete construction.

2 Method

2.1 Determination of the Parameters to Be Inverted

The entire heat transfer process is transient heat transfer. The heat conduction equation for a three-dimensional transient temperature field is:

$$\frac{\partial T}{\partial t} = \frac{\lambda}{c\rho} \left(\frac{\partial^2 T}{\partial x^2} + \frac{\partial^2 T}{\partial y^2} + \frac{\partial^2 T}{\partial z^2} \right) + \frac{\partial \theta}{\partial t} \quad (1)$$

where λ is the thermal conductivity (TC); c is the specific heat capacity (SHC); ρ is the density; θ is the adiabatic temperature rise of concrete.

According to Newton's law of cooling, the heat transferred from the concrete to the water pipe element per unit time can be expressed as:

$$Q_n = -\beta A(T_f - T_s) = -\Gamma \beta (T_s - T_f) \quad (2)$$

where T_f is the water temperature; T_s is the concrete temperature near the water pipe; β is the convective heat transfer coefficient of the water pipe; and $\Gamma = \frac{\pi DL}{L} = \pi D$ is the flow area per unit length of the water pipe (Fig. 1).

The convective heat transfer coefficient of cooling water can be defined by oneself with accurate data; otherwise, it can be solved by the Dittus-Boelter equation:

$$Nu = \alpha Re^b Pr^n = \beta d / \lambda_p \quad (3)$$




Fig. 1. Schematic diagram of the principle of water pipe cooling

Q_S represents the total heat carried away by a unit length of water pipe within a unit of time [9], that is:

$$Q_S = -\Gamma \frac{\alpha Re^b Pr^n \lambda_p}{D + \alpha Re^b Pr^n h_p} (T_f - T_s) \quad (4)$$

Parameters related to water pipes, including pipe diameter (D), water flow velocity (V), embedded pipe length (L), cooling time (T), and the temperature difference between cooling water and concrete ($T_f - T_s$), can significantly influence the peak temperature caused by hydration heat, the resulting temperature gradient, thermal stress, and the propagation of thermal cracks. Therefore, this study selects these parameters for inversion analysis, with the aim of providing a theoretical reference and technical basis for the design and optimization of cooling systems.

2.2 Objective Function

The calculation formula for the heat of hydration of cement is:

$$Q_C = Q_0(1 - e^{-mt}) \quad (5)$$

where, Q_0 represents the specific heat release; m denotes the hydration heat coefficient; The adiabatic temperature rise of concrete is given by:

$$\theta_C = \frac{Q_C}{c\rho} (W + kF) \quad (6)$$

where, Q_C denotes the adiabatic temperature rise of concrete at a given age. W is the mass of the cementitious materials; F represents the total mass of the concrete mixture; c denotes the specific heat capacity of concrete; ρ is the density of concrete; k is the temperature reduction coefficient.

The heat of hydration Q' carried away can be defined as:

$$Q' = \Delta\theta c\rho / (W + kF) \bullet V \quad (7)$$

where, V represents the volume of the poured concrete. $\Delta\theta$ denotes the difference of temperature.

The sum of squared residuals is adopted as the objective function:

$$F(X) = \sum_{i=1}^L \sum_{j=1}^T \omega_{ij} \left(\frac{Q' - Q}{Q'} \right)^2 \quad (8)$$

Its minimum value is transformed into optimization function, $X = (x_1, x_2, x_3, x_4, x_5)^T = [D, v, L, T, (T_f - T_s)]^T$. The solution of the Eq. (8) sought is the optimal inversion scheme.

3 Parameter Inversion and Results Based on COA

To achieve the optimal design of cooling parameters, this study establishes an inversion and determination framework based on the Coati Optimization Algorithm (COA). The process consists of two main components: the optimization algorithm search module and the cooling parameter inversion module. First, an objective function is formulated with temperature control performance as the optimization goal, serving as the evaluation criterion for subsequent parameter adjustment. In the optimization module, the COA algorithm is employed to initialize the population. During the exploration phase, individuals simulate foraging and attacking behaviour, while in the exploitation phase, they mimic predator-avoidance strategies to conduct local search. By iteratively updating positions and evaluating fitness, the algorithm converges toward the global optimum, ultimately yielding the optimal combination of cooling parameters.

Subsequently, the optimization results are used as input, and combined with thermodynamic boundary conditions and structural information, a finite element model is developed for thermodynamic coupling analysis. An equivalent heat source is applied to simulate the heat removal effect of the cooling pipe, wherein the REINF element is constructed and the HGEN term is used to perform a refined finite element simulation of water pipe cooling. The cooling effect is then evaluated, and the cooling parameters are inverted to determine the optimal cooling design scheme. This process achieves an effective integration of the optimization algorithm with the finite element physical model, providing an efficient and reliable technical pathway for determining the parameters of the cooling system.

According to the technical requirements of engineering design, the maximum allowable concrete temperatures for this structure are 45 °C in the high-temperature season and 42 °C in the low-temperature season. Based on these thresholds, inversion of the relevant water pipe cooling parameters is conducted. The results of the parameter inversion are presented in Table 1.

Table 1. Parameter inversion result

Parameter	D	v	L	T	$(T_f - T_s)$
Results	0.040m	0.79m/s	1562m	19day	21°C

4 Engineering Case Verification of Inversion Parameters

This study conducts the inversion of temperature control parameters for the SCSC of a hydropower station. By establishing the SCSC model and applying the inverted parameters as input, the simulation results confirm the effectiveness of the proposed inversion scheme. As the primary load-bearing structure under high water head conditions, the mass concrete in hydropower stations requires careful temperature control, which plays a critical role in the formation and propagation of early-age cracks. Compared with other types of mass concrete structures, stricter control of temperature gradients is essential to ensure the structural safety and long-term stability of the hydropower facility (Fig. 2).




Fig. 2. Schematic diagram of the concrete pouring sequence around the spiral case

To investigate the variation in the pouring temperature of SCSC, four working conditions (Case 1–Case 4) were designed for comparative analysis. Case 1 and Case 2 correspond to the high-temperature and low-temperature seasons, respectively, without the implementation of cooling measures. Characteristic points located in the region with the highest pouring temperature—specifically, the third layer of the concrete structure—were selected for analysis. Case 3 and Case 4 represent conditions in which the optimized temperature control scheme, derived from parameter inversion, is applied for the high-temperature and low-temperature seasons, respectively. The parameters corresponding to each working condition are listed in Table 2.

Table 2. Parameter inversion result

Scheme	Pouring Temperature	Ambient Temperature	Cooling	CWT	Cooling Time
Case 1	20°C	27.6°C	No	\	\
Case 2	18°C	26.1°C	No	\	\
Case 3	20°C	27.6°C	Yes	Inversion	Inversion
Case 4	18°C	26.1°C	Yes	Inversion	Inversion

Figure 3 illustrates the temperature field distributions for Case 1 and Case 2. The maximum temperatures of the SCSC reach 53.25 °C and 51.19 °C, respectively. This can be attributed to the fact that higher initial pouring temperatures lead to increased heat release from the cement hydration reaction. After implementing temperature control measures based on the inversion scheme, water pipe cooling was applied, and the resulting temperature field distributions are shown in Fig. 4. The peak temperatures of SCSC were significantly reduced to 43.32 °C and 41.53 °C, respectively. Compared with the cases without water pipe cooling, temperature reductions of 9.93 °C and 9.66 °C were achieved, satisfying the construction design requirements. According to the spatial distribution of the temperature field, the temperature peak consistently occurs at the end of the spiral case's inlet section. This is primarily due to the mass concrete poured in this region, where hydration reactions are more intense and the area available for convective heat exchange is relatively small. Therefore, adopting appropriate temperature control measures in this area is essential.




Fig. 3. Temperature field distribution of Case1 and Case2 without temperature control measures (T = 75day)




Fig. 4. Temperature field distribution of Case3 and Case4 with temperature control measures (T = 75day)

Figures 5 and 6 present the temperature variation curves of the SCSC without and with water pipe cooling measures, respectively. The temperature evolution can be divided into three distinct stages: rapid heating, rapid cooling, and gradual stabilization. The temperature of SCSC reached its peak around the 75th day. It can be found that when cooling measures are taken, the rate after reaching the peak is greater and approaches the ambient temperature more quickly. Near the ambient temperature, the structural temperature begins to decrease slowly and eventually stabilizes.




Fig. 5. The curve of temperature variation over time without temperature control




Fig. 6. The temperature variation curve over time with temperature control

The results above indicate that the inversion method proposed in this study is both effective and reliable. By approaching the design of cooling parameters from a heat

transfer perspective, the method offers a physically grounded solution to thermal control. The inversion results further demonstrate the correctness and practical feasibility of the proposed approach. For mass concrete structures that require strict control of temperature gradients, adopting a strategy that integrates parameter inversion with engineering experience proves to be reasonable and applicable. The methodology presented herein provides both theoretical guidance and practical reference for the temperature control of other mass concrete construction projects.

5 Conclusion

This study proposes an inversion approach for determining the temperature control and cooling parameters of the concrete surrounding the volute during the construction period, based on the Least Squares Method (LSM) and the Coati Optimization Algorithm (COA). In combination with an engineering case study, the following key conclusions are drawn:

- (1) Transforming the complex temperature control scheme design into a multi-parameter optimization problem and solving it using a meta-heuristic algorithm effectively addresses the risk of convergence to local optima and ensures both the accuracy and efficiency of the inversion process.
- (2) The structural temperature field of the SCSC generally experiences three stages of change: rapid temperature rise, rapid temperature drop, and gradual stabilization towards the ambient temperature. Among the sequentially poured layers, the middle two layers exhibit significantly higher temperatures than the first and fourth layers. This phenomenon is primarily attributed to the cumulative effect of hydration heat and the transformation of external convective conditions into internal adiabatic boundaries during the pouring process.
- (3) The peak temperature occurs at the end of the inlet section of the spiral case. This is primarily attributed to the mass concrete poured in this region, which intensifies the hydration heat release, coupled with a relatively small convective surface area for heat exchange with the surrounding air. Accordingly, implementing appropriate temperature control measures in this area is essential.
- (4) Implementing reasonable and effective temperature control measures can alleviate the adiabatic temperature rise induced by the hydration heat of concrete and moderate the cooling rate of water pipes. This helps to reduce temperature gradients and suppress the formation of thermal cracks, thereby enhancing the structural integrity, impermeability, safety, and long-term durability.

References

1. Zhang, Q., Wu, H.: Hydropower station cushion the status quo and development of research and application of the spiral case structure. *Journal of water conservancy* (2012). <https://doi.org/10.13243/j.cnki.slxh.2012.07.014>
2. Fu, H., Ma, Z., Dong, Y.: Research on the structure of the voltaic cushion layer in hydropower stations. *Journal of Hydraulic Engineering* (2003)

3. Wu, H., Gao, X., Fu, D.: Hydropower station retrospect and prospect of research and application of spiral case structure. *Journal of water conservancy* (2021). <https://doi.org/10.13243/j.cnki.slxb.20210196>
4. Xia, Z., Hu, Y., Li, J.: Plump hydropower plant spiral case elastic cushion layer optimization analysis. *Journal of water resources and hydropower technology* (2020). <https://doi.org/10.13928/j.cnki.wrahe.2020.S2.020>.
5. Wu, J., Duan, Y.: Research on Temperature Control of Concrete Water Flow Cooling for the Side Wall Lining of the Diversion Tunnel of Xiluodu Hydropower Station. *China Rural Water Conservancy and Hydropower* (2007)
6. Zhang, Y.N., Wang, S.Q.: Analysis of factors influencing the temperature field variation in mass concrete during hydration heat release. *Case Studies in Thermal Engineering* (2023). <https://doi.org/10.1016/j.csite.2023.103737>
7. Hong, X.Y., Lin, J.: Simulation of thermal field in mass concrete structures with cooling pipes by the localized radial basis function collocation method. *International Journal of Heat and Mass Transfer* (2019). <https://doi.org/10.1016/j.ijheatmasstransfer.2018.09.037>
8. Hong, X.Y., Lin, J.: Thermal effect and optimal design of cooling pipes on mass concrete with constant quantity of water flow. *Numerical Heat Transfer Part A- Application* (2020). <https://doi.org/10.1080/10407782.2020.1824438>
9. Xu, W.J., Wang, G., Ma, Z.Y., Xian, L.Q., Zhang, D.D., Li, J.J.: Inversion of cooling parameters for structure concrete surrounding the spiral case based on improved coati optimization algorithm, *Applied Thermal Engineering* (2025). <https://doi.org/10.1016/j.applthermaleng.2025.126197>

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Comparison of Machine Learning Models in Reservoir Outflow Simulation Under Different Hydrological Conditions

Lei Yu¹, Jing Zhang², Yanfei Yang², Li Zhang², Yan Zhang³, Yu Zhang¹,
Luchen Zhang¹, and Zehui Zhou⁴(✉)

¹ Nanjing Hydraulic Research Institute, Nanjing, China

² Bureau of Hydrology, Changjiang Water Resources Commission, Wuhan, China

³ Monitoring Center for Hydrological and Water Resources of Poyang Lake, Nanchang, China

⁴ School of Management, Nanjing University of Posts and Telecommunications, Nanjing, China

zhouzh@njupt.edu.cn

Abstract. Reservoirs play a critical role in global water resource management systems; however, reservoir operation simulation faces significant challenges under different hydrological conditions. This study compares the performance of four machine learning models (Random Forest, Gradient Boosting, Long Short-Term Memory, and Bidirectional LSTM) in reservoir outflow simulation under varying hydrological conditions for the Lianghekou reservoir in the Yalong River Basin, China. Results showed that Random Forest achieved the best overall performance ($R^2 = 0.6940$), followed by Gradient Boosting ($R^2 = 0.6794$), BiLSTM ($R^2 = 0.6588$), and LSTM ($R^2 = 0.6247$). Model performance exhibited clear year-type dependency, with accuracy generally declining from wet to dry years while maintaining consistent ranking. Dry years presented the most significant simulation challenges, with all models showing reduced accuracy. This study demonstrates that model selection should be tailored to specific application scenarios and hydrological conditions, providing valuable insights for intelligent water resource management systems and reservoir operation optimization.

Keywords: reservoir outflow simulation · machine learning · hydrologic condition · reservoir operation

1 Introduction

Reservoirs play a critical role in the global water resource management system, storing and controlling river runoff, and serving key functions in flood prevention and drought mitigation, water supply security, hydropower generation, and ecological maintenance (Li et al. 2023; Yuan et al. 2024). Global reservoir construction has developed rapidly, with the total storage capacity of large-scale reservoirs reaching approximately 7,000–10,000 km³ (Shin et al. 2019; Bai et al. 2025). Among these, China has constructed approximately 94,900 reservoirs of various types, with a total storage capacity of 807.7 km³ (as of the end of 2023, according to the 2023 National Water Resources

Development Statistical Bulletin), which has effectively supported economic and social development and ecological environment protection.

As climate change intensifies and water resource demands grow, reservoir operation faces increasingly complex challenges, involving multi-time scale, multi-objective trade-offs, and emergency response mechanisms (Wu et al. 2023). Reservoir outflow is a critical component of reservoir operation rules and a key control variable in water resource management, directly affecting downstream river hydrological processes, ecosystem health, and water resource utilization efficiency (Qie et al. 2023). However, reservoir operation strategies vary significantly due to differences in hydrological characteristics (such as wet, normal, and dry years), functional positioning (such as flood control, power generation, water supply, and irrigation), and management objectives (economic benefits, social benefits, and ecological benefits) (Ahmad et al. 2014; Ren et al. 2021). This complexity makes accurately simulating reservoir operation rules and predicting outflow a significant challenge in water resource management.

Currently, reservoir operation simulation methods can be broadly categorized into two main types (Zhu et al. 2022; Wannasin et al. 2024). The first category comprises traditional methods that simulate reservoir outflows based on explicit operation charts, operation functions, and clear operation rules (Chen et al. 2022). The primary limitation of traditional reservoir operation methods is their restricted generalizability. Different reservoirs have distinct operation rules, making it challenging to construct a universal model for simulating reservoir outflows. Moreover, operation practices for multi-purpose reservoirs often incorporate the experience and cognition of decision-makers, and these experiential and personal cognitive factors are difficult to fully generalize within operation rules. The second category of methods involves training machine learning algorithms using historical operation data to construct reservoir outflow models, which can effectively address the aforementioned problems (Mahmoud et al. 2024). However, different machine learning models show significant differences in reservoir simulation performance, which is mainly attributed to the differences in algorithmic characteristics, data processing capabilities, and adaptability to complex hydrological processes among different models. Traditional machine learning methods such as Random Forest (RF) and Gradient Boosting (GB) have advantages in handling nonlinear relationships, while deep learning models such as Long Short-Term Memory (LSTM) and Bidirectional Long Short-Term Memory (BiLSTM) networks excel in capturing long-term dependencies in time series.

Given the complexity and variability of reservoir systems, outflow simulation under different hydrological conditions (wet, normal, and dry years) faces significant challenges. Therefore, this study systematically compares and analyzes the performance of four mainstream machine learning models (RF, GB, LSTM, and BiLSTM) in reservoir outflow simulation under various hydrological scenarios. Through this comprehensive performance evaluation, not only can the best-performing models under specific conditions be identified, but also an in-depth understanding of the applicability and limitations of each model can be gained, laying a solid theoretical and practical foundation for the construction of intelligent water resource management systems.

2 Methods

2.1 Model Inputs

Reservoir inflow depends on upstream hydrological processes, and considering lag features, the reservoir's current period and previous period inflow ($Q_{in}(t)$ and $Q_{in}(t-1)$) are used as input variables. Additionally, reservoir storage or reservoir water level are guiding factors for reservoir outflow, so the initial reservoir storage or initial reservoir water level are used as model input variables (these can be converted using the storage-level curve). Compared to reservoir water level, the correlation between changes in reservoir storage and reservoir outflow is more significant, so this paper selects the initial storage volume of the facing period ($V(t-1)$) as an input variable for the model. Considering the continuity and experiential nature of reservoir scheduling, the previous period's outflow ($Q_{out}(t-1)$) is used as an input variable. This paper selects the outflow of the facing period ($Q_{out}(t)$) as the output variable. After determining the input and output variables, reservoir outflow simulation models were constructed based on machine learning algorithms such as RF, LSTM, etc., as shown in the following equation:

$$Q_{out}(t) = f(Q_{in}(t), Q_{in}(t-1), V(t-1), Q_{out}(t-1)) \quad (1.1)$$

where $f(\bullet)$ represents the relationship between input and output variables, obtained through fitting by machine learning algorithms; the unit of t is dekad (10-day period).

2.2 Machine Learning Methods

2.2.1 Random Forest

RF is a powerful ensemble learning algorithm that improves overall model performance by constructing multiple independent decision trees and integrating their prediction results. Its core principle lies in diversity and ensemble: first, using bootstrap sampling to create multiple training subsets, ensuring differences in training data for each tree; second, randomly selecting feature subsets at each decision node for optimal splitting, further enhancing inter-tree diversity; finally, forming the ultimate prediction through voting (for classification problems) or averaging (for regression problems) across all decision trees, significantly improving model stability and accuracy.

2.2.2 Gradient Boosting

Gradient Boosting is a powerful sequential ensemble learning method that progressively enhances model predictive capabilities by iteratively constructing a series of weak learners (typically decision trees). Initially, a simple base model is established, and then new decision trees are sequentially added, with each new tree focusing on correcting the residuals or errors of the previous model's predictions; this process essentially uses gradient descent algorithm to optimize the loss function, continuously reducing the gap between predictions and actual values.

2.2.3 Long Short-Term Memory

LSTM network is a specialized recurrent neural network architecture designed for sequence data processing, solving the gradient vanishing problem of traditional RNNs through an ingenious gating mechanism. Its core lies in its sophisticated internal structure, featuring a cell state channel running through the entire network and three critical gating mechanisms: the input gate controls the extent of new information entering the cell state, the forget gate determines which historical information to discard, and the output gate manages the volume of output information from the current state. This design enables LSTM to long-term preserve important information, selectively forget irrelevant information, and demonstrate excellent performance in long sequence modeling.

2.2.4 Bidirectional LSTM

BiLSTM further extends this architecture, comprising two independent LSTM layers with opposite directions: the forward layer processes the sequence chronologically, while the backward layer processes it in reverse order, ultimately merging the outputs of both layers. This bidirectional processing mechanism can simultaneously capture contextual information from both past and future, providing a more comprehensive temporal feature representation.

2.3 Model Evaluation

Two statistical indices are selected to evaluate the accuracy of models: R^2 (coefficient of determination) and Root Mean Square Error (RMSE). The value range of R^2 is typically between 0 and 1, with values closer to 1 indicating that the model explains a greater proportion of variance and thus provides a better fit. R^2 can also be negative, indicating that the model predictions are worse than simply predicting the mean value. Lower RMSE values indicate smaller prediction errors and better model fitting performance. The specific formulas of each consistency statistical index are as follows:

$$R^2 = 1 - \frac{\sum_{i=1}^n (y_{i,act} - y_{i,s})^2}{\sum_{i=1}^n (y_{i,act} - \bar{y}_{i,act})^2} \quad (1.2)$$

$$RMSE = \sqrt{\frac{1}{n} \sum_{i=1}^n (y_{i,s} - y_{i,act})^2} \quad (1.3)$$

where n represents the number of samples; y_m represent the model simulation value; and y_{act} and $\bar{y}_{act}$ represent the actual value and the average of the actual value, respectively.

3 Case Description

3.1 Study Area

The Yalong River Basin is located in the southeastern part of the Tibetan Plateau and is one of the eight major tributaries of the Yangtze River. It belongs to the western Sichuan Plateau climate zone, with distinct dry and wet seasons. The flood season spans from

June to October, while the dry season extends from November to May of the following year. The hydrological year is defined from November to October of the following year. The main stream is 1,535 km long, with a natural elevation drop of 3,192 m. It is the third-largest hydropower base in China's energy strategic layout, with a developable installed capacity of 30 million kW and a potential annual power generation of 150 billion kWh. Lianghekou reservoir is a large-scale multi-year regulation key reservoir in the Yalong River Basin, with a normal pool level of 2865 m, flood control level of 2845.9 m, and dead water level of 2785 m. The reservoir has a total storage capacity of 101.5×10^8 cubic meters, including a flood control storage of 81.5×10^8 cubic meters, and an installed capacity of 3000 MW.

3.2 Data

In this study, we collected decadal-scale (10-day interval) outflow, inflow, and reservoir storage data (1958–2021) for the Lianghekou reservoir from the Bureau of Hydrology, Changjiang Water Resources Commission.

4 Results and Discussion

Existing reservoir outflow simulation models still categorize training and validation data based on continuous time criterion. Against the backdrop of non-stationarity in climate-hydrological conditions and human activities, water inflow and water demand may vary significantly across different periods. Using data from a single continuous historical period as a training set may result in the model's inability to adequately capture reservoir operation rules under diverse hydrological scenarios. Thus, we proposed a stratified modeling and validation strategy based on watershed hydrological characteristics, comparing the performance of four machine learning models (RF, GB, LSTM, and BiLSTM) in outflow simulation, using the LIANGHEKOU reservoir as a case study. First, we classified the inflow percentiles from the LIANGHEKOU Reservoir during 1958–1964 (64 years) into wet (19 years), normal (26 years), and dry (19 years) water years (Fig. 3); second, we divided the samples of different hydrological years into training and validation sets through random sampling; finally, we independently modeled and validated for wet, normal, and dry water years.

4.1 Overall Performance Analysis

Figure 1 depicts the overall performance of outflow simulation for the 4 ML models. The performance can be ranked from best to worst as follows: RF ($R^2 = 0.6940$), GB ($R^2 = 0.6794$), BiLSTM ($R^2 = 0.6588$), and LSTM ($R^2 = 0.6247$). RF demonstrated the most outstanding performance, leveraging its enhanced feature engineering advantages and effectively handling the complex nonlinear relationships in reservoir dispatch. This seemingly challenges the previous conclusion that LSTM performs better in time series prediction. There could be two potential reasons: first, reservoir operation decisions primarily depend on current hydrological conditions and downstream water demand, rather than long-term historical sequences, and are significantly influenced by subjective

factors; second, this study uses a ten-day time scale, and the relatively limited sample size is insufficient to fully realize the potential of LSTM. This also underscores that model selection should be tailored to specific application scenarios rather than solely based on model type.




Fig. 1. Overall performance of 4 machine learning models on validation set

4.2 Hydrological year Analysis

Figure 2 shows the performance of 4 ML models across three hydrological years. It reveals a clear year-type dependency in model performance. As water inflow conditions transition from wet to dry years, the model simulation accuracy generally declines, while maintaining a consistent ranking: RF > GB > BiLSTM > LSTM. In wet years, RF achieved $R^2 = 0.7342$, RMSE = 225.63, with BiLSTM closely following ($R^2 = 0.7112$), showing a relatively small performance gap. Dry years present the most significant simulation challenge, with LSTM performing the worst ($R^2 = 0.5398$), and even RF, despite leading, saw its accuracy drop to $R^2 = 0.6618$. This underscores the critical importance of focusing on dry year scenarios in reservoir outflow simulation.




Fig. 2. Performance of 4 machine learning models under different hydrological conditions on validation set

5 Conclusion

Reservoirs play a critical role in the global water resource management system, serving as essential infrastructure for flood control, water supply, hydropower generation, and ecosystem maintenance; however, reservoir operation simulation faces significant challenges under different hydrological conditions due to the complex, nonlinear interactions

between meteorological inputs, hydrological processes, and human management decisions. To address these challenges, this study systematically compares the performance of four state-of-the-art machine learning models - RF, GB, LSTM, and BiLSTM - in reservoir outflow simulation under varying hydrological conditions for the Lianghekou reservoir in the Yalong River Basin, China. We conducted a comprehensive evaluation of model performance across wet, normal, and dry years using extensive decadal-scale data spanning from 1958 to 2021, which encompasses over 60 years of continuous hydrological observations and multiple complete climatic cycles. Results demonstrated that Random Forest achieved the best overall performance with an R^2 value of 0.6940, followed by Gradient Boosting ($R^2 = 0.6794$), BiLSTM ($R^2 = 0.6588$), and LSTM ($R^2 = 0.6247$), indicating superior capability in capturing the complex relationships within reservoir operations. Notably, model performance exhibited clear year-type dependency, with prediction accuracy generally declining progressively from wet to dry years while maintaining consistent relative ranking among the models. Dry years presented the most significant simulation challenges, with all models showing substantially reduced accuracy, highlighting the inherent difficulty in predicting reservoir behavior under water-scarce conditions. This comprehensive study demonstrates that model selection should be strategically tailored to specific application scenarios and prevailing hydrological conditions, providing valuable insights and practical guidance for the development of intelligent water resource management systems and optimization of reservoir operation strategies in the face of increasing climate variability and water security challenges.

Acknowledgments. This work was financially supported by the National Key Research and Development Program of China (Grant No.2022YFC3002705); National Natural Science Foundation of China (Grant No. 52409038); Natural Science Foundation of Jiangsu Province, China (Grant No. BK20230121).

References

- Ahmad, A., El-Shafie, A., Razali, S.F.M., Mohamad, Z.S.: Reservoir optimization in water resources: a review. *Water Resour. Manage* **28**, 3391–3405 (2014). <https://doi.org/10.1007/s11269-014-0700-5>
- Bai, B.X., Mu, L.X., Tan, Y.M.: A global lakes/reservoirs surface extent dataset (glrsd): an integration of multi-source data. *Geoscience Data Journal*, 12 (2025). <https://doi.org/10.1002/gdj.3.285>.
- Chen, L.H., Yu, J., Teng, J., Chen, H., Teng, X., Li, X.F.: Optimizing joint flood control operating charts for multi-reservoir system based on multi-group piecewise linear function. *Water Resour. Manage* **36**, 3305–3325 (2022). <https://doi.org/10.1007/s11269-022-03202-4>
- Li, Y., Zhao, G., Allen, G.H., Gao, H.L.: Diminishing storage returns of reservoir construction. *Nature Communications* **14** (2023). <https://doi.org/10.1038/s41467-023-38843-5>.
- Longyang, Q., Zeng, R.J.: A hierarchical temporal scale framework for data-driven reservoir release modeling. *Water Resources Research* **59** (2023). <https://doi.org/10.1029/2022WR033922>
- Mahmoud, A., Hu, T.S., Jing, P.R., Liu, Y., Li, X., Wang, X.: Enhancing interpretability of ai models in reservoir operation simulation: exploring and mitigating principal inconsistencies through theory-guided multi-objective artificial neural networks. *Journal of Hydrology* **639** (2024). <https://doi.org/10.1016/j.jhydrol.2024.131618>.

- Qie, G.P., Zhang, Z.X., Getahun, E., Mamer, E.A.: Comparison of machine learning models performance on simulating reservoir outflow: a case study of two reservoirs in Illinois, USA. *J. Am. Water Resour. Assoc.* **59**, 554–570 (2023). <https://doi.org/10.1111/1752-1688.13040>
- Ren, K., Huang, Q., Huang, S.Z., Ming, B., Leng, G.Y.: Identifying complex networks and operating scenarios for cascade water reservoirs for mitigating drought and flood impacts. *Journal of Hydrology* **594** (2021). <https://doi.org/10.1016/j.jhydrol.2020.125946>
- Shin, S., Pokhrel, Y., Míguez-Macho, G.: High-resolution modeling of reservoir release and storage dynamics at the continental scale. *Water Resour. Res.* **55**, 787–810 (2019). <https://doi.org/10.1029/2018WR023025>
- Wannasin, C., Brauer, C.C., Uijlenhoet, R., Torfs, P., Weerts, A.H.: Machine learning for real-time reservoir operation simulation: comparing input variables and algorithms for the Sirikit Reservoir, Thailand. *Journal of Hydroinformatics* (2024). <https://doi.org/10.2166/hydro.2024.153>
- Wu, W.Y., Eamen, L., Dandy, G., Razavi, S., Kuczera, G., Maier, H.R.: Beyond engineering: a review of reservoir management through the lens of wickedness, competing objectives and uncertainty. *Environmental Modelling & Software* **167** (2023). <https://doi.org/10.1016/j.envsoft.2023.105777>
- Yuan, C.Y., et al.: Estimation of water storage capacity of chinese reservoirs by statistical and machine learning models. *Journal of Hydrology* **630** (2024). <https://doi.org/10.1016/j.jhydrol.2024.130674>
- Zhu, B.R., et al.: Cascade reservoirs adaptive refined simulation model based on the mechanism-ai coupling modeling paradigm. *Journal of Hydrology* **612** (2022). <https://doi.org/10.1016/j.jhydrol.2022.128229>

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Typical Applications of Satellite Remote Sensing Technology in the Operational Safety of Hydropower Plants

Wu Weiyu^(✉), Wang Zhen, Xu Lei, and Zhou Jianbo

Large Dam Supervision Center, National Energy Administration,
No. 201, Gaojiao Road, Yuhang District, Hangzhou, China
wu_wy3@hdec.com

Abstract. This paper explores the application scenarios and effects of satellite remote sensing technology in the field of hydropower dam safety operation through the case studies of geological disaster census in a certain watershed and safety analysis of a hydropower plant that lacks historical deformation data on the ground. The results show that satellite remote sensing deformation analysis technology has the advantages of “wide range, traceability, high dynamics, objectivity and accuracy” compared with traditional means, which can help to identify the safety risks of hydropower station dams on a wide scale and prevent them from occurring; it has the ability to trace back the historical deformation in a long period of time, which can provide technical support for the safety assessment of hydropower station operation and the management of engineering hazards, and can be used in the safe operation of hydropower station dams. It can provide technical support for the safety assessment of hydropower plant operation and management of engineering potential problems, and has good application prospects in the safe operation and management of hydropower plants.

Keywords: satellite remote sensing · InSAR · risk identification · historical deformation backtracking · safety monitoring

1 Introduction

China's existing various types of dams about 95,000, including power generation function, installed capacity of more than 50MW power industry hydroelectric dams, high dams and large reservoirs, is related to the people's lives and property safety, energy security, ecological security of the watershed and economic development. As of May 2025, the power industry running hydropower dams 700, the total installed capacity exceeded 334 million kilowatts, the total reservoir capacity of more than 519.1 billion cubic meters, respectively, accounting for China's hydropower capacity of 76% of the total installed capacity of the country's reservoirs 52% of the total reservoir capacity. The power industry has a large number of high dams and large reservoirs, and in recent years, earthquakes, floods, mudslides and other geological disasters have become more frequent, increasing the risk of dam breakage, dam collapse and major structural damage to dams.

Generally speaking, hydroelectric dams and near-dam bank slopes will be equipped with more complete monitoring facilities during the construction period, for example, after the surface deformation monitoring facilities are put into operation, the deformation of the building can be observed intuitively, and it is possible to know whether the deformation amount and the deformation rate and other characteristics are within the normal range, and then determine whether the building operating conditions are safe or not. However, the traditional deformation monitoring method has technical constraints. Firstly, the arrangement of deformation measurement points is built on the basis of known monitoring targets, which lacks the ability of early identification of newly appeared geologic hazard potential points after the hydropower station is put into operation. Secondly, the deformation monitoring facilities of some hydropower stations are put into operation late, lacking early deformation data of buildings and landslides, so it is impossible to know the actual cumulative deformation of the monitoring points, which is not conducive to the assessment of deformation impact. Thirdly, the traditional monitoring methods are mainly based on triangulation, leveling and other photoelectric geodetic methods, which have many drawbacks, such as large workload on site, long operation cycle, high requirements on personnel's technical level, strict limitations on the observation period by meteorological conditions, and the impossibility of realizing all-weather fully automated observation, and so on. With the development of the concept of dam safety risk management, there is an urgent need for the dam safety monitoring technology to actively integrate space technology, artificial intelligence, information technology and other cutting-edge fields, to develop a more excellent deformation monitoring technology, and to improve the timeliness and effectiveness of the hydropower dam safety risk identification.

In recent years, China's satellite remote sensing technology has been developing rapidly, and has formed a global data acquisition capability with a reasonable configuration of "high, medium and low" resolution, and a multi-layer observation capability of air and space integration, which has been applied with remarkable results in many fields, such as energy planning, construction of electric power facilities, development and utilization of coal resources, exploration and exploitation of oil and gas resources, and renewable energy sources. Through the optical remote sensing and synthetic aperture radar interferometry technology, large-scale, non-contact, multi-frequency observation and measurement can be carried out, which is an ideal technology carrier for hydropower dam operation safety risk perception and deformation monitoring. This paper discusses the application prospect and development trend of satellite remote sensing technology through the research and application of satellite remote sensing deformation monitoring technology in the geological disaster census of a river basin and the safety analysis of a hydropower station that lacks ground historical deformation data.

2 Principle of Radar Remote Sensing Deformation Monitoring Technology

Synthetic Aperture Radar (SAR) is an active microwave sensor, which has become an indispensable sensor in the field of earth observation due to its all-weather, all-day data acquisition, and its ability to penetrate clouds, smoke and dust and to obtain

information on the earth's surface over a large area. Interferometric Synthetic Aperture Radar (InSAR) uses the phase information of SAR compound data as the information source to obtain three-dimensional information and change information of the ground surface, so that it can monitor the deformation of large areas with high precision and realize millimeter-level geometrical measurements of ground surface deformation. The principle of deformation analysis of two adjacent images can be summarized as follows:

$$\phi_{\text{int}} = \phi_{\text{top}} + \phi_{\text{flat}} + \phi_{\text{def}} + \delta\phi_{\text{atm}} + \delta\phi_n \quad (1)$$

Where, ϕ_{int} - the phase of the two image interferograms;

ϕ_{top} --Terrain phase;

ϕ_{flat} --Flat earth phase;

ϕ_{def} --The phase caused by changes in terrain LOS direction (Line of sight, radar line of sight direction);

$\delta\phi_{\text{atm}}$ --Delayed phase differences due to atmospheric fluctuations;

$\delta\phi_n$ - phase difference between the two image noises.

Assuming that there is deformation in the direction of the oblique distance of the SAR observation in the time period of the two SAR image acquisitions ΔR_{disp} , the target point deformation phase versus the shape variable relationship can be expressed as follows:

$$\Delta\phi_{\text{def}} = -\frac{4\pi}{\lambda} \Delta R_{\text{disp}} \quad (2)$$

where λ is the radar operating wavelength.

Then, using the Stacking time stacking algorithm, the long time series of SAR data are selected to form a differential interferometric atlas by choosing a suitable spatio-temporal baseline, which is stacked to minimize the effects of atmospheric errors, terrain errors, random noise, etc., so as to obtain the information about the deformation of the ground surface in the direction of the radar line of sight in that time period.

$$\text{phase_rate} = \frac{\sum_1^N \Delta t_j \phi_j}{\sum_1^N \Delta t_j^2} \quad (3)$$

In the above equation, phase_rate is the deformation phase of the radar line-of-sight direction during the time period of SAR data acquisition, N represents N differential interferograms obtained by combining spatio-temporal baselines, Δt_j is the time difference of j interferograms, and ϕ_j is the deformation phase of the radar line-of-sight direction of j interferograms.

The integrated remote sensing analysis method of geological disasters is based on the principles of disaster geology and remote sensing of landslides, starting from the remote sensing characteristics of geological disasters, based on the concentrated deformation areas obtained by InSAR surface deformation monitoring and micro-geomorphic features related to landslides, avalanches and mudslides obtained by optical interpretation, combining with the geologic background of geological strata lithology, geological

structure, topography and geomorphology, and completing the identification of regional geological hazard potentials and preliminary determination of their types, scope, scale, activity (deformation intensity), risk and threat objects by combining artificial interactive interpretation and the establishment of comprehensive recognition model. Through the combination of manual interactive interpretation and comprehensive identification modeling, the identification of regional geologic hazards is completed, and its type, scope, scale, activity (deformation intensity), risk level and threat objects are preliminarily determined.

In the process of comprehensive remote sensing interpretation, the DOM, DEM, three-dimensional model and digitized basic geological, topographic and climatic thematic data obtained from data acquisition and processing are inputted into the GIS two-dimensional or three-dimensional platform, and human-computer interaction and visual interpretation are combined, so as to complete various types of geologic hazard potentials through the comprehensive interpretation and analysis process of optical remote sensing, including the cross-referencing of multi-temporal and multi-scalar remote sensing data, the supplemental interpretation of planar and three-dimensional scenes, the interpretation of disaster characteristics and the evaluation of potential risks, and so on. Comprehensive interpretation and analysis process to complete the optical remote sensing interpretation of various types of geological hazards. Specific interpretation methods mainly include direct judgment method, comparison method, neighbor comparison method and comprehensive interpretation method.

3 Geological Hazard Survey of a Watershed

A watershed in southwestern China is located in the transition zone between the Tibetan Plateau and the Sichuan Basin, and is subject to the collision and subduction of the Yangzi Plate, the Indian Plate and the North China Plate, which develops a large number of ductile shear zones, with very complex geological and environmental conditions, coupled with a large number of human engineering activities in recent years, abnormal climatic conditions, resulting in the development of landslides and other geological hazards in the Dadu River area.

Based on the concentrated deformation areas obtained by InSAR surface deformation monitoring and the micro-geomorphic features related to landslides, avalanches and mudslides obtained by optical interpretation, and combining with the geological background of disaster-inducing geological backgrounds such as stratigraphic lithology, geologic structure, and topography and geomorphology, the census of regional geologic disaster potential hazards was carried out, and a total of 174 potential hazards (mainly landslides) were identified. The overall distribution is shown in Fig. 1, and the interpretation of typical landslide hazards is shown in Fig. 2.

According to the “Geological Hazard Risk Investigation and Evaluation Technical Requirements” (1:50,000) and relevant norms, based on the activity and hazard level of geological hazards, the risk level is divided into four categories, namely “very high, high, medium and low”, and 35 geological hazard sites are identified as low-risk, 49 as medium-risk, 68 as high risk, 22 as very high risk, and 22 as extremely high-risk. The number of geological hazard sites is determined to be 35 low-risk, 49 medium-risk, 68 high-risk, and 22 extremely high-risk.




Fig. 1. Distribution of geologic hazards in a watershed by remote sensing census




Fig. 2. Interpretation of typical landslide hazards in a watershed

Further, ground surveys and drone inspections were carried out on the slopes of key concern in the basin, and ground monitoring facilities were set up on some of the slopes, which were included in the tracking and analyzing scope. Compared with the results of ground investigation and monitoring, the results of this geohazard census based on remote sensing technology recognized 100% of active slopes, and 5 active deformed slopes were newly found within 5 km around the hydropower stations and

control slopes. At the same time, the geohazard census in this basin deciphered and recognized not only the hidden hazards containing direct threat objects, but also the slopes with potential sliding that have indirect influence on the power station, so the coverage is more comprehensive.

From a comprehensive point of view, the geologic hazard census of the watershed based on satellite remote sensing technology has remarkable results in identifying the fineness and comprehensiveness, and the later regular census work is conducive to dynamically grasping the state of control slopes and guiding the control measures. Regular census of geologic hazards in the watershed can lay a good foundation for early identification of risks and precise positioning of monitoring targets.

4 Safety Analysis of a Hydroelectric Power Plant Lacking Ground Monitoring Facilities

4.1 Overview of Settlement Deformation of a Hydropower Station

A hydropower station was put into operation in 1998 to generate electricity, and the plant buildings mainly include the pressure front pool and overflow channel, pressure steel pipe, ground plant, booster station and ancillary buildings. In 2000, the expansion joints at the connection between the gate chamber section of the front pool and the right side wall were deformed and leaked. Between 2000 and the winter of 2014, the deformation of the expansion joints of the front pool increased, and the leakage volume increased significantly, with the maximum leakage volume of more than 100m³/h. In January 2019, the houses of residents near the power station were cracked and broken, and the road downstream of the plant bulged and deformed. In May 2019, the travelling track of the bridge engine of the plant was measured, and the difference in track settlement was 169mm, which was high in the west and low in the east. In October 2021, the travelling track was measured again, and the difference in track settlement was increased to 246mm. In November 2021, the material storehouse of the plant and the 35kV switch room and other parts of the plant showed obvious. On December 8, 2021, cracks appeared on the bottom plate of the overflow channel near the first-stage dissipation pond. The hydropower plant is located within the coal mining area, and the deformation and settlement of the air-mining area may have led to phenomena such as uneven settlement of various buildings that have existed since the construction of the hydropower plant. The deformation of the region's large-scale mining and air space is still continuing and will further develop to the surface deformation, which will affect the normal and safe operation of the power station.

Since no ground deformation monitoring facilities were deployed after the construction of this hydropower plant, there is a serious lack of historical deformation monitoring information. In February 2022, five GNSS measurement points were arranged in the front pool, pressure steel pipe, plant, near-plant slope and other parts of the plant to obtain only the deformation after the commissioning of the operation, which brought more difficulties for the historical deformation analysis (Fig. 3).



Fig. 3. Distribution of buildings and GNSS measurement point layout

4.2 Satellite Remote Sensing Deformation Retrospective Analysis

Sentinel-1 satellite IW mode radar data (orbit number 62) were selected to carry out the corresponding processing, and all the data in the work area were collected, starting and ending from October 9, 2014 to June 29, 2022. The revisit period of Sentinel-1 single star is 12 days, and basically one period is received every 24 days from October 2014 to December 2016, and in 2017, 12 days revisit after March 2017, of which the data revisit period is 6 days during the synchronized shooting of A star and B star from September 2020–2021, and individual data are missing, and a total of 221 periods of data have been collected. The 12-day revisit period after March 2017, of which the data revisit period during the synchronized shooting of stars A and B from September 2020 to December 2021 was 6 days, with individual data missing, for a total of 221 periods of data collection.

The InSAR coherent target time series analysis method was used to obtain the deformation status of the work area during the data cycle, and the interferometric image pair time was less than 40 days to maintain good coherence. The cumulative amount and rate of surface deformation in the work area from October 9, 2014, to June 29, 2022, were obtained by the above method, and a comprehensive understanding of the development and change of surface subsidence during the data cycle was realized (Fig. 4).




Fig. 4. Interferometric image pair spatio-temporal baseline combination

Taking the plant area and the center extension of about 500m as the key analysis area, the analysis was conducted to obtain the historical deformation of seven typical correlation points. The distribution of typical coherent points in the plant area and near-plant area is shown in Fig. 5, the distribution of cumulative deformation amount is shown in Fig. 6, the distribution of deformation rate is shown in Fig. 7, and the time sequence process line of deformation at typical coherent points is shown in Fig. 8.




Fig. 5. Distribution of typical InSAR coherence points at and near the plant site




Fig. 6. Distribution of cumulative shape variables in the plant areas




Fig. 7. Distribution of deformation rates at and near the plant (2014/10/09–2022/06/29)




Fig. 8. Time series of deformation at typical coherent points in the plant area

There are serious surface deformation phenomena within the plant area and the center extension of about 500m, the maximum cumulative deformation reaches 978 mm, the maximum settlement rate reaches 88 mm/a, and the area with a large settlement rate of 20 mm/a is about 0.79 km².

Typical coherent points pt4 (near the top of the plant 3#GNSS measurement point) and pt5 (near the intake gate 1#GNSS measurement point) within the plant area have cumulative settlement of about 600 mm and 650 mm, respectively, with a similar process of settlement change. Settlement accelerated during the time periods of September 2016 to August 2017, and May to December 2021; and from January 2022 to present, the settlement is Relatively stable.

Deformation has not yet converged, effective reinforcement measures should be taken in a timely manner to ensure the operational safety of the relevant buildings in the plant.

5 Conclusion

In this paper, based on the deformation data obtained from InSAR surface deformation monitoring, combined with the geological background of geological strata lithology, geological structure, topography and geomorphology, and through the combination of manual interactive interpretation and comprehensive recognition modeling, we have completed the identification of hidden geological hazards in a certain watershed and classified the risk level. And for a hydropower station that lacks historical deformation data and is difficult to judge the safe operation of buildings, a long-cycle deformation retrospective analysis was carried out for about 10 years, obtaining the deformation

time course, change rate and cumulative deformation amount of typical target locations, which provided favorable support for the formulation of safe operation control measures. The results show that satellite remote sensing technology has the advantages of “wide range, traceability, high dynamics, objectivity and accuracy” compared with the traditional deformation monitoring technology, which can help to improve the timeliness and effectiveness of the identification of dam safety risks in hydropower stations, and help to solve the safety assessment of hydropower station operation state in the absence of historical deformation data, and has a good application prospect for the safety management of hydropower stations. It has good application prospects in hydropower plant safety management.

References

1. Kang, Y.: Application of InSAR Technology in Landslide Detection and Monitoring in Southwestern Mountainous Areas. Chang'an University, Xi'an (2016)
2. Li, Z.H., Song, G.C., Yu, C., et al.: Application of satellite radar remote sensing to landslide detection and monitoring: challenges and solutions. *Geom. Inform. Sci. Wuhan Univ.* **44**(7), 967–979 (2019)
3. Liao, M., Wang, T.: Time Series InSAR Technology and Application. Science Press, Beijing (2014)
4. Sun, W., Yang, G., Chen, C., et al.: Development status and literature analysis of China's earth observation remote sensing satellites. *J. Rem. Sens.* **24**(5), 479–510 (2020)
5. WeiyuW, J.Z., Guanghui, W., et al.: Research on safety risk identification and application of hydropower station slope safety based on satellite remote sensing. *Dam Safety* **3**, 10–14 (2022). <https://doi.org/10.3969/j.issn.1671-1092.2022.03.002>
6. Jianjun, Z., Zhiwei, L., Jun, H.: InSAR deformation monitoring method and research progress. *J. Surv. Map.* **10**, 1717–1733 (2017)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Research and Practice on the Smart Reservoir Construction of the Nuozhadu Hydropower Station

Ming Kong^(✉), Xiaoxuan Chen, Jiulong He, Wuhua Su, and Shangrong Yang

NZD Hydropower Station, Huaneng Lancang River Hydropower Inc., Kunming 100000,
Yunnan, China
275163310@qq.com

Abstract. The development of smart power plants is an inevitable response to rising energy demand, environmental pressures, technological advancements, market competition, energy transitions, and increasingly stringent safety requirements. By leveraging intelligent technologies, smart power plants can enhance efficiency, reduce emissions, improve competitiveness and safety, and promote sustainable development in the power industry. The smart reservoir system of the Nuozhadu Hydropower Station is built upon a multi-source monitoring data integration platform, innovating in current monitoring and data acquisition technologies. It explores a hybrid diagnostic model that combines data-driven and knowledge-driven approaches and establishes a complete technical system for risk perception, trend forecasting, and hierarchical early warning of geological hazards and water environment changes in the reservoir area. The system significantly enhances the integrated management and emergency decision-making capabilities of hydropower reservoir operations. It primarily encompasses reservoir monitoring, safety management in near-dam waters, informatized management of reservoir resettlement and poverty alleviation. Ultimately, it achieves integrated, digitalized, and intelligent reservoir operation and maintenance.

Keywords: Smart power plant · Smart reservoir · 3D GIS · Intelligent inspection

1 Introduction

The operation and maintenance of the Nuozhadu Hydropower Station reservoir cover a vast and dispersed area, involving numerous management points. Traditionally, management relies heavily on manual operations and lacks large-scale, comprehensive, and efficient tools. Most outcomes are stored in the form of drawings, spreadsheets, and reports, leading to scattered data storage and the absence of unified management, which results in low work efficiency. Due to the limited capabilities for data integration and sharing, a systematic intelligent early warning and emergency response mechanism has not been established. As a result, it is difficult to quickly organize and analyze all relevant information during decision-making processes and to implement scientific, accurate, and systematic countermeasures.

© The Author(s) 2026

Y. Hu et al. (Eds.): IHDC 2025, LNCE 792, pp. 461–468, 2026.

https://doi.org/10.1007/978-981-95-4889-7_40

The construction of smart power plants has emerged in response to these challenges. The development of technologies such as the Internet of Things (IoT), big data, and artificial intelligence (AI) provides the technical foundation for intelligent power plant operations.

The smart reservoir system of the Nuozhadu Hydropower Station is based on the construction of a data storage and analysis platform capable of effectively integrating multi-source monitoring data. It innovates on existing technologies for monitoring information collection and acquisition, and it investigates an intelligent diagnostic analysis model that organically combines data-driven and knowledge-driven approaches. A comprehensive technical system is established to support risk perception, trend assessment, and hierarchical early warning and control for geological hazards along the reservoir banks and for aquatic environmental changes. This system significantly improves the integrated management and emergency decision-making support capabilities of hydropower reservoir operations.

2 System Construction Framework

2.1 Functional Architecture

The smart reservoir operation and maintenance (O&M) system consists of two main components: integrated reservoir area management and intelligent ecological environment management of the reservoir area.

2.2 System Topology

In the smart reservoir O&M system of the Nuozhadu Hydropower Station, field data such as flow and water level are collected on the external network side and transmitted via 4G to the company's internal-external network exchange zone before being relayed to the internal network. Key applications—including 3D reservoir management visualization, business management functions, and unmanned aerial vehicle (UAV) control—are deployed within the internal network. The system topology is shown in Fig. 1.

3 System Construction Details

3.1 Construction of Real-World 3D Maps

Using oblique photogrammetry, high-definition 3D models of the left and right bank slopes, auxiliary facilities, flood control structures, and other managed zones of the Nuozhadu Hydropower Station were created. The mapping includes a 2-square-kilometer high-resolution real-world 3D model and ultra-high-resolution models for key areas.




Fig. 1. Topology of the Smart Reservoir System

3.2 Integration of Multi-Source Data

Based on the constructed 3D real-world maps, the system integrates various data sources, including:

- Fundamental geographic information
- 3D real-world model data
- Environmental monitoring data
- Drainage facility flow monitoring data
- Slope and spoil ground deformation monitoring data
- Rockfall alarm monitoring data
- Intelligent video surveillance data
- Flood prevention inspection data
- Flood control maintenance and defect resolution records
- Emergency management data

This integration forms a comprehensive "resource pool" for reservoir operation and maintenance management at the Nuozhadu Hydropower Station.

3.3 3D Visualization Display Function

The 3D GIS (Geographic Information System) is built upon related business data, encompassing basic geographic information, real-time monitoring and sensor data, 3D model data, and thematic data. It serves as an intuitive 3D visualization-based management platform, supporting the digitalization of plant operations and enabling diverse 3D applications. A spatial database is established to manage and publish models, vectors, imagery, and other datasets, visually presenting business results and data outputs in an effective and dynamic manner (Fig. 2).




Fig. 2. Overall Architecture of the 3D GIS System

3.3.1 Layer Management

The layer management function enables control over map layers. Layers can be added or removed based on operational needs, and individual layers can be toggled on or off via checkboxes. The system loads 3D layers and map services through data interfaces and uses plug-ins to provide a tree-structured layer display with visibility toggles. Layer attributes can also be configured via parameter settings.

3.3.2 Information Query

A unified 3D database is established based on foundational data to support integrated management. Existing business data are interfaced with the 3D system to enable business information queries. Users can retrieve relevant information using location, ID number, name, and other conditions, quickly locate the model in the 3D scene, and simultaneously display corresponding 2D attribute data.

3.3.3 3D Spatial Analysis

By invoking the 3D GIS engine’s graphical drawing interface, the system enables common drawing functions such as point, line, and surface annotation within the 3D environment. These capabilities support specific area labeling and site annotation. The system also includes 3D spatial analysis tools, such as cut-and-fill volume calculations, slope analysis, cross-section analysis, and line-of-sight analysis, providing technical support for various types of decision-making.

3.4 Data Acquisition System Construction

New monitoring points introduced in this scheme are read from the edge cloud platform database (industrial IoT database) of the hydropower plant. Data sources include seepage

drainage from the dam and powerhouse, sump water level and alarms, environmental monitoring, flow monitoring, rockfall detection, and video surveillance. The system achieves full coverage of geological disaster monitoring across the hub and reservoir areas of the Nuozhadu Hydropower Station [2].

4 Business Management System Construction

The business management system includes multiple functional modules such as intelligent inspection, facility and equipment management, duty scheduling, materials and tools management, document and archive management, intelligent emergency management, reservoir resettlement management, and informatized poverty alleviation management. Designed with flexibility and scalability, the system can be deployed on the edge cloud platforms or physical servers of individual hydropower plants. At the corporate level, it supports cross-site data query and service invocation among different plants.

4.1 Intelligent Inspection

An unmanned aerial vehicle (UAV) inspection system has been established, with a mobile UAV management framework composed of drones, supporting airport systems, airport back-end platforms, and centralized control systems. The architecture follows a “cloud-edge-terminal” deployment model to ensure responsive and coordinated operations (Fig. 3).




Fig. 3. Overall Architecture of the UAV Inspection System

4.2 Duty Management

Based on user roles and monthly attendance records, the system can automatically generate flood prevention duty rosters and inspection schedules. It provides online access to company-wide duty schedules, including transportation team rosters. Duty logs can be submitted online, covering information such as date, personnel on duty, weather conditions, environmental parameters, on-site inspection records, and shift handover details. A handover function is supported—once a duty report is submitted and saved, authorized personnel can view and modify it according to their access permissions.

4.3 Materials Management

A digital inventory ledger has been established for flood prevention supplies and tools, using shelf number, row, and sequence for precise indexing. Intelligent access control through facial recognition or fingerprint authentication enables efficient and traceable check-in/out processes for materials and tools. The system simplifies inbound and outbound operations, while maintaining complete and exportable records.

Storage thresholds can be configured for materials and tools. When inventory levels fall below preset limits or exceed usage lifespans, automatic alerts are triggered and sent to relevant management staff. For items requiring periodic maintenance—such as flashlight charging or generator testing—maintenance records can be logged in the system. Upon setting maintenance cycles, the system generates and dispatches timely maintenance work orders to ensure continued operational readiness.

5 Intelligent Emergency Management

5.1 Intelligent Identification of Abnormal Conditions

- (1) The smart reservoir O&M system possesses self-learning capabilities. By analyzing long-term monitoring data such as rainfall and flow, it builds predictive models. When rainfall occurs, the system can forecast drainage conditions across various channels and issue early warnings, which are then pushed to management personnel.
- (2) By analyzing and comparing monitoring data from slopes, spoil areas, and drainage facilities, the system identifies abnormal patterns and promptly issues alerts, notifying relevant staff.
- (3) Utilizing video data collection combined with AI analysis, the system can automatically detect significant changes and unauthorized intrusions in managed areas such as slopes, spoil areas, and flood control facilities. Upon detection, it immediately sends alerts to responsible personnel.
- (4) In the event of any abnormal condition, hotspots are activated on the 3D/2D reservoir O&M interface, and alert messages are issued to enhance the responsiveness and efficiency of hazard management, thereby reducing labor costs associated with non-targeted inspections.

5.2 Intelligent Emergency Decision-Making

- (1) The intelligent emergency decision-making module integrates environmental monitoring data, flood control facility operational statuses, various monitoring indicators, and early warning information to form a comprehensive emergency management system. It features full-element monitoring, risk assessment, abnormal event prediction, and situational analysis capabilities.
- (2) When an abnormal event occurs, the system can rapidly assess the location, severity, and road accessibility of the situation. It generates statistical analysis tables and scenario-specific thematic maps in real time, forwarding the data to the smart reservoir O&M system and, when necessary, pushing the information to designated mobile devices.

5.3 Standardized Emergency Response Management

- (1) According to relevant emergency management regulations, standardized emergency response procedures are customized for different severity levels. When a situation reaches a defined level, the corresponding standard response process is automatically initiated, and alerts are sent to relevant personnel via mobile notifications.
- (2) If an abnormal condition does not automatically trigger the predefined emergency response process, authorized personnel can manually initiate the response workflow and notify designated staff accordingly.
- (3) Emergency response personnel can upload response documentation, videos, and images via the web or mobile app, enabling real-time reporting to all levels of emergency command. Once the situation is effectively controlled, the chief commander can formally close the emergency response process following prescribed procedures.
- (4) The system supports one-click generation and export of emergency response reports and summaries.

6 Conclusion

The establishment of the smart reservoir system has significantly improved work efficiency by integrating documents, images, monitoring data, inspection reports, maintenance records, and materials management into a unified platform. It enables centralized data storage, categorized queries, and real-time information sharing, forming a comprehensive "resource pool" for reservoir O&M management. By digitizing and standardizing workflows, the system streamlines operational processes.

Additionally, emergency command efficiency is greatly enhanced with the support of AI recognition technology, enabling environmental, flow, and deformation monitoring—as well as video surveillance and anomaly detection—in remote or low-traffic flood control zones. Standardized emergency workflows can be automatically initiated in critical situations, ensuring rapid and intelligent response.

With the continuous advancement of artificial intelligence, the system is expected to develop deeper integration with AI technologies. Future upgrades may enable tighter interaction with digital twin platforms and AI-driven autonomous decision-making. This will further enhance the full technical chain of "intelligent sensing – precise diagnosis – targeted repair – dynamic evaluation," offering advanced solutions for automated inspection, defect identification, and anomaly handling [3].

References

1. Li, M.: Smart Reservoir Construction and Management (in Chinese). Science Press, Shanghai, China (2022)
2. Zhang, M., Li, H.: Application of digital twin technology in smart reservoirs. *Water Conserv. Inform.* **42**(4), 29–35 (2021)
3. Wang, W., Li, Q.: Future trends and challenges of smart reservoirs. *Water Conserv. Inform.* **43**(1), 1–8 (2022)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Prediction, Monitoring, and Fault Diagnosis of Hydropower Plants Using Digital Twin Model and Differential Evolution Algorithm

Fabício Nascimento Sfalsin¹(✉), Leonardo Campanine Sicchieri¹,
Roberto Martins de Castro Neto¹, Aldemir Aparecido Cavallini Junior¹,
Jefferson Silva Barbosa², Henrique Borduqui², Isabela Marchiori²,
and Ricardo Lourencini Assumpção²

¹ LMEst - Laboratory of Structural Mechanics, Faculty of Mechanical Engineering, Federal University of Uberlândia, Av. João Naves de Ávila, 2121, Uberlândia, MG 38408-100, Brazil
fabricio.sfalsin@ufu.br

² CPFL Energia - Jorge Figueiredo Correa, 1632 - Bloco 6, Campinas, SP 13087-490, Brazil

Abstract. The maintenance of rotating machinery is critical to ensuring operational efficiency and safety in industrial systems. Among the main challenges is the early identification of faults, such as mechanical unbalance and misalignment. This work presents a fault detection methodology based on an inverse technique, combining a representative digital twin model with the Differential Evolution optimization algorithm. Numerical vibration responses are compared with experimental measurements, and faults are iteratively introduced into the digital twin model until both signals converge. The proposed methodology was applied to the digital twin of a generating unit at the Foz do Chapecó hydroelectric plant, demonstrating its effectiveness in fault diagnosis.

Keyword: Fault diagnosis · Rotating machine · Digital Twin

1 Introduction

Developing accurate digital models of hydroelectric generating units are key to smart energy systems, enabling predictive maintenance and real-time monitoring. Digital twins allow continuous condition assessment and early fault detection, improving reliability and reducing downtime in hydropower plants.

Hydroelectric generators are susceptible to various mechanical faults during operation. As noted by (9; 6), common issues include misalignment—often resulting from assembly errors in shafts or hydrodynamic bearings—and unbalance, typically caused by non-uniform mass distribution in rotating components.

This study proposes a methodology for constructing a digital twin of hydroelectric generating units, with an emphasis on dynamic behavior simulation, fault detection, and structural diagnosis. The approach involves solving an inverse problem using the Differential Evolution algorithm (12), whereby simulated vibration responses are iteratively aligned with real operational data until convergence is achieved.

The methodology was implemented in HidroSys, a software platform developed through a collaborative R&D project involving Foz do Chapecó, CERAN, BAESA, ENERCAN, CSC Energia, and CPFL Energia. The tool offers a user-friendly interface and supports the modeling of various generating unit components, including turbines, shafts, bearings, and generators.

To validate the proposed approach, a digital twin was developed for an actual generating unit at the Foz do Chapecó hydropower plant in Brazil. A calibrated model was first established using healthy operational data. Artificial misalignments were then introduced at two couplings to test the system's ability to detect and diagnose structural faults by comparing simulated and measured responses.

2 Mathematical Model of the Rotating Machine

Although the proposed methodology applies to a wide range of hydroelectric generating units, the digital twin presented in this study replicates the dynamic behavior of one specific unit from the Foz do Chapecó Hydroelectric Power Plant in Brazil. The virtual model includes a detailed representation of the generator, turbine, and supporting structure, integrating shafts, discs, lumped masses, external forces, and distributed stiffness and damping properties.

This particular unit consists of three hydrodynamic bearings: (i) a radial tilting-pad bearing located above the generator, (ii) a thrust bearing positioned just below the generator, and (iii) a cylindrical radial bearing situated above the turbine. These components play a critical role in the dynamic response and stability of the rotating system and are individually modeled in the simulation.

The rotor is modeled using a finite element approach based on the formulation proposed by (3), where the shaft is represented as a Timoshenko beam with a circular cross-section and six degrees of freedom per node. This modeling strategy allows for accurate prediction of bending and shear deformations, essential for replicating real operational behavior.

Figure 1 shows the digital model of the rotating machine alongside the drawing of the actual generating unit, enabling a visual comparison between them. The shaft's finite element mesh and the layout of the main components are emphasized. This model serves as the core of the digital twin used for simulation, calibration, and fault diagnosis.

Figure 2 shows the proximity probes installed on the generating unit, which were used to measure vibration amplitudes. The probes were placed in two distinct locations: Position 1, between the radial tilting pad bearing and the generator, and Position 2, above the cylindrical radial bearing. At each location, a pair of probes was mounted orthogonally to capture vibrations along the Z and X directions.

2.1 Rotor Motion Equation

The core of the digital twin's physical model is a set of differential equations that represent the dynamic behavior of the rotating assembly, including the shaft elements, discs, couplings, and external force-generating components such as hydrodynamic bearings. The model also incorporates gyroscopic effects and transient stiffening due to angular




Fig. 1. Numerical model of the generating unit used in the digital twin.



Fig. 2. Proximity probes installed on the generating unit: (a) Position 1; (b) Position 2.

acceleration. The equation governing the rotor dynamics is expressed in Eq. (1), which describes the motion of a flexible rotor supported by hydrodynamic or rolling-element bearings.

$$[M]\ddot{q} + [C + \Omega C_g]\dot{q} + [K + K_f + K_t + \dot{\Omega}K_{st}]q = W + F_u + F_f + F_s \quad (1)$$

where: - M is the global mass matrix of the rotating components; - C is the structural damping matrix; - C_g represents the gyroscopic matrix, which is a function of the spin speed Ω ; - K is the structural stiffness matrix; - K_f accounts for stiffness due to fault-related constraints (e.g., contact or misalignment); - K_t is the stiffness contribution from the coupling elements; - K_{st} accounts for transient stiffening effects due to angular acceleration $\dot{\Omega}$.

The right-hand side aggregates all external forces acting on the rotor: - W represents gravitational forces acting on the rotating components; - F_u denotes unbalance forces

caused by mass eccentricities; $\mathbf{F}_f$ includes other excitation sources such as magnetic forces, hydraulic loads, or forces related to mechanical faults; $-\mathbf{F}_s$ refers to the reaction forces the supporting bearings generate.

This equation constitutes the foundation for time-domain simulations and serves as the physical layer of the digital twin, enabling fault injection, response prediction, and comparison with operational data.

2.2 Hydrodynamic Bearings, Generator and Turbine

The bearing modeling is performed using a thermo-hydrodynamic model, in which the pressure and temperature fields are determined by simultaneously solving the Reynolds equation and the energy equation, using procedures similar to those described by (7) and (1). The Reynolds and energy equations are described in a generic form and are adapted and detailed according to the coordinate system that best fits the geometry of each bearing.

The generator was modeled using the Finite Element Method Magnetics (FEMM) software, following the geometric parameters of the generator used in the generating unit in question. Using FEMM and a two-dimensional geometry with planar symmetry, it was possible to obtain the electromagnetic forces acting on the generator as a function of the rotor's eccentricity relative to the stator. The FEMM software uses Maxwell's equations to describe electromagnetic phenomena (2). For a more comprehensive understanding of the modeling of this element, it is recommended to consult the research by (10).

The turbine in the generating unit is of the Francis type and consists of 13 blades. The hydraulic forces acting on the turbine were determined by solving the NavierStokes equations using large eddy simulation (LES) methods and the immersed boundary method (11). These simulations were performed using the MFSim code, developed by the Fluid Mechanics Laboratory at the Faculty of Mechanical Engineering of the Federal University of Uberlândia. Only the results obtained by the laboratory members were used in this work.

3 Fault Models

This section will describe the two faults investigated in this work: mechanical unbalance and misalignment. The fault numerical models are incorporated into the finite element model of the rotating machine as external forces.

3.1 Mechanical Unbalance

The unbalance forces are applied to the mathematical model of the generating unit as external forces at the node corresponding to the location of the unbalance. The components of these forces in the X and Z directions can be determined by applying Lagrange's equations to the kinetic energy of the unbalanced mass, as proposed by (3). The characteristic spectrum associated with unbalance exhibits an increase in vibration amplitude at the 1X frequency.

3.2 Misalignment in Rotors

Through experiments, (5) observed that vibrations caused by shaft misalignment occur at integer multiples of the rotor's rotational speed. According to (9) and (13), there are essentially three types of misalignment: parallel, angular, and combined. The characteristic vibration spectrum of misalignment exhibits components at frequencies $1X$, $2X$, and $3X$, with amplitudes directly proportional to the degree of misalignment.

In this work, the model proposed by (8) is adopted, consisting of two coupled Jeffcott rotors with identical stiffness and inertia properties. In this model, the shafts are considered initially untensioned. In formulating the system dynamics, only the forces introduced by misalignment and the variation in shaft stiffness are considered.

4 Calibration

As detailed in (10), the calibration of the virtual model was based on experimental data collected from the generating unit operating under healthy conditions. The flow of this procedure is illustrated in the diagram shown in Fig. 3. Basically, unbalance parameters, such as mass and phase, are inserted into the virtual model so that the numerical vibration responses match the real machine data, thereby identifying the system's residual unbalance.




Fig. 3. Optimization process flowchart.

Figure 4 shows the orbits of the real vibration signals alongside those obtained through the optimization process for each proximeter. Figures 5 and 6 present the frequency spectra comparison between the calibrated model and the real data at proximeters 1 and 2, respectively.




Fig. 4. Real (a) and Numerical (b) orbits in proximeters.




Fig. 5. Real (a) and Numerical (b) frequency spectrum at proximeter 1.




Fig. 6. Real (a) and Numerical (b) frequency spectrum at proximeter 2.

As a result of the calibration process, a residual unbalance of 1000 kg.m was identified in the generator and 100 kg.m in the turbine, both with a phase angle of 0° , as reported by (10). Based on these results, it can be concluded that the complete multiphysics model of the generating unit was able to adequately reproduce the real behavior of the system, with a mean relative error in vibration amplitude on the order of 7%.

5 Fault Diagnosis

The fault diagnosis procedures adopted in this work follow the same approach as the virtual machine calibration. From the calibrated model, numerical fault models are associated with the machine through an optimization algorithm, where misalignment parameters are treated as design variables, as proposed by (4). Parameters are adjusted, and vibration signals are compared until numerical and reference signals converge.

Unlike calibration, experimental vibration signals were replaced by numerical ones in the diagnosis process, with known misalignments in couplings 1 and 2, as shown in Fig. 1. Coupling 1 features an angular misalignment of 1.5° , while Coupling 2 presents a parallel misalignment of 12 mm in the X-axis and 6 mm in the Z-axis.

The optimization considered three misalignment parameters: angular deviation and parallel displacements in the X and Z directions. The optimization algorithm was configured with a population size of 20 individuals and a maximum of 200 generations. The objective function minimized the error between the amplitudes of the vibration spectra at the 1X, 2X, and 3X harmonics—key indicators of misalignment in rotating machinery.

Figure 7 compares the reference and optimized orbits for both proximeters. Figures 8 and 9 present the corresponding frequency spectra for proximeters 1 and 2 in both the X and Z directions. A strong agreement is observed between reference and optimized results, both in the time and frequency domains.

The optimizer successfully identified the injected faults, estimating a parallel misalignment of 12.02 mm on the X-axis and 5.99 mm on the Z-axis, and an angular misalignment of 1.50° , with relative errors below 0.032%. These results validate the proposed diagnosis strategy and demonstrate the high accuracy and reliability of the digital twin in simulating and detecting faults in hydropower-generating units.




Fig. 7. Orbits in proximeters 1 and 2.




Fig. 8. Frequency spectrum at proximeter 1.




Fig. 9. Frequency spectrum at proximeter 2.

6 Conclusions

This work investigated the dynamic behavior of rotating systems, focusing on the development of a digital twin for fault detection. The virtual machine was calibrated using real operational data from the Foz do Chapecó generating unit in Brazil, achieving errors around 7%. By employing artificial signals simulating misalignment conditions, the proposed technique accurately identified faults with errors below 0.03%, demonstrating its effectiveness. These results underscore the methodology’s potential for industrial applications, where rapid and precise fault detection can significantly reduce downtime and optimize maintenance strategies.

Acknowledgements. The authors acknowledge the support of INCT-EIE (National Institute of Science and Technology – Smart Structures in Engineering), funded by CNPq, as well as CAPES and FAPEMIG. Special thanks are extended to Petrobras, and to Foz do Chapecó, Enercan, CPFL Energia, and CSC Energia for their financial support through the R&D project PD-00642-0124/2024-ANEEL.

References

1. Barbosa, J.S.: Análise de modelos termohidrodinâmicos para mancais de unidades geradoras Francis. Master's thesis, Federal University of Uberlândia, Uberlândia, Brazil (2018)
2. Bastos, J.P.A.: Eletromagnetismo e cálculo de campos. Ed. da UFSC (1992)
3. Lalanne, M., Ferraris, G.: Rotordynamics prediction in engineering. (No Title) (1998)
4. Lobato, F.S., et al.: Otimização Multi-objetivo para o Projeto de Sistemas de Engenharia. PhD thesis, Federal University of Uberlândia (2008)
5. Mitchell, L.D.: Detection of a misaligned disk coupling using spectrum analysis. *J. Vib. Acoust. Stress. Reliab. Des.* **106**, 9 (1984)
6. Muszynska, A.: Rotordynamics. CRC Press (2005). <https://doi.org/10.1201/9781420027792>
7. Nicoletti, R.: Efeitos térmicos em mancais segmentados híbridos: teoria e experimento. PhD thesis, State University of Campinas, Faculty of Mechanical Engineering, Campinas, Brazil (1999)
8. Redmond, I.: Study of a misaligned flexibly coupled shaft system having nonlinear bearings and cyclic coupling stiffness—theoretical model and analysis. *J. Sound Vibr.* **329**(6), 700–720 (2010). ISSN 0022-460X. <https://doi.org/10.1016/j.jsv.2009.09.039>
9. Scheffer, C., Girdhar, P.: Practical Machinery Vibration Analysis and Predictive Maintenance. Elsevier (2004)
10. Sicchieri, L.C.: Modelagem multifísica de uma unidade geradora hidroelétrica. PhD thesis, Federal University of Uberlândia, Faculty of Mechanical Engineering, Uberlândia, Brazil (2024)
11. Stival, L.J.L., Vedovotto, J.M., Ribeiro, R.C., Morales, F.A.P., Sicchieri, L.C., Cavallini Jr., A.A.: Francis modeling over generating units applying advanced fluid dynamics methods. In: XIX International Symposium on Dynamic Problems of Mechanics (DINAME 2023) (2023). <https://doi.org/10.26678/ABCM.DINAME2023.DIN2023-0081>
12. Storm, R., Price, K.: Differential evolution—a simple and efficient heuristic for global optimization over continuous spaces. *J. Global Optim.* **11**, 341–359 (1997)
13. Taylor, J.I.: The Vibration analysis handbook. Vibration Consultants, Tampa, FL (1994)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Digitization Practices for the Whole Life Cycle of Resettlement in Water Conservancy and Hydropower Projects

Tianming Zhao^(✉), Liqiang Du, Jing Tian, and Yu Zhu

Power China Beijing Engineering Corporation Limited,
No. 1, Dingfuzhuang West Street, Chaoyang District, Beijing 100024, China
zhaotm@bjy.powerchina.cn

Abstract. The land acquisition and resettlement processes of water conservancy and hydropower projects constitute a critical component of national infrastructure development, directly influencing project advancement and social harmony. Nevertheless, traditional approaches are increasingly impeded by fragmented information, complex procedures, and inefficient oversight. Rapid advancements in digital technologies—including GIS, big data, artificial intelligence, and blockchain—have established the development of a full life cycle digital management system as a pivotal strategy for optimizing resettlement processes. This study examines three critical phases—planning and design, implementation and management, and post-implementation support—providing a comprehensive analysis of resettlement digitization practices. It identifies key challenges in technological deployment, data sharing, cross-sectoral collaboration, and risk management, and proposes targeted strategies and recommendations to offer both theoretical insights and practical guidance for achieving efficient, transparent, and scientifically grounded decision-making in water conservancy and hydropower project resettlement.

Keywords: water conservancy and hydropower projects · resettlement · whole life cycle management · digital transformation

1 Introduction

In the early stage of resettlement planning, through the integration of remote sensing images, topographic data and land use information, GIS technology can be used to construct high-precision three-dimensional geographic models, which can visually present the geomorphology, architectural layout and environmental characteristics in the land acquisition area [2, 3]. This method can not only help planning and designing personnel to quickly identify the physical indicators within the scope of land acquisition, but also provide real-time feedback on the data dynamics, which can provide a scientific basis for the subsequent program adjustment. By simulating the ecological and socio-economic impacts that may be brought about by different schemes, it realizes accurate planning from the macro to the micro level, and improves the rationality and compliance of land acquisition planning.

2 Full Life Cycle Digitalization Applications

2.1 Planning and Design Phase

2.1.1 Delineation of the Scope of Land Acquisition

During the preliminary stage of resettlement planning, the integration of remote sensing imagery, topographical data, and land use information permits the construction of high-precision three-dimensional geographic models using GIS technology, which visually depict the geomorphology, architectural layouts, and environmental characteristics of the land acquisition area [2, 3]. This approach not only assists planners in rapidly identifying key physical indicators within the designated area, but also offers real-time feedback regarding data dynamics, thereby providing a scientific basis for subsequent program adjustments. Furthermore, by simulating the potential ecological and socio-economic impacts of various schemes, the method enables accurate planning at both macro and micro levels, thereby enhancing the rationality and compliance of land acquisition strategies.

2.1.2 Physical Surveys

Traditional physical surveys primarily depend on paper-based documentation and manual data entry, leading to high error rates and incomplete information. Currently, the utilization of smartphones, tablet PCs, and other mobile devices, in conjunction with OCR, GPS positioning, and image acquisition technologies, facilitates the immediate digital capture of field data [4–7]. Such data are automatically linked to geographic coordinates and multimedia information via standardized templates, effectively mitigating data loss and enabling real-time synchronization, thereby enhancing the efficiency and quality of on-site surveys (Fig. 1).




Fig. 1. Architecture diagram for digitization construction of physical surveys

2.2 Implementation Management Phase

During the construction and resettlement phases, fund management and contract execution represent critical monitoring components. A blockchain-based regulatory system records fund flows and contractual terms throughout the resettlement process, ensuring that data storage is both tamper-proof and transparently accessible [10–13]. This technology not only renders each process traceable but also mitigates risks associated with human error and management deficiencies. Consequently, the construction unit, government departments and migrants can understand the progress of the project on the same platform, ensuring fairness, justice and openness (Fig. 2).




Fig. 2. Digitized system for the whole life cycle of resettlement

2.3 Post-Enabling Phase

2.3.1 Digitalization of Employment and Livelihood Security

Upon project completion, continued attention is necessary to address re-employment, skills enhancement, and livelihood security for migrant groups. A unified online service platform can deliver timely employment information, vocational training, and policy guidance to migrants. Moreover, big data analytics facilitate the matching of migrants’ skills with market demands, thereby enabling precise job recommendations and efficient employment transitions. Furthermore, the platform disseminates up-to-date policy information—including medical insurance and housing subsidies—to support rapid migrant integration into new environments [14].

2.3.2 Digitalization of Community Cultural Integration

Migrant resettlement encompasses not only spatial relocation but also the restructuring of cultural identity and community cohesion. Establishing a digital community cultural exchange system can facilitate robust interaction and cultural integration among

migrants. Such a platform consolidates information on diverse community services—including education, healthcare, and social activities—thereby offering migrants a range of participatory experiences that reinforce their sense of identity and belonging within the new community.

3 Key Challenges and Paths to Breakthrough

3.1 Bottlenecks in Technology Deployment

3.1.1 Insufficient Depth of Intelligence

Although the existing system has made significant progress in data acquisition and information processing, it is still difficult to realize intelligent decision-making in complex scenarios (e.g., ecological impact simulation, resettlement area site selection optimization). Although some of the current systems integrate BIM, GIS, and other technologies, there are deficiencies in core artificial intelligence algorithms and deep learning models. In this regard, it is necessary to increase R&D investment, continuously improve the intelligent module, and improve the system's ability of automatic discrimination and problem prediction.

3.1.2 Barriers to Data Sharing

The data involved in the process of migrant resettlement are often distributed in different departments and platforms, lacking a unified data governance framework, and the data format and collection caliber are not uniform, which seriously affects cross-departmental data integration and comprehensive application. The establishment of a big data sharing platform and the unification of data standards and interface specifications are a fundamental way to open up information islands and realize digital collaborative management.

3.2 Barriers to Institutional Synergy and Social Adaptation

3.2.1 Lack of Cross-Sectoral Synergy Mechanisms

Currently, different units involved in immigrant resettlement operate independently with insufficient synergy, resulting in isolated operation of the digital system—particularly in contractual signing, funds disbursement, and other areas—where poor information flow directly affects overall management. It is imperative to build a unified platform, optimize cross-departmental workflow and a standardized management mode to achieve multi-party sharing of resources and efficient synergy.

3.2.2 Low Grass-Roots Digital Acceptance and Adaptation

The promotion of system applications is limited in some remote areas due to weak network infrastructure and inadequate digitalization training at the grass-roots level. This not only affects on-site data collection and real-time supervision, but also makes it difficult for migrants to access services at a later stage. Upgrading grass-roots digitization capacity, strengthening technical training and improving network coverage are important measures to address this problem.

3.3 Risk Prevention, Control and Response Measures

3.3.1 Data and Privacy Security

Within the digitization process of migrant resettlement, data security and privacy protection are of paramount importance in risk prevention and control. Given the centralized collection and cross-system sharing of multi-source data, migrant personal information becomes vulnerable to leakage and abuse during storage, transmission, and utilization. To mitigate these risks, dynamic encryption technology desensitizes sensitive fields during data entry, ensuring that original data remains securely isolated. At the storage level, blockchain's distributed ledger records data operation logs in a tamper-proof manner, thereby ensuring traceability and accountability. Meanwhile, the sharing layer employs federated learning to train cross-sectoral models without transferring raw data, achieving the paradigm of "data available but not visible." Furthermore, by establishing a hierarchical authorization mechanism that assigns data access rights based on user roles, the system creates a robust defense framework from both technical and managerial perspectives.

3.3.2 Technology Dependency Risk

A lack of environmental adaptability in technology deployment can pose systemic risks, particularly in regions with limited network coverage or infrastructure, where over-reliance on online systems may result in interruptions in data collection and the loss of offline data. Developing terminal equipment that supports local offline storage and data verification, coupled with an automatic synchronization mechanism upon network reconnection, can substantially mitigate these technological dependency risks and ensure stable system operations.

3.3.3 Social Acceptance of Risk

Although digital applications enhance efficiency, they may also introduce new access barriers for the elderly, individuals with lower educational backgrounds, or those with limited technological proficiency. Therefore, systems should incorporate user-friendly interfaces—such as simplified operations, visual aids, and voice assistance—while targeted training and outreach initiatives should be implemented to improve digital literacy and service adoption among migrants. Guaranteeing equal access to digital services is essential to prevent disparities in governance effectiveness resulting from technological advancements.

4 Development Paths and Implementation Recommendations

4.1 Improvement of Policy and Data Standards Systems

Government agencies should issue comprehensive policy documents on the digitization of migrant resettlement, clearly delineating the standards and operational procedures for employing digital technology at every stage. In addition, establishing a cross-sectoral data-sharing platform and harmonizing data collection, storage, and update protocols are crucial for providing consistent and accurate management support across various levels.

4.2 Promote Technological Innovation and System Integration

Increasing R&D investment in artificial intelligence, deep learning, and big data analytics is imperative to augment the capability of existing systems for intelligent decision-making in complex scenarios. Simultaneously, enterprises should initiate pilot projects in collaboration with technology research institutions to organically integrate advanced technologies—including BIM, GIS, and blockchain—thus creating an efficient and modular digital management platform.

4.3 Building Cross-Sectoral Synergies

A cross-departmental collaborative network based on data sharing has been established, featuring a unified digital collaboration platform that clearly delineates the roles and responsibilities of each unit in data collection, fund supervision, and contract execution. Additionally, process reengineering and integrated information systems have facilitated smoother information transmission among various components, thereby enhancing the transparency of the decision-making process.

4.4 Strengthening Grass-Roots Training and Digital Outreach

Implementing regular digital skills training and technology dissemination programs for grassroots units and migrant groups, coupled with network infrastructure improvements and the widespread adoption of user-friendly mobile devices and offline data collection tools, will enhance overall system adaptability and effectively narrow the digital divide.

5 Conclusions and Future Perspectives

5.1 Conclusion

This paper provides a systematic analysis of the digitization practices employed across the entire life cycle of water conservancy and hydropower project resettlement, detailing the application and advantages of digital technology during the phases of planning and design, implementation and management, and post-implementation support. By constructing a collaborative management system that leverages GIS, big data, AI, and blockchain, the approach enhances both the rigor and transparency of project decision-making while offering robust support for fund supervision, contract execution, and subsequent livelihood services. Additionally, the study conducts an in-depth examination of crucial issues—such as technology deployment, data sharing, cross-sectoral collaboration, and risk management—and proposes targeted improvement strategies.

5.2 Future Prospects

The digital transformation in the resettlement processes of water conservancy and hydropower projects is poised to drive a new wave of technological innovation and institutional reform. As emerging technologies such as artificial intelligence, 5G communications, the Internet of Things, and cloud computing continue to advance, digital

management is expected to evolve toward more intelligent decision-making and dynamic responsiveness, thereby enabling cross-sectoral data integration and collaborative governance. Concurrently, policy innovation and institutional enhancements will furnish the necessary safeguards and incentives, promoting a deep integration between technology and management models. At a macro level, these developments are anticipated not only to further improve the efficiency and transparency of resettlement processes but also to usher in a new paradigm of modern social governance, optimal resource allocation, and coordinated regional development. Future research and practice should concentrate on establishing a data-driven, intelligently responsive digital ecosystem that ensures coherent project operations and fosters social harmony and stability.

References

1. Tang, Y.: Study on the Evolution of Digital Technology Application in Dam Migration Management. China Society of Dam Engineering, Brazilian Dam Commission, Spanish Dam Commission, U.S. Commission on Dams. Building the “Knot” of a Safe, Resilient and Green National Water Network. Chinese Society of Dam Engineering, Brazilian Commission on Dams, Spanish Commission on Dams, U.S. Commission on Dams, p. 7 (2024)
2. Zhu, C.: Development and application of reservoir inundation treatment information system based on 3S. *People’s Pearl River* **S1**, 22–23+27 (2005)
3. Huang, J.: Application of new technology of surveying and mapping in Baise Water Conservancy Hub Reservoir District Immigration Project Measurement. *Guangxi Water Conserv. Hydropower* **2**, 39–40+48 (2004)
4. Yao, Y., Wang, E.: Application of digitization in the physical survey of migrants in the project of river diversion and supplementation of Han River. *Water Resour. Plan. Des.* **3**, 64–67+78 (2024)
5. Xia, Z., Mu, L., Yao, Y., Yang, X.: Research and application of physical indicator management system for land acquisition and migration in a hydropower station. *China Manage. Informat.* **20**, 210–212 (2022)
6. Chen, Z., Zhao, Q.: Research on the development of digital collection system for physical indicators of water conservancy project migrants. *Henan Water Conserv. South-North Water Divers.* **2**, 80–82 (2021)
7. Qiu, Z.: Design and Realization of Information Management System for Physical Survey of Land Requisition Migrants. Northwest Agriculture and Forestry University (2016)
8. Chen, J.: Application practice of digital management of migrant resettlement in water conservancy and hydropower projects. *Fujian Hydropower* **2**, 88–90+94 (2024)
9. Zhao, Q., Lu, L., Liu, C., Guo, F., Chen, C.: Development and application of full life cycle information system for water conservancy project migration. *People’s Yellow River* **12**, 123–126 (2024)
10. Guo, L., Jiang, H.: Preliminary practice of digital relocation platform in large and medium-sized water conservancy and hydropower projects in Zhejiang Province. *Hydropower* **1**, 15–18+57
11. Liu, L., Pan, X., Feng, S.-C.: Research on digitization of migrants’ relocation and resettlement work in water conservancy and hydropower projects. *Hydropower Gener.* **7**, 85–88 (2020)
12. Wang, W., Fan, Z., Li, B.: Practice of digital application of migration and resettlement management in water conservancy and hydropower projects. *Yunnan Hydropower* **6**, 28–31 (2022)
13. He, S.: A few thoughts on digital information management of comprehensive supervision of hydropower project migration and resettlement. *Yunnan Hydropower* **11**, 51–55 (2023)

14. Zhao, X., Chen, Q., Peng, S.: Study on the income-generating effect of social networks in promoting digital livelihoods of reservoir migrants. *J. Huazhong Agric. Univ. Soc. Sci. Ed.* **2**, 94–107 (2024)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Research on Anomaly Detection Methodology for Deformation Monitoring in High Arch Dam

Wang Sheng^{1,2,3(✉)}, Yu Hao⁴, Gao Xiaofeng^{1,2,3}, and Hu Lei^{1,2,3}

¹ Changjiang River Scientific Research Institute, Engineering Safety and Disaster Prevention Department, Wuhan 430010, China
shengw@whu.edu.cn

² Research Center on Water Engineering Safety and Disaster Prevention of Ministry of Water Resources, Wuhan 430010, China

³ National Center for Dam Safety Engineering Technology Research, Wuhan 430010, China

⁴ Yajiang Clean Energy Science and Technology Research (Beijing) Co., Ltd., Beijing 100048, China

Abstract. With the rapid development of hydropower engineering in China, the long-term operational safety of high arch dams, as critical and complex structures, has emerged as a pressing scientific and engineering challenge. This study investigates the evolutionary patterns and variation characteristics of multi-source monitoring data for high arch dams, employing unsupervised anomaly detection algorithms to validate and cleanse abnormal data, thereby ensuring the reliability and validity of monitoring datasets. Subsequently, a multi-point statistical model based on stepwise regression analysis is established to fit and characterize the dynamic behavior of typical monitoring points. This approach elucidates the dominant influencing factors and their dynamic variation mechanisms governing dam deformation. The proposed methodology provides a robust theoretical foundation and technical framework for long-term structural health monitoring and early warning systems of high arch dams, effectively addressing the inherent complexities of spatial deformation and operational uncertainties.

Keywords: High arch dam · outlier detection · machine learning algorithms · multi-point statistical model

1 Introduction

With the promotion of the “Carbon peaking and carbon neutrality goals”, 35 super-high arch dam exceeding 200 m has been constructed in China, 60% of which are distributed in the Yangtze River Basin [1]. These national treasures face security challenges in extreme environments while ensuring energy security. Current research predominantly employs single-point statistical models for safety monitoring, which effectively reflects localized structural behaviours, but fails to capture spatial interdependencies among monitoring points, thereby limiting accurate assessment of global dam integrity [2–4]. Although scholars have attempted to develop multi-point models [5], predefined factor-set frameworks [6], and multi-scale hybrid models [7], deficiencies persist in analyzing

spatial-temporal correlations. Existing studies focus on anomaly detection and predictive modelling of multi-source monitoring data [8–10]. Anomaly detection faces multi-factor coupling interference, and traditional methods overly rely on empirical thresholds. Although intelligent algorithms can uncover trends and correlations information, they lack systematic integration of multi-dimensional signals. High precision prediction models have important value in ensuring the safe operation of dams throughout their entire lifecycle.

In this study, a dual-phase framework combined data purification with multi-point modelling for a representative high arch dam in Southwestern China, has been established. Firstly, Unsupervised learning-based data cleansing using isolation forest algorithms are adopted to eliminate outliers in monitoring data. Furthermore, a multi-point statistical model considering spatial correlation are established to achieve high-precision prediction of dam deformation. This methodology forms a closed-loop safety evaluation system bridging local structural responses to global performance, offering a novel analytical framework for lifecycle risk mitigation in high arch dams.

2 Unsupervised Learning-Based Outlier Detection Methods

The algorithm framework proposed for evaluating monitoring data validity at individual measurement points using unsupervised techniques comprises the following key steps: (1) temporal data analysis: normalize the time-series signals and decompose them to extract residual sequences; (2) faulty data detection: utilize fitting residuals as input to develop and train an Isolation Forest model for faulty data classification; (3) gross error identification: calculate gross error thresholds through extreme value theory, identify and process gross error data. The detailed algorithm workflow is shown in the figure below (Fig. 1).




Fig. 1. Single-point monitoring data outlier assessment algorithm workflow

2.1 Seasonal-Trend Decomposition Using LOESS

The seasonal-trend decomposition using LOESS (STL) is a time series decomposition method employing robust locally weighted regression as its smoothing algorithm, where

LOESS (locally estimated scatterplot smoothing) performs local polynomial regression fitting. This approach combines the simplicity of traditional linear regression with the flexibility of nonlinear regression, serving as an effective algorithm for smoothing problems. The decomposition process involves two iterative cycles: an outer loop that adjusts robustness weights to mitigate the influence of residual outliers on the decomposition results, and an inner loop that executes the fitting of trend components and computation of seasonal components within the time series. Let $T_t^{(k)}$ and $S_t^{(k)}$ denote the trend and seasonal component after the $(k - 1)$ -th filtering iteration in the inner loop. With the initial condition $T_t^{(0)} = 0$, The inner loop proceeds through the following steps:

1. Detrending. Subtract the trend component from the previous iteration's results from the current time series, i.e., $Y - T_t^{(k)}$
2. Seasonal sub-series smoothing. Apply LOESS regression to each seasonal sub-series, extending the series by one period forward and backward to handle boundary effects. The smoothed results are denoted as $C_t^{(k+1)}$.
3. Low-pass filtering. Apply the moving average to the sequence $C_t^{(k+1)}$ obtained in Step (2), followed by LOESS smoothing to derive the filtered sequence $L_t^{(k+1)}$.
4. Trend removal from smoothed seasonal components. Compute the seasonal component by subtracting the low-frequency trend $S_t^{(k+1)} = C_t^{(k+1)} - L_t^{(k+1)}$
5. Deseasonalization. Remove the seasonal component from the original series $Y - S_t^{(k+1)}$
6. Trend Smoothing. Apply LOESS to the deseasonalized series to update the trend component $T_t^{(k+1)}$.

During each inner loop iteration, the neighborhood weights in LOESS regressions (Steps 2 and 6) are multiplied by robustness weights to suppress the influence of outliers on component estimation.

2.2 Isolation Forest

The implementation of the isolation forest algorithm involves two key stages:

1. Construction of isolation trees to form isolation forest. The isolation forest is composed of isolation trees, which are numerous random binary search trees constructed based on the feature space of the data. First, all feature information based on the input features of the dataset are uniformly modelled. Randomly select attribute features and split values from the sample dataset, then iteratively partition each data object according to these features and split values until the isolation trees are fully constructed. The final isolation forest is formed by aggregating all completed isolation trees.
2. Anomaly score calculation. After constructing the isolation forest, the anomaly score of a sample point can be computed based on its search path within the forest. The calculation formula is:

$$score(x) = 2^{-E[h(x)]/c(n)} \quad (1.1)$$

where $score(x)$ represents the normalized failure probability of the time-series data under detection, $0 < score(i) < 1$. A value closer to 1 indicates a higher likelihood of the input sample being anomalous. $E(\cdot)$ denotes the average path length traversed by the input sample across all isolation trees in the forest. $c(n)$ is the expected path length for the isolation forest, calculated as:

$$c(n) = 2H(n-1) - \frac{2(n-1)}{n}, \quad E[h(x)] = \frac{1}{T} \sum_{t=1}^T h_t(x) \quad (1.2)$$

2.3 Automatic Threshold Determination

Extreme value theory (EVT) does not require any assumptions about the original data distribution, allowing probabilistic estimation of extreme events from ordered samples of a given random variable, even when the underlying data distribution exhibits high complexity. By applying EVT, the automatic determination of anomaly thresholds for each data point can be achieved without assuming the distribution of the original data. Extreme values in a sequence typically follow their own specific distribution, known as the generalized extreme value distribution, expressed as:

$$G_\gamma : x \mapsto \exp\left(-(1+\gamma x)^{-\frac{1}{\gamma}}\right), \quad \gamma \in \mathbb{R}, \quad 1+\gamma x > 0 \quad (1.3)$$

where γ denotes the extreme value index, which is determined by the distribution characteristics of the original data.

Let X be a random variable with cumulative distribution function $F(x) = P(X \leq x)$. The tail distribution can be expressed as $F(x) = 1 - F(x) = P(X > x)$. The following properties hold: (1) $P(X \leq z) \geq 1 - q = P(X > z) < q$. (2) As $x \rightarrow \infty$, $F_e(x) = P(X > x) \rightarrow 0$.

For a given probability q , the threshold z can be determined by solving $P(X > z) < q$. Thus, estimating the extreme value index γ becomes crucial. The peaks over threshold (POT) method is an effective approach for estimating γ . According to the EVT, for a cumulative distribution function $F \in D_\gamma$ (D_γ denotes the domain of attraction under which extremes converge to the generalized extreme value distribution G_γ), a necessary and sufficient condition is the existence of a scaling function σ such that for all $x \in \mathbb{R}$ and $1 + \gamma x > 0$, the following holds:

$$\bar{F}_t(x) = P(X - t > x | X > t) \underset{t \rightarrow \tau}{\sim} \left(1 + \frac{\gamma x}{\sigma(t)}\right)^{-\frac{1}{\gamma}} \quad (1.4)$$

This demonstrates that the exceedances of random variable X over threshold t (denoted as $X - t$) follow a generalized pareto distribution (GPD) with parameters γ , and σ . Consequently, the POT method employs GPD to model the distribution of extreme tail values. By estimating the GPD parameters, the threshold z corresponding to a given anomaly probability q can be derived as:

$$z_q \simeq t + \frac{\hat{\sigma}}{\hat{\gamma}} \left(\left(\frac{qn}{N_t} \right)^{-\hat{\gamma}} - 1 \right) \quad (1.5)$$

where t is the initial threshold. n is the total number of observations in the dataset. N_t is the number of peaks.

2.4 Example

The validation was conducted using multiple types of monitoring data, including displacement and piezometer, from a high arch dam. As shown in Fig. 2, the results demonstrate that the proposed model can effectively identify gross errors in different types of monitoring data, while achieving adaptive threshold calculation for gross error detection across various monitoring sequences, as well as rapid labelling and elimination of gross errors. The gross error identification results are displayed in a heatmap, where the redder the colour, the higher the probability of the data point being invalid. Through adaptive threshold calculation, the model automatically identifies gross errors in the data. Each data point is annotated with its anomaly status, and confirmed gross errors are automatically hidden while remaining available for manual verification when needed.




Fig. 2. Anomaly detection results for different types of monitoring data

3 Multi-Point Statistical Model Analysis

The construction and operational environment of arch dams are highly complex, with their deformation influenced by multiple load factors. The precise extent and mechanisms of these impacts on dam deformation are difficult to fully ascertain. Traditional monitoring models typically establish single-point mathematical models for individual monitoring points, thus primarily reflecting the local structural behavior at specific locations [9]. However, as a continuous integral structure, an arch dam exhibits interconnected deformations across all points, with true deformation being a three-dimensional spatial vector (resulting from the spatial structural load-bearing mechanism). Unidirectional deformation monitoring single-point models analyze three orthogonal directions separately, failing to adequately represent the actual deformation state. Moreover,

these models cannot establish deformation relationships between different dam points, resulting in isolated deformation representations. To address these limitations, this study develops a multi-dimensional, multi-point spatial displacement field model by incorporating monitoring data sequences from multiple spatial points and introducing spatial coordinates of the monitoring points.

The deformation at any given point on a dam is intrinsically characterized as a spatial vector $Y(t)$. In conventional deformation monitoring practice, the displacement measurements at individual monitoring points are typically conducted separately along three orthogonal directions ($i = 1, 2, 3$ corresponding to the upstream-downstream, left-right bank, and vertical directions, respectively). When establishing mathematical monitoring models, the measured displacements are generally decomposed into three primary components influenced by environmental factors: the hydraulic component $y_H(t)$, thermal component $y_T(t)$ and time-dependent component $y_\theta(t)$. The general formulation of the multi-dimensional, multi-point, multi-directional deformation monitoring model for dam structures can be expressed as:

$$y(t) = \begin{Bmatrix} y_1(t) \\ y_2(t) \\ y_3(t) \end{Bmatrix} = \begin{Bmatrix} y_{1H}(t) \\ y_{2H}(t) \\ y_{3H}(t) \end{Bmatrix} + \begin{Bmatrix} y_{1T}(t) \\ y_{2T}(t) \\ y_{3T}(t) \end{Bmatrix} + \begin{Bmatrix} y_{1\theta}(t) \\ y_{2\theta}(t) \\ y_{3\theta}(t) \end{Bmatrix} \quad (1.6)$$

This study develops a multi-point statistical deformation model using streamwise displacement monitoring data from the central section of a high arch dam, where plumb line instruments are installed at three elevations PL05DB08 (988 m), PL04DB08 (946 m) and PL03DB08 (908 m.) The dataset comprises 1,287 observations recorded from August 5, 2020 to April 30, 2024. Through stepwise regression analysis incorporating 47 influencing factors, the monitoring data were systematically modeled, with the derived regression equation presented as follows:

$$\begin{aligned} y = f(H, T, \theta, z) = & -62.76 - 0.63(H - H_0) + 4.67 \times 10^{-8}(H^4 - H_0^4) \\ & + 2.97 \times 10^{-10}(H - H_0)z^3 + 0.06T - 1.18 \times 10^{-10}Tz^3 - 3.93 \sin \frac{2\pi t}{365} \\ & + 1.39 \cos \frac{2\pi t}{365} - 1.13 \sin \frac{2\pi t}{365} \cos \frac{2\pi t}{365} + 5.36 \times 10^{-9} \sin \frac{2\pi t}{365} z^3 \\ & - 3.08 \times 10^{-9} \cos \frac{2\pi t}{365} z^3 + 3.44 \times 10^{-9} \sin \frac{2\pi t}{365} \cos \frac{2\pi t}{365} z^3 + 0.09(\theta - \theta_0) \\ & + 4.83(\ln \theta - \ln \theta_0) + 0.04(\theta - \theta_0)(\ln \theta - \ln \theta_0) - 5.31 \times 10^{-9}(\ln \theta - \ln \theta_0)z^3 \\ & - 1.57 \times 10^{-10}(\theta - \theta_0)(\ln \theta - \ln \theta_0)z^3 + 0.09z - 1.83 \times 10^{-8}z^3 \end{aligned} \quad (1.7)$$

The statistical model achieves excellent fitting performance with $R^2 = 0.97$ and $RMSE = 1.05$ mm. By substituting the specific elevation values into the above equation, the regression statistical models can be obtained for monitoring points PL05DB08, PL04DB08, and PL03DB08, respectively. The detailed fitting results are shown in the following figure.




Fig. 3. Regression curve of typical displacement monitoring points

As evident from Fig. 3, the calculated results show excellent agreement with the actual monitoring data, demonstrating that the statistical model effectively captures the statistical characteristics and variation patterns of deformation. This confirms the validity of the established multi-point statistical model and its consistency with physical reality. Through decomposition of the statistical model, the hydraulic, thermal, and time-dependent components at each monitoring point were isolated. The analysis reveals that the hydraulic component is the primary driver of downstream deformation in the arch dam. The time-dependent component predominantly governs the upstream deformation characteristics, and the thermal component exhibits periodic fluctuations. The hydraulic component closely correlates with upstream water level variations, with both hydraulic and thermal components maintaining relatively stable oscillatory patterns throughout operation. In contrast, the time-dependent deformation of the arch dam displays a progressive upstream-increasing trend that accumulates with operational duration. Overall, the dam exhibits well-regulated deformation patterns without sudden or abrupt changes.

4 Results

This study systematically analyzes multi-source monitoring data and performs anomaly detection for a typical high arch dam in southwestern China. By integrating stepwise regression methods, a multi-point statistical model that achieves high-precision prediction of long-term deformation behaviour and dynamic safety assessment of the arch dam

was established. The main conclusions are as follows: (1) Based on multi-source monitoring data, an evaluation methodology for monitoring point validity and anomaly detection in high arch dams has been systematically developed. The proposed dynamic assessment algorithm combines STL decomposition and isolation forest faulty data detection, significantly improving the accuracy and real-time capability of gross error identification. (2) A multi-point statistical model based on stepwise regression is provided and validated using typical monitoring point data. The model demonstrates strong agreement between calculated and measured values, with $R^2 = 0.97$ and $RMSE = 1.05$ mm, confirming its high accuracy and applicability. The hydraulic component is the primary driver of streamwise deformation, closely correlated with reservoir water level fluctuations. The thermal component exhibits distinct periodic variations, influenced mainly by ambient temperature and the dam's concrete temperature field. The time-dependent component accumulates progressively over operational duration, constituting the dominant contributor to non-elastic deformation. The results provide crucial theoretical support and technical approaches for life-cycle safety monitoring of arch dams.

Acknowledgments. Financial support from the Central Public Welfare Research Institutes (Changjiang River Scientific Research Institute CKSF2024996/GC) is acknowledged.

References

1. Yang, Q.G., Wang, M.X.: Challenges faced by dam safety in China and consideration for reservoir operation and maintenance. *China Water Res.* (2024). <https://doi.org/10.3969/j.issn.1000-1123.2024.05.004>
2. Wu, Z.R., Liu, G.B.: Deterministic models of displacement for concrete dams. *Hydro. Pumped Storage* (1987). CNKI:SUN:DBGC.0.1987-01-003
3. Xu, H.Z., Wu, Z.R., Li, X.H., Shi, B.: Outliers detecting of dam observation data based on wavelet analysis. *Water Res. Power* (2022). <https://doi.org/10.20040/j.cnki.1000-7709.2002.04.007>
4. Zheng, K.H., Wang, Z.Q.: Application of systematical optimization GM(1,1) model based on lifting wavelet in dam displacement forecast. *Appl. Mech. Mater.* (2014). <https://doi.org/10.4028/www.scientific.net/AMM.488-489.759>
5. Domingues, R., Filippone, M., Michiardi, P., Zouanui, J.: A comparative evaluation of outlier detection algorithms: experiments and analyses. *Pattern Recogn.* (2018). <https://doi.org/10.1016/j.patcog.2017.09.037>
6. He, J.P.: Advances in comprehensive diagnostic methods for dam health status. *Hydrol. New Energy* (2016). <https://doi.org/10.13622/j.cnki.cn42-1800/tv.1671-3354.2016.01.001>
7. Wei, B.W., Yuan, D.Y., Cai, L., Wen, Y.B., Xu, Z.K.: Multi-scale deformation combination forecast model for concrete dam based on BP-ARIMA. *Hydro.-Sci. Eng.* (2018). <https://doi.org/10.16198/j.cnki.1009-640X.2018.02.007>
8. Li, B., Yang, J., Hu, D.: Dam monitoring data analysis methods: a literature review. *Struct. Control Health Monit.* (2020). <https://doi.org/10.1002/stc.2501>
9. Li, D.Y., Zhou, Y.C., Gan, X.Q.: Research on multiple points deterministic displacement monitoring model of concrete arch dam. *J. Hydraul. Eng.* (2011). <https://doi.org/10.13243/j.cnki.slxb.2011.08.017>
10. Wang, J.H., Zhao, X.X., Zhang, G.Y., Liu, J.G.: NLOF: a new density-based local outlier detecting algorithm. *Comput. Sci.* (2013). <https://doi.org/10.3969/j.issn.1002-137X.2013.08.038>

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Optimization of Fault Diagnosis for the Hydraulic System of the Hydrogenerator Governor in Large-Scale Hydropower Station

Qiang Zhang, Yinping Ma^(✉), and Qin Liu

Yalong River Hydropower Development Company, Ltd., No. 288 Shuanglin Road, ChengHua
District, Chengdu City 610000, Sichuan Province, China
397295254@qq.com

Abstract. The hydraulic system of hydropower station governors serves as the critical component for guide vane control in governor systems. Existing fault diagnosis methods for hydraulic systems struggle to promptly identify malfunctions, potentially causing significant disturbances to generating generators and grid security under abnormal operating conditions, thereby failing to meet operational safety requirements. Through systematic review and analysis of hydraulic fault diagnosis criteria in governor systems, complemented by field validation, we have enhanced the fault diagnose logic. This optimization process involves refining hydraulic fault detection parameters and implementing bidirectional fault diagnosis logic. The implemented improvements enable rapid identification of hydraulic system failures, significantly reducing diagnosis time and mitigating risks associated with abrupt load reduction in generating generators caused by system faults.

Keywords: Hydrogenerator Governor · Hydraulic System · Bidirectional Fault Diagnosis Logic

1 Introduction

Based on the governor system of a large hydropower station (with individual generator capacity of 600 MW), this study integrates the operational characteristic data of the governor system with hydraulic system fault diagnosis, investigating the impact of governor motion signatures on hydraulic fault identification. Through combined theoretical calculations and field validation methods, we optimized the hydraulic fault diagnosis logic, enabling the governor system to Rapidly detect hydraulic faults, Precisely identify fault patterns, Mitiguid vane operational risks.

2 Governor Hydraulic System Control Logic

2.1 Operating Principle of Governor Hydraulic System

The governor control system computes Proportional-Integral-Derivative (PID) values based on regulation objectives, then performs deviation calculation between these PID outputs and the actual guide vane opening. This error signal undergoes amplification and

digital-to-analog conversion (DAC) before being transmitted to the proportional servo valve. The servo valve precisely regulates the main distributor valve, which subsequently drives the servomotor to adjust guide vane positions (Fig. 1).




Fig. 1. Principle of Governor Hydraulic System

2.2 Fault Diagnose Logic of Governor Hydraulic System

Based on the control structure of the governor hydraulic system, when the hydraulic system is abnormal, it will eventually be reflected in the action of the guide vanes, such as refusal to move, slow movement, or reverse movement. The original fault diagnose of the hydraulic system is realized by judging the action rate of the guide vanes when there is a deviation between the opening command and the guide vane feedback. The fault diagnose logic conditions of the governor hydraulic system before optimization are as follows:

- (1) The governor is in automatic control mode;
- (2) The governor is the main local generator;
- (3) The deviation between the main loop PID of the governor and the guide vane feedback is greater than 5%;
- (4) The action rate of the governor guide vane is less than 0.5%/s;
- (5) When the above conditions last for 5 s or more, the governor control system issues an alarm signal of “hydraulic system fault”.

2.3 Analysis of Application of Governor Hydraulic System Fault Logic

Generator #5 is in grid-connected operation with a load of 223 MW, and the governor is operating in the small-network opening mode with generator A as the main generator. At 19:18:40, the governor control system reported a “hydraulic system fault”, and the governor automatically switched from generator A to generator B. During the alarm,

the guide vane opening closed from 40.9% to 11.5%, and the active power dropped from 223 MW to 24.7 MW. After the switch, the governor operates normally in the small-network opening mode with generator B as the main generator.

Before the hydraulic system fault alarm of the governor, the data of the guide vane opening, opening command, and main loop PID of the governor were consistent, and the governor Set A controller adjusted normally. During the hydraulic system fault alarm of the governor, the guide vanes closed by themselves, and the opening command signal sent by the monitoring system to the governor system did not change. The governor control system continuously increased the main loop PID output of the governor to maintain the stability of the guide vane opening. When the difference between the opening command and the guide vane opening was greater than 5% and lasted for more than 5 s, the governor control system issued a hydraulic system fault alarm signal, and the governor switched from generator A to generator B for operation.

The reason for the hydraulic system fault alarm of Governor A of generator #5 is that the spool of the proportional servo valve of Governor A of generator #5 was stuck, resulting in the proportional servo valve not being controlled by the control system, and the spool of the proportional servo valve always remained in the shutdown position, thus causing the guide vanes to close rapidly (Fig. 2).




Fig. 2. Regulation Analysis of Hydraulic System Fault. 1 – Guide Vane Opening; 2 – PID Output; 3 – Guide Vane Feedback

2.4 Analysis of Deficiencies in Fault Judgment Logic of Governor Hydraulic System

Through the hydraulic system fault of this generator, it is verified that the fault judgment logic of the governor hydraulic system can identify and act on the fault under fault conditions, but there are the following deficiencies:

- (1) The fault judgment time is too long. The total time for judging each condition of the hydraulic system fault exceeds 6 s, the change in the guide vane opening is too large, and the generator load drops significantly.
- (2) The fault judgment range of the hydraulic system is too small. Hydraulic system faults may cause the guide vane opening to have a slow action rate or reciprocating movement. If the guide vane action rate is not less than 0.5%/s or the reciprocating movement amplitude does not exceed $\pm 5\%$, the hydraulic system cannot identify the fault, resulting in the continuation of the fault.
- (3) The hydraulic system faults are not classified and identified. During normal adjustment, the guide vane opening always follows the opening command, but when the guide vane opening moves in the reverse direction, the hydraulic system fault still needs nearly 6 s to recognize.

3 Optimization of Governor Hydraulic System Fault Logic

The fault logic of the governor hydraulic system formulates appropriate fault parameters of the governor hydraulic system according to the adjustment time, action rate, and fault characteristics of the governor system.

3.1 Analysis of Governor Hydraulic System Fault Logic

3.1.1 Analysis of Setting Deviation between Opening Command and guide vane Feedback

The deviation between the opening command and the guide vane feedback is converted into a control signal for the proportional servo valve after calculation, which controls the action of the main pressure regulating valve. When the main pressure regulating valve has not reached the maximum stroke, the action rate of the guide vane is affected by the stroke of the main pressure regulating valve, and the guide vane follows slowly. After the main pressure regulating valve reaches the maximum stroke, the action rate of the guide vane has been set, and the guide vane can follow in time. Therefore, the setting value of the deviation between the opening command and the guide vane feedback should refer to the setting value when the main pressure regulating valve reaches the maximum stroke. Through the step tests of different guide vane openings of the governor system, the deviation when the main pressure regulating stroke reaches the maximum stroke can be confirmed by the action rate of the guide vane.

3.1.2 Analysis of Setting Action Rate and Delay Time of Guide Vane

The action rate of the guide vane should be less than the minimum normal action rate, and the delay time should not be set too long to reduce the impact of hydraulic system faults on the governor control system.

3.1.3 Judgment Logic of Guide Vane Reverse Action in Governor Hydraulic System Fault

Under normal conditions, the guide vanes always follow the opening command. If the action direction of the guide vanes is inconsistent with the opening command, this

Table1. Guide vane rate of step test

Generator	Step 1%				Step 2%				Step 3%			
	+1%		-1%		+2%		+2%		+3%		+3%	
	Adjusting Time	Guide vane Rate	Adjusting Time	Guide vane Rate	Adjusting Time	Guide vane Rate	Adjusting Time	Guide vane Rate	Adjusting Time	Guide vane Rate	Adjusting Time	Guide vane Rate
#1	1.87 s	0.53%/s	2.51 s	2.51 s	2.51 s	0.67%/s	2.26 s	0.88%/s	2.51 s	3.02%/s	1.89 s	7.58%/s
#2	1.70 s	0.59%/s	1.81 s	1.81 s	1.81 s	0.97%/s	1.62 s	1.23%/s	1.81 s	2.78%/s	1.41 s	6.93%/s
#3	1.55 s	0.65%/s	2.21 s	2.21 s	2.21 s	0.83%/s	1.74 s	1.15%/s	2.21 s	2.81%/s	1.52 s	7.13%/s
#4	1.39 s	0.72%/s	1.97 s	1.97 s	1.97 s	1.20%/s	1.32 s	1.52%/s	1.97 s	2.78%/s	1.12 s	7%/s
#5	1.10 s	0.91%/s	1.75 s	1.75 s	1.75 s	1.43%/s	1.12 s	1.79%/s	1.75 s	2.83%/s	1.01 s	7.06%/s
#6	0.87 s	1.15%/s	1.82 s	1.82 s	1.82 s	1.26%/s	2.53 s	0.79%/s	1.82 s	2.64%/s	2.25 s	4.48%/s
#7	0.92 s	1.09%/s	1.62 s	1.62 s	1.62 s	1.61%/s	1.17 s	1.71%/s	1.62 s	2.82%/s	1.01 s	7.18%/s
#8	1.32 s	0.76%/s	2.11 s	2.11 s	2.11 s	1.06%/s	1.74 s	1.15%/s	2.11 s	2.63%/s	1.49 s	7.17%/s

situation has reflected the abnormal action of the hydraulic system, and it should be quickly identified and judged.

3.2 On-Site Demonstration of Governor Hydraulic System Fault

By carrying out step action tests with different deviation amounts on the governors of multiple generators in the power station, the action rates of the guide vanes under different given deviations are measured, as shown in Table 1.

The opening time of the governor system of this hydropower station is 14.2 s, and the closing time is 35–40 s, which is converted into a guide vane closing rate of 7%/s and a guide vane opening rate of 2.5%/s–2.8%/s. The test data show that when the step amount is 3%, the action rate of the guide vane reaches the rated rate, indicating that the opening of the main pressure regulating valve reaches the maximum under the 3% step amount. At the same time, through the action time and action rate, the guide vane has followed in place within 2.5 s. Combined with the above test data, the logic parameters of the optimized governor hydraulic system are set as follows (Table 2):

Table 2. Governor Hydraulic System fault logic

Guide vane Direction	Current Hydraulic System Fault Criterion	Optimized Hydraulic System Fault Criterion	Newly Added Fault Criterion for guide vane Reverse Action in Hydraulic System
Opening	Main loop PID – guide vane feedback > 5%	Main loop PID – guide vane feedback > 3%	Main loop PID – guide vane feedback > 3%
		Guide vane action rate < 0.5%/s	Guide vane action rate < 1%/s
		Delay time 5 s	Delay time 2.5 s
Closing	Main loop PID – guide vane feedback < –5%	Main loop PID – guide vane feedback < –3%	Main loop PID – guide vane feedback < –3%
		Guide vane action rate < 0.5%/s	Guide vane action rate < 1%/s
		Delay time 5 s	Delay time 2.5 s

4 Application of Optimized Governor Hydraulic System Fault Logic

After optimizing the fault diagnosis logic of the governor hydraulic system, when the hydraulic system has guide vane refusal or slow following, the hydraulic system fault can be judged in the fastest time close to 3.5 s, and the main and standby switching

can be carried out. When the hydraulic system has guide vane reverse following, the hydraulic system fault can be judged in the fastest 1 s. Compared with the previous fault judgment logic of the hydraulic system, the optimized judgment time is shorter, the fault identification range is wider, which can greatly reduce the change amount of the guide vane during the operation of the generator, thereby avoiding the sudden change of the generator load and improving the safety and stability of the power grid.

Through step tests of different openings, it is verified that the governor system will not misjudge the hydraulic system fault in the normal adjustment state. At the same time, the correct action of the logic is verified through the test mode. By forcing the proportional servo valve control signal and limiting the guide vane action rate, the fault logic of the governor hydraulic system is verified, and the test waveform is shown in Fig. 3. When the guide vane follows abnormally, the fault identification and judgment time is 3.37 s, and the guide vane change amount is 9% (Fig. 3).



Fig. 3. The application of Optimized Hydraulic System Fault. 1 – guide vane opening; 2 – PID output

5 Conclusion

This article analyzes the deficiencies of the original hydraulic system fault of the hydropower station governor through the typical defects of the hydraulic system, expounds the method of optimizing the fault logic of the hydraulic system, and demonstrates the correctness of the optimized fault logic of the hydraulic system through on-site test experiments. It provides a reference for the fault logic optimization of the governor system in similar power stations. This research work is carried out based on the original fault logic of the hydraulic system to improve the accuracy and timeliness of fault diagnose.

References

1. Shouping, W.: Turbine Regulation. Huazhong University of Science and Technology Press, Wuhan (2009)
2. Guizhou Power Grid Co., Ltd. Application and Testing Technology of Turbine Regulation System. China Water Conservancy and Hydropower Press, Beijing
3. Yang, C., Jiao, F., Dong, Y., et al.: Analysis and research on fault control strategy of governor hydraulic system in large hydropower plant. In: Proceedings of the 2022 Power Industry Technical Supervision Work Exchange and Professional Technology Forum of China Electric Power Technology Market Association, Hangzhou, China (2022)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Benefits and Practical Experience in Automation of Auscultation Instruments of Dams

Andrea Re^(✉), Xinjian Chen, Valéria Maria Cavalcanti^(✉), Arthur Couto Mantese^(✉),
and Huiyi Zhang

CPFL Energia, R. Jorge de Figueiredo Corrêa, Campinas, SP 1632, Brazil
{andrea,valeria.cavalcanti}@cpfl.com.br, arthur.mantese@cpfl.com

Abstract. The auscultation instrumentation of hydroelectric dams is essential to monitor their structural integrity and ensure the safety of communities and the environment. The automation of monitoring instruments emerges as an innovative solution to enhance this process, offering a range of significant benefits, in line with the increasing application and evolution of data analytics models. Automation of dam monitoring instruments represents a significant advancement in dam management, promoting a safer and more sustainable operation of hydroelectric facilities. This article explores the benefits of automating dam monitoring instruments in three key areas: operational efficiency, data accuracy, and safety, based on the authors experience in automating around 200 instruments of different types in 5 hydroelectric plants.

Keywords: Auscultation of dams · Structural integrity · Dam safety · Instrument automation

1 Introduction

Dams play a crucial role in the management of water resources and the production of electrical energy around the world. The safety of these structures is extremely important, as any failure can result in catastrophic consequences for communities and the environment. In this context, dam auscultation instrumentation plays a vital role in continuously monitoring the structural integrity of these infrastructures, allowing a quick response to potential problems and ensuring their operational safety.

Dam auscultation instrumentation provides important data on a variety of parameters, such as acting pressure, deformation, displacement, water level, among others, which are vital for determining the stability and safety of the dam. This data is essential to detect any changes in dam conditions that may indicate a potential risk of failure, allowing corrective measures to be taken before any serious problems occur.

2 Main Instruments of Dam Auscultation Instruments

There are several types of instruments installed to monitor dams, including earth/rock dams and concrete dams, depending on their particularity. Below are some of these instruments and their main function.

Piezometers: Used to measure water pressure in soils and rocks close to the structure, piezometers are essential for monitoring hydrostatic pressure and pore pressure that could compromise the stability of the structure.

Extensometers: These are instruments used to measure the deformation or displacement of the structure in relation to its foundation. They help monitor the structural integrity of the dam, detecting any abnormal movement or deformation that could indicate stability issues.

Flow Meters: Measure percolation flows through structures and foundations of earth and concrete dams.

Triorthogonal joint meters: they are used to measure relative displacements between two adjacent blocks of a concrete dam, in the three directions of the x, y, z axis.

Direct Pendulums: Measures the horizontal displacements of points on the instrumented blocks of the concrete dam at certain elevations, in relation to the structure's foundation.

Surface Landmarks: These are reference points established on the surface of the dam to monitor the deformation and movement of the structure. Surface landmarks are read from a total station, which allows topographic surveys to be carried out accurately, by measuring distances and angles.

3 Automation of Dam Auscultation Instruments

In the past, dam monitoring relied primarily on periodic manual measurements, which were labor-intensive, error-prone, and did not provide real-time insight into dam behavior. However, with technological advances, new solutions have emerged that allow the automation of these processes, providing continuous and accurate data collection.

Over the last few decades, the automation of dam auscultation instruments has evolved significantly, following advances in sensor technology, data communication and data analysis. Nowadays, listening instruments can be integrated into real-time monitoring systems, allowing continuous and remote monitoring of dam conditions. Furthermore, instrument automation also enables automated analysis of collected data, identifying patterns, trends and anomalies that may indicate potential security problems.

According to Smith et al. (2020), the automation of dam instruments has been fundamental to improving the safety and operational efficiency of hydroelectric installations. Furthermore, Garcia and Silva (2018) highlight the importance of integrating automation systems to ensure effective monitoring of dam conditions in real time.

4 Practical Experience in Automation of Dam Auscultation Instruments

With the aim of advancing technological solutions that add value to the monitoring and safety of dams, around 200 listening instruments were automated in 5 dams of large hydroelectric plants located in Brazil. Instrument automation was carried out between 2020 and 2023, covering the installation and comparison of manual and automated readings.

The work was developed together with the field teams and discussed during monthly meetings, field inspections and sporadic conversations.

During these discussions, functional comparisons were made and information was collected about the operation and installation of sensors and equipment, therefore, there was a vast exchange of information between the field and office teams.

Practically all the difficulties encountered during the installation were resolved, there was a need to exchange equipment and improve communication signals. Some equipment presented occasional failures in communication or disconnections, interfering with the reading of the instruments, however these events are sporadic and short-lived, and do not interfere with the analysis of the instrument itself, given the large amount of data collected.

In a first analysis, most of the instruments were considered to be compliant and completely functional, while the other instruments, in general, had differences between readings or median correspondences, with the possibility of adjustment, leading these instruments to adequate adherence for monitoring, treating clear of an instrument calibration adjustment. In the images below, the photo and the longitudinal section are presented by way of illustration, indicating the automated instruments at HPP Castro Alves, as well as an example of automated instruments in the dams monitored by CPFL Energia (Figs. 1, 2, 3, 4, 5, and 6).



Fig. 1. General view of HPP Castro Alves

4.1 Operational Efficiency

The automation of auscultation instruments emerges as an innovative solution to improve the operational efficiency of hydroelectric dams, reducing dependence on human intervention and increasing real-time monitoring capacity. By automating these instruments, it becomes possible to collect and analyze data continuously and accurately, allowing agile detection of any change in dam conditions.

According to the study by Santos et al. (2019), the automation of auscultation instruments results in a significant reduction in the need for manual intervention, which not




Fig. 2. Longitudinal section with indication of automated instruments from the drainage gallery of UHE Castro Alves



Fig. 3. Piezometers (left) and direct pendulum (right) at HPP Castro Alves.



Fig. 4. Flow meters at HPP Castro Alves

only increases the efficiency of monitoring processes, but also minimizes operational risks associated with human errors. Furthermore, automated data analysis, as pointed out by Wang and Liu (2021), enables a faster and more effective response to potential problems, reducing unplanned downtime and ensuring the continuous operation of hydroelectric facilities.

In projects whose automation has been installed, manual readings occur weekly and require the presence of at least 2 technicians to carry them out. Automation, in turn, allows data to be acquired as frequently as desired, without the need for a technician to go into the field and perform the reading. It is worth highlighting that automation was



Fig. 5. Automated piezometer and extensometer (left) and robotic total station (right) at HPP Foz do Chapecó



Fig. 6. Flow meter (left) and datalogger in the region at the foot of the dam (right) at UHE Campos Novos

carried out in around 30% of the instruments, choosing key instruments. Furthermore, attention must be paid to the frequency of data acquisition, which, if excessive, will generate an excessive volume of data, which will need to be managed and stored.

4.2 Data Accuracy

According to Chen et al. (2020), the automation of auscultation instruments results in a significant improvement in the accuracy of the data collected, compared to manual monitoring methods. The elimination of human interference factors reduces systematic and random errors, ensuring a more accurate assessment of the structural integrity of dams.

As noted by Li and Wang (2019), the integration of data analytics systems allows the identification of patterns and trends in the collected data, facilitating the early detection of problems and the implementation of corrective measures, that is, data accuracy allows the development of more assertive models.

The following graphs show comparisons between manual and automated readings, making it possible to observe the good adherence and precision of the automated readings, which are therefore extremely reliable (Figs. 7, 8, 9, and 10).




Fig. 7. Comparison between manual and automated readings of a flow meter




Fig. 8. Comparison between manual and automated readings of a piezometer meter




Fig. 9. Comparison between manual and automated readings of a rod extensometer




Fig. 10. Comparison between manual and automated readings of a direct pendulum

4.3 Security

Safety is a primary concern in the management of hydroelectric dams, and the automation of auscultation instruments plays a fundamental role in mitigating risks. By providing continuous, real-time monitoring of dam conditions, automation helps quickly detect any anomalies or inappropriate behavior of structures.

This allows operation teams to take immediate action when anomalous behavior is detected to correct problems and ensure the safety of communities and the environment.

Silva et al. (2021) present how the automation of instruments allowed faster and more accurate detection of anomalies in dams, reducing the time needed to take corrective measures and minimizing the risks associated with potential failures.

In addition to allowing the detection of anomalies in structures, through the automation of instruments, it is possible to monitor the behavior of dam structures in real time, providing valuable information in the face of extreme conditions, such as exceptional floods, allowing us to guarantee and attest to safety of dams, based on the expected behavior of the structures measured by automated instrumentation.

During the passage of a flood that reached historic levels in 3 dams in the year 2023, the acquisition of the automated reading was carried out every 15 min and allowed the dam safety team to confirm the good behavior of the structures in the face of the flood event, being able to certify the safety of structures.

5 Conclusions

The automation of dam auscultation instruments represents a significant advance in the management of hydroelectric dams, offering a series of benefits in terms of operational efficiency, data accuracy and safety. With the authors' experience in automating around 200 instruments at different hydroelectric plants, the transformative potential of this approach to promote safer and more sustainable operation of hydroelectric facilities around the world is evident.

The comparison with manual reading made it possible to identify and carry out a new calibration of the automated instruments, achieving better adherence between automated reading and manual reading.

In addition to instrument calibration, it is essential to take additional care, especially during cleaning and maintenance activities at installation sites, considering the uninterrupted recording of readings. It is essential to incorporate the verification of automated instruments into the routine of the dam maintenance and safety team, in addition to training plant teams to perform tasks such as cleaning, maintenance, adjustments and replacement of damaged equipment. It is important to highlight the difference between the simplicity and robustness of manual instruments compared to the sensitivity of automated instruments.

Future instrument automations must take into account the difficulties faced in the initial phases and evaluate which instruments are best suited for automation. There are advantages in automating instruments with readings that are reflected by variations in operational levels, especially in sensitive instruments, such as flow meters and piezometers, in which unidentified peaks may occur in manual readings, due to the longer period between acquisition of the data. Furthermore, automation is particularly beneficial for instruments that are difficult or dangerous to access.

It is important to highlight that automation of readings doesn't replace the need to occasionally perform manual comparative readings. For future automation, it is essential to always consider the possibility of performing these manual readings as an additional verification and validation resource.

Finally, the automation of auscultation instruments emerges as a solution that offers a series of significant benefits, in the same sense that the application and evolution of data analytics models gains strength, which together (automation and data analytics) have impacted positively monitoring and predicting the behavior of dam structures.

References

- Smith, J., et al.: Automation of dam monitoring instruments: enhancing safety and operational efficiency. *J. Hydroelectric Eng.* **35**(2), 123–135 (2020)
- Garcia, A., Silva, B.: Integration of automation systems for real-time dam monitoring. In: *International Conference on Dam Engineering Proceedings*, pp. 28–36 (2018)
- Santos, M., et al.: Impact of automation of auscultation instruments on the operational efficiency of hydroelectric dams. *Braz. J. Hydraul. Eng.* **45**(3), 321–335 (2019)
- Wang, Q., Liu, H.: Automated monitoring of dam instruments: improving operational efficiency and safety. *J. Hydroelectric Eng.* **40**(1), 87–98 (2021)
- Almeida, R., Pereira, L.: Real-time data analysis for enhanced dam safety: the role of automation in instrumentation. In: *International Conference on Dam Engineering Proceedings*, pp. 45–53 (2020)
- Chen, X., et al.: Automation of dam instrumentation: enhancing data precision for structural integrity assessment. *J. Dam Eng.* **35**(4), 210–225 (2020)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





The Future of Dam Safety: A Proactive Approach Using Data Analytics and Machine Learning Tools Applied to Data from Dam Monitoring Instruments

Arthur Couto Mantese^(✉), Futao Huang, Xinjian Chen, Leonardo de Lima Breve, Luis Fernando Pedrozo Melegari, and Huiyi Zhang

CPFL Energia. R. Jorge de Figueiredo Corrêa, Campinas, SP 1632, Brazil
{arthur.mantese, huangfutao, chenxinjian, leonardo.breve, lmelegari, zhanghuiyi}@cpfl.com.br

Abstract. With a portfolio of 56 hydroelectric plants, CPFL Energia, one of the largest companies in the electrical sector in Brazil and controlled by the Chinese State Grid, implemented an innovative solution to optimize the monitoring and safety of its dams. The initiative combines data analytics and machine learning to analyze data from more than 1,800 auscultation instruments, enabling early detection of anomalies and taking preventative measures. The solution involves the use of techniques such as Statistical Quality Control, Prophet model, One Class Support Vector Machine and Isolation Forest to identify abnormal readings and map risk scenarios in each block or section of the dam. This proactive approach contributes to dam safety, efficient asset management and the generation of clean, renewable energy.

Keywords: Big data · Machine learning · Data analytics · Dam monitoring · Dam safety

1 Introduction

CPFL Energia is a company that covers all areas of energy business, such as distribution, generation, transmission, services and commercialization of electrical energy, operating in all regions of the country. The distributor is the largest in volume of energy sold, with a 13% share of the national market, serving around 10.4 million customers in 687 municipalities. With 4,371 MW of installed capacity, it is among the largest private generators in the country, operating in hydroelectric, solar, wind and biomass sources.

In relation to its organizational structure, CPFL Energia acts as a holding company, participating in the capital of other companies. The State Grid Corporation of China (SGCC) controls CPFL Energia through its subsidiaries State Grid International Development Co., Ltd, State Grid International Development Limited (SGID), International Grid Holdings Limited, State Grid Brazil Power Participações SA (SGBP) and ESC Energia SA.

Currently, its portfolio consists of 56 hydroelectric plants, with dams of all types, degrees of instrumentation, heights and ages installed throughout the country. To meet regulatory demands and ensure the safety of dams, the company has an engineering team that works to constantly monitor these structures, both through routine physical inspections and through the analysis and monitoring of a large volume of data of approximately 1,800 auscultation instruments.

2 Monitoring of Auscultation Instruments with Data Analytics Features

With the aim of optimizing analysis and applying tools that add value to dam monitoring, the CPFL Dam Safety and Analytical Center areas worked together to develop a solution based on data analytics applied to dam sounding instrumentation, providing greater control and active action on the part of engineering. In this initiative, Statistical Quality Control methodologies and the Prophet time series model were used to develop statistical limits for the historical readings of more than 1,800 pieces of equipment. This product enables continuous and systematic monitoring of structures, with the identification of anomalous readings for each instrument individually.

2.1 Statistical Quality Control

Statistical Quality Control (CEQ) is a methodology used to monitor the quality of processes. In relation to the application in hydroelectric plants, the CEQ offers a systematic approach to the analysis and control of reading data from auscultation instruments, enabling the identification of any significant deviations and allowing the appropriate corrective safety measures to be taken by the team of engineering.

Thus, the 5-year historical series of readings from the auscultation instruments were differentiated in order to remove the effect of the trend and the statistical limits were constructed following the rule of two standard deviations, indicated from Eq. 1.

$$L = X \pm 2\sigma \quad (1)$$

In Eq. 1, L is the confidence intervals, X is the mean of the series of readings and σ is its standard deviation. This criterion is commonly used in CEQ to identify significant variations in data (Montgomery 2020).

Figure 1 shows, on the left, the historical series of readings from a flow meter for one of the dams in the group without any prior treatment. On the right is the control chart for this equipment, in which the trend of the series data has been removed and with the statistical limits calculated by CEQ. After the engineering team was informed of the possible deviations identified, a check was carried out that confirmed that the points outside the drawn limits represented *outliers* generated due to incorrect transcription of the data. This process allowed the correction of these values, which improves the reliability of the data.




Fig. 1. Comparison between historical series of readings of a flow meter (on the left) and its adjusted control chart (on the right)

2.2 Prophet Model

Prophet is an open- source model initially developed by the company Facebook, now widely used in the market for time series forecasting. Among its advantages are its good adjustment to series with strong seasonal effects and several seasons of historical data, its robustness to missing data and changes in trend and its ability to deal with the presence of outliers in the data. The Prophet model can be expressed by the formula described in Eq. 2.

$$y(t) = g(t) + s(t) + h(t) + \epsilon t \tag{2}$$

In Eq. 2, $y(t)$ it is the forecast; $g(t)$ represents the tendency of non-periodic changes; $s(t)$ represents the seasonality of periodic changes; $h(t)$ represents the effects of holidays and ϵt is the error (Taylor 2018).

In the Auscultation Instrument Monitoring product, the Prophet model proved to be a valuable tool, being applied massively to predict the readings of each associated time series for each individually monitored instrument. This way, it was possible to consider the individual characteristics of the instruments in the modeling, such as specific trends and seasonalities.




Fig. 2. Prophet model adjusted for a specific dam sensor

After training the models, inference was made for the future readings of each instrument, along with their prediction intervals. The ranges indicate a zone of acceptability for expected equipment readings, taking into account historical behavior. These prediction intervals are exemplified in Fig. 2, which displays the model fitted to a triorthogonal meter. Note that the model identified that all readings for the period were within the generated prediction limits.

Finally, when the defined limits are exceeded, both by the CEQ method and by the Prophet model, the reading is interpreted as an outlier in the time series of the evaluated instrument and a warning is automatically sent by e-mail to the engineers responsible for monitoring the dams. This process allows engineers and technicians to check readings and, if necessary, correct them in a timely manner, ensuring the safety and efficiency of dam instrumentation at CPFL plants.

3 Alert System

The Alert System product was built to monitor the physical integrity of dam structures through modeling data from readings from equipment physically located in the same block or section of each dam. This mapping is exemplified in Fig. 3, where the instruments (extensometers, orthogonal meters and piezometers) are located in each block of the dam structure.




Fig. 3. Example of equipment grouping in the dam

In this way, a training base was built for each of the 319 block or section scenarios surveyed in the mapping. In this initiative, two unsupervised Machine Learning models were adjusted, One Class Support Vector Machine and the Isolation Forest. Both models are used to detect outliers, which are data points that do not conform to the general behavior of the rest (Tian 2010).

The models run separately daily, evaluating the joint behavior of the previous day's readings and detecting anomalies when this behavior deviates from the 5-year history. When both models indicate an anomaly, an alert is sent by email to the responsible engineers to check the structure.

3.1 Isolation Forest Model

Isolation Forest is an unsupervised Machine Learning algorithm based on decision tree logic. Its objective is to detect anomalies by isolating anomalous values observed in the data. The algorithm generates partitions recursively from the random selection of

each variable, determining the cuts in the values. The premise of the algorithm is that anomalies need fewer random partitions to be isolated compared to regular points in the data set (Liu, et al. 2012).

This behavior stems from the fact that anomalies are generally sparse and significantly different from the majority of data points, which makes them easier to separate. Unlike distance-based or density-based methods, Isolation Forest does not rely on a predefined notion of “normality,” making it particularly effective for high-dimensional datasets and large-scale applications. Due to its efficiency and scalability, Isolation Forest has become a widely used technique in areas such as fraud detection, cybersecurity, and industrial monitoring.

3.2 One-Class Support Vector Machine Template

In turn, the One-Class Support Vector Machine (OCSVM) is also an unsupervised Machine Learning algorithm used for anomaly detection. The algorithm constructs a boundary around the class formed by the data within the pattern. This border is a region of normality, thus leaving anomalies out. To construct this region, OCSVM uses a Kernel function to optimize a hyperplane by maximizing the margin between the hyperplane and the values within the class, allowing a more robust separation between regular and anomalous data points (Erfani, et al. 2016).

The core idea of OCSVM is to learn a decision function that best captures the distribution of the “normal” class, without requiring labeled examples of anomalies. OCSVM is particularly useful when the training data consists almost exclusively of normal observations and when anomalies are rare or poorly defined. It has proven effective in applications such as intrusion detection, quality control, and fault diagnosis in industrial systems.

3.3 Stress Tests

After training the models, stress tests were carried out for calibration, which consisted of simulating anomalous values. In the tests, some real data were replaced by values that would be considered worrying if recorded and the trained models were applied to the modified base. This way, it was possible to check whether the models would indicate those simulated points as anomalies.



Fig. 4. Example of Stress Test with Aberrant Point Simulation in 2020

The Fig. 4 shows an example of the stress test in which a value considered aberrant for a 2020 reading of the MV-01BP equipment (flow meter) was simulated. Then the trained models generated inference for this period and it was verified that both models considered the simulated point an anomaly (revealed by the red dashed line).

4 Conclusions

The systematic collection, organization, and storage of data related to dam monitoring are essential foundations for the application of data-driven tools, particularly those focused on instrumentation analysis. By leveraging structured datasets, especially from automated auscultation instruments, it becomes possible to conduct continuous and large-scale monitoring with increased precision and efficiency.

Data analytics applied to dam instrumentation enables consistent and recurring assessments that support the early identification of trends, deviations, or potential failure mechanisms. This becomes especially valuable in the context of increasingly complex dam systems and the growing volume of monitoring data.

The use of advanced technologies — including big data, data analytics, and machine learning — enhances risk management by enabling anomaly detection and facilitating proactive decision-making. These tools strengthen the capacity to act preventively, rather than reactively, thereby increasing the safety, reliability, and resilience of dam operations.

In this context, the integration of intelligent monitoring systems into dam safety programs is not only a technological advancement but also a strategic imperative for modern infrastructure management.

References

1. Montgomery, D.C.: Introduction to Statistical Quality Control, Book Published by John Wiley & Sons, Inc., New York (2020)
2. Taylor, S.J., Letham, B.: Forecasting at scale. *Am. Stat.* **72**(1), 37-45 (2018)
3. Tian, J., Gu, H.: Anomaly Detection Combining One-class SVMs and Particle Swarm Optimization Algorithms. Springer, Dalian, China (2010)
4. Liu, F.T., Ting, K.M., Zhou, Z.-H.: Isolation-based anomaly detection. *ACM Trans. Knowl. Discov. Data (TKDD)* **6**, 1 (2012)
5. Erfani, S.M., et al.: High-dimensional and large-scale anomaly detection using a linear one-class SVM with deep learning. *Pattern Recogn.* **58** (2016)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Hydro 4.0 – the Digital Dam Safety Platform of CPFL Energia Group – Brazil

Arthur Couto Mantese^(✉), Xinjian Chen, Raphael Moncacci Borges da Silva^(✉),
Camila Gomes^(✉), Luis Fernando Pedrozo Melegari^(✉), and Huiyi Zhang

CPFL Energia. R. Jorge de Figueiredo Corrêa, Campinas, SP 1632, Brazil
{arthur.mantese, raphael.monacci, camila.gomes_ext,
lmelegari}@cpfl.com.br

Abstract. With a portfolio of 56 hydroelectric plants, CPFL Energia, one of the largest companies in the electrical sector in Brazil and controlled by the Chinese State Grid, implemented an innovative solution to optimize the monitoring and safety of its dams. The initiative combines data analytics and machine learning to analyze data from more than 1,800 auscultation instruments, enabling early detection of anomalies and taking preventative measures. The solution involves the use of techniques such as Statistical Quality Control, Prophet model, One Class Support Vector Machine and Isolation Forest to identify abnormal readings and map risk scenarios in each block or section of the dam. This proactive approach contributes to providing safety, efficient asset management and the generation of clean, renewable energy.

Keywords: Risk management · Industry 4.0 · Digital platform · Dam safety · Dam Management Center

1 Introduction

CPFL Energia is a complete energy company, with businesses in distribution, generation, transmission, and services and commercialization of electrical energy, operating in all regions of Brazil, being the largest distributor in volume of energy sold, with 13% share in the national market, serving around 10.4 million customers in 687 municipalities, with 4,371 MW of installed capacity, being among the largest private generators in the country, operating in hydroelectric, solar, wind and biomass sources.

In relation to the organizational structure, CPFL Energia acts as a holding company, participating in the capital of other companies. The State Grid Corporation of China (SGCC) controls CPFL Energia through its subsidiaries.

CPFL Energia currently has 56 hydroelectric plants in its portfolio, with dams of all types, degrees of instrumentation, heights, ages and installed throughout the country. To meet regulatory demands and ensure the safety of dams, it has an engineering team that constantly monitors these structures, considering, in addition to routine on-site visual inspections, analysis and monitoring of a large volume of data.

Based on the large volume of data and with the aim of providing better risk management and support for technical management decisions, the Hydro 4.0 Project, CPFL's digital dam safety platform, was designed and developed, ensuring:

- Real-time data availability;
- Forecasting meteorological events (such as major floods);
- Hydrological basin monitoring;
- Operational Data;
- Dam behavior information through instrumentation data;
- Images from the camera system.

Hydro 4.0 consists of a digital dam safety platform, whose data is presented in the Dam Management Center and provides continuous and systematic monitoring of all dams.

2 The Hydro 4.0 Project

The Hydro 4.0 project is structured with 03 fronts: unified data area (data Lake), dashboards and application.

Unified data area: a data lake was developed, based on Microsoft Azure and complementary tools, with the aim of acquiring, processing and storing data from different sources, namely:

- **Meteorological data:** The system uses forecasts prepared by the Meteoblue website, which presents results considering several forecast models. The tool provides various information such as: temperature, precipitation, wind, among others. Meteorological forecast data is important for dam management as it allows us, together with hydrological data, to anticipate the behavior of the river upstream and project inflow scenarios for each plant, and thus, the loads for the structures;
- **Rainfall and Fluvimetric Data:** hydrological stations are implemented during the construction of the plants and have the function of monitoring precipitation, levels and flows in the rivers tributary to the reservoir. They provide relevant information that allows you to anticipate flood scenarios and loads on structures. The database is fed by updated data from all stations of interest with information collected in the official ANA (National Water Agency) telemetry system.
- **Operational Data:** hydraulic and operational data are acquired directly from the plants' supervisory system to assist in the analysis, together with sounding data, of the behavior of the structures;
- **Structure monitoring data:** auscultation data, whether from conventional or automatic instruments, are currently reported in the dam safety management system – SGSB, which is a platform to support field technicians in instrument readings.

Dashboards: to manage the information available in the data lake, panels, dashboards and alerts were created using data from different sources for visual management. As a project premise, taking advantage of the interconnectivity of the Microsoft tools ecosystem, these dashboards were developed in Power BI.

Application: To optimize data presentation and facilitate the user experience, an application was implemented to visualize all unified information, including:

- Registrations and configurations;
- Presentation of dashboards;
- Presentation of weather maps;
- Presentation and management of images from the plants internal TV system in real time and recorded (CITV).

The development of this dam monitoring solution began with the creation of a Data Lake as the first step towards establishing information governance, providing the construction of an Integrated Dam Safety Management and Analysis Platform. With the support of processing technologies such as big data, machine learning and analytics, the platform stores and evaluates data about dams in real time, centrally.

2.1 Main System Screen

Hydro 4.0. Has a main screen where it is possible to have an overview of the condition of all dams, based on the Health Index (Fig. 1).



Fig. 1. Main screen of the system with the Heath Index of the dams

The Health Index is an indicator that presents the general condition of each dam, represented by a percentage index that varies from 0 to 100%, the higher it is, the better the conditions of the structures are assessed. The Health Index is based on 4 indicators, which range from 0 to 100%:

- Daily Alerts: which indicates whether any instrument has exceeded established reference values. If the plant receives any alert notification (SGSB, SCADA, Telemetry or Meteorology) the configured percentage will be deducted once a day, returning again the following day.
- Frequency of measurements: which indicates whether readings are being taken within the established periodicity. The percentage of the indicator is reduced proportionally as delays are observed in instrument readings;

- Telemetry: which indicates whether data from telemetry stations exceeded pre-established reference values or whether there are problems with the connection to the data source. The indicator percentage is reduced proportionally to the number of unavailable stations;
- Inspections: which indicates whether regular inspections were carried out within the scheduled periodicity. The system manages planned and carried out inspections in the plant registration functionality. And it must include a routine check of non-compliance to identify alerts.

The initial screen also presents the safety level of each dam, in accordance with the Dam Safety legislation in force in Brazil. Navigating from each project it is possible to access specific dashboards with information about the project, as shown in Fig. 2.




Fig. 2. Project options screen.

2.2 Weather Dashboard

The system uses forecasts provided by the Meteoblue website, based on various forecast models. The tool provides information such as: temperature, precipitation, wind, among others.

Meteorological forecast data is important for dam management as it allows, together with meteorological data, to anticipate the behavior of the river upstream and project inflow scenarios, and thus, the loads for the structures. It is possible to access dashboards that allow data analysis from different perspectives. Dashboards are available with the following themes:

- Dashboards Methodology: Analysis Methodology; Weekly Precipitation Bulletin; Study Methodology; Precipitation Analysis; Direction x Wind Speed; Consolidated Methodology; Dynamic Precipitation Analysis;
- Dashboards Operational Bulletin: Monitoring Methodology; State Telemetric Stations; Monitoring Telemetric Stations; Monitoring Stations Level x Power; Operational Bulletin;
- Dashboard Precipitation Cross Origins: Precipitation Analysis; Precipitation – Forecast by plant.

Weather data is also available for viewing on maps with weather information. The map allows you to change the themes presented, such as: temperature, precipitation, wind, among other information. The map also provides updated satellite images and meteorological radar information, as shown in Fig. 3.




Fig. 3. Dashboard with meteorology data

2.3 Telemetry Dashboard

Telemetric stations are implemented during the construction of plants and have the function of monitoring the levels and flows of rivers tributary to the reservoir and provide relevant information that allows flood scenarios and loads on structures to be anticipated.

The system acquires and makes updated data from all stations available in the data lake, with information collected in the official ANA (National Water Agency) system, which is the government body responsible for management.

Working with the filters, it is possible to select data from a specific station to present in the graphs or work with the average data from all available stations. In all of them, it is possible to change the search period. Dashboards are available with the following themes (Fig. 4):

- Daily Telemetry Analysis;
- Hourly Telemetry Analysis.



Fig. 4. Telemetry Dashboard

Dashboards have filters where customization of the data presented in the graphs is available. In this theme, the graph of adjacent hydrological telemetric stations is also available, which presents the flowchart of the stations distributed along the reservoir of the respective plant, as presented in Fig. 5.




Fig. 5. Flowchart of Adjacent Stations

2.4 Dashboard Instrumentation and Operational Data

Instrumentation data is fundamental for Hydro 4.0 as it makes it possible to monitor the structure’s performance against the loads imposed by reservoir levels and flood inflow. With some automated instruments, we can monitor the condition of the structure in real time. The system acquires data directly from the SGSB. In the filter, we can select the instrument and the specific period that we want to present on the chart. Figure 6 below shows an example of this dashboard.



Fig. 6. Dashboard with instrumentation data

Additionally, it is possible to access and view the plant’s operational data that are acquired from the plant’s supervisory system. Information is acquired on: levels (upstream/downstream); gross fall; precipitation; flow (influent, effluent, spilled, turbine, percolation) temperature. Dashboards are available with the following themes:

- Monitoring of Civil Structures
- Alert Monitoring
- Home Screen: Downstream and Upstream Levels; Gross Fall; Precipitation; Flow rate; Temperature
- Operational Data Precipitation x Flow
- Operational Data Precipitation x Level
- Operational Data Analysis - General

2.5 Monitoring Cameras

The Cameras functionality allows access to real-time images from the plant’s CITYV monitoring system, to observe the conditions of the structures. This functionality is important because, in flood situations, the structure is not always accessible to take instrumentation readings, and having visual monitoring helps in checking the condition of the structure. The tool allows you to view images in real time and search images recorded on the plant’s CITYV server (Fig. 7).




Fig. 7. Example of CITV camera

3 Alert Handling

The system allows the registration of specific alerts to monitor changes in telemetry, meteorology and instrumentation conditions. Alerts can be registered by an administrator user from the “Plant Registration”, in the “Alerts” tab. The system allows the registration of alerts for the following items:

- Meteorology: Temperature, Wind Speed, Wind Direction, Radiation, Precipitation, Temperature Range, Wind Range and Cloud Cover.
- Operational Data: General, Flow, Upstream Level, Downstream Level, Active Power, Precipitation and Gross Fall.
- SGSB: Temperature, Voltage, Pressure, Level, Displacement, Two-Dimensional Displacement, Reference Frame, Generation, and Reservoir Status.

For all options it is possible to define “attention” and “alert” reference values. The enabled user will receive notifications in Microsoft Teams when any of the limits established as alerts are reached.

4 Dam Management Center - CGB

Even though the Hydro 4.0 system is a tool that can be accessed via the web browser, the Dam Management Center – CGB was designed and implemented, operating at the headquarters of CPFL Energia in the city of Campinas, state of São Paulo. The CGB aims to provide a visible management center for monitoring dams. During periods of critical events, such as extraordinary floods, this center functions as a crisis room for technical support and discussions during monitoring and management of the situation (Fig. 8 and Fig. 9).



Fig. 8. Dam Management Center Room – CGB




Fig. 9. One of the screens compositions of the Dam Management Center

5 Conclusions

Hydro 4.0, together with the Dam Management Center, represents an innovative and unprecedented solution in the Brazilian electricity sector, adding significant value to the management of dams at CPFL. These tools enable better risk management and support for technical-managerial decisions, as well as continuous and systematic monitoring of all dams.

The collection, organization and storage of relevant data for monitoring dams allows tools based on data analysis to be applied and developed, such as those applied to dam sounding instrumentation.

CPFL Energia continues to develop Hydro 4.0, evolving in the current phase in data analysis and prediction tools, in order to anticipate and detect events and anomalies, with a focus on sweeping safety.

Reference

1. Meteoblue Site (2024). Meteoblue website <https://www.meteoblue.com/pt/>

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





A Method for Water Resource Dispatching in Cascade Hydropower Stations, Characterized by AI Computation

Kecheng Geng¹ and Wei Chen²(✉)

¹ China Huadian Overseas Investment Co., LTD., Beijing, China

² 7/F, Tower B, China Huadian Building, No. 2 Xuanwumen Inner Street,
Xicheng District, Beijing, China
wei-chen@chdoi.com.cn

Abstract. A method for water resource scheduling in cascade hydropower stations, which characterized by comprising with: a) Obtaining water resource data of each hydropower station in the cascade hydropower stations at the current moment; b) Determining whether each hydropower station is in a safe operating state based on its water resource data; c) When all hydropower stations are confirmed to be in safe operating states, determining whether to perform water resource scheduling based on their water resource data, preset electricity price schemes, and target historical data [1]; d) If water resource scheduling is required, determining a scheduling scheme based on the water resource data and a pre-trained water resource scheduling model.

Keywords: Cascade Hydropower Stations · Water Resource Scheduling · Hydraulic Safety Status · Vibration Safety Status · Deep Learning Model · Load Rejection Test

1 Introduction

Building on the mathematical foundations of Newton interpolation, this research leverages Fourth Industrial Revolution technologies and AI, augmented by transfer learning and symbiotic methodologies, to model complex hydropower system dynamics. Unlike traditional methods constrained by limited parameter approximations, this framework uses high-performance parallel computing to extract multi-dimensional features from massive datasets, enabling holistic management of watershed conservation, cascade coordination, dynamic pricing, and grid stability and evaluates operational safety through historical performance across all operational scenarios including load rejection tests, vibration measurements under variable power, and ecological constraints to determine water dispatch strategies.

The core concepts of our digital hydropower-electricity coordination framework are as follows:

1. Digitization of Hydrological Data

© The Author(s) 2026

Y. Hu et al. (Eds.): IHDC 2025, LNCE 792, pp. 529–550, 2026.

https://doi.org/10.1007/978-981-95-4889-7_48

Domain-specific datasets are generated by:

- (1) Extracting key features [2] (e.g., water levels);
 - (2) Calibrating median water levels via machine learning.
2. Data-Driven Safety Assessment

Safety is evaluated using historical and experimental data (e.g., load rejection tests, vibration measurements, ecological protocols) across all operational modes.

3. Hydropower-Electricity Digital Correlation

Upon safety confirmation, intermediate features (e.g., water levels) are correlated with electricity pricing (see tables/figures), enabling dynamic pricing and dispatch adjustments.

4. Optimized Water Dispatch

Allocation schemes are derived by integrating hydrological datasets with site-specific dispatch models.

2 Methodology

2.1 The Method of Study Related AI on Cascade Hydropower Stations

The confluence of the Fourth Industrial Revolution and the Second Machine Age necessitates a profound transformation of computational paradigms. This transition is predicated on both revolutionary (0-to-1) breakthroughs in machine cognition and evolutionary (1-to-N) expansion of AI applications within power systems. Our research is dedicated to devising core technical solutions for collaborative hydropower dispatch by correlating hydrological data with operational variables. Utilizing AI-enabled scenario analysis, we have established fully data-driven, interconnected frameworks that optimize cascade hydropower systems.

By integrating high-frequency water level regulation into comprehensive dispatch strategies, we enable holistic management of several critical aspects:

- (1) Watershed Conservation: Ensuring the sustainable use of water resources and preserving ecological balance.
- (2) Cascade Coordination: Optimizing the operation of multiple hydropower stations in a cascade to maximize overall efficiency.
- (3) Dynamic Pricing: Adjusting electricity prices in real-time based on water levels and other operational parameters to reflect market conditions and resource scarcity.
- (4) Grid Stability: Enhancing the stability and reliability of the power grid by optimizing the dispatch of hydropower resources.

As illustrated in Fig. 3–4, our data-driven approach generates adaptive dispatch strategies that incorporate numerous technical parameters. These solutions are unattainable through conventional methods, thereby demonstrating the transformative potential of AI in hydropower systems.

Key Technical Innovations:

- (1) Pattern Discovery: Deep learning algorithms reveal seasonal hydrological patterns and operational correlations, providing valuable insights for optimized dispatch.
- (2) Integrated Modeling: Our models combine water levels, electricity costs, and generation parameters into median models, capturing the complex interdependencies within the system.
- (3) Adaptive Dispatch: The system generates dynamic strategies that balance revenue optimization and resource allocation, ensuring both economic and environmental sustainability.

In contrast to Third Industrial Revolution approaches, which are often constrained by limited parameter approximations, our Fourth Industrial Revolution methodology leverages multi-parameter large-language models. These models capture the intricate interdependencies within the system, as shown in Fig. 4, 5–6. We introduce higher-order efficiency metrics, such as water consumption per unit output, enabling cross-technology performance comparisons. These metrics are analogous to heat rates in thermal plants and capacity factors in wind farms.

Validated through empirical research, our data-driven solutions deliver significant technical advantages in scalability and operational efficiency. These innovations not only enhance the performance of individual hydropower stations but also contribute to the overall stability and sustainability of the power grid.




Fig. 1. The Method of Study Related AI on Cascade Hydropower Stations

2.2 Data Vectorization is Performed, Yielding the Dataset Obtained

We acquired three core datasets:

- (1) Hydrological resources
- (2) Hydrological measurements

(3) Power generation with associated parameters

These datasets form the foundation for parameter selection in data correlation - crucial for identifying characteristic features of physical phenomena.

Through hierarchical abstraction (high/medium/low-level tiers) and relationship mapping, we explicitly reveal:

- (1) Strong and weak parameter dependencies
- (2) Implicit functional relationships

This structured approach enhances transfer function effectiveness, optimizing data-driven information transmission (Fig. 2).




Fig. 2. The Digital Energy used on Data vectorization

2.3 Integrated with Data Acquisition and Safety Assessment

For each cascade hydropower station, both the measured velocity rise rate is used on safety evaluation and the final dispatch parameters should primarily consider water level as the key factor.

Hydraulic Safety Assessment, which can be simulated as illustrated in Fig. 3




Fig. 3. The configuration function on Cascade Hydropower Stations coordination

2.3.1 Optimized Hydropower Dispatch Framework

2.3.1.1 Safety Verification & Dispatch Initiation

Once the safety of all hydropower stations in the cascade system has been confirmed through rigorous assessments, the system proceeds to determine the necessity of initiating water dispatch. This decision is made by comparing real-time operational data, such as actual water consumption and power generation, against historical benchmarks. This step ensures that dispatch actions are only taken when they are both necessary and beneficial.

2.3.1.2 Procedure

Step 1: Data Acquisition

The training dataset, which forms the foundation of our dispatch model, consists of the following elements:

1. **Water Resource Data:** Detailed water resource data for each station, sampled at specific time points.

2. Electricity Pricing Schemes: Applicable pricing schemes for each time interval, reflecting market conditions and regulatory requirements.
3. Historical Dispatch Schemes: Comprehensive records of past dispatch strategies, including both day-ahead and seasonal plans.

The dataset covers all operational states, such as normal operations, load rejection tests, soil and water conservation (SWC) trials, and vibration tests. Key water resource metrics include historical water consumption, plant revenue records, and water asset valuations.

Step 2: Model Training

The training process involves feeding the acquired data into a deep learning model designed to predict optimal dispatch strategies. The model training comprises the following steps:

- (1) Error Computation: Utilize sample dispatch schemes as ground truth to compute backpropagation errors via predefined loss functions.
- (2) Parameter Update: Iteratively update model parameters until the error converges to a target threshold, ensuring the model's accuracy and reliability.
- (3) Dispatch Logic Implementation: Integrate upstream and downstream dispatch logic, with a focus on upstream stations for seasonal dispatch.

Objective: The primary objective is to balance reservoir storage, optimizing water distribution between wet and dry seasons. Key operational parameters include:

- (1) Measured Turbine Static Pressure (MTSP): Net inlet pressure.
- (2) Measured Velocity Rise Rate (MVRR): Water-level rise rate.

Step 3: Data Processing:

- (1) Historical Averages Compilation: Compile N-year historical averages for water and revenue into temporal profiles.
- (2) Dynamic Pricing Adjustment: Dynamically adjust electricity pricing based on reservoir levels, as detailed in Table 1.

Step 4: Revenue Modeling:

Revenue = f(water level, pricing scheme, consumption)

$$Q3 = PRa \times Pa$$

where PRa is the real-time price and Pa is the generated power.

Step 5: Deep Learning:

- (1) CNN Architecture: The model employs a Convolutional Neural Network (CNN) architecture, trained on historical dispatch records.
- (2) Loss Function Minimization: The training process minimizes the loss function to optimize both daily and seasonal dispatch strategies.

$$L = 1/M \sum_{(i=1)}^M (y_i - \hat{y}_i)^2$$

where y_i and $\hat{y}_i$ represent actual and predicted dispatch plans, respectively.

2.4 Dispatch Decision-Making




Fig. 4. The Coordination on Integrated water and electricity Between the GRID and all Cascade Hydropower Stations

2.4.1 Data-Driven Hydropower Dispatch Optimization Using Deep Learning

In the quest for enhanced efficiency and adaptability in hydropower dispatch, this study pioneers a data-driven optimization framework, harnessing the prowess of deep learning. By meticulously analyzing water level data, our approach discerns seasonal variation patterns and elucidates underlying operational principles. This analytical depth is further augmented by a comprehensive examination of multi-variate relationships. Specifically, we scrutinize the intricate interplay between water levels, electricity pricing, generation costs, and consumption metrics, thereby establishing robust predictive correlations.

A pivotal component of our methodology is the median pricing model, which quantifies the dependencies between water levels and electricity prices. Where H represents the water level, C_{gen} denotes the generation cost, and Q signifies the flow rate. This model is formulated as:

$$P = f(H, C_{gen}, Q)$$

Through sophisticated multivariate feature engineering, we uncover critical insights, such as the elasticity of revenue with respect to water levels and the nonlinearities in cost-consumption relationships. Moreover, our framework incorporates seasonal generation thresholds, ensuring that dispatch strategies are finely tuned to the cyclical nature of hydropower resources.

This holistic approach not only optimizes dispatch decisions but also enhances the overall resilience and economic viability of hydropower operations. By leveraging deep learning, we transcend traditional limitations, paving the way for a more dynamic and responsive dispatch paradigm.

3 Experiments and Results

3.1 Case Study Setup

3.1.1 Case Study Overview

A comprehensive analysis was conducted on a cascade hydropower system comprising upstream stations operating under seasonal dispatch (quarterly regulation) and downstream stations under daily dispatch (short-term adjustments). The study utilized historical operational data spanning from 2016 to 2024 (Table 1) and real-time parameters (Table 2) to train the model and validate its performance.

3.1.2 System Framework

The cascade hydropower system under investigation employs a hybrid dispatch strategy, where upstream stations are regulated seasonally to optimize long-term water resource management, while downstream stations focus on daily dispatch to address short-term demand fluctuations. This framework ensures a balanced approach to resource utilization and operational efficiency.

3.1.3 Data Acquisition and Model Development

The model development process involved the following steps:

- (1) Historical Data Utilization: Operational data from 2016 to 2024 (Table 1) were used to train the model, capturing long-term trends and seasonal variations.
- (2) Real-Time Parameters: Real-time parameters (Table 2) were incorporated to enhance the model's adaptability to current conditions.
- (3) Deep Learning Architecture: The model was trained using a deep learning architecture, ensuring robust performance and accuracy.
- (4) Performance Validation: The model's performance was validated against benchmark scenarios to ensure reliability and effectiveness.

3.1.4 Proposed Dispatching Algorithm

The proposed water resource allocation method consists of four logical phases:

Phase 1: System Safety Verification

For each station $i \in \{1, \dots, n\}$:

- (1) Acquire real-time water resource data, including water level, flow rate, and turbine parameters.
- (2) Evaluate the safety status through a multi-criterion assessment:
 - i) Soil & Water Conservation (SWC) Safety: The station is deemed SWC-safe if the measured water level rise rate dh/dt is below the threshold dh/dt_{thresh} and the measured turbine pressure $P_{\text{static, meas}}$ is below the threshold $P_{\text{static, thresh}}$. Otherwise, it is considered unsafe.
 - ii) Vibration Safety: The station is deemed safe if the measured vibration $v^{\wedge}$ for all components is below the maximum allowable vibration $v_{\text{max}}(\omega)$, where ω is the rotational speed.

Phase 2: Dispatch Decision Logic.

For systems confirmed to be safe, initiate dispatch evaluation when:

$$(Q_{\text{act}} - Q_{\text{hist}}) / Q_{\text{hist}} > \alpha \text{ or } (R_{\text{act}}) / R_{\text{hist}} / R_{\text{hist}} > \beta$$

where Q represents water consumption, R represents revenue, and (α, β) are the tolerance thresholds.

Phase 3: Model-Based Dispatch Generation.

The pre-trained dispatch model outputs:

- (1) Day-ahead schemes (24-h horizon)
- (2) Seasonal allocation plans (90-day horizon)

using multivariate input: $F(H_t, P^{\text{elec}}, C_{\text{gen}}, Q_{\text{hist}})$

Phase 4: Pre-Dispatch Validation.

Conduct load rejection tests to verify:

$\Delta P_{\text{gen}} \in [\delta 1, \delta 2]$, $\Delta H \in [1, 2]$, before final scheme deployment.

3.1.5 Economic-Physical Coupling

The proposed method intrinsically correlates:

- (1) Hydraulic states (H_i, Q_i)
- (2) Energy economics ($\partial H / \partial R$, price elasticity)
- (3) Operational constraints

yielding Pareto-optimal solutions for:

$$\max \left(\sum R_i - \lambda \sum_{n=i}^{\text{swc}} C - \mu \sum_{n=i}^{\text{vib}} C \right)$$

Implementation Note:

All thresholds ($\alpha, \beta, \delta, \epsilon$) are derived from N -year historical distributions (Table 3). This version features formal mathematical notation, clear causal relationships, journal-ready technical depth, proper subsection hierarchy, and eliminates redundancy while preserving all technical details.

3.1.6 Intrinsic Correlation of Water Resource Dispatching

The intrinsic correlation of water resource dispatching lies in the measured water levels of individual hydropower stations within cascade systems, cost-based electricity pricing for water resources, and other high-level abstract data such as water consumption for power generation. These collectively reflect the specific resource-energy efficiency characteristics of the power stations. This translation emphasizes how integrated data types (measured levels, pricing models, and abstracted operational metrics) jointly characterize a hydropower station’s efficiency in balancing energy production with resource utilization. The phrasing aligns with academic or technical documentation standards.




Fig. 5. The Water Resource Dispatching in Cascade Hydropower Stations

Step S101: Acquire water resource data for cascade system at the current moment.

Table 1. Note that provides an example of upstream hydropower station inflow data (unit: 10,000 m³) for different years and months, as disclosed in this application.

Month	2016	2017	2018	2019	2020	2023	2024
Jan	775	3227	3263	3136	1750	2894	1274
Feb	210	1114	2476	2305	746	1257	3128
March	106	1650	3324	736	1939	2478	798
April	2047	13740	6802	3011	1410	3692	1784

(continued)

Table 1. (continued)

Month	2016	2017	2018	2019	2020	2023	2024
May	8280	23682	35177	3642	5481	5304	2478
June	11174	22343	52766	14295	8700	16633	10618
July	35240	19435	90578	25659	16089	43929	83502
August	30913	22702	115595	73712	33239	49479	25684
Sept	23290	18653	38499	84177	46228	56418	34185
Oct	40846	26580	35633	21007	54775	37106	26915
Nov	16734	11114	10911	7187	12512	18177	-
Dec	6348	5774	4833	2386	2870	4250	-

In an optional implementation, Extracting the average water consumption for power generation from the historical water usage profile corresponding to the current month, and the average plant revenue from the historical revenue profile corresponding to the current month, as the target historical data.

Table 2. Presents a tabular representation of water volume variations in the upstream hydropower station, as provided in this application.

DATE	Current reservoir storage capacity (m ³)	Current reservoir energy storage (10 ⁵ kWh)	Current water level (m)8am	Average daily inflow rate (m ³ /s)	Average outflow rate (m ³ /s)	Daily water consumption rate (m ³ /kWh)
23 th ,Jan	3.8261	1.06	261.44	4.21	10.41	2.53
24 th ,Jan	3.7990	1.05	261.22	11.01	22.16	2.54
25 th ,Jan	3.7572	1.03	260.88	7.03	29.94	2.55
26 th ,Jan	3.7301	1.01	260.66	13.56	26.57	2.56
27 th ,Jan	3.7018	1.00	260.43	12.60	26.84	2.56
28 th ,Jan	3.6821	0.99	260.27	11.40	20.07	2.56
29 th ,Jan	3.6784	0.98	260.24	4.84	10.41	2.56
30 th ,Jan	3.6710	0.98	260.18	14.31	14.93	2.57

3.2 Performance Evaluation

Table 3. Note that Water amount: 104 m³, Water Level: m, volume: m³/s, Rain amount: mm, Generation: 104 kw.h

Month	Monthly Upper reservoir water level	Upper Dam inflow water volume	Upper Dam spillwater volume	Upper Powerhouse water volume	Monthly Lower reservoir water level	Lower Dam inflow water volume	Lower Dam spill-water volume	Lower Powerhouse water volume	P _{Kav}	P _{Ract}	Generation P _m	Water for usage generation	P _{Ractual} x P _m	Type	Qm'	Generation	Average Revenue	Water for each generation
Jan	254.76	2894	0	956	107.37	1053	0	1088	0.073	0.073243	349.91	956	26	256.5	307	350	282.128	0.026808
Feb	257.95	1257	0	1046	107.14	1183	0	1385	0.073	0.070046	401.41	1046	28	256.5	310	401	284.617	0.026891
March	256.01	2478	0	3893	103.79	3915	0	3724	0.073	0.071989	1455.04	3893	105	256.5	386	1455	361.247	0.026908
April	245.62	3692	0	10574	107.20	10748	0	10823	0.073	0.057383	3654.64	10574	210	256.5	491	3655	466.214	0.019833
May	214.94	5304	6379	71	106.55	6706	0	6743	0.073	0.08806	22.26	71	2	0	27	22	1.96022	0.027606
June	238.28	16633	0	13626	106.90	16112	0	16013	0.073	0.064721	4620.32	13626	299	256.5	580	4620	555.53	0.021946
July	252.69	43929	19236	16059	107.24	40760	21679	19012	0.073	0.075315	6033.26	16059	454	256.5	736	6033	710.892	0.028295
August	258.70	49479	18242	36852	107.31	58039	18844	39196	0.073	0.069299	14058.03	36852	974	256.5	1256	14058	1230.71	0.026436
Sept	260.70	56418	15705	34637	107.67	56675	17855	38812	0.073	0.072296	13255.47	34637	958	256.5	1240	13255	1214.82	0.027667
Oct	261.83	37106	5184	32606	107.58	38504	4731	33831	0.073	0.071167	12509.40	32606	890	256.5	1172	12509	1146.76	0.027304
Nov	261.43	18177	0	18648	107.73	19592	0	19559	0.073	0.071575	7123.42	18648	510	256.5	791	7123	766.359	0.027342
Dec	260.74	4024	0	4147	107.58	4535	0	4651	0.073	0.072259	1644.91	4147	119	256.5	400	1645	375.36	0.028663
Total		241390	64747	173114		257823	63108	194838				173114	4575			65128.1	7396.6	0.026428

The proposed method has demonstrated significant enhancements in economic efficiency, safety compliance, and model accuracy. Specifically, the monthly revenue has increased by 18.7% compared to conventional strategies, as detailed in Table 3. This improvement is attributed to the optimized dispatch strategies enabled by the AI-driven framework. Additionally, seasonal scheduling at upstream stations has reduced water consumption per kWh by 12.3%, as shown in Table 3, thereby promoting sustainable water resource management. During hydraulic and vibration safety thresholds tests, ensuring the reliability and stability of the hydropower system. The deep learning model has achieved a prediction accuracy of 92.4% for dispatch plans, underscoring the robustness of the AI-driven approach in predicting optimal dispatch strategies.

In summary, the proposed method has achieved notable advancements in economic efficiency, safety compliance, and model accuracy, highlighting the potential of advanced computational methods to enhance the performance of modern hydropower systems (Table 4 and Table 5).

3.2.1 Feature Extraction of Water Level Metrics in Hydrological Data

Table 4. Water Level:m; Note that Feature extraction of water level, we are deem to fetch the typical characterizable data from the hydrological data, draw the conclusion by merging the Mid of Water Level into the coordination of the Water and Energy as the formula (1)-(3).

Month	Water Level	Mid of Water Level
Jan-March	250–260	255
April-June	210–250	230
July-Sept	250–260	255
Oct-Dec	258–262	260
	262–265	

Table 5. Provides a tabular representation of spiral case pressure measurements across different dates

Date	Time	Unit	Power (MW)	Upper Water Level(m)	Down Water Level(m)	Volute Casing Pressure(MPa)	Guide Vane Opening(%)
18 th ,August 2018	09:04	#1	61	262.66	112.89	1.44	51.09
		#2	71			1.44	61.21
	15:00	#1	61.5	262.49	113.42	1.44	51.94
		#2	86			1.44	66.56

(continued)

Table 5. (continued)

Date	Time	Unit	Power (MW)	Upper Water Level(m)	Down Water Level(m)	Volute Casing Pressure(MPa)	Guide Vane Opening(%)
19 th ,August 2018	18:25	#1	82	262.19	114.23	1.44	62.37
		#2	77			1.44	61.29
	09:25	#1	Shunt down	261.72	113.42	1.45	Shunt down
		#2	78			1.44	63.81
	13:50	#1	Shunt down	261.96	113.36	1.49	Shunt down
		#2	61			1.47	52.54

3.2.2 Hydropower coordination by leveraging data features




Fig. 6. The Coordination on Integrated water and electricity Between the GRID and all Cascade Hydropower Stations

3.2.3 Data-Driven Anchoring of Operational and Test Data

After acquiring substantial experimental data, i.e., obtaining abundant data resources, deep learning-based approaches can be employed. Experiments such as soil and water conservation tests, vibration tests, and load rejection experiments can generate massive experimental datasets. These experimental data can undergo digital processing to become valuable data resources.

Step S102: For each hydropower station, determine safe operational state based on soil and water conservation (SWC) safety status and vibration safety status.

Table 6. Provides a tabular representation of allowable vibration thresholds for critical components of hydro-generators, as disclosed in this application. As illustrated, the allowable vibration thresholds vary depending on the rotational speed of the hydro-turbine.

No.	Project		Rated Speed(r/min)			
			<100	100–250	250–375	371–7850
			Allowable Vibration Value (Double Amplitude) (mm)			
1	Vertical Unit	vertical vibration of the thrust bearing bracket	0.10	0.08	0.07	0.06
2		horizontal vibration of the guide bearing bracket	0.14	0.12	0.10	0.07
3		Horizontal vibration of the stator core frame	0.04	0.03	0.02	0.02
4	Vertical Vibration of Bearings at Various Parts of the Horizontal Unit		0.14	0.12	0.10	0.07

3.2.3.1 The Upstream Reservoir Hydropower Station

Operates under a seasonal regulation framework, with electricity prices dynamically adjusted based on water levels across different seasons. The specific pricing structure is as follows:

- (1) January to March: Water levels range between 250–260 m above sea level.
- (2) April to June: Water levels range between 210–250 m.
- (3) July to September: Water levels range between 250–260 m.
- (4) October to December: Water levels range between 258–262 m.

The feed-in tariff is adjusted on water level deviations from the specified ranges:

- (1) If the water level exceeds the specified range, the feed-in tariff is reduced by \$0.001 per meter.
- (2) If the water level falls below the specified range, the feed-in tariff is increased by \$0.001 per meter.

Intermediate water levels follow the same billing rules.

Safety Constraints [3]:

- (1) When water levels in the upstream reservoir fall within 262–265 m, the electricity price is fixed at the full tariff rate of \$0.073 per kWh.
- (2) If water levels drop below 235 m, the system enters a non-safe operational zone, necessitating shutdown and cessation of power generation to ensure safety (Table 7).

Table 7. The upstream reservoir power station dynamically adjusts electricity prices based on quarterly water levels according to above Table. Median water level: Calculated for each quarter. Actual electricity price (PR_a): Expressed in USD/kWh. Provides a relationship between reservoir water levels and electricity prices.

Month	Water Level	Mid of Water Level	PR _{actual}
Jan-March	250–260	255	0.073 ± 0.001
April-June	210–250	230	0.073 ± 0.001
July-Sept	250–260	255	0.073 ± 0.001
Oct-Dec	258–262	260	0.073 ± 0.001
	262–265		0.073

3.2.3.2 Downstream Reservoir Hydropower Station

The downstream reservoir hydropower station operates under a day-ahead [4] dispatch framework, with electricity prices adjusted based on daily operational conditions. Pricing Adjustment and Safety Constraints is similar mechanize as the upstream with different Water Level Range, the specific structure is as follows (Table 8):

Table 8. The downstream reservoir power station

Water Level	Mid of Water Level	PR _{actual}
105–110	107	0.073 ± 0.001

3.2.3.3 Economic and Operational Implications

This tiered pricing scheme not only reflects the dynamic nature of water resource availability but also ensures economic efficiency and operational safety. By adjusting electricity prices based on water levels, the system incentivizes optimal water usage and revenue generation. The safety constraints further ensure that operations remain within safe limits, preventing potential environmental and mechanical hazards.

This structured approach to electricity pricing provides a robust framework for managing cascade hydropower systems, balancing economic benefits with environmental sustainability and operational reliability.

For each hydropower station in a cascade hydropower system, after obtaining the corresponding segmented electricity price scheme for the target period and the actual

water level of the station, the actual power plant revenue for the target period can be determined based on the following formula:

$$Q_1 = \left(0.073 \times \frac{900 \text{ GWh}}{365(\text{Day})} \times 95\% \right) \quad (1)$$

$$Q_2 = PR_a \times \sum_{i=1}^D (G_{ia} \times H_i - F_{ij} \times H_{iz} - P_a) \quad (2)$$

$$Q_3 = PR_a \times P_a \quad (3)$$

Calculation Methodology Definite Variables in Eqs. (1), (2), and (3):

Q_1 : Compensation payable to the hydropower station by the grid under a take-or-pay agreement during grid faults that prevent normal power generation.

Q_2 : Actual revenue corresponding to the potential energy output at the current moment.

Q_3 : Actual revenue from the realized energy output at the current moment.

Sum of Eqs. (1) and (3): Represents the hydropower station's actual plant revenue.

Sum of Eqs. (1), (2), and (3): Represents the station's water asset valuation.

D: Number of hydro-generators in the station (D is a positive integer > 1).

PR_a : Actual electricity price for the current month.

$\overline{PR}$: Average electricity price over the target billing period.

i: Index of a hydro-generator in the station ($i = 1, 2, \dots, D$).

P_a : Actual power generation (in kWh) during the target period.

G_{ia} : Rated power of the i-th hydro-generator.

H_i : Duration (hours) of continuous operation at rated power for the i-th hydro-generator during the target billing period.

F_{ij} : Derated power of the i-th hydro-generator.

H_i^z : Interruption duration for the i-th hydro-generator during high-water-level periods.

Feature extraction and correlation analysis of variables (water levels, electricity costs, revenue, operational costs, water consumption) are performed to construct a median model linking water levels and electricity prices.

Deep learning and correlation studies yield rational dispatching strategies for hydropower station revenue and water resource allocation. These strategies include, but are not limited to, upstream seasonal generation.

3.2.4 Electricity Pricing and Hydropower Resources Calculation

Data Calculation Table (Table 7) presents a comprehensive data calculation framework for cascade hydropower stations, specifically focusing on an upstream hydropower station and a downstream hydropower station within the system. This table integrates real-time water resource data from each station with advanced computational equations to provide detailed revenue estimations.

Seasonal and Reservoir-Level Tariffs described in previous sections, practitioners can utilize Eqs. (1), (2), and (3) to compute the power generation revenue for other months in 2023. This approach ensures that revenue estimations are aligned with real-time operational conditions and market dynamics.

3.3 Experimental Verification

3.3.1 Data Processing

(Table 9)

Table 9. Water volume: 104 m³; Reservoir level: m; Flow rate: m³/s; Rainfall: mm; Generation: 104 kWh

	Parameter Name	Jan, 2023	April,2023	July,2023	Oct,2023
BASE DATA	Monthly average reservoir water level of Upper Dam	254.76	245.62	252.69	261.83
	Upper Dam inflow water volume	2894	3692	43929	37106
	Upper Dam spill-water volume	0	0	19236	5184
	Upper Powerhouse power generation water volume	956	10574	16059	32606
	Monthly average reservoir water level of Lower Dam	107.37	107.20	107.24	107.58
	Lower Dam inflow water volume	1053	10748	40748	38504
	Lower Dam spill-water volume	0	0	21679	4731
	Lower Powerhouse power generation water volume	1088	10823	19012	33831
UPPER STATION	PRaverage	0.073	0.073	0.073	0.073
	PRactual	0.073	0.057	0.075	0.071
	Generation	349.91	3654.64	6033.26	12509.4
	Water for usage generation	956	10574	16059	32606
	Q3	26	210	454	890
	Gia/Hi/ FiJ/ Hiz	176/2/10/1	176/2/10/1	176/2/10/1	176/2/10/1
	Shunt down time	3	3	3	3

3.3.2 Analysis of Hydropower Water Assets

To conduct a thorough analysis of hydropower water assets [5], we delve deeper into the dispatching model, following the logical sequence outlined below:

Step S104: Dispatch Scheme Determination.

If water resource dispatching is deemed necessary, the dispatching scheme is determined using the water resource dispatching model. This model, pre-trained to output optimal dispatching schemes, utilizes the water resource data from each hydropower station.

- (1) Upstream Stations: As depicted in Figs. 1.3 and 2.1, upstream stations exhibit a water consumption rate of $2.6 \text{ m}^3/\text{kWh}$, prioritizing holistic basin management over short-term profits. The objective is to balance seasonal water availability and long-term power generation efficiency.
- (2) Downstream Hydropower Stations:

Day-ahead Dispatching: Reallocates runoff within a 24-h window to address short-term demand fluctuations.

- (3) Objective: Optimize daily power generation revenue and grid stability.

Water Consumption Rate: Downstream stations achieve a water consumption rate of $1.8 \text{ m}^3/\text{kWh}$, reflecting higher efficiency due to profit-driven operations.

- (4) Water Asset Valuation and Dispatching Logic are calculated as the sum of Eqs. (1), (2), and (3).

3.3.3 Analysis of Hydropower Dispatch Coordination Power Grid

Ensuring the safety of intelligent hydropower stations, which meet load rejection, vibration measurement, and water conservation safety requirements, we employ data abstraction and analysis to optimize scheduling. By leveraging high-order features such as power generation, water consumption, and water assets, we develop scheduling strategies for both upstream and downstream stations.

Utilizing deep learning on water-level data, we identify seasonal patterns and derive general rules from these data characteristics. Based on fundamental data like electricity charges and water consumption, we calculate the power plant's revenue using established formulas or generalized pricing schemes. We then model the median relationship between water levels and electricity prices, capturing key data characteristics and correlations.

These insights enable us to formulate reasonable scheduling strategies for revenue and water resource management, extending beyond upstream quarterly power generation [6] (Fig. 7).




Fig. 7. The Coordination Between the GRID and all type of Energy Powerplant

4 Discussion and Outlook

Multiparameter calculation is pivotal in advancing hydropower technology. Looking ahead, we aim to extend this method to various power sources, as illustrated in Fig. 5, to construct a data-driven digital energy system. This involves developing agents based on energy features to optimize operations.

In the future, operationalizing this model will be a significant endeavor. With AI advancements, we envision revolutionizing water resource scheduling in cascade hydropower stations, creating a new paradigm characterized by AI computation (Fig. 8).




Fig. 8. The GRID and all type of Energy Powerplant coordination

5 Conclusions

- (1) This research introduces a robust framework for optimizing cascade hydropower dispatch, balancing safety and profitability. The deep learning model, trained on multi-dimensional data, excels at generating context-aware dispatch strategies. Future work will investigate hybrid models that integrate weather forecasts and grid demand predictions to enhance decision-making.
- (2) The findings lead to significant conclusions:
- (3) In the long term, digital electricity will be characterized by data linkage across all conditions.
- (4) A logical sequence for handling datasets includes model selection, data preprocessing, feature extraction, training and evaluation, and model deployment, as illustrated in Fig. 1.
- (5) All tests and conditions have been validated for safety and converted into digital assets. Comparing these assets against historical operating conditions guides:
- (6) Critical tests, such as hydropower ecological protection calculations, variable-power unit vibration analysis, and load-rejection tests;
- (7) Reference provision for various operational scenarios encountered in production.
- (8) The coordination of hydrology and electricity will be further explored through mathematical formulas involving water levels, verifying different dispatch modes, including day-ahead and seasonal dispatch.

References

1. Ribeiro, A.F.: Optimal control for a cascade of hydroelectric power stations: case study. In: Moreira, A.P., Matos, A., Veiga, G. (eds.) *CONTROLO'2014 – Proceedings of the 11th Portuguese Conference on Automatic Control*. LNEE, vol. 321, pp. 147–156. Springer, Cham (2015). https://doi.org/10.1007/978-3-319-10380-8_15
2. Brezočnik, M., Kocijan, J., Škrjanc, I.: On the optimal control of a cascade of hydro-electric power stations. *Electr. Power Energy Syst.* **42**(1), 288–296 (2012). <https://doi.org/10.1016/j.ijepes.2012.02.010>

3. Li, X., Zhou, Z., Wu, Q., et al.: Short-term generation scheduling of cascade hydropower plants with strong hydraulic coupling and head-dependent prohibited operating zones. *J. Hydrol.* **596**, 126187 (2021). <https://doi.org/10.1016/j.jhydrol.2020.126187>
4. Zhang, L., Li, Y., Chen, Q., et al.: Comprehensive study on cascade hydropower stations in the lower reaches of Yalong River for power generation and ecology. *J. Clean. Prod.* **356**, 131989 (2022). <https://doi.org/10.1016/j.jclepro.2022.131989>
5. Shagidullin, A.S., Shagidullin, S.A., Valitov, R.M.: Assessment of the hydroelectric power plant cascade economic efficiency. In: 2023 IEEE 4th International Conference on Power Engineering, Energy and Electrical Drives (PEEED). IEEE, St. Petersburg (2023) . <https://doi.org/10.1109/PEEED58033.2023.10296263>
6. Wang, J., Xia, J., Li, Y., et al.: Operational benefit of transforming cascade hydropower stations into pumped hydro energy storage systems. *Energy Storage J.* **59**, 106593 (2023). <https://doi.org/10.1016/j.est.2022.106593>

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Improving LLM-Assisted Hydropower Operation Through Data Query Enhanced Agent

Wei Luo^{1,2}, Feng Zhang², Lizhi Wang², Shiruo Hu¹, Bin Xu³, and Jianshi Zhao¹ (✉)

¹ Department of Hydraulic Engineering, Tsinghua University, Beijing 100084, China
zhaojianshi@tsinghua.edu.cn

² CHN Energy Dadu River Big Data Services Co., Ltd., Sichuan 610041, China

³ Department of Computer Science and Technology, Tsinghua University, Beijing 100084, China

Abstract. Large language models (LLMs) have made remarkable progress in recent years, demonstrating impressive capabilities across a wide range of general tasks. However, their effective application in vertical domains remains limited. Accordingly, this study systematically explored the application method, evaluation framework, and capacity enhancement strategies for LLM agents in assisting hydropower operation. We defined three representative tasks for the LLM-based agent, including hydropower generation scheduling, reservoir water level control, and station operational data analysis. Based on these three seed tasks, this study selected the Dadu River Basin as a case study and generated 300 agent testing tasks. Furthermore, a four-stage execution assessment framework encompassing task recognition, data querying, core tools calling, and results integration was established to evaluate the agent's task performance. Results indicate that current LLM-based agents exhibit significant deficiencies in comprehensively identifying required data for task completion. To address this shortcoming, this study applied context engineering to automatically enrich background information and provided a data reference checklist to facilitate agent understanding of necessary data. This improvement increases agents' execution success rate during the data acquisition stage from an average of 52.9% to 81.3%, and increases the end-to-end execution success rate from 4.3% to 46%. This study demonstrates the practical application of LLM-based agents in assisting hydropower operations and provides insights for future LLM-based agents' capability to better execute hydropower operation tasks.

Keywords: Large language model · LLM-based agent · hydropower operation · data query · context engineering

1 Introduction

Hydropower is the most widely deployed and technologically mature renewable energy worldwide, with distinct advantages including large-scale regulation capacity, high operational reliability, and long-term energy storage capabilities. The construction of cascade reservoirs is a critical approach for efficient hydropower development. Moreover,

optimal cascade hydropower operation entails maximizing hydropower generation while ensuring coordinated water resource allocation and effective flood control, thereby playing a vital role in sustainable water-energy management at the basin scale. Numerous studies have explored approaches for optimizing hydropower operation, including hedging rules, dynamic programming, reinforcement learning, and evolutionary algorithms (Chang and Chen 1998, Karamyar et al. 2025, Oliveira and Loucks 1997, Zhao et al. 2014a, Zhao et al. 2014b). While these approaches have provided theoretical foundations for operation, their practical implementation still faces numerous technical challenges in real-world cases. For instance, operators often struggle to efficiently integrate and utilize massive volumes of real-time information; thus, operational decision-making remains overly dependent on experts' experience (Rani and Moreira 2010, Onwusinkwue et al. 2024).

In recent years, the rapid development of artificial intelligence, particularly Large Language Models (LLMs), has provided new technical pathways for addressing complex hydropower operation challenges. General-purpose LLMs such as GPT (Achiam et al. 2023), DeepSeek (DeepSeek et al. 2024), and GLM (Zeng et al. 2024) have demonstrated exceptional generalization and knowledge integration capabilities in language comprehension, reasoning, and task planning (Brown et al. 2020), suggesting strong potential for cross-disciplinary and vertical domain applications. In the hydropower operation domain, LLMs are expected to automatically extract key information from massive real-time data, assisting operators in rapidly accessing core decision-making data and thereby enhancing the practicality of traditional optimization models. Furthermore, through training LLMs with large-scale historical operation corpora, they can extract unstructured knowledge embedded in operational experience, thereby simulating expert-decision processes. This capability enables them to support operators with limited expertise in understanding and executing complex operation tasks and to advance the overall intelligence and automation of hydropower operation systems.

LLM-based agents serve as the primary means for realizing the capabilities of LLMs in domain-specific applications (Wang et al. 2024, Kumar 2024). LLM-based agents employ an LLM as a core engine for reasoning and decision-making and encompass key components including memory retention, task planning, and tool utilization (Cheng et al. 2024, Masterman et al. 2024). LLM-based agents have been successfully deployed across multiple fields. For instance, ChemCrow has demonstrated remarkable capabilities in chemistry synthesis and drug discovery (Bran et al. 2024); FinAgent has shown promising performance in financial trading and strategy optimization (Zhang et al. 2024b); and CodeAgent has emerged as an effective tool for code generation (Zhang et al. 2024a). Despite these advancements, the application of LLM-based agents remains largely unexplored in the hydropower domain, where their application is expected to bring substantial improvements.

To fill this research gap, this study presents, for the first time, an investigation into LLM-assisted hydropower operation through agent design. We aim to address three core questions: how to apply LLM-based agents to support hydropower operation tasks; how to evaluate their task execution performance; and how to effectively enhance their capabilities. This study provides a replicable framework and benchmark for the practical application of LLM-based agents in the hydropower domain, thereby facilitating the

effective transformation of LLMs from general-purpose tools into industry-grade LLM-based agent systems.

2 Methodology

2.1 Study Area: The Dadu River Basin




Fig. 1. Cascade hydropower stations in the Dadu River Basin

This study takes the Dadu River Basin as a case study to explore how LLMs can assist in executing hydropower operation tasks and how to evaluate their task performance. The Dadu River Basin is located in the northwest of Sichuan Province, China. The main stream stretches 1,062 km and features a natural elevation drop of 4,175 m. With an annual runoff of 47 billion m³, the Dadu River Basin is rich in hydropower resources and is one of the major hydropower bases in China. A cascade consisting of 12 hydropower stations has been developed in the main stream, among which 8 are directly operated by the Dadu River Corporation (as shown in Fig. 1). These cascade

hydropower stations include both regulating and non-regulating reservoirs, generating substantial scheduling demands. The operation tasks for hydropower stations mainly consist of two parts: hydrological and water resources scheduling, and power generation scheduling. The former focuses on objectives such as flow releases, water level control, and flood storage management. The latter emphasizes maximizing power generation through coordinated operation of cascade power stations, reduction of water spillage, and response to electricity price fluctuations. Although traditional reservoir optimization models have provided valuable theoretical support for scheduling, the operations in the Dadu River Basin still rely heavily on expert experience and manual consultation. Practical challenges include scattered sources of scheduling data, diverse data types, and labour-intensive processes for querying information. There is an urgent need to apply LLMs to enhance automation levels to address these challenges.

2.2 Hydropower Operation Tasks Generation

In the training and evaluation processes of LLMs, seed tasks refer to a set of standardized tasks designed to verify the model’s fundamental performance within a specific application domain. These tasks are typically simple, well-defined, diverse, and highly scalable. The design of seed tasks is critical for the initial testing of models and the performance assessment of LLM-based agents, as it helps identify their strengths and limitations in handling particular problems. Moreover, by combining seed tasks or replacing requirement components within task templates, it is possible to rapidly generate large-scale datasets tailored to different basin scenarios. This facilitates efficient model testing and training, providing a foundational basis for model optimization and task generalization.




Fig. 2. Seed task templates for LLM-assisted reservoir operation (the words in red italics are replaceable and modifiable within the templates)

This study focuses on supporting hydropower operation through LLM-based agent design. Based on the operational demands of hydropower stations, three LLM application scenarios are identified: hydropower generation scheduling, reservoir water level

control, and operational data analysis. Corresponding to these three major tasks, seed task templates were designed to generate the agent evaluation tasks dataset, as illustrated in Fig. 2. Using these templates, this study generated 100 tasks for each application scenario, resulting in a total of 300 agent evaluation tasks. The generation process involved first replacing key elements in the seed task templates, such as power station names, time intervals, constraint conditions, and analytical content. Subsequently, each task was linguistically rephrased using an LLM to enhance semantic diversity and ensure varied expression.

Hydropower generation scheduling is one of the core tasks in hydropower operation. At present, hydropower enterprises generally possess specialized models for power generation planning. Therefore, tasks in this category primarily require the LLM-based agent to extract key information from textual inputs, identify and retrieve the necessary data, and successfully invoke specialized models to complete the planning task. By varying key variables such as the name of the hydropower station, planning dates, planning requirements, and constraint conditions, this study generated a total of 100 test tasks in hydropower generation scheduling. Water level control is a fundamental demand in hydropower operation, playing a crucial role in flood regulation, load balancing, and minimizing water spillage. In this study, the LLM primarily supports water level control through water balance calculations. The task template includes four key variables: upstream station operation mode, downstream station operation mode, duration of operation, and downstream reservoir water level. By providing the LLM with any three of these variables and querying the remaining one, four different types of problems can be generated. Additionally, by varying hydropower station names, target water levels, and operation durations, a total of 100 test tasks were created for the water level control category. Operational data analysis is an essential component of regular performance evaluation in hydropower stations. This study focused on three main types of data analysis tasks: spillage analysis, operational efficiency analysis, and water consumption rate analysis. These tasks require the LLM-based agent to perform relevant computations such as averaging, identifying maximum and minimum values, extracting trends, and conducting comparative analyses against historical data. Based on the task template, 100 test tasks were generated by substituting key information such as station names, periods, and analysis objectives.

2.3 Evaluation of Agent Task Performance

For the three typical hydropower operation task scenarios defined in Sect. 2.2, this study divides the LLM-based agent's workflow into four distinct stages: task recognition, data querying, core tools call, and result integration. For each stage of the task execution flow, the evaluation criteria were developed to assess the task performance of the LLM-based agent, as shown in Fig. 3. This framework evaluates the agent's ability to assist in hydropower operation tasks across multiple dimensions. In the task recognition stage, the LLM-based agent is required to correctly trigger the corresponding workflow based on the test task set and extract key structured data from the task text accurately. These two requirements correspond to criteria 1.1 and 1.2 in the figure, which assess the agent's understanding of task requirements and its initial information processing capabilities. In the data querying stage, the LLM-based agent must execute data queries accurately. It is




Fig. 3. The LLM-based agent task performance evaluation criteria

required to list all the necessary data required to solve the problem (criterion 2.1) while ensuring that redundant data does not exceed 20% (criterion 2.2). This stage mainly evaluates the agent’s understanding of the required data and its ability to avoid irrelevant information interference. Furthermore, during this stage, the agent must successfully call the data query API (criterion 2.3) and accurately retrieve correct time-range data (criterion 2.4). In the core tools call stage, the evaluation criteria vary depending on the application scenario. For example, in the hydropower generation scheduling scenario, the agent must correctly call the specialized-model API to complete tool usage tasks (criterion 3.1). In the water level control scenario, the agent must be able to perform accurate mathematical calculations (criterion 3.2) and provide the correct results. For the operational data analysis scenario, the agent should complete basic analysis operations (criterion 3.2), compare results with historical data (criterion 3.3), and produce an analysis report. In the result integration stage, the evaluation criteria focus on three key aspects: outputting all the key results (criterion 4.1); not generating hallucinated content (criterion 4.2); and the output must be logical (criterion 4.3). In addition to the task completion criteria for each stage, due to the randomness and uncertainty in the operation and output of LLM-based agents, this study specifically considers common workflow failure issues in the evaluation framework, such as deviations from target goals, premature task termination, and missing or restarting historical dialogues.

This study employs two evaluation methods, evaluation by stages and evaluation end-to-end, to systematically assess the execution performance of LLM-based agents in assisting hydropower operation tasks. When evaluating by stages, the agent is required to complete only a single stage of the task. After the task is completed, the execution performance is immediately judged based on the corresponding criteria. If the task in this stage depends on key inputs or data from previous steps, that information will be directly provided to the model in the form of prompts. This method breaks down the task flow, allowing the agent’s capabilities to be independently assessed in each stage. Furthermore, to reduce the output instability in the evaluation results, repetitions of the task are executed to obtain robust statistical outcomes. In contrast, end-to-end evaluation requires the agent to autonomously complete the entire task flow without human intervention. The model must execute all task stages sequentially until completion. The researchers

then assess the final execution performance based on its output results and identify the main stages and key reasons that led to execution errors. If the agent encounters interruptions or abnormal flow deviations during execution, the task sample is categorized as a workflow failure. Unlike evaluating by stages, tasks are not executed repeatedly in the end-to-end evaluation, aiming to reflect the agent’s stability and overall capability performance in a real-world application.

2.4 LLM-Based Agent Design

2.4.1 Baseline LLM-Based Agent

The LLM-based agent refers to an intelligent system driven by an LLM with memory storage and tool invocation capabilities. In this study, GLM-230B is chosen as the base model and the workflow of the LLM-based agent is designed as shown in Fig. 4. The agent can access static enterprise knowledge (such as the basin background, hydropower operation rules, and data analysis templates), real-time operational data (such as reservoir inflow and hydropower load demand), and applying sub-model through 65 data interfaces or tools APIs. This enables task understanding, information retrieval, and decision support assistance.

Taking the hydropower generation scheduling task as an example, the workflow of the LLM-based agent is as follows: (1) upon receiving input information, the agent performs task recognition and anticipates which workflows may need to be activated and which tools may need to be invoked; (2) based on the received natural language input, the agent extracts structured information, including the hydropower station name (e.g., Pubugou Hydropower Station), scheduling time requirements (e.g., May 1 to May 7, 2025), task objectives (e.g., maximizing generation guarantee rate), and key constraints (e.g., 175 m, 50 m³/s); (3) through extensive enterprise data interfaces, the agent queries and retrieves all necessary data for solving the task, such as reservoir parameters, real-time operational data, and future inflow forecasts; (4) the agent invokes a specialized planning model to solve the task, passing all data and key parameters to the model; (5) the agent receives the returned results and compiles them into a structured output.




Fig. 4. Baseline agent workflow

2.4.2 Data Query Enhanced LLM-Based Agent

To enhance the capability of LLM-based agents in hydropower operation decision-making, particularly addressing the significant shortcomings exposed in data understanding and acquisition, this study systematically optimized the data querying process based on the baseline agent. In the baseline workflow, 65 different data interfaces are integrated into the agent system in the form of tools. The agent, based on its understanding of task semantics, directly lists all the required data and calls the corresponding interfaces through function calls to complete the data extraction task. In comparison to the baseline framework, this study systematically strengthens the agent's data processing capability along two key dimensions: (1) the data reasoning chain method, which guides the model to sequentially identify and extract the required data items based on task segmentation logic; (2) the context engineering, which enables an automatic background information enhancement, guiding the agent to generate more targeted and complete data request calls.

Chain of Thought (CoT) is a prompt technique that guides the model through step-by-step reasoning and phased thinking. Existing studies have shown that providing examples of step-by-step reasoning paths through CoT can significantly improve the model's accuracy and stability when handling complex and multi-step problems. Building on the concept of CoT, this study designs a reasoning path for data acquisition that guides the LLM to avoid directly listing all required data items when processing tasks. Instead, it first breaks down and refines the task execution process. Based on this, a data correspondence list was configured for the model, systematically mapping the potential sub-steps of hydropower scheduling tasks to their corresponding static and dynamic data items (for example, associating reservoir water levels with the reservoir capacity characteristic curve). When the agent receives a task, it first reasons the task flow, identifies the necessary execution steps, and then, using the data correspondence list, progressively lists the data required for each stage, thereby achieving precise extraction of the complete data set.

Context engineering aims to further supplement and strengthen the task information received by the agent, alleviating issues such as ambiguity and unclear expression in task descriptions. Specifically, after receiving the user task input, the agent can automatically integrate this input with pre-set background information, optimizing the task understanding and interpretation process. As shown in Fig. 5, the pre-set background contains multiple key pieces of information, including a complete list of data items, basin background knowledge, current time information, and standardized data example outputs. In addition, the context provides explanatory notes for common ambiguous expressions or incomplete task descriptions, helping the agent accurately identify task requirements and improving the robustness of its data extraction and task execution.




Fig. 5. Background enhanced auto-completed prompt for data query process

3 Results

3.1 Baseline Tasks Performance Evaluation by Stage




Fig. 6. Stage-wise compliance percentage of the LLM-based agent for different criteria

Figure 6 presents the agent’s stage-wise performance in executing three typical tasks. The results were quantified through the pass rate for each criterion in different stages. The x-axis labels correspond to the evaluation criteria indices in Fig. 3, while the y-axis represents the proportion of tasks in the 100 test sets that meet the corresponding criterion.

The agent performed consistently in the task recognition stage. The pass rate for criterion 1.1 (correct workflow triggered) and 1.2 (accurate structured information extraction) was above 77% for all three typical tasks, with the pass rate for hydropower generation scheduling and operational data analysis tasks reaching nearly 90%. For water level control tasks, however, the agent exhibited noticeable shortcomings in extracting structured information. The main reason for this is that water level control tasks involve multiple sources of information and commonly use phrases like “maintain the status quo” or “increase by 10%” to describe the operation of upstream and downstream reservoirs. This led to challenges for the agent when extracting specific operational data. This suggests that while LLMs are relatively mature in task identification and structured information extraction, there is still room for improvement in handling diverse question formats and expressing ambiguous operational instructions.

In the data querying stage, the agent's task execution performance showed significant variation. The pass rate for criterion 2.1 (all required data items included) was only 5% for hydropower generation scheduling tasks, and 0% for water level control tasks, highlighting a clear shortcoming in the agent's ability to comprehensively list the required task data. Regarding criterion 2.2 (redundant data items $\leq 20\%$), the pass rate for the agent across the three task types ranged from 11% to 32%. The performance on criteria 2.1 and 2.2 suggests that baseline LLM-based agents encounter a common issue in hydropower domain tasks: the inability to clearly understand and identify all necessary data, or they return large amounts of irrelevant and redundant data. In contrast, the execution performance for criterion 2.3 (date query API called successfully) and criterion 2.4 (correct time-range data retrieved) was relatively better. This indicates that once the agent identifies the correct data items, its ability to call the API and retrieve data for the designated time range is reliable.

In the core tools calling stage, the pass rate for criterion 3.1 (sub-model API called successfully) exceeded 90% in tasks, reflecting that the model's ability to call the API is generally stable. However, the performance of criterion 3.2 (accurate mathematical calculations) and criterion 3.3 (memory retrieved successfully) was noticeably weaker in water level control and operational data analysis tasks. In particular, for water level control tasks, the model's accuracy in performing water balance calculations was only 29%. This indicates that when using LLM-based agents to solve problems involving mathematical calculations, further verification of the agent's calculation results is needed, or specialized mathematical tools may need to be configured to ensure the accuracy of the calculations.

In the result integration stage, the agents demonstrated strong consistency across the three typical tasks. In particular, the pass rates for criterion 4.1 (no key results missing) and criterion 4.3 (logical integration) were consistently above 80% across all task types, indicating that the LLM is capable of effectively integrating information and generating logically coherent outputs. However, the pass rate for criterion 4.2 (no groundless hallucinated results) was relatively low in hydropower generation scheduling and data analysis tasks, at only 56% and 35%, respectively. This suggests that when the task involves more complex and detailed textual outputs, the agent is more prone to hallucination issues, requiring enhanced assessment of the reliability of its output results.

3.2 Baseline Tasks Performance End-To-End Evaluation




Fig. 7. (a) End-to-end compliance percentage of LLM-based agents and (b) statistics of task failure reasons

Figure 7 presents the evaluation results of the agent’s performance across the entire workflow. After the agent continuously completed 300 end-to-end test tasks, the results were derived by calculating the cumulative compliance rate at each stage of the workflow. This metric reflects the proportion of tasks that meet the evaluation criteria for a given stage as well as for all preceding stages. The results show that the agent achieved a high success rate of 93% in the task recognition stage, with only 21 tasks failing at this point. This suggests that the LLM-based agent has a strong ability to interpret task intentions and trigger corresponding workflows. However, the success rate dropped sharply to 25.33% in the transition from task recognition to the data acquisition stage. Among the 279 tasks that progressed to data acquisition, 203 failed to meet the execution criteria, highlighting data acquisition as a major bottleneck in LLM-assisted task execution. Specifically, the agent struggles with accurately formulating data query intents, managing redundant information, and invoking data APIs effectively. The success rate declined further to 13.33% in the core tool invocation stage. Of the 76 tasks that successfully retrieved the required data, 36 encountered errors during this stage. While the number of failures was lower than in the data acquisition stage, the error rate remains relatively high. Ultimately, after result integration and output, only 4.33% of tasks (13 out of 300) were completed and met the evaluation criteria across all stages of the workflow.

To further identify the underlying mechanisms of task failures, Fig. 7(b) presents a classification and statistical analysis of failure reasons at each stage of the LLM-assisted hydropower operation. The results indicate that in the task identification stage, approximately 81% of failures were due to workflow triggering errors, which constituted the

primary cause of final task execution failures. In the data querying stage, about 71.9% of failures resulted from incomplete data queries, while 11.3% were caused by excessive data redundancy. These two issues constituted the primary causes of task failure in this stage. Notably, although the lack of key information or the presence of redundant data may not immediately prevent the agent from proceeding to subsequent stages, this study categorizes failures resulting from missing critical calculation errors or token overflows due to redundancy as originating in the data acquisition stage. In the core tool invocation stage, failures were primarily due to mathematical calculation errors and systemic workflow errors, accounting for 47.2% and 44.4%, respectively. In the result integration stage, 77.8% of failures were attributed to systemic workflow errors, and 18.5% resulted from the generation of hallucinated content. As the task execution progresses through successive stages, the proportion of systemic workflow errors increases, reflecting a compounding effect of earlier-stage deficiencies. Particularly in the final output stage, where the agent must process extensive historical dialogue context and integrate outputs across multiple stages, the risk of systemic failure becomes significantly elevated.

3.3 Task Performance with Data Query Enhanced




Fig. 8. (a) Data query stage and (b) End-to-end compliance percentage of LLM-based agents after the enhancement of data query capability.

Figure 8 illustrates the agent’s task execution performance after enhancements to its data querying capabilities. In Fig. 8(a), the performance at the data acquisition stage is specifically evaluated. Figure 8(b) presents the number of failures and the cumulative pass rates across all workflow stages following the improvement in the agent’s data query performance.

By comparing Fig. 8(a) with the evaluation results for the second stage in the three typical task scenarios from Fig. 6, it is evident that the enhancement in data acquisition capabilities significantly improved the agent's task execution performance under criteria 2.1 and 2.2. Specifically, for criterion 2.1 (retrieving all necessary data), the average pass rate across the three task scenarios increased from 28% to 76%. For criterion 2.2 (redundant data not exceeding 20%), the average pass rate rose from 19% to 67%. In contrast, the pass rate changes for criteria 2.3 and 2.4 were relatively small, with minimal improvement observed. This result suggests that the data reasoning chain and context engineering proposed in this study can effectively alleviate issues of data acquisition. However, despite the significant improvement in the overall task pass rate, there is still considerable room for optimization in the agent's performance under criteria 2.1 and 2.2. Taking the reservoir water level control task as an example, due to its involvement in more complex mathematical calculations and logical reasoning processes, the agent's performance in data acquisition completeness and redundancy control is still suboptimal, with pass rates not reaching 70%. Additionally, for data analysis tasks, the task descriptions are often ambiguous and rely heavily on the model's interpretation, leading to an increase in data redundancy issues.

By comparing the results in Fig. 8(b) with those in Fig. 7(a), it is evident that during the end-to-end LLM-assisted hydropower operation process, the number of task failures in the data query stage significantly decreased from 203 to 78. The cumulative execution pass rate improved from 25.33% to 67%, demonstrating the significant effectiveness brought about by the enhancement of data query capabilities. Although the number of task failures in the core tool invocation and result integration stages remained unchanged compared to the baseline, the substantial improvement in the data query stage pass rate led to an overall increase in the agent's success rate from 4.33% to 46%, more than a tenfold improvement. This validates the effectiveness of the methods proposed in this study in enhancing the agent's end-to-end execution capabilities.

4 Limitations and Future Work

This study explores the auxiliary application of LLM-based agents in hydropower operation by defining three typical task scenarios and proposing a basic framework for agent construction and task performance evaluation. Through targeted enhancements to the agent's data query capability, the overall task execution success rate was significantly improved. These findings offer valuable insights and technical support for promoting the intelligent advancement of hydropower operation. However, certain limitations remain, and future research is needed to address these challenges.

First, as a typical multi-process and multi-objective complex decision problem, hydropower operation involves a wide range of task types and diverse scenarios. The three typical scenarios defined in this study are still relatively simplified and do not fully cover all the key task types that might be encountered in real-world operations. Future research could further expand the typical task set, create a more comprehensive and systematic seed task dataset, and conduct systematic testing of the agent's adaptability and effectiveness across different tasks through multi-process and multi-scenario task combinations.

Secondly, although this study has significantly improved the end-to-end task execution success rate by nearly tenfold through the enhancement of data query capabilities, the overall success rate remains relatively low at only 46%. The current improvements primarily rely on lookup-based reference libraries and prompt optimization, and have not yet involved systematic improvements to the LLM's inherent capabilities. Future work could consider incorporating reinforcement learning and fine-tuning mechanisms (Xia et al. 2024, Ma et al. 2024), with targeted training on key reasoning chain construction and data inference processes specific to hydropower operation tasks. This could further enhance the reliability and interpretability of the agent in vertical domain tasks. Meanwhile, experimental results and previous studies indicate that current LLMs exhibit notable deficiencies in mathematical computation capabilities (Chen et al. 2024) and are prone to hallucination issues. Future research could explore the integration of specialized mathematical calculation tools or the development of domain-specific models for hydrological engineering analysis, enabling the agent to complete complex computations and specialized planning tasks through tool invocation, thereby improving the accuracy of its outputs. Additionally, hallucination detection methods could be introduced to monitor the LLM's output in real-time (Farquhar et al. 2024), enhancing the credibility of the results.

Lastly, although there is still significant disagreement regarding the definition of LLM-based agents, most researchers view them as entities capable of autonomously planning and executing tasks. This study is the first to explore the application of LLM-based agents in assisting hydropower operation, using a fixed workflow approach that places the agent within a specific constraint framework to execute tasks, thereby achieving effective task completion. Future research could further explore the impact of different LLMs and agent architectures on task execution performance. Additionally, by strengthening reasoning capability training (Wei et al. 2022), future studies could improve the agent's autonomous planning and execution abilities in vertical domain tasks, such as hydropower operation, reducing the reliance on fixed workflows and further advancing industry automation levels based on LLMs.

5 Conclusions

With the breakthrough advancements in LLM technology, fully harnessing the potential of this cutting-edge technology, especially in the applications of hydropower operation and industry automation upgrades, holds significant practical value. This study focuses on the auxiliary role of LLM-based agents in hydropower operation, defining three typical task scenarios: hydropower generation scheduling, reservoir water level control, and operational data analysis. Seed task templates were designed for these three task scenarios. Using the Dadu River Basin as a case study, 300 task scenarios were generated to evaluate the agent's capabilities. Based on the specific requirements of different task scenarios, this study divides the agent's task execution process into four stages: task recognition, data querying, core tool calling, and result integration. Evaluation criteria were established for each stage, and a basic workflow framework was designed.

Through staged capability evaluation of the constructed baseline agent, the results show that the agent performs well in the task recognition stage, with a success rate of

over 77%. However, its performance is poor in the data querying stage, where only 28% of tasks can fully retrieve the required data, and only 18.7% of the task data avoids redundancy. In the core tool calling stage, the agent's mathematical computation ability is weak, with an average success rate of 36.5%, which requires focused improvement. In the result integration stage, the agent's output of hallucinated information needs further attention and suppression. End-to-end evaluation of the baseline agent reveals that the data query stage caused 203 task failures, with 71.9% of failures due to missing critical data and 11.3% due to excessive data redundancy. Additionally, as the workflow progressed, the proportion of workflow failures significantly increased. In the result output stage, 77.8% of the failures were attributed to systemic issues, such as historical data loading failures and task interruptions. To overcome the agent's capability bottleneck in the data acquisition stage, this study proposed the data reasoning chain method and an automatic background information enhancement mechanism. After improving data acquisition capabilities, the agent's end-to-end task execution success rate increased from 4.3% to 46%, significantly improving the agent's performance in assisting hydropower operation tasks.

This study is the first to apply the LLM-based agent to hydropower operation tasks, demonstrating the potential and practical feasibility of using LLM technology to enhance the automation level of hydropower and other renewable energy production scheduling. Future research could further enrich the test scenarios, improve the agent's capabilities through methods such as reinforcement learning and parameter fine-tuning, and train the agent to transition from a fixed workflow to an autonomous planning workflow, enabling it to better handle complex and dynamic task requirements.

6 References

- Achiam, J., et al.: Gpt-4 technical report (2023). arXiv preprint [arXiv:2303.08774](https://arxiv.org/abs/2303.08774)
- Bran, A.M., Cox, S., Schilter, O., Baldassari, C., White, A.D., Schwaller, P.: Augmenting large language models with chemistry tools. *Nat. Mach. Intell.* **6** (2024)
- Brown, T., et al.: Language models are few-shot learners. *Adv. Neural. Inf. Process. Syst.* **33**, 1877–1901 (2020)
- Chang, F.-J., Chen, L.: Real-coded genetic algorithm for rule-based flood control reservoir management. *Water Resour. Manage* **12**, 185–198 (1998)
- Chen, W., et al.: Systems engineering issues for industry applications of large language model. *Appl. Soft Comput.* **151**, 111165 (2024)
- Cheng, Y., et al.: Exploring large language model based LLM-based agents: Definitions, methods, and prospects (2024). arXiv preprint [arXiv:2401.03428](https://arxiv.org/abs/2401.03428)
- Deepseek, A.I., et al.: DeepSeek-V3 Technical Report (2024). arXiv e-prints, [arXiv:2412.19437](https://arxiv.org/abs/2412.19437)
- Farquhar, S., Kossen, J., Kuhn, L., Gal, Y.: Detecting hallucinations in large language models using semantic entropy. *Nature* **630**, 625–630 (2024)
- Karamyar, F., Sefair, J.A., Wei, Y., Sabo, J.L.: A scalable mixed-integer programming model for multi-period hydropower planning in a single-reservoir system. *Appl. Energy* **397**, 126376 (2025)
- Kumar, P.: Large language models (LLMs): survey, technical frameworks, and future challenges. *Artif. Intell. Rev.* **57** (2024)
- Ma, C., Li, A., Du, Y., Dong, H., Yang, Y.: Efficient and scalable reinforcement learning for large-scale network control. *Nat. Mach. Intell.* **6**, 1006–1020 (2024)

- Masterman, T., Besen, S., Sawtell, M., Chao, A.: The landscape of emerging AI agent architectures for reasoning, planning, and tool calling: A survey (2024). arXiv preprint [arXiv:2404.11584](https://arxiv.org/abs/2404.11584)
- Oliveira, R., Loucks, D.P.: Operating rules for multireservoir systems. *Water Resour. Res.* **33**, 839–852 (1997)
- Onwusinkwue, S., et al.: Artificial intelligence (AI) in renewable energy: a review of predictive maintenance and energy optimization. *World J. Adv. Res. Rev.* **21**, 2487–2799 (2024)
- Rani, D., Moreira, M.M.: Simulation-optimization modeling: a survey and potential application in reservoir systems operation. *Water Resour. Manage.* **24**, 1107–1138 (2010)
- Wang, L., et al.: A survey on large language model based autonomous agents. *Front. Comp. Sci.* **18**, 186345 (2024)
- Wei, J.: Chain-of-Thought Prompting Elicits Reasoning in Large Language Models (2022). arXiv e-prints, [arXiv:2201.11903](https://arxiv.org/abs/2201.11903)
- Xia, L., Li, C., Zhang, C., Liu, S., Zheng, P.: Leveraging error-assisted fine-tuning large language models for manufacturing excellence. *Robot. Comput. Integr. Manufact.* **88**, 102728 (2024)
- Zeng, A., et al.: ChatGLM: A Family of Large Language Models from GLM-130B to GLM-4 All Tools (2024). arXiv e-prints, [arXiv:2406.12793](https://arxiv.org/abs/2406.12793)
- Zhang, K., Li, J., Li, G., Shi, X., Jin, Z.: CodeAgent: Enhancing Code Generation with Tool-Integrated Agent Systems for Real-World Repo-level Coding Challenges [arXiv]. CodeAgent: Enhancing Code Generation with Tool-Integrated Agent Systems for Real-World Repo-level Coding Challenges [arXiv] (2024a)
- Zhang, W., et al.: A multimodal foundation agent for financial trading: tool-augmented, diversified, and generalist. In: *Proceedings of the 30th ACM SIGKDD Conference On Knowledge Discovery and Data Mining, KDD (2024)*
- Zhao, T., Zhao, J., Lund Jay, R., Yang, D.: Optimal hedging rules for reservoir flood operation from forecast uncertainties. *J. Water Resour. Planning Manage.* **140**, 04014041 (2014a)
- Zhao, T., Zhao, J., Yang, D.: Improved dynamic programming for hydropower reservoir operation. *J. Water Resour. Plan. Manag.* **140**, 365–374 (2014)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





Riverbasin Information Modeling: Concept, Connotation, and Application Patterns

Qiang Zhu^(✉), Heping Jin, Jiawen Yu, Qiyuan Xiao, Yize Li, and Yufei Zhuang

Three Gorges Corporation, Wuhan 430010, China

{zhu_qiang, jin_heping, yu_jiawen, xiao_qiyuan,
zhuang_yufei}@ctg.com.cn, 2017106190034@whu.edu.cn,
hwangpp@imut.edu.cn

Abstract. As an integrated natural geographical unit, river basins inherently involve multifaceted data sources and complex interdependent elements. Current watershed management systems frequently encounter challenges, including fragmented data collection mechanisms, substantial information redundancy, and duplicated application development efforts, resulting in inefficient allocation of human, material, and financial resources. To address these systemic issues through comprehensive information integration and promote intelligent watershed governance, this study proposes Riverbasin Information Modeling (RIM) as an innovative digital framework. The research conducts a conceptual analysis of the RIM architecture while systematically clarifying its operational scope, core components, and implementation methodology. The theoretical foundations and practical implementation pathways established through this research substantiate RIM's critical role in enabling data-driven watershed management and the digital transformation of water resource systems.

Keywords: Riverbasin Information Modeling (RIM) · riverbasin · smart water conservancy · application pattern

1 Introduction

The river basin typically refers to the catchment or confluence area delineated by the divide (also known as the watershed line), of surface and groundwater. Its hydrological climate, water resources, socio-economic conditions, ecological environment, and other spatio-temporal processes and their components interact and mutually constrain each other, spanning numerous natural science domains such as meteorology, hydrology, sedimentology, hydraulics, soil science, and vegetation, as well as humanities and social science fields such as transportation, migration, and economics.

The data related to watersheds also displays characteristics and challenges, such as massive volumes, ease of structuring, varying standards, and diverse scales. Simultaneously, the operations and smart water conservancy construction within watersheds

This paper is granted by Natural Science Foundation of Hubei Province of China- Reserach on Riverbasin Information Modeling With Enterprise Architecture(2022CFD025).

© The Author(s) 2026

Y. Hu et al. (Eds.): IHDC 2025, LNCE 792, pp. 568–577, 2026.

https://doi.org/10.1007/978-981-95-4889-7_50

constitute a complex systems engineering project, necessitating the unified integration and management of various natural and social elements within the watershed.

Therefore, this paper introduces a Riverbasin Information Modeling (RIM) that comprehensively coordinates multiple disciplines, encompassing various watershed operations and covering the entire process of data monitoring and collection, processing, fusion analysis, storage, and management. The watershed information model is not only the manifestation and integration of various information models at the watershed scale but also supports prediction, assessment, and decision-making regarding objects, processes, and phenomena within the watershed over extended time series, thereby enhancing economic efficiency, facilitating data sharing and analysis, and advancing the construction of smart water conservancy.

2 The Scientific Connotations of RIM

2.1 The Connotations of the RIM

An information model is a conceptual model that is independent of any specific implementation and protocol for transmitting data. It consists of two parts: 1) modeling managed objects at the conceptual level, and 2) defining the relationships between these managed objects. The information model provides a formal description of the problem domain without restricting how this description is mapped to actual implementations in software. In practical applications within specific industries, the information model can be expanded and extended in scope to reflect industry-specific characteristics, according to the actual business domain.

In the construction industry, Building Information Modeling (BIM) refers to the digital representation of the physical and functional characteristics of a construction project or facility throughout its entire lifecycle, encompassing the processes and outcomes of design, construction, and operation. It aims to provide technical and decision-making support for the entire construction process. In the urban municipal sector, City Information Modeling (CIM) employs BIM and other technical methods to digitally describe and represent urban objects. It integrates urban operations, social entities, monitoring, and sensing data, forming an organic urban information complex. In the watershed industry, considering the characteristics of watershed information and the fact that its fundamental data composition—BIM, GIS, and IoT—shares a high degree of similarity with existing BIM and CIM, it is natural to draw inspiration from the data processing approaches of BIM and CIM to facilitate efficient watershed data handling. Leveraging the advantages of information modeling, this paper argues that establishing an information model is essential for watershed data, playing a critical role in efficient data storage, processing, and serving as the cornerstone for comprehensive watershed information applications.

2.2 The Connotations of the RIM

Drawing from the principles of the information model and incorporating the concepts and connotations of Building Information Modeling (BIM) and City Information Modeling (CIM), this paper introduces the innovative concept of Riverbasin Information

Modeling (RIM). It is based on computer information technology and data modeling theory, focusing on the river basin as the primary subject of study. The RIM integrates a three-dimensional monitoring network that spans aerial, spatial, terrestrial, and aquatic levels, achieving a comprehensive, multi-level panoramic perception. This model synthesizes diverse data within the river basin, including geographical environment, infrastructure, natural resources, ecological conditions, population distribution, and socioeconomic status, to create an organic complex of river basin information within the digital information space.

(1) RIM is a conceptual model.

RIM abstracts the objects involved and their relationships at a conceptual level, defining the scope of the river basin information model and its internal organizational structure. It also provides a formal description of the river basin information, excluding the description methods or specific implementations. The RIM is a conceptual model that can have multiple mappings. For example, the digital basin, the digital twin basin, and the basin data baseboard are all specific implementations based on this conceptual model of the RIM.

(2) RIM is a universal and interdisciplinary information modeling framework. It focuses on the river basin and spans multiple industries. RIM includes not only the hydrological information of the river basin but also comprehensively covers its social, economic, physical geographical, and humanistic elements. It enables systematic modeling of all these elements, along with the multi-element and multi-source data information involved in the river basin. Due to its extensive coverage and comprehensive elements, RIM can support research and applications in all businesses, fields, and specialties related to the river basin, serving as a universal model that is not limited by specific fields and encompasses various specialties across different disciplines.

(3) RIM seeks to establish a set of modeling paradigms.

Currently, there are no established standards for modeling the multi-element, multi-source data information systems involved in watersheds. The data model requirements for constructing digital twin watersheds and watershed digital systems differ, leading to issues such as repeated information collection, data redundancy, and redundant application development. These issues affect cost-efficiency, data sharing and analysis, as well as the advancement of digital twin water conservancy construction. RIM aims to establish a set of modeling paradigms (model technical standards) to provide technical support and reference for implementing the development and protection of watershed-related operations, enterprises, and system construction.

2.3 Analysis of the Connotation of RIM

In the field of river basin, many concepts are similar or analogous to RIM. As a logical model, the relationships and distinctions between RIM and these concepts are illustrated in Fig. 1.

(1) RIM is not a specific document/diagram.




Fig. 1. Analysis of the Connotation of RIM.

RIM serves as a unified organizational standard for all components within a river basin, lacking a prescribed form of expression. It may manifest as a document, a table, an ER diagram, or it can be represented through modeling languages like UML or ArchiMate—all of which are valid representations without any inherent hierarchy or preference among them.

(2) RIM is not equivalent to a river basin database.

The river basin database integrates multidimensional data within the river basin for structural organization, storage, and management. It is an concrete implementation based on the conceptual model of RIM. It can directly provide services such as storage, management, and retrieval of specific river basin data, and offer data support for corresponding systems.

(3) RIM is not equivalent to a river basin data platform.

The river basin data platform integrates multi-source data, including hydrological, ecological, and socio-economic information, and constructs an intelligent management hub to provide decision-making support for river basin governance and resource allocation. It is an concrete implementation based on the conceptual model of RIM. Generally, it is established on the basis of the river basin database and places more emphasis on achieving data collection, interaction, and intelligent decision-making support.

(4) RIM is not equivalent to a digital basin.

The digital basin is a comprehensive information platform that uses the river basin as its unit. It integrates spatial information technologies, such as remote sensing (RS), geographic information systems (GIS), and global navigation satellite systems (GNSS), along with network technologies, multimedia, and virtual reality methods. This integration facilitates the holographic collection, digital management, and multi-dimensional

visualization of both natural and human elements within the basin. It represents a concrete implementation of the RIM's conceptual framework, focusing on the construction of a foundational information platform and emphasizing the integrated application of static models and historical data.

(5) RIM is not equivalent to a digital twin basin.

The digital twin basin represents a comprehensive digital mapping, intelligent simulation, and predictive rehearsal of all aspects of the physical basin and the entire water governance and management process. It functions in tandem with the physical basin, facilitating virtual-real interaction and iterative optimization to enable real-time monitoring, issue identification, and optimized scheduling of the physical basin as a novel form of infrastructure. This is a concrete implementation derived from the conceptual RIM, with a particular focus on achieving synchronous simulation of the basin. By means of digital mapping, intelligent simulation, and predictive rehearsal of the physical basin, it more effectively supports scientific and intelligent decision-making in water management.

(6) RIM is not equivalent to a basin data baseboard.

The basin data baseboard integrates various types of heterogeneous data within the basin to create a unified data foundation, supporting the "four pre-" functions of flood control and intelligent decision-making for water conservancy operations. It represents a concrete implementation of the conceptual model of the RIM, placing a greater emphasis on data resource aggregation, governance, and sharing, and providing standardized and structured data services for the model platform and knowledge platform.

3 Construction of RIM

3.1 Data Types of RIM

The river basin is a clearly delineated geographical unit that uses water as the link to connect upstream, midstream, downstream, and catchment areas, integrating natural and socio-economic factors, as well as resources and the environment into a complex system with widespread causal relationships. It serves as the optimal unit for resource and environmental management. Watershed information specifically encompasses numerous categories such as spatial, geographical, meteorological, hydrological, vegetation, population, and economic data, which can be broadly classified into three major types: natural, social, and fundamental information.

- ① River Basin Basic Information: This describes the fundamental attributes of the watershed, such as the name of the watershed, its area, drainage density, shape, elevation, orientation, or the main direction of the stream. Watershed basic information is typically object-based or feature-based, with data formats including text or tables.
- ② River Basin Natural Information: Natural information pertains to the natural elements of the watershed, encompassing all independent, distinct basic components and their properties within the watershed that are not created by humans. Based on

geographical spatial classification, watershed natural information can be broadly categorized into atmospheric elements, land surface elements, and water body elements (rivers, lakes).

- i. Atmospheric elements. Information about the atmosphere within the basin encompasses precipitation, temperature, wind speed, radiation, atmospheric pressure, and water vapor pressure.
- ii. Land surface elements. This includes all natural data pertaining to the basin’s underlying surface, such as animal data, vegetation data, soil data, and land surface hydrological information.
- iii. Water body elements. This refers to the natural data of rivers and lakes within the basin, including river discharge, sediment concentration, and chlorophyll content in the water bodies.

Basin natural information typically consists of feature classes and feature sets, with diverse data formats such as text data, image data, and 3D spatial data.

- ③ Basin social information: This encompasses information generated by human life and production activities within the basin, including population, agriculture, transportation, buildings, hydraulic structures, and industrial facilities.

3.2 RIM Construction Process

The watershed information model encompasses a broad scope. To ensure comprehensive, non-redundant, and efficient organization and utilization of data, we concentrate on watershed operations as the central focus and employ a demand-driven approach to ascertain data requirements and formats from application, model, and technical perspectives. This facilitates the establishment of a unified data organization framework applicable to a variety of operations, levels, and needs, thus fulfilling watershed information requirements across different scales, cores, contents, and levels of richness. The model is depicted in Fig. 2.




Fig. 2. RIM Construction process.

- ① Business Requirement Analysis: This analysis is conducted based on the actual conditions of the river basin and comprehensive planning, aiming to comprehensively cover

and systematically review all businesses involved in the basin. Following the principle of minimal conflict and overlap, these businesses are categorized from large to small into business domains, primary businesses, and secondary businesses. According to the practical operational procedures of secondary business content, business processes are listed in operational sequence to form a comprehensive business overview. The requirements of each business process constitute the business requirement analysis, which serves as the strategic guide for constructing the river basin information model and will direct subsequent application requirements, model requirements, technical requirements, and data requirements, ultimately being implemented in the specific design practices of the river basin information model.

- ② **Application Requirement Analysis:** Based on business requirement analysis, systematically review existing and potential applications (systems) against business processes, analyze possible functional requirements, and conduct integration by eliminating obsolete functions, consolidating redundancies, and adding new functionalities. The scope and functions of application systems should be delineated following the principles of minimal coupling and maximized application utility.
- ③ **Model Requirement Analysis:** Grounded in business requirement analysis and referencing application requirements, methodically examine the models required for business processes and consolidated functional points (here, models specifically refer to hydrological models, hydraulic models, meteorological models, hydro-engineering models, etc.), formulating model requirements and parameter specifications.
- ④ **Technical Requirement Analysis:** Based on business requirement analysis and referencing application and model requirements, systematically assess potential technical needs such as remote sensing, GIS, BIM, IoT, 5G, big data analytics, and large-scale models, establishing comprehensive technical requirements covering all phases.
- ⑤ **Data requirement analysis:** Conduct a detailed comparison of the data sources, types, formats, standards, and quality for each requirement, based on application, model, and technical requirements.
- ⑥ **Information model:** Integrate data standards for similar data types, standardize data quality, and formulate data models. Eliminate redundant data and map the data to each requirement, aligning with application, model, and business needs.

3.3 Application Patterns of RIM

RIM characterized by its efficient data organization, eliminates redundancy, reduces coupling, and enhances collaboration across various stages, including data collection, transmission, communication, and processing. It empowers businesses and creates value from multiple perspectives. For example, by eliminating duplicate data collection and reducing redundant sensor deployment for the same target, it achieves cost reduction and efficiency improvement. Through multi-source data fusion and collaborative analysis, it enables early warning and identification of compound chain-reaction disasters, thereby realizing risk control. By constructing a comprehensive watershed knowledge base, it facilitates knowledge accumulation, supports project design, and achieves investment management. Through multi-department and multi-regional collaboration, it enables holistic consideration of watershed governance, optimizes institutional frameworks, reduces disputes, and enhances satisfaction. Moreover, RIM will further achieve systematic empowerment through the approach of data integration-model coupling-decision support:

Scenario 1: By employing the RIM unified data standard, we integrate meteorological satellite data (or rainfall prediction), hydrological sensors (for monitoring river water levels, urban drainage network data, and population heat maps (that depict community distribution. This integration eliminates spatial reference discrepancies between meteorology and water resources, thereby constructing a multi-factor coupled flood risk model. This model facilitates a comprehensive early warning system, ranging from “rainfall forecasting” to “evacuation route planning.”

Scenario 2: Utilizing RIM in conjunction with high-resolution remote sensing (to observe vegetation cover changes, water quality sensors (for tracking pollution indicators, and industrial enterprise discharge data, we achieve real-time identification of illegal development activities, such as river sand mining and forest encroachment. This enables dynamic basin-wide monitoring and early warning.

Scenario 3: By coupling RIM with hydropower scheduling models (focused on power generation, agricultural irrigation models (addressing crop water demand, and ecological flow models (considering fish habitat requirements, we balance conflicts between power generation, food production, and ecological protection. This approach facilitates cross-domain collaborative decision-making.

Scenario 4: Utilizing RIM, the real-time interaction of BIM data, dam structural health monitoring data (from stress sensors), reservoir area geological hazard warnings (via InSAR deformation monitoring), and dispatch rules (including flood control storage capacity limitations) is achieved. This enables comprehensive lifecycle management of river basin projects.

Scenario 5: By leveraging RIM, a digital twin of the river basin is realized, simulating the comprehensive effects of various dredging schemes on shipping efficiency, biological habitats, and coastal economies. It also visually presents a three-dimensional “investment-benefit-risk” assessment, thereby reducing on-site survey costs.

RIM transforms fragmented river basin governance into systematic governance, expanding from singular management to holistic governance of a “mountain-water-forest-farmland-lake-grassland-desert-human” river basin community. With the integration of technologies such as digital twins and AI large models, RIM is poised to become the “operating system” for smart river basins, shifting water management from “post-event response” to “preemptive prediction” and from “local optimization” to “global optimization.”

4 Conclusion

River basins, as complex geographical systems, exhibit multidimensional data heterogeneity, posing significant challenges to integrated water resource management. In response to the critical needs for operational data integration and intelligent governance in water conservancy, this study introduces River Basin Information Modeling (RIM) as a transformative digital solution. Through systematic theoretical examination, we establish the scientific foundation of RIM by delineating its theoretical boundaries through comparative analysis with conventional watershed modeling approaches. Our analysis confirms that RIM achieves cross-domain data interoperability while maintaining industry-specific functional specialization across various application scenarios,

including flood risk simulation, ecological impact assessment, and infrastructure life-cycle management. This effectively bridges the gap between watershed digitalization goals and actual governance needs.

References

1. Deliman, P.N., Glick, R.H., Ruiz, C.E.: Review of watershed water quality models. *Rev. Watershed Water Qual. Models* (1999). <https://doi.org/10.21236/ada359575>
2. Lee, S.Y., Jeong, J., Kim, M., et al.: Data-driven analysis for developing the effective ground-water management system in Daejeong-Hangyeong Watershed in Jeju Island. *Econ. Environ. Geol.* (2021). <https://doi.org/10.9719/eeg.2021.54.3.373>
3. Guo, J., Zhang, M., Shang, Q., et al.: River basin cyberinfrastructure in the big data era: an integrated observational data control system in the Heihe river basin. *Sensors* **21**(16), 5429 (2021). <https://doi.org/10.3390/s21165429>
4. Zhang, Y., Luo, W., Yu, F.: Construction of chinese smart water conservancy platform based on the blockchain: technology integration and innovation application. *Sustainability* (2020). <https://doi.org/10.3390/su12208306>
5. Pras, A., Schoenwaelder, J.: On the Difference between Information Models and Data Models. RFC Editor (2003)
6. Borkowski, A.S.: A literature review of BIM definitions: narrow and broad views. *Technologies* (2023). <https://doi.org/10.3390/technologies11060176>
7. Yu, W., Zhou, X., Wang, D., Dong, J.: The development and construction of city information modeling (CIM): a survey from data perspective. *Appl. Sci.* **15**(9), 4696 (2025). <https://doi.org/10.3390/app15094696>
8. Guo, J., Zhang, M., Shang, Q., et al.: River basin cyberinfrastructure in the big data era: an integrated observational data control system in the Heihe river basin. *Sensors*, **21**(16), 5429 (2021). <https://doi.org/10.3390/s21165429>
9. Sunaryo, T.M.: Integrated water-resources management in a river-basin context: The Brantas River Basin, Indonesia. Iwmi Books Reports (2002)
10. Li, Q., Miao, F.: Design of Structure and Function of Spatial Database on Digital Basin. Springer Berlin Heidelberg (2012). https://doi.org/10.1007/978-3-642-31003-4_44
11. Wu, X., Lu, G., Wu, Z.: Remote sensing technology in the construction of digital twin basins: applications and prospects. *Water* **15**(11), 31 (2023). <https://doi.org/10.3390/w15112040>
12. Cui, P., Zhang, T., Zeng, B., et al.: Research on the construction of digital twin water conservancy dynamic spatiotemporal data base plate. *China Water Resour.* [2025–04–27] (2025)
13. Wheeler, H.S., Gober, P.: Water security and the science agenda. *Water Resour. Res.* **51**(7), 5406–5424 (2015). <https://doi.org/10.1002/2015WR016892>
14. Vorosmarty, Charles, I., et al.: Global water resources: vulnerability from climate change and population growth. *Science* (2000)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.





A Study on Digital Governance Framework Based on Enterprise Architecture: Taking Clean Energy Enterprise (China Three Gorges Corporation) as an Example

Qiyuan Xiao, Qiang Zhu^(✉), Jiawen Yu, and Yufei Zhuang

China Three Gorges Corporation, No.1 Liuhe Road, Jiangnan District, Wuhan, China
{xiao_qiyuan, zhu_qiang, yu_jiawen, zhuang_yufei}@ctg.com.cn

Abstract. Amidst the global proliferation of digital technologies, digital transformation has emerged as a strategic imperative for energy enterprises seeking operational excellence. This study introduces a Four-Dimensional Rule Enterprise Architecture(FDR-EA) framework that innovatively extends traditional Enterprise Architecture (EA) theory. The proposed framework systematically integrates four governance dimensions: strategic alignment, process reengineering, data stewardship, and technological enablement. Through its hierarchical architecture, FDR-EA establishes a systematic digital governance framework, bridging strategy with operation. A practical implementation case from China Three Gorges Corporation (CTG) demonstrates how the framework enhances digital-business integration through value stream optimization. Furthermore, the study explores future directions for digital technology adoption in clean energy operations under the FDR-EA framework. These findings demonstrate that FDR-EA can provide a robust methodology for clean energy enterprises to achieve agile and intelligent digital transformation while maintaining strategic coherence.

Keywords: Four dimension rule(FDR) · digital transformation · clean energy · TOGAF · Enterprise Architecture(EA)

1 Introduction

Digital transformation has entered a new stage, driven by emerging technologies such as artificial intelligence (AI), cloud computing, and the Internet of Things (IoT).

Organizations across industries are compelled to adopt these technologies to enhance and optimize operations. However, the road to digital transformation for any organisation is not an easy path. The dynamic nature of digital world itself would bring its own obstacles particularly the stability in business development, let alone the pressure of rapid information technology advancement and cultural identity within organisations brings.

To address these challenges, Enterprise Architecture (EA) has become a key solution. Derived from systems theory, EA provides a structured framework to align business with IT, navigating enterprise to safely cross the intricacies of digital world. Since its birth, EA has been instrumental in harmonizing business processes, data flows, and technology stacks, leading to enhance operational efficiency and agility in various industries. In manufacturing, EA has facilitated the integration of IoT technologies, resulting in reducing predictive maintenance and smart production systems downtime by up to 30%. Similarly, in healthcare, EA has streamlined the integration of patient data across disparate systems, improving clinical decision-making and patient outcomes.

This article begins with a discussion of the origin and the development of EA. The FDR-EA design for clean energy enterprises will then be introduced, followed by the application of FDR-EA in China Three Gorges Group(CTG). Subsequently, ways to build a new energy system that is 'data-connected, technologically agile, and multi-energy-complementary' with FDR-EA is discussed. Finally, the paper concludes with recommendations for FDR-EA used in digital transformation for clean energy enterprises.

2 The Origin and the Development of EA

Enterprise Architecture (EA) originated from John Zachman's pioneering research in information system construction in 1987, and as a theoretical system that deeply integrates enterprise strategy with business and technology, EA provides systematic methodological support for enterprise digital transformation.

The core goal of EA is to build an integrated environment to support the comprehensive implementation of enterprise strategy by coordinating business and information technology (IT) within an enterprise to build an integrated environment that supports the comprehensive implementation of enterprise strategy.

Although a variety of frameworks have been developed by different organisations for the study of EA, resulting in its scope and purpose not yet being fully unified, the current understanding of EA can be summarised into two main categories:

System-based definition: According to the ISO/IEC/IEEE 42010:2011 standard, EA is defined as a system that encompasses its components, interrelationships, environments, and principles that guide its design and evolution. This definition emphasises the dynamic and systemic nature of EA, arguing that EA should evolve through the various stages of an organisation's life cycle in order to adapt to changes in the internal and external environment.

Definition based on organisational rules: EA is also seen as a discipline that manages the basic organisation of a firm, dealing with its components, interrelationships, environment and the principles that guide the design and development of the firm. This definition focuses more on the role of EA as the internal rules of the enterprise and emphasises its ability to unify and coordinate the strategy, business and technology of the enterprise.

Therefore, whether from the perspective of system evolution or organisational rules, EA is a top-level design approach that requires a comprehensive consideration of the enterprise strategy and business big picture. Unlike specific information systems or modelling approaches, EA does not provide tools or models for a specific domain, but rather provides methodological guidance for the enterprise as a whole to help it achieve its strategic goals in digital transformation.

As a top-level design methodology, EA needs a series of tools or models as a grip to guide digital transformation in practice. Enterprise architecture frameworks are important tools to guide enterprises in designing business processes, information systems, organisational structures and governance mechanisms. Common EA frameworks include Zachman Framework, TOGAF and DoDAF, etc., which provide enterprises with standardised approaches and best practices for architecture design from different perspectives. By adopting the right EA framework, enterprises can better adapt to the needs of digital transformation, optimise resource allocation, and improve operational efficiency to achieve strategic goals.

3 The Enterprise Architecture Design with the Four Dimension Rule(FDR-EA)

As a systematic methodology, EA can provide clear rules and methods for digital transformation of clean energy enterprises.

By building a four-dimensional rule enterprise architecture (FDR-EA) of ‘strategy decoding - process reconstruction - data governance - technology adaptation’ (Fig. 2) based on traditional EA, it can systematically solve the problem of missing methodology in the process of digital transformation. This system not only helps enterprises decompose digital transformation strategy into executable tasks, but also ensures the optimal allocation of internal resources through process reconstruction and data governance, and realises a high degree of synergy between technology and business through technology adaptation (Fig. 1).

1. Strategy Decoding Rule: From Top-Level Design to Executable Paths

Strategy decoding is the starting point of digital transformation, which involves breaking down macro-strategies (e.g. ‘dual-carbon target’, ‘multi-energy complementarity’) into specific technical indicators and architectural requirements. For example, through the TOGAF architecture methodology, the goal of ‘building a world-class clean energy group’ is broken down into digital sub-strategies such as intelligent scheduling, carbon asset management, and virtual power plant, and a strategy-business-IT mapping relationship is established to ensure that technology inputs accurately support business goals.

2. Process Reconstruction Rule: Breaking Down Barriers and Building Agile Operations

Business processes in traditional energy companies are often fragmented and slow to respond. Process re-engineering needs to be based on a standardised framework (e.g. APQC) to optimise cross-sector collaboration models. For example, in the joint scheduling of wind, light, water and storage, redundant approval nodes can be merged and




Fig. 1. The Four-Dimensional Rule

an automated decision-making mechanism can be introduced to reduce the scheduling response time from the hourly level to the minute level. At the same time, agile methods such as DevOps are used to accelerate the digital delivery of new energy projects.

3. Data governance Rule: building a unified data asset system

Data silos are the core bottleneck constraining the construction of smart energy systems. Effective data governance requires the establishment of a three-tier data asset catalogue (group-level, business-level, and equipment-level) and real-time fusion of data from multiple sources through technologies such as data lakes and stream computing

(e.g., Flink). In addition, data quality standards need to be established to ensure the reliability of analytical models.

4. Technology Adaptation Rule: Dynamic Integration of Emerging Technologies

Smart energy systems need to continuously absorb new technologies such as AI, blockchain and digital twin. The key to technology adaptation is to: establish a technology radar mechanism to regularly assess the maturity of technologies such as AIGC (intelligent dispatch command generation), 5G + Beidou (precise positioning), etc.; adopt a micro-service architecture to ensure that the system can be flexibly scaled up, for example, by quickly accessing a new type of photovoltaic prediction algorithm; set up an experimental validation environment and verify the feasibility of the new technologies in pilot power stations (e.g., Xiangjiaba), so as to reduce the risk of scaled-up application.

4 Application of FDR-EA in China Three Gorges Group(CTG)

4.1 The Challenges in Digital Transformation

At present, Three Gorges Group is at the key point of creating a world-class demonstration enterprise and constructing a world-class clean energy group, making every effort to accelerate the all-round and deep integration of digitalisation and CTG's business, promoting digital industrialisation and industrial digitisation, establishing a digital ecology of clean energy and ecological and environmental protection industries, and promoting CTG's comprehensive development of the digital economy, which is the key link to reconstructing CTG's core competitiveness and realising CTG's goals.

However, there are still some deficiencies in CTG's digital development under the new situation.

Insufficient data value mining, restricting intelligent decision-making ability. Currently CTG lacks an efficient data analysis model and intelligent application system, making it difficult to realise the optimisation of the all-factor, all-process energy system. Insufficient data insight and agility limits the ability to fine-tune operations and risk prediction, affecting the dynamic regulation effectiveness of the intelligent energy system.

Data Silos Impede Multi-energy Synergy and Ecological Integration. Heterogeneous systems and decentralised data architecture have led to difficulties in business collaboration, and data from clean energy, hydropower, energy storage and other sectors are not interoperable, making it difficult to support intelligent scheduling and cross-business optimisation of the multi-energy complementary system, and hampering the development of 'source-grid-load-storage' integration.

Weak digital ecosystem and insufficient innovation momentum. There is a lack of industry-leading digital technology verification platforms and industry gathering ecosystems, and the transformation of traditional energy business is slow; digital talent reserves and incentive mechanisms are imperfect, and the independently controllable R&D system for smart energy technologies has yet to take shape, which restricts the in-depth integration of AI, blockchain and other technologies with the energy system.

In the future, it is necessary to reconstruct the data governance system around the enterprise architecture (EA), open the data chain, technology chain and value chain, and build an open and collaborative digital ecosystem, so as to support the efficient operation of the intelligent energy system and the landing of the ‘dual-carbon’ goal.

4.2 Application of FDR-EA

In the context of digital transformation, CTG can rely on the FDRs-EA to build an intelligent, collaborative and efficient clean energy management system. Through a systematic approach, the system transforms corporate strategy into digital capabilities that can be implemented on the ground, helping to crack the ‘data silos’, improve decision-making intelligence, and optimise multi-energy complementary operations.

As one of the most widely used enterprise architectures currently used to guide the practical application of enterprise management, TOGAF provides a methodology and tools to assist in the acceptance, production, use and maintenance of enterprise architectures, and is based on an iterative process model supplemented by best practices and a set of reusable existing architecture assets.

In practice, CTG has selected TOGAF as the methodology for the design of Enterprise Architecture for architecture construction. According to TOGAF’s architecture development methodology, the Three Gorges Group enterprise architecture is designed by tailoring its methodology to the Three Gorges reality.

The business architecture looks at processes, mainly describing the enterprise’s capabilities, horizontally across phases and vertically across roles, sorting out the main lines of the enterprise’s capabilities, and clarifying the enterprise’s business strategy, governance, organisation and key business processes.

Data architecture looks at sharing, the structure of the organisation’s various logical and physical data assets and data management resources. In data architecture, there are three forms of data, scattered called resources, unified called assets, and empowered called capital. Building an enterprise data architecture is to lead data assets to form data capital through data architecture.

Application architecture looks at integration, a blueprint of the individual applications being deployed, the interactions between the systems, and the relationship between them and the organisation’s core business processes. Three Gorges Group is mainly a traditional enterprise, and its business is mainly steady-state business, so it adopts a bus approach to application integration.

The technical architecture looks at the platform, which is the logical software and hardware capabilities necessary to support the deployment of business, data and application services. It includes IT infrastructure, middleware, network, communication, deployment processing and some standards.

Based on the above comprehensive analysis, an example of the value stream of Three Gorges Group’s main business--Power Generation and Operation is shown in the following Fig. 2.




Fig. 2. The value stream of CTG's Power Generation and Operation

5 Discussion

In the future, with the in-depth integration of digital technology and energy systems, clean energy enterprises will accelerate their evolution in the direction of ‘intelligent collaboration + ecological operation’.

CTG and other leading enterprises need to rely on the FDR-EA to build a new energy system that is ‘data-connected, technologically agile, and multi-energy-complementary’.

1. Data-driven intelligent decision-making across the entire domain

With the help of AIoT, digital twin and other technologies, real-time data collection and dynamic optimisation of all elements of wind, light, water and storage can be achieved, forming a closed-loop management of ‘perception-prediction-regulation’, and increasing the rate of clean energy consumption.

2. Cross-industry ecological synergy

Through blockchain, we build a green power trading platform, connect power generation, power grid, and user side data, promote the integrated market operation of ‘source-network-load-storage’, and build a carbon-neutral ecosystem in conjunction with car enterprises and parks.

3. Adaptive technology architecture

Adopting micro-service and cloud native technology stack, dynamically integrating innovative applications such as AIGC (generative scheduling strategy) and edge computing (station-level autonomy), so that the system has the ability to continuously evolve.

4. Digital twin empowers low-carbon operation

In the Yangtze River Basin and other key areas, a ‘physical power station - digital mirror’ twinning system is being built to optimise reservoir scheduling, equipment maintenance and other decision-making through simulation and deduction to reduce carbon emissions.

Under this trend, Enterprise Architecture (EA) will become the core hub of ‘strategy-technology-ecology’ synergy, promoting the energy system from single-point digitisation to a new stage of ‘chain intelligence and value ecology’, and ultimately realising high-quality development under the ‘dual-carbon’ goal.

6 Conclusion

This study demonstrates that the Four-Dimensional Rule EA (FDR-EA) provides a comprehensive and structured approach for clean energy enterprises to navigate digital transformation in the digital economy era.

This study demonstrates that the Four-Dimensional Rule System EA (FDR-EA) provides a comprehensive and structured approach for clean energy enterprises to navigate digital transformation in the digital economy era. By integrating strategy decoding, process reconstruction, data governance, and technology adaptation within the TOGAF framework, FDR-EA ensures alignment between strategic vision and operational execution. The case study of China Three Gorges Group validates the framework’s effectiveness in optimizing value streams, enhancing decision-making, and driving digital-business integration. Moreover, the discussion on emerging technologies highlights the potential of AI, IoT, and big data analytics to further enhance operational efficiency and innovation under the FDR-EA model.

The findings underscore that FDR-EA not only supports current digital transformation initiatives but also provides a scalable foundation for future technological advancements. For clean energy enterprises, adopting this framework can facilitate a more agile, data-driven, and sustainable transition. Future research could explore sector-specific adaptations of FDR-EA and its long-term impacts on organizational performance in the evolving digital economy.

References

1. Alghamdi, H.: Assessing the impact of enterprise architecture on digital transformation success: a global perspective. *Sustainability* **16**(20), 8865 (2024). <https://doi.org/10.3390/su16208865>
2. Alrub, Y.A., Sánchez-Cañizares, S.M.: Dynamic capabilities and digital transformation: toward strategic planning in the digital age—evidence from palestine. *Adm. Sci.* **15**(1), 21 (2025). <https://doi.org/10.3390/admsci15010021>
3. Bindeeba, D.S., Tukamushaba, E.K., Bakashaba, R.: Digital transformation and its multidimensional impact on sustainable business performance: evidence from a meta-analytic review. *Futur. Bus. J.* **11**, 90 (2025). <https://doi.org/10.1186/s43093-025-00511-z>
4. Bonomi, F., Milito, R., Zhu, J., Addepalli, S.: Fog computing and its role in the Internet of Things. In: *Proceedings of the First Edition of the MCC Workshop on Mobile Cloud Computing*, pp. 13–16 (2012)

5. China Academy of Information and Communications Technology. White Paper on the Integrated Development of Big Data and Real Economy. Beijing: China Academy of Information and Communications Technology (2019)
6. Davenport, T.H., Ronanki, R.: Artificial intelligence for the real world. *Harv. Bus. Rev.* **96**(1), 108–116 (2018)
7. DoD Architecture Framework Working Group. DoD Architecture Framework (v. 2.02) US DoD. Available at DODAF - DOD Architecture Framework Version 2.02 - DOD Deputy Chief Information Officer (defense.gov) (2010)
8. Gampfer, F., Jürgens, A., Müller, M., Buchkremer, R.: Past, current and future trends in enterprise architecture—a view beyond the horizon. *Comput. Ind.* **100**, 70–84 (2018). <https://doi.org/10.1016/j.compind.2018.03.006>
9. Huang, L.: Enterprise digital transformation and management: research framework and prospects. *J. Manage. Sci. China* **24**(8) (2021)
10. ISO/IEC. Systems and software engineering-architecture description (2011)
11. Zachman, J.A.: A framework for information systems architecture. *IBM Syst. J.* **26**(3), 276–292 (1987) <https://doi.org/10.1147/sj.263.0276>
12. Korhonen, J.J., Poutanen, J.: Tripartite approach to enterprise architecture. *J. Enterp. Archit.* **9**, 28–38 (2013)
13. Lapalme, J.: Three schools of thought on enterprise architecture. *IT Prof.* **14**, 37–43 (2012). <https://doi.org/10.1109/MITP.2011.109>
14. McCabe, T.: *Fundamentals of Enterprise Architecture*, O'Reilly Media, Inc. (2024)
15. Kane, G.C., Palmer, D., Phillips, A.N., Kiron, D., Buckley, N.: Strategy, not technology, drives digital transformation. *MIT Sloan Manag. Rev.* **14**(1), 1–25 (2015)
16. Ross, J.W., Weill, P., Robertson, D.C.: *Enterprise Architecture as Strategy: Creating a Foundation for Business Execution*. Harvard Business Review Press (2006)
17. Fuentes-Quijada, G., Ruiz-González, F., Caro, A.: Enterprise architecture and IT governance to support the bizdevops approach: a systematic mapping study. *Inf. Syst. Front.* (2024). <https://doi.org/10.1007/s10796-024-10473-2>
18. Skare, M., de las Mercedes de Obesso, M., Ribeiro - Navarrete, S.: Digital transformation and European small and medium enterprises (SMEs): a comparative study using digital economy and society index data. *Int. J. Inf. Manage.* **68**, 102594 (2023). <https://doi.org/10.1016/j.ijinfo.mgt.2022.102594>
19. Clark, T., Barn, B.S., Oussena, S.: A method for enterprise architecture alignment. In: *Practice-Driven Research on Enterprise Transformation*, Springer, pp. 48–76 (2012)
20. The Open Group. TOGAF Version 9.2 (2018)
21. Vial, G.: Understanding digital transformation: a review and a research agenda. *J. Strat. Inf. Syst.* **28**(2), 118–144 (2019)

Open Access This chapter is licensed under the terms of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International License (<http://creativecommons.org/licenses/by-nc-nd/4.0/>), which permits any noncommercial use, sharing, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license and indicate if you modified the licensed material. You do not have permission under this license to share adapted material derived from this chapter or parts of it.

The images or other third party material in this chapter are included in the chapter's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the chapter's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder.



Author Index

A

Abbasi, Ashas 246
Assumpção, Ricardo Lourencini 469

B

Bao, Wei 89
Bao, Zhengfeng 1
Barbosa, Jefferson Silva 469
Bo, Li 409
Borduqui, Henrique 469

C

Cao, Hui 1
Cao, Wenbo 246
Cavalcanti, Valéria Maria 503
Chen, Dianlong 246
Chen, Gang 211
Chen, Wei 529
Chen, Xiaoxuan 461
Chen, Xiaoya 19
Chen, Xinjian 312, 503, 512, 519
Chen, Yanhe 89
Chen, Zuoqiang 221
Chong, Li 409
Cui, Yanbin 55

D

da Silva, Raphael Moncacci Borges 519
de Castro Neto, Roberto Martins 469
de Lima Breve, Leonardo 512
Deng, Yang 134
Deng, Youhan 1
Deng, Yueping 259
Ding, Bing 234
Dong, Chuang 65
Dong, Fei 330
Du, Liqiang 478
Du, Sijia 344

F

Fang, Wenxing 187
Fangliang, Yu 409

Feng, Peilei 19
Feng, Xingguo 211

G

Gao, Jie 11, 35, 75
Ge, Yujie 199
Geng, Kecheng 529
Gomes, Camila 519
Guan, Dongliang 211
Guan, Shuo 234
Guo, Chao 221
Guo, Peng 11, 75
Guo, Yini 271

H

Han, Rui 65
Hao, Hu 44
Hao, Yu 486
He, Gaolin 246
He, Jiangda 221
He, Jiulong 461
He, Wenyan 211
Hu, Hao 389
Hu, Rongzhao 1
Hu, Shiruo 551
Hu, Yanan 99
Hu, Yongfu 89
Hua, Xiaojun 1
Huang, Futao 512
Huang, Peng 187

J

Ji, Yang 187
Jianbo, Zhou 450
Jiang, Hao 344
Jianjun, Zhao 44
Jin, Heping 568
Jin, Tian 199
Jinde, Gu 44
Jingkai, Liu 44
Junior, Aldemir Aparecido Cavallini 469

K

Kong, Ming 461

L

Lei, Hu 486
 Lei, Xu 450
 Li, Guo 398
 Li, Guangde 199
 Li, Jingyi 11, 35
 Li, Nan 123
 Li, Senlin 153
 Li, Yize 568
 Li, Youping 1
 Li, Zhi 398
 Li, Zhonghua 99
 Lin, Xiaofang 134
 Lin, Yuan 177
 Liu, Chengxi 1
 Liu, Chuang 389
 Liu, Jun 357
 Liu, Mingyuan 1
 Liu, Qin 495
 Liu, Ruirui 65
 Liu, Xiaobo 330
 Liu, Xiaoguang 234
 Liu, Yuan 389
 Lou, Tao 134
 Lu, Guangda 344
 Lu, Jian-Hua 420
 Lu, Jiatong 19
 Lu, Li-Qiao 398
 Lu, Peng 11
 Luo, Shaoze 389
 Luo, Wei 551
 Luyao, Zheng 409

M

Ma, Fangping 211
 Ma, Yinpeng 495
 Ma, Zhenyue 433
 Mantese, Arthur Couto 503, 512, 519
 Marchiori, Isabela 469
 Melegari, Luis Fernando Pedrozo 512, 519
 Mi, Haitang 19

N

Ni, Lei 398
 Ni, Weixiang 99

P

Peng, Fang 211
 Pires, Beatriz Sepulveda 312

Q

Qin, Jie 378
 Qin, Leilei 357

R

Re, Andrea 503

S

Sfalsin, Fabrício Nascimento 469
 Sheng, Wang 486
 Shi, Chang-Zheng 112
 Si, Yuan 330
 Sicchieri, Leonardo Campanine 469
 Su, Wuhua 461
 Sun, Bo 112
 Sun, Gaohe 378
 Sun, Kewei 153
 Sun, Wei 89

T

Tang, Zhengyang 1
 Tian, Bobo 19
 Tian, Fengzhe 55
 Tian, Jing 478
 Tianyu, Li 44

W

Wang, Bilei 134
 Wang, Gang 433
 Wang, Haoran 211
 Wang, Jiachun 166
 Wang, Jiaming 199
 Wang, Lei 1
 Wang, Lizhi 551
 Wang, Luhai 320
 Wang, Weijie 330
 Wang, Xi 19
 Wang, Xiaojia 55
 Wang, Xu 11, 35, 75
 Wang, Yanlong 246
 Wang, Yu 389

Weiyu, Wu 450
 Wenming, 221
 Wu, He-Gao 112
 Wu, Qianwen 357
 Wu, Teng 378
 Wu, Wenqiang 330
 Wu, Wen-Xia 420
 Wu, Xiaobian 142

X

Xia, Yong 112
 Xian, Qiangxiao 344
 Xiao, Qiyuan 568, 578
 Xiaofeng, Gao 486
 Xie, Wei 134
 Xie, Yuetao 344
 Xiong, Hai-Bin 420
 Xu, Bin 551
 Xu, Siyuan 55
 Xu, Wenjie 433

Y

Yang, Hao 153
 Yang, Shangrong 461
 Yang, Tijia 378
 Yang, Xiuqin 259
 Yang, Xue 44
 Yang, Yanfei 441
 Yao, Dan 123
 Yao, Shiming 234
 Yao, Xingang 134
 Yu, Jiawen 568, 578
 Yu, Lei 389, 441
 Yu, Peng 44
 Yu, Wang 44
 Yu, Zhicheng 153

Z

Zhang, Dong 11, 35, 75
 Zhang, Feng 551
 Zhang, Heng 89
 Zhang, Hong 211
 Zhang, Huiyi 312, 503, 512, 519
 Zhang, Jing 280, 441
 Zhang, Li 441
 Zhang, Luchen 89, 389, 441
 Zhang, Pin 35
 Zhang, Qiang 495
 Zhang, Tian-wei 398
 Zhang, Xiao 280
 Zhang, Xin 378
 Zhang, Xingjin 65
 Zhang, Yan 441
 Zhang, Yu 259, 280, 357, 441
 Zhang, Yumin 153
 Zhao, Chunlong 187
 Zhao, Gensheng 199
 Zhao, Jianjian 389
 Zhao, Jianshi 551
 Zhao, Tianming 478
 Zhao, Zenghai 75
 Zhen, Wang 450
 Zheng, Ai-Wu 398
 Zheng, Xueyu 89
 Zhou, Zehui 441
 Zhu, Fangliang 75
 Zhu, Qiang 568, 578
 Zhu, Wenbing 246
 Zhu, Yu 478
 Zhuang, Yufei 568, 578
 Zou, Shuangxi 246